

# GAZETTEER

OF THE

## BOMBAY PRESIDENCY.

VOLUME XXIV.

17362



KOLHÁPUR.

*Under Government Orders.*

R 910.3095431G  
G. B. P. / kol

Bombay:

PRINTED AT THE  
GOVERNMENT CENTRAL PRESS.

1886.



CENTRAL ARCHAEOLOGICAL  
LIBRARY, NEW DELHI.

Acc. No. .... 17362 ...

Date. .... 23.2.59 ...

Call No. R 910.309542/G/G.B.P./Kol

Handwritten text on the right margin, partially visible and oriented vertically.

SPECIAL acknowledgments are due to Ráv Bahádur Yashvant Moreshvar Kelkar and Lieutenant-Colonel W. F. F. Waller.

Much help was also received from Lieutenant-Colonel H. N. Reeves, Political Agent, Ráv Bahádur Mahádev Vásudev Barve, C.I.E., Diván of Kolhápur, Dr. G. Sinclair, and Messrs. B. N. Joshi, B. B. Vakhárkar, K. G. Kelkar, Anáji Venkatráv, and L. R. Golvalkar.

JAMES M. CAMPBELL.



# CONTENTS.

## KOLHATPUR.

Chapter I.—Description.	PAGE
Position and Area ; Sub-Divisions ; Boundaries ; Aspect ...	1-4
Hills ; Rivers ; Wells ; Ponds ... ..	5-12
Geology ; Climate ; Rainfall ; Heat ... ..	13-17
Chapter II.—Production.	
Minerals ; Forests ... ..	18-24
Domestic Animals ; Wild Animals ; Snakes ; Fish ; Birds ...	25-34
Chapter III.—People.	
Census Details ; Houses ; Villages ; Communities ; Move- ments ... ..	35-42
HINDUS :	
Bráhmans ; Writers ... ..	43-64
Maráthás ... ..	65-85
Traders ; Husbandmen ; Craftsmen ; Musicians ; Shepherds.	86-103
Labourers ; Unsettled Tribes ; Depressed Classes ; Beggars.	104-117
Lingáyats ... ..	118-132
Jains ... ..	133-146
MUSALMÁNS ; CHRISTIANS ; BUDDHISTS ; JEWS ; PÁRSIS ...	147-152
Chapter IV.—Agriculture.	
Husbandmen ; Seasons ; Soil ; Arable Land ; Holdings ; Stock ; Plough ; Field Tools ... ..	153-159
Ploughing ; Sowing ; Manure ; Irrigation ; Weeding ; Threshing ; Winnowing ; Mixed Sowings ; Woodash Tillage ; Crop Rotation ; Fallows ... ..	160-163
Crop Details ... ..	164-187
Blights ; Locusts ... ..	188
Famines ... ..	189-191
Chapter V.—Capital.	
Capitalists ; Currency ; Insurance ; Bills ; Saving Classes ; Moneylending ; Interest ; Borrowers ; Mortgages ; Wages ; Weights and Measures ; Prices ... ..	192-197
Chapter VI.—Trade.	
Roads ; Tolls ; Railways ; Passes ; Ferries ; Bridges ; Rest Houses ; Post and Telegraph Offices ; Trade Centres ; Fairs ; Shopkeepers ; Peddlers ; Carriers ; Imports ; Exports ...	198-206
CRAFTS :	
Gold and Silver ; Copper ; Iron ; Stone ; Lime ; Earth ; Glass ; Wood ; Leather ; Weaving ; Oil-pressing ; Paper ; Perfume ... ..	207-217

	PAGE
<b>Chapter VII.—History.</b>	
EARLY HINDUS (A.D. 100-1347) ... ..	218-223
MUSALMÁNS (1347-1700) ... ..	224-225
MARÁTHÁS (1700-1885)	
Shiváji II. (1700-1712); Sambháji II. (1712-1760);	
Shiváji III. (1760-1812) ... ..	226-236
Shambhu (1812-1821); Sháháji (1821-1837); Shiváji IV.	
(1837-1866); Rájárám II. (1866-1870); Shiváji V.	
(1870-1883); Sháhu the present Rája; Genealogical	
Table ... ..	237-246
<b>Chapter VIII.—The Land.</b>	
Staff (1844-1884); Village Officers; Tenures; Cesses;	
Revenue History ... ..	247-253
Survey; Survey Results; Season Reports ... ..	254-265
<b>Chapter IX.—Justice.</b>	
Civil and Criminal Justice before 1845; Changes (1848,	
1862, 1867, 1873, 1882); Civil Courts (1877-1883);	
Registration; Magistracy; Criminal Courts (1877-1883);	
Village Police; Criminal Tribes; Police; Offences; Jails.	266-277
<b>Chapter X.—Finance.</b>	
Land Revenue; Balance Sheet; Local Funds; Municipalities.	278-280
<b>Chapter XI.—Instruction.</b>	
Schools; Libraries; Newspapers ... ..	281-284
<b>Chapter XII.—Health.</b>	
Climate; Diseases; Epidemics; Hospitals and Dispensaries;	
Lunatic Asylum; Vaccination; Cattle Disease; Births and	
Deaths ... ..	285-289
<b>Chapter XIII.—Places</b> ... ..	290-323
<hr/>	
<b>Sángli:</b>	
Description; Production; People; Agriculture ... ..	324-334
Capital; Trade ... ..	335-342
History; The Land ... ..	343-353
Justice; Finance; Instruction; Health ... ..	354-358
Places ... ..	359-377
Miraj ... ..	378-383
Kurundvád ... ..	384-385
Jamkhandi ... ..	386-387
Mudhol ... ..	388-395
Rámdurg ... ..	396-399
<hr/>	
<b>Appendix A.—Thermometer Readings and Rainfall</b> ... ..	400-405
<b>Appendix B.—Trees and Healing Plants</b> ... ..	406-413
<b>Appendix C.—Marátha Surnames</b> ... ..	414
<b>Appendix D.—Spirit Possession</b> ... ..	415-421
<b>Appendix E.—Inscriptions at Panhála</b> ... ..	422-425
<b>Index</b> ... ..	427-436

---

KOLHÁPUR.

---

[illegible]

Month	Number of People
January	10
February	15
March	20
April	25
May	30
June	25
July	20
August	15
September	10
October	5
November	5
December	5

# KOLHÁPUR.

## CHAPTER I.

### DESCRIPTION.

THE State of Kolhápur<sup>1</sup> lies between 17° 10' 45" and 15° 50' 20" north latitude and 74° 44' 11" and 73° 43' 16" east longitude. Including the outlying districts of Ráybág and Katkol in the east and south-east, the state has an area of 2493 square miles and in 1881 had 800,000 people or 320 to the square mile and a yearly revenue of about £308,834 (Rs. 30,88,340).

For administrative purposes the territory of Kolhápur is distributed over ten sub-divisions with an average of 249 square miles, 108 villages, 80,000 people, and a revenue of £30,883 (Rs. 3,08,830). The following statement gives the details:

*Kolhápur Administrative Details, 1880-81.*

SUB-DIVISION.	VILLAGES.					Total.	AREA.	PEOPLE, 1881.	REVENUE.
	State.	Alienated.							
		Religious.	Service.	Smaller Chiefs.					
Karvir ... ..	91	10	21	13	135	251	130,533	40,092	
Panhála ... ..	170	12	14	8	204	432	100,504	34,835	
Alta ... ..	34	2	6	7	49	219	95,071	42,404	
Shirol (a) ... ..	35	6	9	13	63	323	95,651	42,049	
Gadinglaj (a) ...	55	1	54	66	176	473	119,138	40,472	
Bhudargad ... ..	145	11	22	15	193	263	83,840	28,083	
Vishálgad ... ..	46	6	14	...	66	122	31,004	12,604	
Bánda ... ..	47	1	20	1	69	136	30,356	7783	
Kágal ... ..	34	1	5	6	46	129	49,064	21,196	
Ichalkaranji (a)...	60	1	17	...	78	145	55,843	21,466	
Total ... ..	717	51	182	129	1079	2493	800,189	308,834	

The sub-divisions marked (a) have petty divisions, Shirol has Ráybág, Gadinglaj has Katkol, and Ichalkaranji has Ajra.

Of these ten sub-divisions four, Vishálgad in the north-west, Bánda in the west, Kágal in the centre, and Ichalkaranji in the south are subordinate states whose chiefs exercise independent jurisdiction.

Kolhápur is bounded on the north by the Várna river, which, for about sixty-six miles from Prachitgad to its meeting with the

Chapter I.  
Description.

SUB-DIVISIONS.

BOUNDARIES.

<sup>1</sup> The ancient name of Kolhápur appears to have been Karvir, and though to a great extent superseded by the more modern and better known name, Karvir survives. *Sarkár Karvir* is the name by which the Kolhápur State is known in the vernacular, and the *mámlatdár's* district, in which the capital is situated is the Karvir sub-division. The present name has given rise to the legend of Kola an *asur* or demon whom the goddess Mahálakshmi slew on a hill near the city. The most likely origin is *kolih* the Kánarese name for the lotus.



Chapter I.  
Description.

Krishna two miles south of Sāngli, separates Kolhápúr from the Válva sub-division of Sátára; on the east it is bounded by the rivers Krishna and Dudhganga, the Patvardhan states of Miraj and Sāngli, and the Chikodi sub-division of Belgaum; on the south by Belgaum; and on the west by the Sahyádris which separate it from Sávantvádi and Ratnágiri.

ASPECT.

Kolhápúr is an irregular belt of the Deccan plateau lying along the east of the Sahyádris crest, about sixty-five miles from north to south and eight to fifty miles from west to east. In the north a point of land, eight to twelve miles broad, runs about sixteen miles along the Sahyádris. It then spreads east till it has a breadth of about fifty miles, and again about sixteen miles to the south narrows to about thirty miles and keeps thirty to forty miles broad to within ten miles of the extreme south, where it runs to a point about sixteen miles east of the Sahyádris. Besides this main irregular belt, there are three isolated groups of villages, two to the east and one to the west. The western group lies within Ratnágiri limits, to the west of Bávda, which is about the middle of the Kolhápúr section of the Sahyádris. Of the two isolated blocks to the east Ráybág is a little to the north of east, about sixteen miles north and south by ten east and west, from eight to twenty miles distant from the east of Kolhápúr. About twenty miles south-east of Ráybág are Katkol and Torgal an irregular belt lying nearly north and south, about sixteen miles long and six to sixteen broad.

Outlying Belts.

The block of Kolhápúr below the Sahyádris includes the lands of forty-three villages and forms a belt about thirty miles from north to south and ten to fifteen broad. Except a few rugged villages at the foot of the Bávda pass, about twenty-four miles south-west of Kolhápúr, most of the Kolhápúr-Konkan is composed of level tablelands. These uplands were formerly thickly wooded with teak and other useful trees, but all the valuable timber has long been cut leaving bare or scrub-clad hill-sides. The village sites as a rule are well wooded and the village homesteads are surrounded by groves of mango, jack, and *undi* trees, and in Pomburle, Kokisre, Khambále, and Nánivde by cocoa and betel palms. The climate is healthy, though in April and May the heat is oppressive. The two outlying blocks in the east, Ráybág and Torgal, lie far within the limits of the Deccan plain. The country is tame and level with a few ranges of low hills, the whole very bare of trees except some clusters of mangoes and *bábhuls* near village sites and on the banks of streams. The rainfall is scanty, but the ground is fertile and yields good crops. The villages are flat-roofed and are surrounded with mud walls. Apart from these outlying blocks to the west and to the east, the main body of Kolhápúr, in the plateau immediately to the east of the Sahyádris crest, varies from thirty to fifty miles in breadth and from 2000 to 1800 feet above the sea. The line of the Poona-Belgaum road, which passes nearly north and south through Kolhápúr, Kágál, and Nipáni thirty to forty miles east of the Sahyádris crest, divides Kolhápúr into two unequal parts a rugged tract of hills and valleys to the west known as the Hill-top Konkan or *Konkan Ghát Mátha*, a wet and cool region, and a more open block to the north-east stretching

about thirty miles east from the western belt and from north to south varying in breadth from fifteen to twenty miles. This is known as the plain or *desh* and passes into the hot and dry region of the Central Deccan. The western or hilly belt consists of the Sahyádris range and a series of six valleys separated by lines of hills which run north-east and east. In the west among and close to the Sahyádris, the scenery is wild and picturesque. The hills are said to have been once thickly covered with trees, and though most of the timber has disappeared, there are still fine groves and stretches of hill-side closely covered with brushwood. The people of the hilly west are chiefly Dhangars, Bhandáris, and Mhárs. Their hamlets consist of a few thatched huts generally in thickly shaded sites, and their tillage is confined to the growth of rice and hill grains along the banks of streams. Beyond the immediate neighbourhood of the Sahyádris, the country, still within the wet and cool region, stretches east about thirty miles in the six main valleys of the Várna, Panchganga, Dudhganga, Vedganga, Hiranyakeshi, and Ghatprabha. These valleys are rolling plains several miles broad, their surface seamed by streams which drain into the bed of the central river. For twenty or thirty miles from the Sahyádris the valleys are flanked by ranges of hills which rise about 1000 feet with bare sides ending in broad level tablelands, or broken into cones and quaint peaks many of them fortified. The people, though generally poor, are hardworking and skilful husbandmen, chiefly Kunbis and Maráthás. Their villages are small, often close together on the banks of streams, and near springs on the lower hill slopes. They are generally open without walls or towers and surrounded by groves of tamarind mango and jack trees. Near the village and on the banks of streams where they can be watered by lifts, are patches of rich sugarcane and other garden crops. Beyond the patches of garden land stretch grain fields many of them yielding excellent crops, and towards the edges the valleys gradually pass into poor soils growing only the coarser grains. Besides the trees which shade the village sites, most villages have their clumps or groves of mangoes tamarinds or *pipals*, and the lands of the different villages are generally separated by a strip of wood or bushland. The hill-sides are bare but in many places are built in a succession of small terraces carefully tilled and yielding good crops especially of rice. Over the whole belt the rainfall is certain and sufficient the supply varying from as much as 250 inches in some of the highest most exposed bluffs of the Sahyádris to fifty or sixty inches towards the east of the belt. There are no large water works, but except in March April and May there is no want of water.

The plain or *desh* section of Kolhápúr, which passes into the hot and dry region of the Central Deccan, stretches east from the line of the Poona-Belgaum road between the Várna on the north and the Dudhganga on the south, a block of land about thirty miles from east to west and ten to twenty miles from north to south. It includes the mouths of the valleys of the Várna, the Panchganga, the Dudhganga and the Vedganga, and beyond the mouths of the valleys part of the broad Deccan plain broken by low ridges of hills and single

## Chapter I.

## Description.

## ASPECT.

*Hill-top Konkan.**The Plain.*

Chapter I.  
Description.

ASPECT.  
*The Plain.*

peaks. In the west of this plain or open country the banks of the chief rivers are fringed with *bábhul* trees and the valleys are dotted with rich village groves and lines of shady lanes and patches of watered garden lands. Further to the east, though it yields rich crops of millet and wheat and has garden lands with sugarcane and tobacco, the plain is bare of trees except a few mangoes and *bábhuls*, and is broken by low lines of hills some lying east and west and others lying north and south. The whole south of Kolhápúr lies within the wet and cool region to the west of the Poona-Belgaum road. Just beyond the road to the east the country passes into the dry and hot Deccan region. The rainfall suddenly dwindles, the plants change, and flat-roofed villages take the place of cottages with tiles and deep eaves. In the eastern block of Kolhápúr the rainfall is lighter and less certain; the air though healthy is hotter; and the people though less hardworking are better off than in the west. Where water is near the surface much land is watered from wells, and a large area is under sugarcane, turmeric, chillies, and other profitable crops. The villages of flat-roofed and tiled houses are built on bare rising ground generally some distance from rivers to be free from the risk of floods. They were formerly guarded by walls, which, as they are no longer needed, have been allowed to fall into decay.

HILLS.

Its hills are the chief natural feature of Kolhápúr. They include the main range of the Sahyádris running north and south for about a hundred miles, and six large spurs which stretch north-east and east thirty to fifty miles from the Sahyádris, and divide the Kolhápúr plateau into six main valleys. In the eastern plain are two minor outlying groups the Ráybág and the Katkol hills. The Sahyádris run in an irregular line about 100 miles from north to south. Except at Bávda near the middle of the line, where part of the State runs west into the Konkan, the line of the Sahyádris follows the western border of Kolhápúr. Within Kolhápúr limits the crest of the Sahyádris varies from 2000 to 3500 and averages about 2500 feet above the sea. The Sahyádris are full of wild and beautiful scenery, the lower slopes and the hollows thickly wooded, and the upper slopes rising in terraces separated by great scarps of rock to bluff even-topped headlands, relieved by an occasional cone-shaped peak or pinnacle. With a little aid from art many of these hill-tops have been turned into almost impregnable fortresses. Within Kolhápúr limits, in or close to the crest of the Sahyádris, are nine of these fortified hill-tops. In the extreme north beyond the Sátára border is Prachitgad. About two miles south of Prachitgad on the Kolhápúr border is Bahirgad. About eight miles south in a direct line is Mahimatgad. About twelve miles further south in a straight line, but a good deal more following the crest of the hill, is Vádi Máchál fort 3348 feet above the sea and about ten miles west of the Kolhápúr town of Malkápur. A little to the south of Vádi Máchál is the famous fort of Vishálgad or Khelna, about 3350 feet above the sea, strongly fortified with walls part of which are said to date back to A.D. 1000. It is about ten miles west of Malkápur and about forty-five miles north-west of Kolhápúr. The next fort of consequence is Bávda about thirty miles

Chapter I.  
Description.  
HILLS.

south of Vishálgad in a direct line, and about the middle of the Kolhápúr section of the Sahyádris. The hill rises out of the Konkan with sheer lofty scarps. About ten miles further south, close to the north of the Phonda pass, is Shivgad 3240 feet above the sea. About fifteen miles more is Bhairavgad and about twelve miles more, on a point that stretches far to the west, is Ránga or Prasadhagad a favourite fort of Shiváji's. Beyond Ránga point the main crest passes east for about ten miles where are the two notable hills of Manohar and Mansantosh within Sávantvádi limits. In the extreme south of the State, the southern shoulder of the Párpoli pass rises to a height of 2778 feet. Within the 100 miles of their Kolhápúr course the Sahyádris are crossed by ninety-four passes of which three the AMBA pass in the north, the PHONDA pass about the middle, and the AMBOLI pass in the south are furnished by roads fit for carts and carriages. Of the remaining passes fourteen are fairly easy and are fit for laden cattle, and the rest are little better than rough foot-paths. Beginning from the north on the Sátára border is the South TIVRA pass, which, with Prachitgad fort to the right, leads about nine miles down a steep tract, especially in the last two miles, to the Ratnágiri village of Tivra about eleven miles east of Sangameshvar town in Ratnágiri. About five and a half miles south of the Tivra pass is the KUNDI pass, a difficult road, from Cháandel on the top four and a half miles to Kundi at the bottom, which is eight and a half miles north-east of the Ratnágiri town of Devrukh. About eleven miles south of the Kundi pass is the AMBA pass one of the main lines between Kolhápúr and the sea. The head of the pass is about thirty-five miles north-west of Kolhápúr and the foot is about the same distance east of Ratnágiri. A road fit for carts and carriages was made between 1871 and 1883, for which £10,520 (Rs. 1,05,200) were contributed by the Kolhápúr state. About five miles to the south of the Amba pass, on each side of the narrow neck of land which joins Vishálgad fort to the crest of the Sahyádris, are two small foot tracks, DEVDA on the north and PRABHÁNVALLI on the south. Nine miles south of the Vishálgad passes is the ANASKURA pass about thirty miles north-west of Kolhápúr, and separated from it by a difficult hilly country. About twenty miles south-west of the Anaskura pass is the old Ratnágiri port of Rájápur. In 1826 the pass was described as about three miles long, a good road paved with large stones in a few places where it was rather steep. About the centre of the pass was a toll-house for collecting dues. The approach on the Konkan side was very bad but with a little labour it might be made practicable for guns.<sup>1</sup> About five miles south of the Anaskura pass is the KÁJRDA pass, about twenty-five miles west of Kolhápúr, from which it is the straightest route to Rájápur in Ratnágiri. In 1826 the road was passable for cattle, but was closed that tolls might be taken in other passes. About ten miles south is the Bávda pass a road for walkers and possible to laden cattle. It is now the chief route from Kolhápúr to Rájápur. About eight miles south, close to the Sivgad fort, is the SIVGAD pass a route from Kolhápúr

<sup>1</sup> Clunes' Itinerary, 149.

Chapter I.  
Description.  
HILLS.

to Málvan. Guns were formerly brought up this pass, but in 1826 it was out of repair. About two miles further is the PHONDA pass, the chief opening between the Deccan and the Ratnágiri port of Málvan. About 1820 a detachment with artillery went down the Phonda pass to Vádi. The road was made practicable for ordnance, but in 1826 was seldom used though a little labour would put it in good repair.<sup>1</sup> About ten miles south of the Phonda pass, close to the south of Bahiravgad fort, is NARDAVA, a small bullock pass. About five miles further is the GHOTGE pass, described in 1826 as used by laden cattle, a good road except some bad places at the top passing from Kolhápúr to Málvan. About four miles to the south-west, in the point which is guarded by Ránga fort, is the RÁNGNA pass. It was described in 1826 as frequented by laden cattle from Kolhápúr to Málvan. The road passed through a gateway along a ridge which on the left fell right down to the Konkan. About two miles east of the Ránga pass is the HANMANT pass. In 1826 it was a cattle road but very bad. About fifteen miles to the south-east is the AMBOLI or PÁRPOLI pass formerly the main line between Goa and the Deccan. In 1818 Colonel Dowse's force marched through the Amboli pass to invest Redi about ten miles south of Vengurla. The Pioneers of the force in three days made it passable for small guns. In 1826 it was described as about  $5\frac{1}{2}$  miles from Amboli at the top to Párpoli at the foot, a strong descent in no part very steep, but in consequence of zigzags very difficult for heavy ordnance. About 1871 a road fit for carts and carriages was made. In the extreme south of the state about eight miles south of the Amboli pass and one mile north of the Rám pass is the TÁLKHAT pass. Close beyond the southern boundary is the RÁM pass, the great highway between Belgaum and Vengurla, and formerly one of the main openings between Goa and the inland parts. A road thirty feet wide was finished in March 1821, and in 1826 the ascent was easy and passable for every description of wheel carriages. Since 1826 the road has been more than once improved and is now one of the easiest routes across the Sahyádris.

<sup>1</sup> From the confused mass of hills to the east of the Sahyádris six great ranges stretch east and north-east thirty to fifty miles across the Kolhápúr plateau. Their bare sides rise 700 to 1000 feet above the plain to flat tops, often with broad tablelands, broken at intervals by peaks and conical knobs, crowned sometimes by forts sometimes by shrines. Of the six ranges the only one that stretches east nearly at right angles to the main crest of the Sahyádris, is the Vishálgad-Panhála range in the north. It leaves the Sahyádris at the great Vishálgad fort (3348 feet) near Malkápur, about forty miles north-west of Kolhápúr. From Vishálgad it stretches south-east about twenty-five miles, separating the valley of the Várna in the north from the Panchganga valley on the south, where it is crowned by the two fortified peaks of Panhála and Pávangad about 1000 feet above the plain and about fifteen miles north of Kolhápúr. From Pávangad it stretches east about

## Chapter I.

## Description.

## HILLS.

twenty-five miles more till it breaks into separate hillocks and sinks into the plain near the Krishna. In an offshoot from this range, about three miles east of Pávangad and about 1000 feet above the plain, is a hill crowned with a temple of Jotiba, and on peaks a few miles further east are temples of Sidhoba, Dhuloba, Alamprabhu, and Rámling. Beyond Rámling, about fifty miles from the Sahyádris, the range gradually sinks into the plain near the Krishna. To the west of Kolhápur the country is very rugged, full of short irregular ranges and spurs, stretching about north-east from the Sahyádris, separated by a number of small streams which drain into the Panchganga. The second main spur, which may be styled the Phonda-Savgaon range, leaves the Sahyádris to the south of the Phonda pass about forty miles south-west of Kolhápur. From this it runs north-east to about five miles south of Kolhápur. It then stretches east, forming the water-parting between the Panchganga on the north and the Dudhganga on the south, and after about twenty miles more, or a total length of about fifty miles, falls into the plain. The third of the leading spurs, the Khánápur-Mudhol range, is the water-parting between the Dudhganga and its feeder the Vedganga. It leaves the Sahyádris near the Nardava pass about ten miles south of Phonda, and after stretching north-east for about thirty miles falls into the plain about eight miles south of Kágál. The fourth of the leading spurs, the Bhudargad-Nipáni range or the north Ghatprabha spur, is the largest of the six. It divides the drainage of the district into two systems, a northern which drains east and north-east, and a southern which drains east and south-east. This range of hills leaves the Sahyádris near the two important forts of Manohar and Mansantosh about ten miles north of the Amboli pass. From this it runs north-east, a well-marked line of hills, about thirty miles, to within five miles of Nipáni, where it passes out of Kolhápur and runs about twenty miles south-east across the Chikodi sub-division of Belgaum. Beyond Chikodi it runs east about fifty miles and then south twenty-five miles till it is cut off by the valley of the Ghatprabha close to where that river joins the Krishna.<sup>1</sup> This range is the water-parting between the Vedganga which flows north-east into the Dudhganga and the Hiranyakeshi which flows east into the Ghatprabha. About twenty miles south-west of Nipáni on a spur that runs west from the main range is the important fortified hill of Bhudargad, which has old shrines to Kedárling, Bahirav, and Jakhrubái, and fortifications which were repaired by Shiváji in 1677. The fifth spur, which may be called the Sámángad range, is the water-parting between the Hiranyakeshi and the Ghatprabha. It leaves the Sahyádris from the high ground (2778 feet) to the south of the Amboli pass, and runs north-east a well-marked line of hills about thirty miles to Sámángad a small hill fort, but whose great artificially scarped sides make it one of the strongest places in Kolhápur. In the extreme south the north Malprabha-Gandharvagad range, starting from the hills to the north of the Talkhat pass, runs into Belgaum where it has the fort of Chandgad,



Chapter I.  
Description.

HILLS.

and again entering Kolhápúr a little to the east, rises in the great hill of Gandharvagad. It is then cut by the valley of the Tāmraparni but rises again, and, stretching across Belgaum, forms the water-parting between the Ghatprabha and the Malprabha passing east as far as the Amingad hill in Hungund in the south-east of Bijápúr, about 130 miles from the Sahyádris.<sup>1</sup> Besides these ranges several isolated hills rise 150 to 300 feet from the plain. Two, Vágjái and Tungjái in Panhála, are 700 feet high and two, Sálván in Bávida and Mahádev in Ichalkaranji, rise 800 feet above the plain.

RIVERS.

Krishna.

Except the group of villages in the Konkan which slope west towards the sea, the drainage of Kolhápúr is eastwards into the Krishna. The Krishna forms the north-eastern boundary of Kolhápúr for about twenty-five miles. It first touches the state close below Sánгли, where it receives from the right the waters of the Várna, which forms the northern boundary of Kolhápúr. From Sánгли the Krishna flows, with a winding south-easterly course, about twenty miles to Kurundvád, where it receives the Panchganga from the right. About nine miles further to the south-east, part of which passes through Belgaum villages, it receives the united waters of the Dudhganga and the Vedganga. Below this it passes about three miles south-east through Belgaum, and then turning east, for about ten miles, forms the north boundary of the isolated Kolhápúr division of Ráybág. During the thirty-five miles with which it is connected with Kolhápúr the Krishna is a noble river, about 1300 feet broad, in a shallow bed between banks of earth. With the exception of a fall of a few yards it flows unbroken from Kurundvád, where it is joined by the Panchganga, for a hundred miles towards Haidarabad. During the hot weather it passes, with a very leisurely flow, through a succession of deep pools and shallow fords. Even then experiments have shown that there would be little difficulty in navigating it with flat-bottomed boats, rigged with mast and sail and drawing twelve inches of water. Along the river banks shrubs called *shevri* are planted and in floods break the force of the water and allow the silt to gather on the ground. These deposits yield rich cold weather crops. Within Kolhápúr limits the Krishna is crossed by one bridge at Udgaon and by five ferries. Though so large and important a river the Krishna is not strictly a Kolhápúr stream. The characteristic rivers of Kolhápúr are six in number the Várna, Panchganga, Dudhganga, Vedganga, Hiranyakeshi, and Ghatprabha. These rivers rise in the Sahyádris and flow south-east, east, or north-east fifty to sixty miles across the Kolhápúr plateau towards the Krishna. In addition to these streams the outlying district of Torgal in the extreme south-east is crossed by the Malprabha. The leading Kolhápúr streams have generally deep banks of an average height of about forty feet, and soft beds varying in breadth from 200 to 600 feet.<sup>2</sup> During the first thirty miles of their course, before they pass out of the mountainous country, the Kolhápúr rivers are fed by numerous

<sup>1</sup> Mem. Geol. Surv. of India, XII. 5.

<sup>2</sup> Major Graham (Kolhápúr, 82) gives Várna 222, Panchganga 577, Vedganga 192.

streams. Further east in the plain country they receive few additions. Though, especially in the west, their courses are winding, there are no falls and few rapids, and in former times every year between October and January, rafts of many hundreds of beams used to be floated down forty to 100 miles. During the rains the masses of water that are poured down the western hills, the deep and winding channels of the streams, and the very slight fall towards the Krishna combine to cause backwaters which sometimes stretch as far as thirty miles, and overflowing large areas of land cause serious loss to the river-bank villages. The high Bhudargad-Nipáni spur that runs north-east across the southern parts of Kolhápúr marks the division between four streams the Várna, Panchganga, Dudhganga, and Vedganga which pass east and north-east into the Krishna within Kolhápúr limits; and two streams the Hiranyakeshi and Ghatprabha which drain east and south-east and do not fall into the Krishna for more than a hundred miles beyond the eastern border of Kolhápúr.

The Várna which takes its rise in the Sahyádris, about thirteen miles north of Kolhápúr limits, forms the northern boundary of Kolhápúr for about eighty miles. It flows with a fairly straight south-east course along the northern borders of Malkápur, Panhála, Alta, and Shirol and falls into the Krishna at Haripur about one mile south-west of Sângli. At its meeting with the Krishna it has a breadth of about 220 feet. The sloping banks of the Várna yield good cold-weather crops. Its chief feeders in Malkápur and Panhála are the Kánasa, which, after a twelve-mile course from the village of Udgiri in Malkápur, meets the Várna near Málevádi in Panhála. About twelve miles further east it is joined by the Kadvi which rises in a hill near Amba and, after a winding course of about thirty miles, falls into the Várna near Thergaon in Panhála. The Kadvi is bridged near Malkápur on the new road to the Amba pass. During its course it is joined by five smaller streams, near Karungale by the Potphugi from near the Chándel pass; at Malkápur three miles lower by the Sháli after a twelve-mile course from near Gajápur; at Molavde about four miles lower by the Ambardi from near the village of Ambardi; at Charan about six miles lower by the Ambira after a seven-mile course from the foot of the Pishvi hills; and at Sátve about eight miles lower by the Kándra after a north-west course of about nine miles from Borivde in Panhála. In the fair season the Várna and its chief feeder the Kadvi are fordable but during the rains boats ply at five places on the Várna and at three on the Kadvi.

The Panchganga is formed from north to south of four streams, the Kásári, the Kumbhi, the Tulsi, and the Bhogávati. The fifth stream is the underground Sarasvati. The Kásári is an important stream. It rises in the Sahyádris near the village of Gajápur in Malkápur and flows east for about fifty miles till it joins the united waters of the Kumbhi and the Tulsi at Pádali about three miles west of Kolhápúr. During its course of fifty miles the Kásári receives several minor streams of which the chief are the Mangar, the Jámbhli, and the Gádavli. The Kumbhi rises near Bávda, flows about fifteen miles north-east, and then, with a winding course,

## Chapter I. Description.

### RIVERS.

#### *Várna.*

#### *Panchganga.*



**Chapter I.**  
**Description.**

**RIVERS.**  
*Panchganga.*

turns east and joins the united Tulsi and Bhogávati near Bahireshvar about eight miles south-west of Kolhápúr. The Tulsi rises about five miles east of the Kumbhi and after a north-easterly course of about fifteen miles falls into the Bhogávati about eight miles south-west of Kolhápúr. The Bhogávati, which is the chief of the four streams, takes its rise in the Sahyádris a few miles south of the Phonda pass, and after a nearly northerly course of about twenty-eight miles, almost parallel to the Phonda road, joins the Tulsi river near the historical village of Bid or Berad. About two miles north-west of Bid the Bhogávati receives the Kumbhi and about eight miles further north they are joined from the left by the Kásári about three miles west of Kolhápúr. From Kolhápúr the Panchganga, as the river is now called, winds east about thirty miles till it falls into the Krishna at Kurundvád. In the thirty miles of its course, to the east of Kolhápúr the Panchganga receives only one considerable stream the Hátkalangda or Kabnur which, rising from the Alta hills and passing Hátkalangda and Korochoi joins the Panchganga near Kabnur about fifteen miles below Kolhápúr. The waters of all these streams which join to form the Panchganga are much used for growing sugarcane. In October, towards the close of the south-west rains, a series of fair-weather earthen dams are built across the river beds and the water is raised by lifts worked by bullocks. The meeting of the Bhogávati and Kásári has much local sanctity, being like Allahabad known as Prayág or Triveni, and being visited by large numbers of pilgrims during the cold months. Two small streams, the Jayanti or Jiti and the Gomati, join this river near Kolhápúr. They do not flow all the year round, but they are held sacred and are mentioned in the local holy books. The Jiti is crossed near Kolhápúr by three costly and ornamental bridges. The valley of the Panchganga is reckoned the most fertile in Kolhápúr and is famous for its hay. The bed of the river is shallow and its sloping banks yield rich crops during the cold weather. At Kolhápúr the Panchganga is crossed by two beautiful bridges one near the Brahmapuri hill on the north side of Kolhápúr town on the road leading to the Amba pass, and the other a few miles to the east on the Poona road. The Panchgnaga and its feeders are fordable in the hot season. In the rainy season large and small boats ply at twenty-three fords.

*Dudhganga.*

The Dudhganga has its source in the Sahyádris near the Nardava pass in the Bhudargad sub-division about thirty-five miles south-west of Kolhápúr. After a course of about twenty miles to the north-east near Kágál, where it is bridged, it flows east for about six miles, and about a mile before it receives the Vedganga from the south, it enters Belgaum and flows east about fifteen miles till it falls into the Krishna near Kallol. The river bed is shallow and muddy and in the fair weather crops are grown on its earthen banks. In Bhudargad its waters are used for watering sugarcane. Except in the rainy season, the river is at all times fordable. In the rainy season it is crossed by ferry-boats at ten places. Of these two, at Saravde and Chuve in Bhudargad, are first class ferries. The other boats are small managed by one or two ferrymen and carrying not more than ten passengers.

The Vedganga rises a few miles north of Ránga, and after a course of about thirty-eight miles to the north-east joins the Dudhganga in the Chikodi sub-division of Belgaum. Its chief feeder is the Chikotra, which flows through the Kápsi valley and joins it near Chikhli about four miles to the south of its meeting with the Dudhganga. The bed of the Vedganga is shallow and muddy. In Kágál its banks yield rich crops during the cold season and in Bhudargad a large area is watered. The river is bridged near Yamgarni on the Poona-Belgaum road. It is fordable except during the rains, when it is crossed by ferries in nine places Gárgoti, Shengaon, Madilge, Mhamdápur, Nidori, Anur, Chikhli, Bange, and Dánvād.

The Hiranyakeshi takes its rise in the Amboli pass in the extreme south-west of the State. It has an irregular north-east course of about forty miles to near Sankeshvar, where it enters Belgaum, and after a south-easterly course of about fifteen miles joins the Ghatprabha about five miles south-east of Hukeri. Its bed is shallow and its banks yield good crops though not so rich as those grown on the Panchganga. Its chief tributary is the Chitri which takes its rise near the village of Aundi in the Ajra petty division, and after a northerly course of about ten miles joins the main stream near the town of Ajra. Two first class ferries cross these streams one at Ajra on the Hiranyakeshi on the Amboli road, the other across the Chitri on the Nesri road. First class ferry-boats are also kept at Hitni, Harli, Bhadgaon, and Jarli on the Hiranyakeshi, carrying fifty to seventy passengers and one and a half tons of luggage. Small boats, carrying five or six men, are kept at Sálgaon, Ingli, Hiralge, and Kaulge.

The Ghatprabha takes its rise in the south slopes of the Párpoli pass in the extreme south of the State. It flows about twenty-five miles north-east through the south of Kolhápúr territory and about twenty miles further to the north-east, and joins the Hiranyakeshi about five miles south-east of Hukeri. From Hukeri it passes about ninety miles east through Gokák, Mudhol, and Bágalkot till it falls into the Krishna at Chimalgi about fifteen miles north-east of Bágalkot. During the twenty-five miles of its course through Kolhápúr its banks and bed are rocky. During the rainy season a small boat carrying eight passengers is kept at Nesri in Gadinglaj.

The Malprabha runs through the outlying district of Torgal far to the south-east. Its bed is rocky and its banks steep. Among Hindus the Malprabha in sanctity ranks next to the Krishna. No boat is kept on the river. When in flood it is crossed on rafts buoyed by dry gourds.

Kolhápúr on the whole is well supplied with water. Besides the six chief rivers and their numerous feeders, spring water is available in most parts twenty to fifty feet below the surface. In Karvir, Ráybág, and Alta, which have about 5000 or half of the whole number of wells and have a large area of watered crops, especially of sugarcane, there is abundance of water at twenty to thirty feet and in some of the Ráybág villages at ten feet below the surface. In Vishálgad, Panhála, Bhudargad, and Ajra in the west close to the Sahyádris wells are few as they have to be sunk

Chapter I.  
Description.  
RIVERS.  
*Vedganga.*

*Hiranyakeshi.*

*Ghatprabha.*

*Malprabha.*

WELLS.

Chapter I.  
Description.  
WELLS.

at least fifty feet. Compared with 11,098 wells shown in the 1850 returns the 1881 village returns give a total of 10,344. The fall of 754 in the number of wells is said to be due to the fact that the holes or *budkis* dug in the beds of rivers, of which there are now about 4000, were included in the 1850 returns. Of the 10,344 wells in 1881, 7547 were in repair and 2797 were out of repair. About 2500 are masonry built and the rest are either unbuilt or faced with dry rubble. Over 6000 wells or considerably more than one-half are used for watering and the rest for drinking. A well costs to sink from £10 (Rs.100) where the water is near the surface and the soil is soft to £50 (Rs. 500) where the soil is hard and the well has to be sunk thirty-five feet or more. A masonry lined well according to the soil costs £100 to £300 (Rs.1000 - 3000) to build. Except by a few Persian wheels water is drawn by the *mot* or leather bag, of which one and sometimes two are worked at a time. The leather bag holds about sixty gallons, four-fifths of which find their way into the water channel. In the cold weather, about one-fourth of an acre is watered by one bag working eight hours a day; in the hot season, when the springs are lower not more than one-eighth of an acre can be watered. A well with water enough to work a bag all the year round is held to be able to water two acres of garden land. In years of average rainfall the wells can be trusted to yield enough to bring the sugarcane crops safe through the hot weather. But in a year of special light fall as in 1881-82 with 32.16 inches, the springs fail and great loss is suffered. In spite of this risk a strong desire is shown to sink new wells and the number of working wells increases every year.

PONDS.

The only complete protection from the risk of the failure of its springs is in storing water in lakes and reservoirs. The numerous streams offer many sites suitable for dams, but no work of this kind has yet been carried out. Compared with 197 in 1850 the 1881 returns show a total of 112 village ponds. The fall of eighty-five in the number of ponds is said to be due to the fact that a number of damp hollows, which were entered as ponds in the 1850 returns have since 1850 been turned into rice fields. Of the 112 ponds in 1881, only four the Rankále and the Padmále ponds in Kolhápúr and the Atigre and Ráybág ponds, have an area of more than twenty-five acres. Among these the only piece of water of considerable size is the Rankále lake in Kolhápúr town. Its circumference is about two miles and a half and its mean depth thirty-five feet. It has lately been improved at a cost of £26,000 (Rs. 2,60,000) and supplies drinking water to part of Kolhápúr, besides watering a hundred acres of garden land. At Kolhápúr, besides the Rankále lake the Padmále pond is of considerable size covering about fifty and watering about thirty-five acres. It is mentioned in the local history or *mahátmya* and is held sacred. The Atigre pond, the only other pond of any size, on the Miraj road about twelve miles north-east of Kolhápúr covers fifty acres but is shallow and dries during the hot weather. It is mentioned in the local history and is held sacred. During the cold season it has generally some water-fowl. About a mile south-east of Ráybág in the Shirol sub-division the Ábu pond covers about twenty-five acres and holds water all the year round. During the cold season it is a resort

of water-fowl. Of the remaining ponds 62 are less than one acre in area, forty-four are under ten acres, and two are under twenty-five. Most of them dry in the hot season. In ordinary seasons the supply of drinking water is sufficient. About 700 of the 1079 villages stand close to rivers and streams which flow throughout the year. In the remaining 379 villages the streams and ponds dry in the hot months (April-June) and the people take their water from wells and pits dug in the stream beds. Kolhápur and Kágál are supplied with drinking water brought from outside of the towns in iron pipes. At Ichalkaranji the water is pumped from the Panchganga river and is carried into the town along masonry ducts.

Except in the south where are some ridges of sandstone and quartzite, Kolhápur comes within the area of the great Deccan trap fields. The chief varieties of trap are basalt, amygdaloid trap, vesicular trap, and clayey trap, which, with some few intertrappean sedimentary beds and numerous highly ferruginous clayey beds, make up the great mass of the trap-flows. The lower flows are mostly basaltic in character, the medium flows are alternately basaltic and amygdaloid, and the upper are chiefly basaltic capped by beds of clay and laterite. In the Sahyádrí region the position of the flows is more distinct than further east. When carefully studied from some commanding point they are seen to dip at a very low angle generally to the north-east.<sup>1</sup> About twenty-five or thirty miles from the edge of the Sahyádris the dip becomes more easterly and so gradual as to be hardly traceable by the eye. The flows exposed in the Konkan show a very low westerly dip. The direction of the course of the upper waters of the rivers rising in the Sahyádrí region and falling into the Krishna coincides with the general dip of the trap-flows. It is probable, therefore, that the subaërial cutting of these valleys began immediately after the final outpouring of the last trap-flow, and has been ever since going steadily on. Till the whole of the Deccan trap area has been geologically examined, it will not be possible to say which was the last flow, but if the youngest of those now remaining in the Kolhápur and Belgaum Sahyádris was the last poured out, and represents the close of this tremendous volcanic activity, then the work done by atmospheric agencies since the close may be roughly estimated as a direct vertical erosion of 1000 to 1500 feet the latter depth being that of the valley of the Vedganga in South Kolhápur opposite the great mass of Bhudargad, one of the eminences capped by the highest of the remaining trap-flows. At present the most prevalent direction of the wind during the south-west monsoon, as shown by the inclination of the trees on the highest and most exposed ridges, does not coincide exactly with the dip of the trap-flows and strike of the main valley, but is more westerly by one or two points of the compass. The

## Chapter I.

## Description.

## PONDS.

## GEOLOGY.

<sup>1</sup> The dip is too slight to be measured with a clinometer, but a calculation of the difference in the height of some of the chief trigonometrical stations which are capped by outliers of one and the same bed shows the north-easterly slope to range from nine to twenty-three feet a mile, giving a mean of sixteen feet a mile. Mem. Geol. Surv. XII. 173.

Chapter I.  
Description.  
GEOLOGY.

greatest thickness of the trap within the South Kolhápúr area may roughly be estimated at 2000 to 2500 feet; it increases to the north. Further south the trap grows thinner for the beds forming the southern boundary of the area near the crest of the Sahyádris are high in the series and overlap by a wide space many of the underlying flows seen further north in the scarp overhanging the Konkan.

The grandest sections of the trap series are in the great western scarp of the Sahyádris; but their vast size often makes these hard to study, as some of the great basaltic flows form long unbroken lines of cliff several hundred feet high. They may be best examined along the two roads, one across the Phonda and the other across the Amboli pass. The cuttings along these roads give almost perfectly continuous sections of the whole thickness of the trap-flows they cross. The iron-clay bed, an outlier of the laterite is important as being the youngest known, the most constant, and the most safely determinable member of the Deccan trap series in this quarter. This iron-clay bed caps all the highest ridges and peaks in the Kolhápúr hills and may be called the summit bed. Of all the mountains those which iron-clay caps are the most perfectly table-topped and in most cases the capping is sharply scarped all round the edge. As these scarped plateaus crown all the highest hills and were easily made very strong, many of them, notably Bhudargad and Sámángad, were chosen by local chiefs as strongholds. The flows underlying this iron-clay bed show great likeness throughout the larger area they cover. The correspondence of flows in different great spurs is especially clear in the three ridges into which the Bhudargad spur divides. It is admirably seen looking west from the high bluff on the eastern ridge which towers over Belvádi. The view northward from Bolávi at the northern end of the lofty part of the western ridge on which Bhudargad itself stands, shows this correspondence and extensions of the flow-terraces most distinctly in all the ridges on either side of the Vedganga valley and in others beyond as far north as the Panhála mountain.<sup>1</sup>

Quartzites and sand stones are found at Vátangi covered on three sides by the flows of the Deccan trap series. If the ridge of trap which covers the quartzites west and north of Vátangi be crossed the quartzites will be found to reappear in the valley of the Hiranyakeshi river, and to occupy a very considerable area in that valley forming an inlier which may be called the Mángaon inlier, from the most important village which stands upon it. No peculiar features are presented by the rocks forming this inlier. They consist of quartzites and grits, mostly dipping northward, or north-by-west, at low angles. They are best shown in the row of hills which runs east-south-east from Súlgaon on the bank of the Hiranyakeshi river. The quartzites and grits are mostly pale coloured and fine grained, and form a series of beds several hundred feet thick, although both the top and the

<sup>1</sup> Mem. Geol. Surv. XII. 182.

bottom of the series are hidden under trap. Petrologically identical with the Mángaon beds are beds forming several smaller inliers in the valley of the Vedganga, eight miles to the north-west. These latter lie in the centre of the valley between Ainghol and Shenggaon, and are four in number, of which the southmost, close to the village of Ainghol, forms a small but conspicuous isolated hill 200 to 300 feet above the plain. Here all the beds dip  $5^{\circ}$  to  $10^{\circ}$  north-north-west. The other inliers are simply exposures on the flanks of the great ridges. A great thickness of quartzites and grits of identical character is exposed in a small inlier at Phay in a side valley two miles west-north-west of Shenggaon. In the valley of the Dudhganga two good-sized quartzite inliers lie north-west of the Phay and Shenggaon inliers of which both on petrological and stratigraphical grounds they must be considered the extensions, nor can it be reasonably doubted that they form a true link with the very similar series of rocks exposed at the foot of the Phonda pass nine miles to the west-north-west. As in the Mángaon and Shenggaon inliers, the quartzites and grits of the Váki and Aini inliers are pale coloured, whitish, drab, or pinkish, and fine grained. They have been little disturbed, rolling in angles of  $8^{\circ}$  to  $10^{\circ}$  in various directions. In both inliers the western edge passes under the trap with a westerly dip of  $8^{\circ}$  to  $10^{\circ}$ . The quartzites do not show in the valley of the Bhogávati between Valivde and the top of the Phonda pass. In the Aini inlier, the beds, which are nearly horizontal, cannot be less than 400 to 500 feet thick, measured from the level of the river. Both here and in the Váki and to a less extent in the Phay inlier, the light coloured rocks have been so blackened by weathering, and perhaps by forest fires, that except on close inspection it is often difficult to recognize detached masses.<sup>1</sup>

The climate of the Kolhápúr plain which varies from about 2000 feet above the sea in the west to about 1700 in the east, like the rest of the western Deccan is temperate. Towards the Sahyádrí hills, which are covered with wood and drenched during the rainy months, the air is always cooler than in the east, which during April May and June is liable to hot easterly winds. At the same time almost the whole territory is under the influence of a sea breeze, which sets in during the afternoon and lasts till about eight at night.

The seasons may be broadly divided into wet, cold, and hot. The wet season, with an average fall of about forty inches, lasts from June to October. Except in the extreme west it is chiefly showery, seldom with such heavy continuous rain as to put a stop to field work. The rainy months are the healthiest time in the year. The strong damp breeze is always cool and pleasant and occasionally is cold. The daily changes of heat and cold vary from  $67^{\circ}$  to  $88^{\circ}$ . The cold season, which lasts from November to the end of February, is the most dry and unhealthy part of the year. Dry east winds, with no bracing or tonic influence, prevail and daily changes of heat and cold are considerable averaging about  $83^{\circ}$ . The hot weather

## Chapter I.

## Description.

## GEOLOGY.

## CLIMATE.

<sup>1</sup> Mem. Geol. Surv. XII. 92-94.



**Chapter I.**  
**Description.**  
**CLIMATE.**

lasts from March to June. The temperature is high during these months. In the daytime the air is hot at times rising to  $97.8^{\circ}$  and averages about  $91.3^{\circ}$ . The evenings are cooled by a sea breeze and the nights are never oppressive. Its situation opposite a gap in the line of western hills gives Kolhápúr city the benefit of a strong sea breeze and cool nights.

Meteors, igneous and luminous, are of frequent occurrence. Violent storms of thunder lightning and wind are unusually prevalent, not only at the beginning of the south-west monsoon but occasionally at other periods. These storms appear to travel round the horizon often beginning and disappearing at the same point and not unfrequently making the circuit twice. Though at times disastrous, the storms are generally beneficial to health. During April and May when the hot winds prevail, numerous hill forts, rising about 3000 feet above the sea, give a pleasant retreat. Of these hill forts Panhála, twelve miles north-west of Kolhápúr, with good water and cool bracing air has been set apart as a health resort.

**RAINFALL.**

For the twenty-one years ending 1881 rain returns are available for six stations. During these twenty-one years the highest recorded fall is 361 inches at Bávdá in 1861 and the lowest is five inches at Alta in 1865. As a rule rainfall varies with the distance from the Sahyádrí crest. During the twenty-one years ending 1881, of the six stations at Alta, which is about forty-five miles east of the Sahyádrí crest and twelve miles north-east of Kolhápúr, the fall varied from forty-four inches in 1874 to five inches in 1865 and averaged twenty-three inches; at Bávdá, which is on the Sahyádrí crest and thirty miles south-west of Kolhápúr, the fall varied from 361 inches in 1861 to 121 inches in 1864 and averaged 220 inches; at Bhudargad, which is ten miles east of the Sahyádrí crest and thirty miles south of Kolhápúr, the fall varied from 120 inches in 1861 to thirty-nine inches in 1880 and averaged seventy-six inches; at Kolhápúr, which is twenty-five miles east of the Sahyádrí crest, the fall varied from fifty-six inches in 1874 to twenty-seven inches in 1876 and averaged 39.88 inches; at Panhála, which is twenty miles east of the Sahyádrí crest and twelve miles north-west of Kolhápúr, the fall varied from eighty-four inches in 1878 to thirty-seven inches in 1877 and averaged fifty-three inches; and at Vishálgad, which is on the Sahyádrí crest and about thirty-five miles north-west of Kolhápúr, the fall varied from 111 inches in 1875 to thirty-two inches in 1877 and averaged sixty inches. The details are:

*Kolhápúr Rainfall, 1861-1881.*

STATION.	From the Sahyádris.	1861.	1862.	1863.	1864.	1865.	1866.	1867.	1868.	1869.	1870.	1871.
	Miles.	In.	In.	In.	In.	In.	In.	In.	In.	In.	In.	In.
Alta ...	45	24	28	18	22	5	9	14	17	20	15	28
Bávdá ...	...	361	241	239	121	134	173	178	178	189	184	192
Bhudargad ...	10	120	108	98	84	84	79	64	76	65	62	66
Kolhápúr ...	25	45	45	35	38	40	29	40	36	30	44	38
Panhála ...	20	56	57	62	52	47	51	42	44	49	50	40
Vishálgad ...	...	53	51	48	46	44	42	36	47	72	104	55

*Kolhápur Rainfall, 1861-1881—continued.*<sup>1</sup>

STATION.	1872.	1873.	1874.	1875.	1876.	1877.	1878.	1879.	1880.	1881.	Twenty-one years.
	In.	In.	In.	In.	In.	In.	In.	In.	In.	In.	In.
Alta ... ..	20	22	44	43	18	31	30	35	27	18	23
Bánda ... ..	243	189	311	326	200	194	235	256	211	218	220
Bhudargad ...	117	70	105	69	...	48	63	61	39	46	76
Kolhápur ... ..	40	32	56	55	27	45	51	49	37	32	40
Panhála ... ..	50	48	71	79	47	37	84	60	40	56	53
Vishalgad ... ..	60	58	84	111	61	32	79	71	46	55	60

Chapter I.  
Description.  
RAINFALL.

Kolhápur heat is temperate. During the thirty-one years ending 1881 the yearly maximum varied from 97° in 1872 to 79° in 1851 and averaged 87°; the yearly minimum varied from 74° in 1851 to 62° in 1872 and averaged 67°; the yearly mean maximum varied from 87° in 1876 to 79° for the five years ending 1858 and averaged 83°; and the yearly mean minimum varied from 74° in 1860 to 67° in 1872 and averaged 70°. A return of the thermometer readings for the thirty-one years ending 1881 is given in the Appendix.

HEAT.

<sup>1</sup> Besides these, rain returns for the station of Kolhápur are available for the ten years ending 1860. During these ten years the fall varied from sixty-four inches in 1853 to thirty-four inches in 1860 and averaged forty-five inches. The details are : In 1851 thirty-seven inches, in 1852 fifty-six inches, in 1853 sixty-four inches, in 1854 forty-four inches, in 1855 thirty-nine inches, in 1856 fifty-two inches, in 1857 forty-six inches, in 1858 forty-two inches, in 1859 thirty-eight inches, and in 1860 thirty-four inches.



## CHAPTER II.

## PRODUCTION.

Chapter II.  
Production.  
MINERALS.

IRON ore occurs in a few of the spurs which run east from the Sahyádris. It is sometimes found on the surface in irregular masses mixed with other stones, but it is generally reached by sinking shafts, two to ten feet below the surface, through a thick layer of iron-clay mixed with a composite stone locally known as *jámhla* or purple stone. The ore stratum is seldom more than eight or ten inches thick and thirty to forty feet broad. It appears to dip from north to south at an angle of about 12°. Formerly iron was much smelted. In 1854 thirty furnaces were at work with a yearly outturn of 225 tons worth about £900 (Rs. 9000). The mining and smelting employed 180 miners, who belonged to a wandering class of Musalmáns named Dhavads. Since 1854, the dearthness of fuel and the cheapness of European iron, have between them destroyed the smelting industry. It still goes on in ten hill villages, five in Bhudargad and five in Vishálgad. In 1881 fifteen furnaces yielded about two tons of iron and employed fifty-three Dhavad workmen during six months in the year whose average season's earnings were about £5 (Rs. 50). Besides smelting the iron the Dhavads make it into field tools and cooking vessels, which they offer for sale in the nearest markets. A small fee of 4s. to 8s. (Rs. 2-4) is charged for the use of the ground in which the shafts are sunk.

The ore is of three kinds *borgale*, *shelga*, and *tatha*. The process of smelting, though simple, is slow and costly. The ore is dug from the pits with crowbars and pickaxes; the large pieces are broken by the hammer and then fired. When cold, the ore becomes brittle and is made ready for the furnace by grinding it to powder on a hard slate. One of the most important parts of the furnace is a flint tube which is known as *mus*. To make this tube a number of flints are thrown into a fire and merged under large stones, as they are apt to burst with the heat and wound the workmen. When fired, the flints are ground to powder and mixed with clay and water. When sufficiently kneaded and pliable, the mixture is rolled into a ball and a round rod sixteen inches long and about one and one-fourth inches in diameter is thrust into the mass and covered with a uniform coating of the flinty clay. The rod is laid in the sun and when the clay has dried it is drawn out leaving a hollow tube. On the tube thus formed a second layer of flint and clay is laid and the tube is again dried. To make the furnace, a round hole about three feet deep and one and one-fourth broad is dug. At first one side is left open and the other sides are lined with a mixture of moist clay and powdered flint or iron ore. At the bottom powdered charcoal is heaped about six inches high and water is poured on it and about four *shers* of powdered charcoal are added. The flint and clay tube or *mus* is placed in the open side of the furnace, which, like the other side, is closed with clay and flint

Charcoal is thrown in till the furnace is half full. The noses of two large bellows are set in the outer end of the tube. They do not fill the mouth of the tube and in the space left open a movable ball of clay is placed which can be taken out if the workmen have to clear any thing likely to stop the free passage of air. When every thing is ready two men begin to blow the bellows; one of them simply blows. Close to the other man is a long iron spoon and two heaps one of charcoal the other of powdered ore. As he blows he every now and then passes a ladle full of ore into the furnace and then fills it with charcoal. So great is the heat that the ore rapidly fuses. Powdered ore and charcoal are again and again added and an unbroken blast is kept from the bellows until the heap of ore is finished. To feed the furnace and know the moment of fusion require both experience and skill. The miners say that as soon as fusion sets in, the flame turns from reddish to white. The ball or *mudga* of metal which forms at the bottom of the furnace, weighs ten to twenty pounds ( $\frac{1}{4}$  -  $\frac{1}{2}$  *man*). It takes three hours to make and uses about forty pounds of charcoal and thirty pounds of powdered ore. The metal is left to cool in the furnace and is taken out with a pair of pincers. The furnace lasts for two or three smeltings, but before each smelting requires fresh lining of clay and flint and the flint and clay tube or *mus* never stands more than two smeltings. After the iron is hammered it is ready to be worked into field tools and cooking vessels. Each furnace gives employment to six men, two bellowsmen and two labourers who bring charcoal and water and repair the furnace, and two men who gather ore and fuel.

Good building stone occurs in almost every part of the State. The building stone in general use is a blue or dark gray trap or basalt. It is obtained either from large hill-side boulders or from quarries which are carried through the broken trap or *murum stratum*. Quarry stone in many places shows stratification and in quarrying often goes off in layers, presenting an uniform surface generally coated with a thin layer of white substance which is probably olivine carried in solution and deposited. Red veins due to iron make the stone unfit for use, as when exposed to heat and damp it is apt to split along the line of the red vein. Boulder stone is hard, fine in grain, and takes a high polish. In the Ajra and Torgal districts a pinkish white granite is used for building, but care must be taken in choosing it as the softer kinds which look like sandstone cannot stand the weather. Laterite or iron-clay is chiefly found in the Ajra subdivision in the south-east and in the Panhála subdivision in the north-west. It is seldom used for building, except where there is neither trap nor basalt. On a part of the road between Ajra and Amboli the drains and culverts are of a reddish iron-clay. This stone is of an open texture either nodular or cellular and is easily quarried by wedges into cubical blocks, which on exposure become hard and durable.

For ordinary building quarried trap is the easiest stone to dress, but it is seldom used for fine carving as it is apt to split along the scales and red veins. For carved and polished work columnar basalt

## Chapter II. Production. MINERALS.

### BUILDING STONE.

## Chapter II. Production.

### BUILDING STONE.

or boulders are better than quarried trap as they are generally free from flaws. Boulder trap takes a high polish and is often used for inscription tablets or ornamental bases and capitals in Hindu temples. Most of the polished boulder trap is brought from Jotiba's hill about seven miles north-east of Kolhápur.

The Kolhápur masons are either Musalmáns or Maráthás. The Musalmáns are the best workmen turning out superior carved and ornamental work and showing an aptness for inventing scroll and flower designs. In recent times Kolhápur masons first showed their talent for original designs when the Kolhápur high school was being built, and since then high class ornamental work has been executed in various buildings. Kolhápur does not require to import masons for any class of stone work. The cost of ordinary good building rubble delivered at the quarry is 4s. 6d. (Rs. 2¼). A poorer class of stone can be got at 3s. 6d. (Rs. 1½). For *fádis* or stones hewn on one side and *khándkis* or chips the rate varies in proportion to the size of the stone and is generally paid by the foot, the length from face to tail varying from 12" to 18". Block stones that is stones in the shape of a cube or parallelo-piped cost 5¼d. the cubic foot if from two to four cubic feet in size; 7½d. the cubic foot if from four to six cubic feet in size; 10½d. the cubic foot if from six to eight feet in size; and 1s. the cubic foot if from eight to ten cubic feet. Uncoursed rubble in foundations costs £1 12s. (Rs. 16) and in superstructure £1 16s. (Rs. 18) the cubic foot. Coursed rubble in superstructure costs £2 10s. (Rs. 25) the cubic foot for the first sort and £2 (Rs. 20) for the second sort. Fine cut-stone work costs about 3s. 6d. (Rs. 1¾) the cubic foot.

### ROAD METAL.

As good crumbly trap or *murum* is found over nearly the whole of Kolhápur, broken stone is seldom used for metalling roads. What little is used is broken from nodular basalt or quarried. Metal broken from basalt nodules costs 5s. (Rs. 2½) and from quarried basalt 7s. (Rs. 3½) the hundred cubic feet. Laterite, which makes a good lasting road, is also used in the Ajra sub-division at a cost of 4½s. (Rs. 2¼) the hundred cubic feet.

### SAND.

Sand or gravel is found in the beds of rivers and streams. The building sand is of superior quality and is free from large pebbles, salt, shells, and other impurities. Common sand is also used for bindage in mending metal and *murum* roads at a cost of 2½s. (Rs. 1¼) the hundred cubic feet at the river side.

### LIME.

Lime is made from limestone nodules or *kankar* which usually occurs on the surface of black soil fields. The nodules are irregular in shape, from half an inch to three or four inches in diameter, and composed within of tolerably compact carbonate of lime and on the surface of a mixture of carbonate of lime and clay. Lime is burnt either on the intermittent or on the continuous system. Under the intermittent system the whole kilnful is burnt at once. The kiln is cylindrical both inside and outside. It varies in size according to the supply required and is usually built of stone and mud. At the bottom of the kiln a layer of charcoal or cowdung-cakes is laid, and, over the charcoal, alternate layers of lime nodules and *bábhul* or tamarind firewood twelve to fifteen inches thick. The top layer ends in a conical

mound. The fire is lighted below as well as at the top. As the lime burns the contents of the kiln subside and the space left at the top is filled with fresh layers of nodules and fuel and plastered over with clay. When the nodules are burnt, the kiln is allowed to cool, and the burnt limestone is taken out and slaked by spreading it on the ground in a layer about one foot thick and pouring water over it. For every hundred cubic feet of limestone two and three-quarters to three *khandis* of firewood are required. A kiln takes about ten days to burn and slake. Every hundred cubic feet of *kankar* yield, when slaked, one hundred and twenty-five cubic feet of lime. Under the continuous system the burnt nodules are gradually removed from the bottom of the kiln. Inside the kiln is shaped either like a cylinder or an inverted cone. It is built of stone and mud and has an inner lining of brick. The burnt lime is removed through an opening below called the draw-hole. At the lower end of the inverted cone is an iron grating on which are laid nodules and charcoal mixed in the proportion of one thousand pounds of charcoal to one hundred cubic feet of *kankar*. When the nodules are sufficiently burnt they are removed from the draw-hole and fresh nodules and charcoal are added from the top. The continuous system is not often used in Kolhápur, as, unless the kiln is skilfully managed, the lime is apt to be unequally burnt and useless. Slaked lime varies in price from £1 18s. to £2 2s. (Rs. 19 - 21) the *khandi* of a hundred cubic feet.

Clay for making bricks and tiles is found almost everywhere. The bricks usually made are of two kinds, flat and thick. The sizes are  $9\frac{1}{2}'' \times 6\frac{1}{2}'' \times 1\frac{1}{2}''$  and  $9'' \times 4\frac{1}{2}'' \times 2\frac{1}{2}''$ . The cost of thick bricks is 14s. (Rs. 7) and of flat bricks £1 4s. (Rs. 12) the thousand. Bricks are seldom used for building, as they are much more costly than stone. Tiles are of two kinds, flat and arched. The cost of flat tiles is 3s. 6d. (Rs.  $1\frac{3}{4}$ ) and of arched tiles 7s. 6d. (Rs.  $3\frac{3}{4}$ ) the thousand. Ridge tiles cost 10s. (Rs. 5) the thousand.

Yellow white and red earth, decomposed hornblende, felspar, and iron-charged clay are commonly used for colouring house walls. They are of little value and are used only by those who cannot afford the better sorts of foreign pigment.

The wet rugged west and the high spurs which stretch from the Sahyádris to near the east border of the State, give Kolhápur a large area suitable for forests. It is said that up to the early part of the present century the slopes and spurs of the west of Kolhápur were covered with timber. The country was thinly peopled and except near hill forts tillage was scarcely possible. During the last fifty years as population increased tillage spread westward and timber was felled without restriction except in a few hills or *dángs* set apart as game preserves. The practice of *kumri* or wood-ash tillage cleared brushwood and young trees from the Sahyádris spurs. The first attempt to save the forests was in 1874 when a staff of thirteen rangers and one inspector was entertained. In 1878 a separate department was organized under a forest officer lent by the British Government and the conservancy and protection of the Kolhápur forests were placed on the same footing as in the neighbouring British

## Chapter II. Production.

### LIME.

### TILES.

### COLOURED EARTH.

### FORESTS.

## Chapter II.

## Production.

## FORESTS.

*Settlement.*

districts. In 1882 the forest establishment included one forest officer, nine inspectors, nineteen head foresters, one hundred and nineteen foresters, one draftsman, three clerks, and eight messengers representing a yearly cost of £1737 (Rs. 17,370).

In the sub-divisions of Panhāla, Karvir, Alta, and Shirol about 177 square miles have been set apart for forests of which 122 square miles are reserved and fifty-five are protected. Demarcation is in progress in other sub-divisions and will be completed in two or three years. In choosing lands for forest reserves, the forest officer consults the district revenue officer as to private rights. Special care is taken to meet the needs of husbandmen in the matter of forest produce. Under certain restrictions they are allowed free grazing, firewood, loppings for ash manure, wood for housebuilding, and field tools.

*Description.*

No detailed information is available, but it is estimated that when the demarcation is completed the forest area of the State will include about 500 square miles. The forest blocks of the Kolhápúr State may be grouped under two classes, those that belong to the main range of the Sahyádris and those that belong to the spurs and valleys that strike across the State to the north-east and east. The main line of the Sahyádris, though in places the hill sides have been stripped for wood-ash tillage, has fine evergreen forests with much valuable timber. The Sahyádris forests may be roughly arranged under two groups, a smaller section in the north stretching as far south as the Anaskura pass and a larger section in the south including the rest of the Kolhápúr Sahyádris. The northern section covers about 100 square miles and includes the forest lands of Amba, Pándhrepáni, Marshi Májre, Gajápúr, Yelvanjugai, and other villages. These reserves are patchy and scattered, but, where spared from branch-logging and reckless cutting, they are thickly stocked with evergreen trees, among which the chief are the *ain* *Terminalia tomentosa*, *nána* *Lagerstræmia lanceolata*, *hirda* *Terminalia chebula*, *kinjal* *Terminalia paniculata*, *jámbhul* *Eugenia jambolana*, *báva* *Cassia fistula*, *karmal*, *shevri*, *cher*, *kumb*, and *surung*.<sup>1</sup> The chief divisions of the southern and longer section of the Sahyádris are the Anaskura, Kájirda, Bávdá, and Phonda hills. The forest land in these hills covers an area estimated at about 160 square miles. Except in places where they have been stripped by careless cutting, these reserves are well stocked with the commoner forest trees, and yield large stores of inferior timber and firewood. They also contain blackwood, teak, *khair*, *kinjal*, and bamboo. The forest lands along the ranges and the streams that stretch east and north-east from the Sahyádris lie in the cool and moist belt to the west of Kolhápúr city, seldom passing more than twenty miles east of the crest of the Sahyádris. Of nine chief blocks, two, the Várna and the Mhasái-Páthár, are in the Várna valley; four the Asandoli, Bhadara, Manbet, and Mainghole are in the valleys of the Bhogávati and its feeders; one, the Váki lies near the source of the Dudhganga; one, the Mhasrang lies near the source of the Vedganga; and one, the Ajra lies near the source of the Hiranyakeshi.

<sup>1</sup> A list of trees found in the State is given in the Appendix.

In the north the VÁRNA block, with an area of about fifteen miles, stretches along the hills to the south of the Várna in the upper part of its course. Except near the centre the Várna block is well stocked with *ain*, *kinjal*, *jámḃhul*, *nána*, and other common forest trees. To the south-west of the Várna block is the MĤASÁI-PÁTHÁR reserve, a valuable tract of forest land in the hill range that lies between Panhála and the Sahyádris. All of its area of about twenty square miles is covered with a flourishing growth of *ain*, *kinjal*, *hirda*, and other common forest trees. About twelve miles south of the Mhasái-Páthár forest and about twenty miles west of Kolhápúr is the ASANDOLI block. This has an area of twenty square miles most of it in a chain of hills that runs east from the Sahyádris as far as the village of Kale. It is crossed by the Tulsi stream a feeder of the Bhogávati. It is one of the best forest reserves in North Kolhápúr, being well stocked with *ain*, *kinjal*, *jámḃhul*, *nána*, *hirda*, and other common trees. During floods timber rafts can be floated down the Tulsi to Kolhápúr. Five to ten miles south-east of the Asandoli block are the BHADARA forests in the Bávda sub-division, chiefly composed of the hill sides which drain into the valley of the Kumbhi a feeder of the Bhogávati. The Bhadara forest land stretches from the Sahyádris about ten miles east to the village of Sálvan which is about fifteen miles west of Kolhápúr. It has an area of about fifteen square miles and is well stocked with *ain*, *kinjal*, *hirda*, and other forest trees. Teak and the bamboo do not occur. About eight miles to the south-east of the Bhadara forest lands, on the banks of the Dhámni which runs north-east nearly parallel with the Bhogávati, is the MANBET block. It has an area of about twelve square miles and is well stocked with the commoner forest trees, mixed with *ain*, *kinjal*, *hirda*, *báva*, *ávala*, and the rattan and bamboo canes. Six to twelve miles east and south-east of the Manbet reserve along the banks of the Bhogávati, is a stretch of forest land known as the MAINGHOLE reserve. It covers an area of about twenty-five square miles which are thickly wooded with mixed forest, the chief trees being the *ain*, *kinjal*, and *hirda*. About ten miles to the south, along the upper course of the Dudhganga, the VÁKI forest range covers about twenty square miles. It contains fine blocks of forest, yielding many thousand *hirda* trees and much bamboo mixed with *ain*, *kinjal*, and other commoner trees. About ten miles further south, in the upper course of the Vedganga, the MĤASRANG block comprises several ridges and valleys covering about twenty square miles. Like the Váki block this is a splendid tree-producing tract. It is thickly covered with almost all kinds of local trees among which the *ain*, *kinjal*, and *hirda* are the chief. About ten miles to the east, across the great Utur-Bhudargad or North Ghatprabha spur in the west of the Ajra division, are about twenty miles of forest land which are known as the AJRA block. Most of this lies within the drainage area of the Hiranyakeshi on three spurs of which the Cháloba hill is the chief.

To secure the goodwill of the people who live in and near the forest lands the poor are allowed tickets under which they can remove headloads of firewood free of charge. Firewood and thorns may also be taken free of charge by all who live in and

## Chapter II. Production.

### FORESTS. *Description.*

#### *Ticket System.*



## Chapter II.

## Production.

## FORESTS.

near the forest lands for home use and for field purposes provided none but matured trees and shrubs are cut. Any dead sticks and branches may be taken from the forests, but no reserve trees may be cut or lopped. Fuel for kilns, distilleries, and other industrial purposes may be cut and removed on paying 2s. (Re. 1) the *khandi* and 2½d. (1½ as.) the bullock, ass, pony, or buffalo load.

## Forest Tribes.

The Dhangars spend most of their time in the forests with their flocks of sheep and herds of cattle but there are no separate forest tribes. Forest workers are paid daily wages varying from 3d. to 6d. (2-4 as.). Between 1878 and 1881 forest receipts rose from £49 to £6047 (Rs. 490 - Rs. 60,470) and charges from £1124 to £3986 (Rs. 11,240 - Rs. 39,860). In 1881-82 of the whole receipts, £4523 (Rs. 45,230) were from myrobalan or *hirda* berries, £647 (Rs. 6470) were from building timber, £236 (Rs. 2360) from firewood, and £637 (Rs. 6370) from minor produce.

## Timber Trade.

There has never been any regular timber trade in Kolhápúr. Formerly all were allowed, according to their wants, to go into the forests and cut what timber they might want. The large teak beams used in the old buildings of Kolhápúr came either from Kánara or from Burmah. Since the introduction of forest conservancy cutting is as far as possible confined to worn-out or decaying trees and the produce is disposed of at auction sales, which are held in different parts of the State. The chief minor products are the myrobalan or *hirda* berry, grass, and honey. The *hirda*, which of late years has become an important article of trade, is bought yearly at the forest stores by wholesale dealers for export to Europe, where it is valued for dyeing. The *hirda* harvest begins early in November and ends at the close of February. During these four months the berries are gathered by people of all classes under the supervision of the forest officers, and are delivered at the rate of ¾d. (½ a.) the *páili* of five pounds. Grass grows freely over almost all the forest land. In 1882 grass yielded a revenue of £503 (Rs. 5030). The yield from wild honey is chiefly confined to the reserves of Bhudargad, Panhála, Bávdá, and Vishálgad. Most of it is produced by four varieties of bees the *kolambi* or *ágya*, the *sátin*, the *pova*, and the *kánta*. During the flowering periods of the *kárvi* or *Strobilanthus*, which generally happen at intervals of seven years, the yield is so abundant that honey sells for about ten pounds for 1s. The combs of *kolambi* or *ágya* bees are found on the face of rocky cliffs and hanging from the boughs of large trees. A single comb often contains as much as twenty *shers* of honey. Bee-spoiling goes on at night and is generally difficult and often dangerous. The nest is sometimes several hundred feet below the crest of the scarp and the man has to be lowered in a cradle held by a single rope. When the cradle has reached the level of the combs, the men above swing the rope until the cradle touches the face of the rock. The bee-spoilers have a bundle of chips of the wild sago palm *bherla* or *surmád* *Caryota urens* which they keep alight and the smoke drives off the bees, especially as the attack is generally made at night. The comb of the *sátin* bee is found in the cliffs of rocks and on small trees, and the quantity of honey obtained from one hive is generally about four pounds (2 *shers*).

The comb of the *pova* bee is found in the hollows of large rocks and in decayed trees. This honey is finer than either of the other kinds, and crystallizes when kept for any length of time. Each nest yields about a pound ( $\frac{1}{2}$  *sher*). The comb of the *kánta* bee is found in thorny shrubs and bushes. The cells always cluster round a single branch instead of hanging like the combs of other bees. The honey harvest is in April when the *dhádyti* *Grislia tomentosa* tree and the *kárví* are in blossom. The second crop of honey in August is watery and does not keep. The right of gathering honey is farmed at £5 to £10 (Rs. 50 - 100) a year. But much smuggling goes on as the people get oil from the village shopkeepers in exchange for honey.

Teak, sandal, and blackwood are the property of the State and are nowhere allowed to be cut. The cutting of nineteen other trees is forbidden in lands set apart as forests. These are, *ain* *Terminalia tomentosa*, *heddu* *Naucllea cordifolia*, *bíbla* *Pterocarpus marsupium*, *hirda* *Terminalia chebula*, *sissu* *Dalbergia sissou*, *kalam* *Naucllea parviflora*, *koshimb* *Schleichera trijuga*, *shivan* *Gmelina arborea*, *ránphanas* *Artocarpus hirsuta*, *kinjal* *Terminalia paniculata*, *nána* *bondára* *Lagerstræmia parviflora*, *kátvin* *Tetranthera lauginosa*, *kumbiya* *Careya arborea*, *khair* *Acacia catechu*, *ásan* *Briedelia spinosa*, *bondára mothá* *Lagerstræmia lanceolata*, *jámdbhul* *Eugenia jambolana*, and mango.

During the last twenty years the growth of roadside trees has received much attention. Almost all the chief roads are lined with rows of trees, in some places beautifully grown, in others still small. The kinds most used are the *bádbhul* *Acacia arabica*, *nimb* *Melia azadirachta*, *nándruk* *Ficus benjamina*, and the *vat* or banian *Ficus indica* and other kinds of fig.

The domestic animals are oxen, cows, buffaloes, horses, camels, asses, sheep, goats, cats, and dogs.

The 1881-82 returns show a total of about 149,762 oxen. During the last thirty years the breed of oxen has been improved by the introduction of Gujarát bulls and the breed of buffaloes by the introduction of Maisur buffalo bulls. Three breeds of bullocks are used for field and draught purposes, the *hanam* or half-Maisur breed, the *surati* or half-Gujarát breed, and the *khadki* or local breed. The *hanam* or half-Maisur bullock is a straightthorned handsome animal, of middle size, strong, and hardy, but bad-tempered and hard to tame. They trot faster than other bullocks and will do thirty-six miles in a day. A good pair of *hanam* bullocks costs £10 to £20 (Rs. 100 - 200). The *surati* or half-Gujarát bullock is taller than the *hanam*, and has long ears and a hanging dewlap. It is less active than the *hanam* but is stronger and better suited for field work. A *surati* bullock costs £5 to £25 (Rs. 50 - 250) and a good pair £10 to £50 (Rs. 100 - 500). The *khadki* or local bullock is small and has little strength or beauty. But as it costs only £1 10s. to £7 10s. (Rs. 15 - 75), it is much used in ploughing, draught, and pack carrying. Some *khadki* bullocks are brought into Kolhápúr from the cattle fairs at Chinchli fifty-five miles east of Kolhápúr at Narsinh's Well.

## Chapter II. Production.

### FORESTS.

#### Honey.

#### Reserved Trees.

#### Roadside Trees.

### DOMESTIC ANIMALS.

#### Oxen.



## Chapter II. Production.

### DOMESTIC ANIMALS.

#### Oxen.

and at Mangsoli forty miles north east of Kolhápur, but most are reared in Kolhápur by husbandmen. Bull calves are generally castrated when five years old. In a short time they are used for light work and when six years old are considered fit for hard work. In ploughing red or *masari* lands one or two pairs of bullocks are enough, but in black soils where deeper ploughing is wanted three or four pairs are required. The area that can be ploughed in one day varies from half an acre in heavy soil to one acre in light soil. In working wells two pairs of bullocks are required to draw a water-bag or *mot* holding sixty gallons of water. A pair of bullocks will draw a country cart with a load of about  $8\frac{1}{2}$  hundredweights (6 *mans*). The field wagons or *gádás* are much larger and are drawn by two to four pairs of oxen. Before the days of roads the carrying trade was in the hands of Lamáns who kept pack-bullocks to carry grain and other articles of trade from and to the coast. With the opening of roads, especially of cart roads down the Sahyádris, the Lamáns have disappeared and the number of pack-bullocks has greatly fallen. Still there are estimated to be about 8000 pack-bullocks. The Vánis and petty traders of the west keep them and make trips to Rájápur and other coast places, taking cereals, molasses, turmeric, chillies, and tobacco, and bringing back salt, sugar, cocoanuts, spices, and dates. The peddlers who retail piece-goods from market to market, keep pack-bullocks to carry their goods. Another class of pack-bullock keepers are the Balvars, who bring fuel from the forests into the towns. A pack-bullock carries on an average about 200 pounds. Besides for field work and for draught and pack-carrying bullocks are ridden by Lingáyats husbandmen both men and women. Among Lingáyats when the bridegroom brings the bride home, the newly married couple generally ride on a bullock. Bullocks are also used to carry water either in leather bags or in metal pots. In towns a single small bullock is often driven in a light driving cart. The Pánguls, a class of wandering showmen, teach bullocks to perform tricks and lead them about dressed in gay clothing. Bulls are often devoted to the village gods and never put to work, and are allowed to roam through the streets and fields and serve as stallions. The setting loose of calves and heifers is also a part of the twelfth day funeral services.

#### Cows.

The 1881 returns show a total of about 112,000 cows. In the east, especially in the Krishna-bank villages, the *surati* or half-Gujarát cows are greatly prized and for six to eight months after calving are said to yield as much as twenty-one pints of milk a day. In the west of the State the cows are small and poor. The price of a cow varies from 10s. to £4 (Rs. 5-40). Cows calve in their fourth or fifth year and for six to eight months give two to ten pints of milk morning and evening. They give milk till their fifteenth year and calve nine or ten times. The cultivating classes, and, in towns, Bráhmans and other high class Hindus keep cows. Husbandmen rear their own calves. Townspeople generally hand their calves to husbandmen to be taken care of, the owner receiving them back when full-grown at half the market value. The rearers generally have the option to keep the animal by paying the owner one-half of its estimated value.

The 1880-81 returns show about 61,000 male buffaloes. They are chiefly found in the west where they are used in field work and for carrying water-bags. Vadárs or quarrymen also use them for drawing loads of stone in their low block-wheeled carts. Gavlis or milkmen give male calves no share of their mother's milk and either give them away or let them die. The price of a male buffalo varies from £1 to £4 (Rs.10-40). Male buffaloes are sometimes brought to Chinchli fair from as far north as Dhulia and Málegaon. They are put to work in their fourth or fifth year. Female buffaloes are returned at about 74,000. The best variety is known as *jáfrábádi* from Jáfrabad in South Káthiáwár. Animals of this breed are said to yield twenty-seven pints of milk a day from six to twelve months after calving. A good she-buffalo costs £8 (Rs. 80), but fair animals can be bought at £3 to £5 (Rs.30-50). Buffaloes usually calve in their third or fourth year and give over bearing at eighteen or twenty. They have twelve to fifteen calves. Buffaloes are kept by husbandmen, well-to-do townspeople, Gavlis or milkmen, and Dhangars or forest herdsman. Buffalo's milk is preferred to cow's except for infants and for the weak. Townspeople who keep cattle generally use all the milk in their own families. Townspeople who do not keep cattle are supplied with milk, and to some extent with butter, by milkmen of the Gavli caste. The rest of the butter used in towns is brought from the country by Dhangars who send in weekly supplies of clarified butter and drink the buttermilk or give it to the calves.

The east is well off for fodder, millet stalks or *kadbi*, river-bank grass, and the juicy creeping *hariáli* *Cynodon dactylon*. Most of the cattle are healthy and well nourished, a contrast to the western cattle whom a diet of dry hill grass and rice and *náchni* straw leaves lean and stunted. Except during the rains, when they are taken to graze in the grass lands, oxen are generally stall-fed. They get grass, millet or *náchni* stalks, rice straw, bran, grain husks, cotton seed, and oil cake. Draught cattle are also allowed some grain generally millet or *math* and salt or oil in the cold season or when sick. The monthly keep of a field bullock costs about 8s. (Rs. 4) and of a draught bullock about 16s. (Rs. 8). Milch cows and buffaloes are stall-fed at night and are left to graze in grass lands or fields during the day. They are given cotton seed, oil cake, chopped gourds, and boiled grain such as millet wheat and gram. The monthly cost of a cow's keep varies from 8s. to 12s. (Rs.4-6) and of a buffalo's from 12s. to 16s. (Rs.6-8).

Sheep are generally black or black and white. They are fed by Dhangars and sometimes by cultivators for their milk, butter, wool, and flesh. The sheep are sheared twice a year in November and in June. The Dhangars cut the wool with a heavy pair of shearing scissors. An average fleece weighs half a pound which is worth 3d. to 3½d. (2-2½ as.). Most of the local wool is woven into blankets and some is used for making felt or *burnus*, and native saddles. Very little raw wool leaves the State. The rutting season is in June and the ewe carries for five months. A sheep yields milk from November to May and generally one pound a day. During the first two months the lambs get the whole milk. They are afterwards allowed half

## Chapter II. Production.

DOMESTIC  
ANIMALS.  
*Buffaloes.*

*Feed of Cattle.*

*Sheep.*

## Chapter II. Production.

### DOMESTIC ANIMALS.

#### Sheep.

and the rest is either used by the Dhangars or is made into butter. The milk of twenty sheep in four days would yield two pounds of butter worth about 1s. (8 *as.*). Sheep begin to bear when three years old and go on bearing till they are about seven. A good ewe is worth 10s. (Rs. 5), and the average price varies from 3s. to 6s. (Rs. 1½ - 3). Sheep are generally killed by Mulánis or Musalmán village priests of whom most large villages have one or two families, and the mutton is eaten by all castes except Bráhmans, Shenvis, Jains, Lingáyats, and Kásárs. During the rainy season in the daytime sheep graze in meadows or *kurans*, or on hill sides, and at night are driven to a coat or pen on some rising ground near the village fenced with a thorn hedge to keep off wolves. When the harvest is over, the cultivators engage flocks of sheep and goats to graze on their rice and garden lands. So valuable are their droppings as manure that the herdsmen are usually paid forty to eighty pounds of grain for 400 sheep for one night. Sheep at times suffer grievously from diseases much like the rinderpest and the foot and mouth disease among cattle. They also suffer from small-pox. Allowing for accidents a flock of 100 sheep, fairly cared for, increases 25 or 30 per cent every year. A considerable number of sheep go to Poona and Bombay. Some Maráthás and Musalmáns rear fighting rams, which are specially fed on gram or millet and when young their horns are drawn out two or three times by pouring oil and redlead over them. A good fighting ram costs as much as £1 10s. (Rs. 15).

#### Goats.

There are two kinds of goats, *kui* or white and *khadki* or local. The white goat gives two to four pints of milk a day and costs 4s. to 16s. (Rs. 2 - 8). The local goat gives a half to one pint of milk and costs 2s. to 6s. (Rs. 1 - 3). Goat's flesh is eaten by all castes who eat mutton. He-goats are castrated and used to draw children's carts. A well trained he-goat is worth £1 (Rs. 10).

#### Camels.

Camels are reared by Musalmáns and used for riding and baggage carrying and by the State for commissariat and riding purposes. Their price ranges from £4 to £12 10s. (Rs. 40 - 125). They are usually fed on gram and grass and on the leaves of the *nimb*, *bábhul*, and other trees. Salt is given them when hardworked or overworked. The milk is used by Musalmáns. A baggage camel carries 480 pounds and a riding camel trots forty to fifty miles in a day. The monthly cost of a camel's keep is about £1 (Rs. 10).

#### Cattle-keeping.

To estimate the profits of keeping cows and buffaloes a term of two years must be taken as a cow calves only every second year. The cost of keeping a herd of fifty cows for two years may be estimated at about £165 6s. (Rs. 1653) of which about £90 (Rs. 900) are for cut grass, £20 (Rs. 200) for grazing fees, and £37 10s. (Rs. 375) for oil-cake and bran. Of the rest about £16 16s. (Rs. 168) is for the cowherd and a boy and £1 (Rs. 10) for gear.<sup>1</sup>

<sup>1</sup> The details are: Under cut grass for sixteen months at 7½ bundles or *pulis* a day for each cow 11,250 bundles a month or 180,000 bundles for the sixteen months; this at Rs. 5 the thousand gives a total expenditure on grass of Rs. 900; grazing during the four rainy months or eight months in all at 8 *as.* a month for each cow amounts to Rs. 200; oil cake and bran for eight months at half an *anna* a day for each cow Rs. 375; pay of a cowherd at Rs. 4 a month for two years Rs. 96; a boy on Rs. 3 a month for two years Rs. 72; ropes, pegs, and other gear Rs. 10; that is a total cost of Rs. 1653.

The earnings may be brought under the three heads of milk, manure, and calves. Cows continue to give milk six to eight months after calving, and during those months the quantity steadily decreases. The daily yield of milk and the time during which the milk lasts vary in the different breeds of cows. The estimate is therefore complicated. The result is during the eight months a yield of 22,020 *shers* or 32,532 pints worth £169 8s. (Rs. 1694).<sup>1</sup> Under<sup>2</sup> the head of manure the profit in the two years is estimated at about £28 (Rs. 280) if the dung is made into fuel cakes, and at about £24 (Rs. 240) if it is used as manure. The<sup>3</sup> calves of the fifty cows are estimated to yield £22 (Rs. 220) and the cost of keeping them amounts to about £19 16s. (Rs. 198) that is a balance of profit of £2 4s. (Rs. 22). The total receipts under the three heads are, under milk £169 8s. (Rs. 1694), under manure £26 (Rs. 260), and under calves £2 4s. (Rs. 22), or a total of £197 12s. (Rs. 1976). This, after deducting £165 6s. (Rs. 1653) the cost of keeping, leaves a profit on the fifty cows of £32 6s. (Rs. 323) or at the rate of 6s. 6d. (Rs. 3½) a year on each cow.

The corresponding estimates for a herd of fifty buffaloes are<sup>4</sup> under expenses about £330 (Rs. 3300), and under receipts milk £480 (Rs. 4800), manure about £50 10s. (Rs. 505), and calves £4 10s. (Rs. 45) or a total income of £535 (Rs. 5350), that is a total balance of £205 (Rs. 2050) or at the rate of about £2 (Rs. 20) a year on each buffalo.

## Chapter II. Production.

DOMESTIC  
ANIMALS.  
*Earnings.*

1 The details are :

*Fifty Cows for Two Years : Yield of Milk.*

	Months 1 and 2.	Months 3 and 4.	Months 5 and 6.	Months 7 and 8.
	<i>Shers</i> a Day.	<i>Shers</i> a Day.	<i>Shers</i> a Day.	<i>Shers</i> a Day.
Twelve cows at 6 <i>shers</i> each ...	72	48	24	12
Twenty cows at 3 <i>shers</i> each ...	30	40	20	10
Eighteen cows at 2 <i>shers</i> each ...	36	27	18	...
Total ...	168	115	62	22

<sup>2</sup> The details are : For fuel cakes ¼ *anna* a day for each cow or Rs. 562 for the fifty cows half of which goes to pay for the labour. For manure fifty cows in two years will yield 480 carts which at 8 *as.* a cart is Rs. 240.

<sup>3</sup> The details under calves are : Fifty calves are born of which ten or one-fifth die. Of the forty calves who live twenty are stirks worth Rs. 6 each and twenty are heifers worth Rs. 5 each or a total value of Rs. 220. The expenses are grass for the forty calves for three months at two bundles a day for each calf 7200 bundles which at Rs. 5 the thousand bundles gives Rs. 36; during the next three months at four bundles a day 14,400 bundles costing Rs. 72; and during the next three months at five bundles a day 18,000 bundles costing Rs. 90, or a total charge of Rs. 198.

<sup>4</sup> The details are : Under expenses dry grass for sixteen months at fifteen bundles a day for each animal 750 bundles a day or 360,000 bundles in all at Rs. 5 the thousand bundles Rs. 1800; grazing for eight months at Re. 1 a month for each buffalo Rs. 400; boiled millet or *bājri* for one month after calving ½ *sher* a day to each buffalo at 4 *pailis* the rupee, Rs. 47; oilcake and bran to 15 buffaloes one *anna* a day for one year Rs. 337, to 15 buffaloes ¾ *a.* a day Rs. 253, and to twenty buffaloes half an *anna* a day Rs. 225, that is a total cost of keep Rs. 3052. Wages amount to Rs. 240 including a buffalo-keeper at Rs. 4 a month and two boys at Rs. 3 each. Ropes and other charges come to about Rs. 15. Under the head of

## Chapter II. Production.

### DOMESTIC ANIMALS. Earnings.

Sheep pay well as the wool is in good demand, and the older animals can be readily sold to the butcher. The<sup>1</sup> estimated yearly cost of a flock of one hundred sheep, allowing £1 (Rs. 10) for grazing, 10s. (Rs. 5) for *bábhul* pods, and £7 (Rs. 70) for the wages and keep of a shepherd and a boy, amount to £8 10s. (Rs. 85). The return under wool is estimated at £18s. (Rs. 14), under lambs at £8 10s. (Rs. 85), and under manure at £2 5s. (Rs. 22½), that is a profit on the hundred sheep of £3 13s. (Rs. 36½). The profit to a sheepowner or his son who was also the shepherd would according to the same estimates amount to £10 10s. (Rs. 105). In some villages sheep are tended by contract under an arrangement that for every hundred sheep delivered to the shepherd he should replace any sheep that die and increase the flock by twenty-five lambs.

### Horses.

Horses are returned at 5583. Except the State horses and those kept by a few of the gentry which are imported, Persians Arabs and Australians, the greater number are mere ponies. The State stud includes twenty-five excellent broodmares, and some proprietors grant-holders and village heads also own good breeding mares. Stallions are kept by the State for the use of their own and other mares. During the last seven years the State stallions covered eighty-six mares. The climate though not specially favourable is not unsuited for horse-breeding, and the State authorities hope to do more to improve the breed by adding to their stud and by establishing a yearly show.

receipts it is estimated that the herd of fifty buffaloes will yield 62,775 *shers* of milk which at 13 *shers* the rupee amounts to Rs. 4829. The details are :

*Fifty Buffaloes for Two Years: Yield of Milk.*

	Months 1 and 3.	Months 4 and 6.	Months 7 and 9.	Months. 10 and 12
	<i>Shers</i> a Day.	<i>Shers</i> a Day.	<i>Shers</i> a Day.	<i>Shers</i> a Day.
Fifteen buffaloes of the first sort giving 10 <i>shers</i> of milk... ..	150	97	60	30
Fifteen do. 6 do. ....	90	60	45	22½
Twenty do. 3 <i>shers</i> a day ...	60	40	30	20
Total ...	300	190	135	72½

The Rs. 530 for dung is calculated midway between Rs. 560 the estimated value in tons if the dung was made into cakes, and Rs. 490 in country parts where the dung would be used entirely for manure. The Rs. 47 under calves is the balance between Rs. 195 the estimated value of the calves and Rs. 148 the cost of keeping them. The details of value are : Of fifty calves twenty die. Of the rest fifteen are male worth Rs. 5 each and fifteen female worth Rs. 8 each. The details of keep are : Grass for the second three months at two bundles each a day at Rs. 5 a thousand Rs. 27 ; grass for the third three months at four bundles a day Rs. 54 ; and grass for the fourth three months at five bundles a day Rs. 67½.

<sup>1</sup> The details are : Waste land taken for pasturing sheep assessed at Rs. 10 and Rs. 5 for *bábhul* pods Rs. 15 ; one shepherd for twelve months Rs. 15 ; one assistant for twelve months Rs. 10 ; two *kámblis* at Rs. 2 each ; two pairs of shoes at Re. 1 each, two turbans at 12 *as.* each, and four *langotis* at 2 *as.* each Rs. 8 ; feeding to shepherds for twelve months at Rs. 1½ per month for each Rs. 36 ; 1½ *páulis* of salt and two *páulis* of *javari* for sheep during the year Re. 1 ; that is a total expense of Rs. 85.

The current average price of local or Kolhápúr bred horses varies from £7 10s. to £20 (Rs. 75-200) and averages about £12 10s. (Rs. 125). Ponies vary from £1 to £6 (Rs. 10-60) and average £2 10s. to £4 (Rs. 25-40). The corresponding figures given by Major Graham show that the price of horses has not risen, but that ponies are dearer and scarcer than they were in 1853. The less valuable horses and ponies when out of work are left to feed as they can near villages on the boundaries of fields and in pasture lands. When in work they are given a small daily allowance of grain. Animals of the better class are fed on grass, millet stalks, gram, and millet. After hard work or when an animal is out of condition it is given a mess of flour and molasses; clarified butter and spices or *masála* are also given in the cold weather. The monthly cost of a horse's keep varies from £1 to £2 (Rs. 10-20).

Asses are found all over Kolhápúr. They are reared by Lonáris, Vadárs, Ghisádis, Dombáris, potters, and washermen, who use them to carry clay, bricks, fuel, clothes, and grain. A donkey costs £1 to £2 (Rs. 10-20). They are generally left to pick their food as they can.

Fowls are reared in large quantities by all castes except Bráhmans Lingáyats and Jains. They are of two varieties *pegu* and *khadki*. A hen varies in price from 6d. to 1s. 6d. (4-12 as.), and a *pegu* or fighting cock fetches as much as 4s. (Rs. 2). Eggs cost 2d. to 3d. (1½-2 as.) the dozen. None of the local flesh-eating classes object to eat fowls. Ducks, turkeys, and pea and guineafowls are not reared in Kolhápúr, and are seldom seen, except a few which are brought from Goa and the neighbouring British districts for the use of European residents. Numbers of tame pig are seen about the eastern villages. They are owned and eaten by Vadárs and Korvis, who leave them to pick up any garbage they can.

Cats and Dogs most of them ownerless abound in every village. Some of the higher Marátha families keep foreign dogs for hunting. Shepherds have sheep dogs and Vadárs, Korvis, and Haran Shikáris have dogs who help them to catch hares and other small game.

Formerly large game was common in the Sahyádris and the west parts of the leading spurs. The increase of population and the spread of tillage have reduced their numbers, but tigers and panthers still find shelter in Western Kolhápúr.

The Tiger *patáit vágh* *Felis tigris* is found in the hills of Mhasrang, Megholi, Pháyáchákáp, Bakryáchádang, Pátyáchádang and Kolik in Bhudargad; in Vashi and Barki in Panhála; and in Yelvan-Jungái, Chándel, and Udgiri in Vishálgad. About two tigers on an average are slain every year. During the five years ending 1881 the returns show a loss by tigers of 83 human beings and 2138 cattle.

The Leopard *dáhánya vágh* *Felis jubata*, that is the spotted tiger, is said to be occasionally found and to be more dreaded than the tiger.

Panthers *bibiya* *Felis pardus* are said to be of three kinds two large and one small. One of the large kinds called *karanjya* is said to be specially dangerous. It is found only in the thick forests of Bhudargad. The other large panther known as *tendva* is more

## Chapter II. Production.

### DOMESTIC ANIMALS.

#### *Horses.*

#### *Asses.*

#### *Poultry.*

#### *Cats and Dogs.*

### WILD ANIMALS.

#### *Tigers.*

#### *Leopards.*

#### *Panthers.*



## Chapter II. Production.

### WILD ANIMALS.

common occurring in the forests and hills of Bhudargad, Panhála, and Malkápur. The small or Dog Panther known as *khadki* or *bimbita* not unfrequently enters villages and carries off dogs cats and even poultry. The returns for the five years ending 1881 show that about forty-one panthers were killed. The Hunting Leopard *chita* is rare.

#### Cats.

Three varieties of Wild Cats occur, *Felis chaus rán mánjar* or the jungle cat, *Paradoxurus musanga kavali mánjar* or the tiled cat, and *Viverra malaccensis jávadi mánjar* or the civet cat. The *rán mánjar* is found all over the State. The *kavali mánjar* has a thick coating of fur like small pieces of tiles, which is said to be proof against a sword or spear-cut. The civet cat *jávdí mánjar*, is valued for its civet or *kasturi*. The *kavali* and *jávdí* are rare occurring only in the thick forests in and near the Sahyádris.

#### Hyæna.

The Hyæna *taras* *Hyæna striata* is fairly common in all hills and forests. It is generally found in holes or bushes in broken ground.

#### Wolf.

The Wolf *lándga* *Canis pallipes*, is found in the plain country. Wolves generally hunt in packs of five or six and carry off sheep and goats at night. They seldom attack human beings but sometimes carry off young children. Some years ago a man was killed by wolves in Karvir.

#### Jackal.

The Jackal *kolha* *Canis aureus*, and the Fox *khokad* *Vulpes bengalensis* are common in the open east.

#### Wild Dog.

The Wild Dog *kolsunda* *Cuon rutilans* is found in Bhudargad and other hill parts generally in packs of twenty-five or thirty.

#### Bears.

The Indian Black Bear *asval* *Ursus labiatus* is occasionally found in Bakryáchádáng in Bhudargad and in Morayáchákoda near Bávdá and in Udgiri in Vishálgad. During the day he lives in rocks and ravines and at night comes into the plains to feed on honey-combs and *moha* flowers of which he is very fond. He also feeds on ants and insects. He seldom attacks man unprovoked, and does no injury to cattle.

#### Boars.

The Wild Boar *dukar* *Sus indicus* is found in the hill parts of Bhudargad, Panhála, Malkápur, and Torgal. They generally come out at night in herds and ravage the neighbouring crops. Boar-hunting with the gun or spear is a favourite sport among the Maráthás, and with the help of their dogs the Vadárs spear them on foot.

#### Bison.

The Bison *gau* *Gavæus guarus* is found in the Barki, Vási, Patyáchádáng and Udgiri hills. Maráthás hold the bison to be a bull and few of them will shoot him. The Stag *sámbar* *Rusa aristotelis* is found in all the hill tracts except in Bhudargad where it is rare. The Spotted Deer *chital* *Axis maculatus* is found in the forests and hills of Vasundi and Aduli in Bhudargad and of Kaljavde, Pisatri, and Manvad in Panhála. Of *Bhekar* *Cervulus aureus* there are three kinds. The *khatkati bhekar* has horns like the stag and gets his name from knocking them against the trees. He is said to use his long teeth or tusks when attacked by dogs. The four-horned *bhekar*, though rare, is sometimes seen in the Bhudargad forests; the Málsade *bhekar* is commonly found among thin brushwood. The Indian Antelope *kálvit* Antelope *bezoartica* moves in bands of five to ten in the open parts of Ráybág, Shirol, and Datvád.

Of smaller animals the Hare *sasa* *Lepus ruficaudatus* is found in all parts of the State. Hares jackals and foxes in the small hills round Kolhápúr and Panhála give excellent coursing which is a favourite amusement with the higher Marátha families.

There is no special establishment for destroying wild animals. Rewards are granted at the following rates: for a large tiger £2 8s. (Rs. 24), for a middle sized tiger £1 4s. (Rs. 12), and for a small tiger 12s. (Rs. 6); for panthers the rates are one-half of the tiger rates, and 8s. (Rs. 4) is the reward for a wolf.

Monkeys, both *mákads* and *vánars*, are found in large numbers all over the State. The *vánar* the larger and more powerful animal is generally seen near villages while the *mákad* prefers forests and lonely places. Out of respect to Hanumán the monkey-god the people suffer with patience the mischief done by these animals in their gardens. They seldom attack men but are said to threaten children and women and take from them any eatables they may be carrying.

The hilly parts of Kolhápúr especially Bávda, Vishálgad, and Bhudargad are more or less infested with snakes both poisonous and harmless. During the five years ending 1881 sixty-one deaths from snake bites were recorded, of which eighteen were in 1877, seven in 1878, twelve in 1879, ten in 1880, and fourteen in 1881. There are no professional snake-charmers among the regular inhabitants, but a husbandman or a Bráhmaṇ is sometimes found clever in catching and handling snakes. Some village doctors profess to know herbs and roots that cure snake bite. Among the snakes found in Kolhápúr are: Of Pythonidæ, the Indian Python *ár* Python *molurus* is occasionally seen in the thick forests and groves near the Sahyádrí hills. They are caught and shown by professional charmers of the Dombári caste. Pythons are believed to be able to squeeze to death men and cattle. Of Erycidæ the Black Sand Snake *dutonda* *Eryx johnii* or a closely allied species, the Red Sand Snake *Gongylophis conicus* is found throughout the State. It is generally harmless. Of Colubridæ the Rock Snake *dháman* or *ádhela* *Ptyas mucosus*, is found throughout the State. Its bite is admitted to be harmless but they are believed to cause injury by blows of the tail. It is also said to twist itself round the legs of cattle and suck their milk. The Checkered Snake *pán divad* *Tropidonotus quincunciatus* usually known as *virola* is found in wells, ponds, and rivers, living on frogs and small fish. It is two to four feet long and harmless. Of Triophidæ the Common Green Tree or Whip Snake *sarptoli* *Passerita mycterizans* is occasionally found all over the State. It is believed to be poisonous and to attack the eyes of any one who passes under its tree.

Two kinds of *manyár* are known, one is called *manyár* and the other *ághi* or the burning *manyár*. Both are considered poisonous. The cobra *nág* *Naja tripudians* is found everywhere and is considered more venomous than any snake except perhaps the *phursa* *Echis carinata*. It is worshipped by all classes of Hindus on the Cobra's Fifth or Nágpānchmi Day which falls in August. Persons who have

## Chapter II. Production.

### WILD ANIMALS.

#### Hares.

#### Monkeys.

#### SNAKES.



Chapter II.  
Production.  
SNAKES.

left hidden treasures are believed to come back after death in the form of cobras and guard the hoard. Of Viperidæ the poisonous Chain Viper *ghonas* or *kândar* Daboia elegans is found in the hills. The poison of the *ghonas*, the *pharad*, and the *mahamdol*, acts much slower than cobra poison. The *phursa* *Echis carinata* the most feared of all snakes is generally found under rocks and boulders in the hilly west. Like the *ghonas* the *phursa*'s poison acts slowly destroying the blood which oozes through the skin and the victim dies a painful and lingering death. A reward of 3*d.* (2 *as.*) is given for a cobra and of  $\frac{3}{4}$ *d.* ( $\frac{1}{2}$  *a.*) for other poisonous snakes.

## FISH.

The fisheries of the State are of little importance. The chief kinds of fish are *támbar*, *parag*, *másil*, *khirit*, *kolsi*, *air*, *vám̃b*, *maral*, *mhas̃ka* otherwise called *mangsha*, *váyandi* or *muni*, *tákri*, *vanji*, *chikali*, *valsivda*, *bobari*, *muranga* *ph̃t̃nkut*, *shengála*, *kharab*, *dokara*, *khavli*, *gerya*, *muli*, *ghogara*, *káchki*, *alkut*, *khavalchor*, *ichka*, *kurdu*, *zinga*, *kadvi*, and *tokáli*. Of these fish the *maral* and *vám̃b* or eel are much sought after. In the Krishna *másil* and *khirit* are sometimes found 4½ feet long 2½ feet broad and weighing nearly seventy pounds. Besides in the Krishna fish are found in the pools of the Panchganga, Várna, Hiranyakeshi, Dudhganga, and Vedganga. Alligators and turtles are found in the larger streams, and freshwater crabs in the banks of rivers. The only local class of professional fishers are the Bhois who number 1756. They use casting and drag nets. When they go fishing they generally start in the early morning and come home about three or four. The women and old men then carry the fish to the market or hawk them from door to door. A fisher's earnings are small from 3*d.* to 6*d.* (2 - 4 *as.*) a day. The Rankála, Padmála, Rávaneshvar, Kotitirth, and other big ponds round Kolhápur abound in fish which are preserved for palace use. There is no local fish-curing but considerable quantities of salt and dry fish are brought from Ratnágiri and Goa.

## BIRDS.

Most of the birds given by Captain E. A. Butler in his catalogue of the Birds of the Deccan and Southern Marátha Country are found in Kolhápur.

## CHAPTER III.

## PEOPLE.

THE population of Kolhápúr includes six classes Hindus, Musalmáns, Christians, Pársis, Jews, and Chinese Buddhists. The Musalmáns who form 4.12 per cent of the population partly represent the Upper Indian and foreign Musalmán soldiers and others who settled during the period of Musalmán rule in the Deccan (1300-1710) and still more local Hindu converts to Islám. Besides 1201 Native converts the Christians include a few European officers. The Pársi for there is only one and the Jews who number only five are latecomers who are not permanently settled in the State. The Chinese Buddhists are temporary residents.

Three numberings of the people are on record in 1853, in 1872, and in 1881. In 1853 the people numbered 546,156 living in 101,708 houses or five to a house. Of the whole number 283,002 or 51.81 per cent were males and 263,154 or 48.18 per cent were females; 522,110 or 95.59 per cent were Hindus and 24,046 or 4.40 per cent were Musalmáns. The 1872 census showed an increase from 546,156 to 804,103 or 47.22 per cent. The increase was evenly spread over all parts of the State and was due to the long term of peace and good government which the State had enjoyed. The 1881 census showed a slight fall of 0.49 per cent the whole number amounting to 800,189 or 284.158 to the square mile.

The following statement gives, for the year 1881, details of the population of each fiscal sub-division of the State according to religion, age, and sex:

*Kolhápúr Population Sub-Division Details, 1881.*

SUB-DIVISION.	HINDUS EXCLUDING JAINS.								
	To Twelve.		Twelve to Thirty.		Above Thirty.		Total.		Grand Total.
	Males.	Females	Males.	Females	Males.	Females	Males.	Females	
Karvir ...	19,269	18,342	19,708	18,973	22,048	21,914	61,025	59,229	120,254
Panhála ...	16,892	16,261	16,017	14,889	17,428	17,043	50,337	48,193	98,530
Bhudargad ...	12,965	12,700	13,739	12,668	14,520	14,155	41,224	39,523	80,747
Shirol ...	10,811	9817	14,096	10,414	16,382	12,369	40,789	32,600	73,389
Gadinglaj ...	17,821	17,401	17,796	17,153	19,462	19,884	55,079	54,438	109,517
Alta ...	12,824	12,223	11,329	11,188	14,230	14,242	38,383	37,653	76,036
<i>States.</i>									
Vishálgad ...	4941	4920	5065	4463	5546	4882	15,552	14,265	29,817
Bávida ...	6262	6285	5896	5679	6692	7165	18,850	19,120	37,970
Kágal ...	7168	7049	6514	6489	8186	8007	21,868	21,635	43,503
Ichalkaranji...	8125	7916	7709	7278	9090	9274	24,924	24,468	49,392
Total ...	116,578	112,914	117,869	109,194	133,564	129,025	368,031	351,133	719,164

## Chapter III.

## People.

## CENSUS DETAILS.

1853, 1872, 1881.

## Chapter III.

## People.

CENSUS DETAILS.  
1881.

Kolhápúr Population Sub-Division Details, 1881—continued.

SUB-DIVISION.	JAINS.									
	To Twelve.		Twelve to Thirty.		Above Thirty.		Total.		Grand Total.	
	Males.	Females	Males.	Females	Males.	Females	Males.	Females	Persons.	
Karvir ...	746	707	806	716	1000	988	2552	2411	4963	
Panhála ...	55	49	72	50	95	71	242	170	392	
Bhudargad ...	127	143	201	164	252	234	580	541	1121	
Shirol ...	2404	2246	2888	2287	3584	2632	8876	7135	16,011	
Gadinglaj ...	514	514	549	576	735	708	1798	1793	3,591	
Alta ...	2016	2020	2058	1888	2605	2468	6079	6376	13,055	
<i>States.</i>										
Vishálgad ...	6	6	17	6	17	11	40	23	63	
Bávida ...	38	41	44	41	57	49	139	131	270	
Kágál ...	613	630	551	519	747	768	1911	1917	3828	
Ichalkaranji...	561	524	511	446	688	708	1790	1678	3468	
Total ...	7080	6880	7697	6643	9780	8652	24,557	22,175	46,732	
MUSALMA'NS.										
Karvir ...	823	778	817	795	973	920	2613	2493	5106	
Panhála ...	269	262	264	257	316	262	849	781	1630	
Bhudargad ...	248	241	252	210	287	249	767	700	1487	
Shirol ...	911	807	1318	749	1462	1003	3691	2569	6250	
Gadinglaj ...	903	892	951	892	1037	1023	2891	2807	5698	
Alta ...	1093	964	860	841	1112	1110	3065	2915	5980	
<i>States.</i>										
Vishálgad ...	196	207	204	162	283	194	633	568	1196	
Bávida ...	218	196	152	174	184	181	554	551	1105	
Kágál ...	360	307	307	319	387	403	1054	1029	2083	
Ichalkaranji...	421	400	410	363	426	467	1287	1230	2487	
Total ...	5442	5054	5535	4762	6417	5812	17,394	15,628	33,022	
CHRISTIANS.										
Karvir ...	34	30	37	29	40	29	111	88	199	
Panhála ...	8	5	11	9	6	3	25	17	42	
Bhudargad ...	75	78	80	92	83	77	233	247	485	
Shirol ...	...	...	...	...	1	...	1	...	1	
Gadinglaj ...	68	56	58	51	42	56	168	163	331	
Alta ...	...	...	...	...	...	...	...	...	...	
<i>States.</i>										
Vishálgad ...	3	2	2	3	3	...	8	5	13	
Bávida ...	...	...	1	...	1	...	2	...	2	
Kágál ...	10	7	5	6	5	6	20	19	39	
Ichalkaranji...	22	13	30	26	27	23	79	62	141	
Total ...	220	191	224	216	208	194	652	601	1253	
OTHERS.										
Karvir ...	2	2	1	1	4	1	7	4	11	
Panhála ...	...	...	...	...	...	...	...	...	...	
Bhudargad ...	...	...	...	...	...	...	...	...	...	
Shirol ...	...	...	...	...	...	...	...	...	...	
Gadinglaj ...	...	...	...	...	1	...	1	...	1	
Alta ...	...	...	...	...	...	...	...	...	...	
<i>States.</i>										
Vishálgad ...	1	...	2	1	1	...	4	1	5	
Bávida ...	...	...	...	...	...	...	...	...	...	
Kágál ...	...	...	...	...	1	...	1	...	1	
Ichalkaranji...	...	...	...	...	...	...	...	...	...	
Total ...	3	2	3	2	7	1	13	5	18	

## Kolhapur Population Sub-Division Details, 1881—continued.

## Chapter III.

## People.

CENSUS DETAILS.  
1881.

SUB-DIVISION.	TOTAL.								
	To Twelve.		Twelve to Thirty.		Above Thirty.		Total.		Grand Total.
	Males.	Females	Males.	Females	Males.	Females	Males.	Females	
Karvir ...	20,874	10,859	21,369	20,514	24,065	23,852	66,308	64,225	130,533
Panhála ...	17,224	16,577	16,864	15,205	17,845	17,379	51,433	49,161	100,594
Bhudargad ...	13,415	13,162	14,272	13,134	15,142	14,715	42,829	41,011	83,840
Shirol ...	18,626	12,870	18,302	13,400	21,429	16,024	53,357	42,294	95,651
Gadimglaj ...	19,306	18,863	19,354	18,672	21,277	21,066	59,937	59,201	119,138
Alta ...	15,933	15,207	14,247	13,917	17,947	17,820	48,127	46,944	95,071
<i>States.</i>									
Vishalgad ...	5147	5135	5290	4635	5800	5087	16,237	14,857	31,094
Bánda ...	6518	6522	6093	5894	6934	7395	19,545	19,811	39,356
Kágal ...	8099	7887	7337	7260	9267	9214	24,703	24,361	49,064
Ichalkaranji ..	9181	8959	8700	8186	10,290	10,532	28,171	27,677	55,848
Total ...	129,323	125,041	131,328	120,817	149,996	143,684	410,647	389,542	800,189

These details show that the proportion of males in the whole population was 51·32 and of females 48·68. Exclusive of Jains, Hindu males numbered 368,031 or 51·17 per cent and Hindu females 351,133 or 48·83 per cent of the Hindu population. Jain males numbered 24,557 or 52·55 per cent and Jain females 22,175 or 47·45 per cent of the Jain population. Musalmán males numbered 17,394 or 52·68 per cent and Musalmán females 15,628 or 47·32 per cent of the Musalmán population. Christian males numbered 652 or 52·04 per cent, and Christian females 601 or 47·96 per cent of the Christian population. Other males numbered 13 or 72·22 per cent, and other females 5 or 27·78 per cent of the other population.

Infirm persons were returned at 3003 (males 1725, females 1278) or thirty-seven in ten thousand. Of these 179 (males 101, females 78) or two in ten thousand were of unsound mind; 578 (males 319, females 259) or seven in ten thousand were deaf and dumb; 1444 (males 700, females 744) or eighteen in ten thousand blind, and 802 (males 605, females 197) or ten in ten thousand lepers.

The following statement gives the number of each religious class according to sex at different ages, with, at each stage, the percentage of the whole population of the same sex and religion. The columns referring to the whole population omit religious distinctions but show the difference of sex:

## Kolhapur Population by Age, 1881.

AGE IN YEARS.	HINDUS EXCLUDING JAINS.				JAINS.				MUSALMA'NS.			
	Males.	Percentage on Males.	Females.	Percentage on Females.	Males.	Percentage on Males.	Females.	Percentage on Females.	Males.	Percentage on Males.	Females.	Percentage on Females.
1 Year ...	10,170	2·78	10,058	2·86	639	2·00	576	2·59	525	3·01	448	2·86
1 to 5 ...	32,997	8·96	34,116	9·71	2186	8·90	2302	10·38	1532	8·80	1496	9·57
5 to 12 ...	73,411	19·94	68,740	19·57	4255	17·32	4002	18·04	3385	19·46	3110	19·90
12 to 20 ...	52,618	14·29	43,754	12·48	3510	14·29	2701	12·18	2387	13·72	1893	12·11
20 to 30 ...	65,251	17·72	65,440	18·63	4187	17·05	3942	17·77	3143	18·09	2869	18·35
30 to 40 ...	56,406	15·32	50,080	14·26	3906	15·90	3183	14·35	2704	15·54	2385	14·62
40 to 50 ...	37,376	10·29	34,635	9·86	2783	11·33	2346	10·57	1848	10·62	1502	9·61
50 to 60 ...	22,333	6·06	22,889	6·10	1743	7·09	1559	7·03	1063	6·11	966	6·18
Over 60 ...	16,969	4·61	21,421	6·51	1348	5·48	1564	7·05	802	4·61	1059	6·77
	368,031		351,133		24,557		22,175		17,394		15,628	

### Chapter III.

## People.

CENSUS DETAILS.  
1881.

*Kolhapur Population by Age, 1881—continued.*

AGE IN YEARS.	CHRISTIANS.				OTHERS.				TOTAL.			
	Males.	Percentage on Males.	Females.	Percentage on Females.	Males.	Percentage on Males.	Females.	Percentage on Females.	Males.	Percentage on Males.	Females.	Percentage on Females.
1 Year	19	2.91	21	3.49	1	7.69	...	...	11,354	2.76	11,103	2.85
1 to 5	59	9.04	57	9.48	...	...	...	...	36,774	8.93	37,971	9.74
5 to 12	142	21.77	113	18.50	...	15.38	...	...	51,185	19.77	75,967	19.50
12 to 20	113	17.33	92	15.30	...	7.69	...	...	53,620	14.27	48,441	12.43
20 to 30	111	17.02	124	20.33	...	15.38	...	...	72,690	17.70	72,376	18.57
30 to 40	96	14.72	83	13.81	...	...	...	...	63,116	15.36	55,632	14.28
40 to 50	59	9.04	45	7.43	...	30.76	...	...	42,566	10.38	38,598	9.59
50 to 60	35	5.36	32	5.32	...	15.38	...	...	25,176	6.13	25,446	6.50
Over 60	18	2.76	34	5.65	...	7.69	...	...	10,183	4.66	24,078	6.18
	652		601		13		5		410,647		389,542	

*Marriage.*

The following table shows the proportion of unmarried, married and widowed:

*Kolhāpur Marriage Details, 1881.*

[illegible]

According to occupation the 1881 census returns divide the population into six classes: i. In state service, learned professions, literature and arts 19,330 or 2·42 per cent; ii. In house service 9414 or 1·17; iii. In trade 3848 or 0·48 per cent; iv. In agriculture 492,957 or 61·61 per cent; v. In crafts and industries 67,417 or 8·42 per cent; and vi. In indefinite and unproductive occupation including children 207,223 or 25·90 per cent of the population.

According to the 1881 census, of 145,184 houses 129,148 were occupied and 16,036 were empty. The total gave an average of 51·56 houses to the square mile and the 129,148 occupied houses an average of 6·20 inmates to each house. Except tile-roofed mansions owned by rich men in towns and large villages, most Kolhápura houses are thatched in the rainy west and flat-roofed in the dry east. Most houses in the Gadinglaj and Shirol sub-divisions and in the petty divisions of Katkol and Ráybág are flat-roofed and in the Ajra, Bávda, Bhudargad, and Vishálgad sub-divisions which are close to the wet Sahyádris are thatched. Town houses are generally built with burnt brick; most rural houses are built of stone or sun-dried brick and mud, mortar-pointed mud, or mortar. Window and door frames, door panels, and window shutters are generally made of *bábhul*, mango, or *jámbhul*, sometimes of *umbar*, and in the houses of the rich of teak. Bamboo and teak rafters are largely used.

Kolhápura houses may be arranged under four classes. Houses of the first class, which are generally two-storeyed or *dumajli*, are built round quadrangles with stone or burnt brick walls, tiled roofs, and verandas. These houses contain *osris* or halls used for large dinner parties and office room, three or more sleeping-rooms, rooms for keeping clothes and ornaments, a central store-room, a cook-room, and a god-room. In the rear of the house are a cattle shed and a bathing-room. A privy is attached to a distant corner either in front or behind according to convenience of the building. In the rear yard, where there is a rear yard, are flower and plantain trees with a *tulas* or holy basil bush in a masonry pillar pot. The houses have room for fifty to eighty retainers, but are close and badly aired. The fronts are ornamented with carved wood, and on the front walls in gaudy colours are drawn pictures of gods, goddesses, heroes, and wild beasts with alternate bands of white and red to scare the cholera spirit. Houses of the second class are generally one-storeyed with burnt or unburnt brick walls and tiled or flat roofs; they contain three or four rooms. In towns the second class houses are roomy and showy and when held by shopkeepers and craftsmen the verandas are made into shops or work rooms. Houses of the third class though smaller than first or second class houses, when occupied by husbandmen are roomy and have large cattle sheds. They are one-storeyed with unburnt brick walls and two rooms. Houses of the fourth class are single-roomed thatched huts with mud or mud wattled reed, millet, or cotton stalk walls, roofed by a bamboo frame covered with grass and *palas* leaves. Houses of this class are generally owned by labourers.

According to the 1881 census five towns, three in Kolhápura and two in the smaller states, had more than 5000 and one of the five

### Chapter III. People.

#### CENSUS DETAILS. Occupation.

#### Houses.

#### Villages.

## Chapter III.

## People.

## CENSUS DETAILS.

## Villages.

more than 20,000 people. Excluding these five towns, which together numbered 66,023 or 8·25 per cent of the population, the 734,166 inhabitants of Kolhápúr were distributed over 1056 villages giving an average of one village for every 2·66 square miles and of 695 people to each village. Of the 1056 villages 184 had less than 200 people, 382 between 200 and 500, 306 between 500 and 1000, 123 between 1000 and 2000, 34 between 2000 and 3000, and 27 between 3000 and 5000. The Kolhápúr villages are of two classes, walled and open. Some of the village walls are of burnt brick and mud and some are of stone and mud. Some old villages have stately gates and ruined fortifications. Though proud of their old walls and gates, the villagers seldom take any steps to keep them in repair. In most villages houses are not built in rows but are scattered all over the village site. Kunbis or husbandmen, Maráthás, Jains, and Lingáyats, form the bulk of the village population. Dhangars or shepherds and other herdsmen live with their herds on the hills. In the skirts of the villages are the quarters of the Mhárs, Mángs, Chámhbárs or shoemakers, and Dhors or tanners whom most villagers hold impure.

## COMMUNITIES.

As in the Deccan the Kolhápúr villages, besides husbandmen and labourers, have the regular staff of *balutedárs* or hereditary village officers and servants. The *balutedárs* are: the *pátíl* or headman, the *kulkarni* or accountant, the *joshi* or astrologer, the *gurav* or temple servant, the *sutár* or carpenter, the *lohár* or blacksmith, the *kumbhár* or potter, the *sonár* or goldsmith, the *nhávi* or barber, the *parit* or washerman, the *tarál* or beadle, the *gasti* or watchman, the *gávasanadis* or plain militia and the *gadkaris* or hill fort garrisons, the *mhár* or sweeper, the *máng* or rope-maker, and the *chámhbár* or leather-worker. Besides these some villages have a *jangam* or Lingáyat priest, an *upádhyá* or Jain priest, a *kázi* or Muhammadan marriage registrar, and a *mulla* or Musalmán priest and butcher. In large villages, in addition to these office bearers and servants, are the *shetya* or broker, the *magdum* or carter, and the *chaugula* or assistant headman who supplies provisions to travellers. Though they enjoy hereditary lands, the *deshmukh* or hereditary district revenue superintendent and the *deshpándya* or hereditary district accountant have no official duties. The members of the village staff are divided into State servants and village servants. The State members include the *pátíl* or headman, the *kulkarni* or accountant, the *tarál* or beadle, the *gasti* or watchman, the *mhár* or sweeper, and either the *gávasanadis* or village militia, or the *gadkaris* or fort garrison. Militia and fort garrisons are not found in small villages and some villages have no *gastis* or watchmen. The *pátíl* or headman is occasionally aided by a *náik* or leader, who in the headman's absence exercises the full powers of a headman.

Towns and large villages have two headmen one called the *mulki* for revenue work and the other for police work. Each *pátílki vatan* or headman's hereditary estate is generally shared by two or three persons called sharers or *takshimdárs* the different sharers taking charge of the office in rotation. Village headmen are generally Maráthás, Jains, or Lingáyats, and in rare cases Bráhmans, Musalmáns, Berads, and Mhárs. Besides a plot of rent-free land each headman



when in office receives a fixed yearly cash payment. The office of headman is generally hereditary, and is much sought after. He holds a high position among the villagers and is greatly respected. As the social head of the village he leads all village festivals and is the first to receive the betel-packet or *pánsupári* at marriages and on all public occasions. On *Dasara* Day in September-October he leads the *shami* Prosopis spicegera worship; on *Holi* in February-March he is the first to worship the bonfire and orders it to be lighted; at a marriage he is the first to receive the betel-packet and distributes money among *balutedárs* or village servants; no widow-marriage or *pát* can be performed without his consent; and at a feast he and his wife are given the first seats. Petty squabbles are referred to his arbitration, and his wife takes a most active though indirect part in village affairs. Her word is respected and she has considerable influence in settling family disputes. In many villages the headman lends money to the villagers and has a good name for treating his debtors kindly. Many are known to have for years never sought the aid of the civil courts or pressed their debtors severely. The village clerk or accountant called *kulkarni* keeps the village accounts. With a few exceptions the *kulkarnis* are Bráhmans. According to their size and revenue each accountant has a charge of one or of a group of two or three small villages. The office of village accountant is generally hereditary. Where there is no hereditary village clerk, his work is done by a stipendiary clerk. Besides rent-free land they have fixed money stipends. The *tarál* or beadle, who is either a Mhár, Máng, Berad, Koli, or Nhávi sweeps the village office or *chávdí*, lights its lamp and carries the village account books. He is paid in land. The *gastí* or watchman is also paid in land. Almost all villages have a Mhár sweeper, who is generally hereditary and who is paid partly in land and partly in cash. Besides as a sweeper, the Mhár acts as a guide to travellers and carries public and private messages and public money. He removes dead cattle, and, besides the skin of the dead animals, receives a grain allowance from the village landholders. The *gávsandís* or militia and the *gadkaris* or fort garrisons are paid in land and are village police. The members of the village staff are generally paid by the landholders in grain. The *joshi* or astrologer, who is not found in some small villages, is a Bráhman. He reads the almanac, fixes lucky days for marriages and for ploughing sowing and reaping, calculates eclipses, prepares birth-papers, and conducts marriage death and other ceremonies for all Bráhmanic Hindus. Lingáyats have their own priests called *jangams* and Jains have their priests called *upádhyás*. The temple servant who is almost always a Gurav by caste cleans and lights the temple, takes the offerings made to the gods and supplies water to Government servants. The *sutár* or carpenter makes and mends field tools and the high marriage-stools called *chaurangs*, and supplies travellers with tent and cattle pegs. The *lohár* or blacksmith makes and mends the iron parts of field tools and carts. The *kumbhár* or potter supplies villagers and travellers with earthen pots. The *sonár* or goldsmith who is also called *potdár* or assayer, tests the coins paid into the State, and makes gold and silver ornaments. The *nhávi* or

## Chapter III.

## People.

## COMMUNITIES.

## Chapter III.

## People.

## COMMUNITIES.

barber who is also the village surgeon, shaves the villagers, and trims their bullocks' tails. The *parit* or washerman washes the villagers' clothes, gives them *pásodi* or rough cloth for crystallising molasses, and at marriage spreads a large white cloth for the bridegroom's kinsfolk to walk on. The *máng* plays the *halgi* or tabor, gelds cattle, and makes ropes. The *chámhbár* or leather-worker makes and repairs shoes and the leather work of field tools. Besides husbandmen, labourers, and craftsmen, grain dealers and moneylenders are found in most villages. They are either Gujarát or Márwár Vánis who have come to the State during the last fifty years. The older settlers are considerate to their debtors; but the newcomers are grasping, unscrupulous, and hard. Each villager is free to graze any number of cattle in the village pasture, which in most cases lies near the village. The cattle drink out of the village trough or from the river. When the crops are standing, cattle are grazed by a boy during the day and confined in cowpens at night; at other times they are let loose to graze. Except by the depressed classes, who have generally either a well of their own or a cistern filled for them from the village well, the village drinking reservoir or well is used by all classes. If a river or stream runs by the village the depressed classes draw water from it below the village. If they want a new work of local usefulness or want to repair an old work, villagers apply to the State to aid from local funds. Contributions for repairing temples and other works of religion and charity are levied on holdings and ploughs. Fuel is gathered from common lands about the village and bush lands near the hills. For two generations after they arrive a family of newcomers do not gain the full rights of villagers.

## MOVEMENTS.

Except Lamáns or carriers who are said to have come within the last 200 years and who wander as carriers all over the State, few people move about or leave the State in search of work. Living is cheap, and the State public works which have been in progress for several years keep up a constant local demand for labour. Of outsiders who have settled in the State, Bráhmans have come from the Konkan, Belgaum, and Dhárwár and settled as clerks, government servants, and priests; a few Gujarát and Márwár Vánis have come from Gujarát and Márwár as traders and moneylenders; Musalmáns have come from Miraj as traders, shopkeepers, and moneylenders; Lonáris or lime-burners have come from Sátára and permanently settled as lime-makers; and the few Chinese came as wood and cane-workers, and now take public-works contracts. Besides these a large number of Vadárs or stone and earth-workers, carpenters from the Konkan, and Kadiyás or bricklayers from Bombay are employed on State public works.

Kolhápúr Hindus belong to three main religious classes, Bráhmanical Hindus, Jains, and Lingáyats. Before the rise of Basav (1100-1168) the founder of the Lingáyat faith, like the rest of the Bombay Karnáta, Kolhápúr was under a Jain prince, a feudatory of the Jain Kalachuri Bijjal (1156-1167) who had usurped the throne of Kalyán. After the time of Basav the Lingáyat faith spread in Kolhápúr and became the popular religion. For descriptive purposes Kolhápúr Bráhmanical Hindus may be arranged into

Bráhmans, writers, fighting men, traders, husbandmen, craftsmen, musicians, servants, shepherds, labourers, unsettled tribes, depressed classes, beggars, and miscellaneous classes.

**Bra'hmans** include thirteen classes with a strength of 29,446 or 3·84 per cent of the Hindu population. The details are :

*Kolhápúr Bráhmans, 1881.*

DIVISION.	Males.	Females	Total.	DIVISION.	Males.	Females	Total.
Chitpávans ...	2247	1859	4106	Karhádás ...	2026	1633	3659
Deshasths ...	9646	8470	18,116	Mádhyaúdins ...	40	30	79
Devrukshás ...	43	33	76	Saváshás ...	26	35	61
Dravids ...	21	17	38	Shenvís ...	1506	1410	2916
Golaks ...	101	91	192	Telangs ...	19	9	28
Gujarátis ...	30	6	36	Tirguls ...	57	50	107
Kanaujs ...	22	10	32	Total ...	15,793	13,653	29,446

**Chitpávans**, supposed to mean pure from the pyre, but who probably take their name from Chitapolan the Sanskrit form of Chiplun in Ratnágiri, are returned as numbering 4106 and as found over the whole district.<sup>1</sup> Most of them have come to Kolhápúr during the last fifty or sixty years. They are fair and thrifty like Poona Chitpávans from whom they do not differ either in appearance or in religious or social customs. Most of them are State servants and a few are moneylenders, traders, priests, and beggars. They send their children to school and are well-to-do. They are a pushing class.

*Chitpávans.*

**Deshasths**, generally supposed to mean Upland but more probably meaning Local Bráhmans, are returned as numbering 18,116 and as found over the whole State. They form the largest section of Kolhápúr Bráhmans and are settled both in towns and in villages. Almost all village accountants or *kulkarnís* are Deshasths. Except some Joshis or astrologers, Japes or bead-counters, and Pujáris or ministrants who say that about 700 years ago they came there to conduct the worship of Ambábái in Kolhápúr, they have no memory of any former settlement. Deshasths are of two main classes Rigvedis and Yajurvedis. Rigvedis are divided into Smárts and Vaishnavs and Yajurvedis into followers of the white and of the black Yajurved. These four classes of Deshasths and Yajurved Dravids and Telangs eat together, but families who follow different Veds do not intermarry. The names in common use among men are Anant, Govind, Shankar, and Vitthal; and among women Bhaváni, Durga, Ganga, Lakshmi, Rama, and Yamuna. Among men, such compound names as Manohar, Gauri-Shankar, and Yajneshvar are not uncommon. When a woman loses several infants, to deceive the evil spirits and make them think the child is little valued and is not worth carrying away, she calls her next child Dhondu that is stone or Keru that is rubbish. When a son is greatly wanted, if a girl is born she is called Thaki that is deceiver or Ámbi that is sour. Men add *ráv*, *bába*, *tátya*, *káka*, and *bháu* to their names and women *bái* to theirs. Most Deshasth surnames are either office or calling names or place names, such as Deshmukh,

*Deshasths.*

<sup>1</sup> Details of the mythical origin and customs of the Chitpávan Bráhmans are given in the Poona Statistical Account.

### Chapter III. People.

#### BRÁHMANS, Deshasths.

Kulkarni, and Ajrekar. They belong to the Agasti, Angiras, Atri, Bhrigu, Káshyap, Vasishth, and Vishvámitra *gotras* or family stocks. Among members of the same section intermarriage cannot take place if the family stocks or *gotras* are the same, but persons bearing the same surname can intermarry if the surname is merely an office or calling name and the family stock is different. Their family gods are Ambábái of Kolhápúr, Bánsankari of Bádámi, Durga, Gajánan, Jogeshvari, Jotiba of Vádi-Ratnágiri in Kolhápúr, Khandoba of Jejuri in Poona, Rám, Shiv, and Vishnu.

As a rule Deshasths are dark strong and regular featured, rougher harder and less acute than Chitpávans. The women like the men are dark rough and not so goodlooking as Chitpávan women. Both at home and abroad they speak less correct Maráthi than the local Chitpávans and pronounce the words more like Kunbis. In their speech they add the termination *ki* to every verb and change the initial *i* to *vi* and *vi* to *i*. They speak a broad Maráthi with a drawl and without the Chitpávan nasal twang.<sup>1</sup> Most Deshasths live in houses of the better class generally two storeys high with brick walls and tiled roofs. As a rule their houses are dark and badly aired. The rooms are low and the staircases steep and narrow. The privy is generally so close to the door that the entrance is most unsavoury. The houses of the rich are large and comfortable; but many of the poor are badly housed or plantains are reared in front of and behind the house where the dirty water is allowed to gather. Their house goods include copper and brass vessels, cots, bedding, and quilts. A few rich families have servants and pet animals and many have cows and buffaloes. They are strict vegetarians and good cooks, their staple food being millet bread, pulse, clarified butter, curds, milk, and condiments. They eat rice only on holidays and their special dishes are the same as those described in the account of the Poona Chitpávans. Except the Shákts or worshippers of female spirits, and some English-taught youths, they do not use liquor and few among them either smoke tobacco or hemp, or drink hempwater. Snuff-taking and tobacco-chewing are common and betel-eating is universal. The men shave the head except the topknot and the face except the moustache and sometimes the whiskers. The women dress their hair neatly, smooth it with oil, plait it in a braid which they wear at the back of the head in an open circular coil in shape like a scorpion's sting. They generally wear false hair but do not use flowers. The indoor dress of a Deshasth man is a waistcloth and a shouldercloth and sometimes a shirt. When he goes out he puts on a coat, a turban or headscarf, and a pair of sandals or shoes. While taking food or performing his twilight or *sandhya* worship he dresses in a silkcloth or *mukta* or freshwashed untouched cotton cloth and lays a small piece of cloth on his shoulder. Deshasth women dress in the long Marátha robe and bodice passing the skirt back between the feet. Married

---

Among peculiar Deshasth words and expressions may be noted : *hata* a key, *mola* a nail, *gavari* for *govari* a cowdung cake, *haito* for *aheto* he is, *vhay* for *hoy* yes, *nhava* for *náhi* no, *astýata* for *astát* are, *jáva* for *já* go, *phava* for *pohás* beaten fried rice, *tyánsni* for *tyánd* to them, *viláj* for *iláj* remedy, and *istav* for *vistav* fire.

women as a rule mark the brow with vermilion and put on the lucky necklace and toerings or *jodvis*, while widows shave their heads and cover them with one end of their robes and never put on bodices. Children of less than six run naked about the house. A schoolboy on ordinary days wears a coat and a cap or headscarf and on holidays a small turban and waistcloth. When the thread-girding ceremony is performed he puts on a loincloth or a waistcloth. A girl before she is ten wears a petticoat or *parkar* and a bodice; after ten she wears a small robe or *sáddi* without passing the end over her shoulder like a grown woman, and either leaves the bosom bare or covers it with a bodice. When she is married the husband draws the end of the robe over her shoulders and she then dresses like a grown woman. Women almost never wear shoes. The use of shoes and a parasol marks the courtesan. Both men and women have a store of rich clothes and ornaments<sup>1</sup> many of which have been handed down two or three generations. As a class Deshasths are indolent and untidy but thrifty and hospitable and franker and less cunning than Chitpávans. Their want of enterprise has given them the name of *dhámyás* or stay-at-homes and their slovenliness is so great that Deshasth disorder is a byword.<sup>2</sup> They are writers, bankers, moneylenders, moneychangers, traders, leeches, landholders, priests, and beggars. The priests and beggars are poor; the rest are well-to-do. Their daily life does not differ from that of Ahmadrnagar Deshasths. They claim to be superior to all classes, and profess to look down on Chitpávans as new Bráhmans or Parashurám *srishti* that is Purashurám's making. At the same time they freely associate and eat with Chitpávans and Karhádás, though, except in a few cases, they do not marry with them. They are both Smárts and Bhágvats, worship all Bráhmanic and local gods and goddesses, and keep all fasts and festivals of which the *shimga* or boundary festival in February-March is perhaps the chief. Their priests belong to their own caste and they make pilgrimages to all Bráhmanic sacred places and rivers. Their high priest is Shankarácharya, the great Smárt pontiff who lives at Sankeshvar. They worship all local and boundary gods, and believe in witchcraft and soothsaying and lucky and unlucky omens.

Under the head of customs come the sacraments or *sanshárs*, which are of two kinds, *nitya* or usual and *náimittik* or special. The sixteen usual sacraments must be performed; the performance of the twenty-four special sacraments is a matter of choice. The sixteen sacraments are the *garbhádán* or conception which is performed soon after a girl comes of age; the *punsavan* or son-giving that the child may be a boy; the *anavalobhan* or longing-satisfying during the seventh month of pregnancy when the juice of the sacred grass is dropped down the girl's left nostril that the unborn child may grow, the *simántonnayan* or carrying to the limit in the sixth or eighth month when the woman's hair is parted down the middle and a *bábhul* thorn is drawn along her head and fixed into her hair behind;

### Chapter III. People.

BRÁHMANS.  
*Deshasths.*

<sup>1</sup> Details are given of Chitpávan customs in the Poona Statistical Account.

<sup>2</sup> The Maráthi runs: *Deshasth Vá gairshist*, Deshasth or disorder.

## Chapter III.

## People.

BRÁHMANS.

*Deskasthis.*

the *Vishnu bali* or Vishnu offering during the eighth month to free the child from sin and ensure a safe birth; the *játharm* or birth ceremony when before the navel-cord is cut, honey is dropped into the child's mouth; the *námakaran* or naming on the twelfth day when also the child is cradled; the *suryávalokan* or sun-showing in the child's third month when the mother, holding a churning rod in her hand, shows the child to the sun; the *nishkraman* or going out in the third month when the child is taken to a temple and well-water is worshipped; the *upaveshan* or sitting in the fifth month when the child is first allowed to sit on the ground; the *annaprāshan* or food-eating, the first feeding on solid food in the fifth or sixth month; the *chaul* or shaving in the fourth or fifth year; the *upanayan* or initiation also called the *munj* from the grass Saccharam munja; the girding with sacred thread in the boy's seventh or eighth year; the *samāvartan* literally returning or freeing from being a *brahmachāri* or unwed student on the twelfth day after the *munj* or thread-girding; the *vivāh* or marriage at any time after the eighth year; and the *svargāvrohan* literally heaven-mounting that is death. The chief of these sacraments are those at birth, thread-girding, marriage, girl's coming of age, pregnancy, and death. During the first ten mornings after the birth of a child the father employs Kunbi women to pour water on the threshold of the house in honour of the birth. Sometimes the father is made to bathe in cold water, and clad in his wet clothes to drop a little honey from a gold ring into the child's mouth and then bathe in warm water. The midwife cuts the child's navel-cord, waves a silver coin round the cut cord and buries it outside of the house along with another copper or silver coin. The midwife is presented with the silver coin which was waved round the navel cord. She attends the mother ten to ninety days. Every evening at the mother's house the family priest recites soothing verses or *shāntipāth* over a pinch of ashes or *angāra* and hands it to some elderly woman to be rubbed on the brow of the mother and child as a guard against attacks of the evil eye or of spirits. On the fifth night the maternal uncle lays a sickle washed with lime and covered with a piece of bodicecloth on a low stool in the lying-in room, and lays before the sickle sandal-paste, flowers, turmeric paste, vermilion, and food in the name of the Pānchvi or Mother Fifth. A blank sheet of paper and a reed pen and ink are set before the goddess and the priest burns asafoetida or *hing*, repeats sacred verses over some ashes, and gives them to be rubbed on the child and the mother and on other young children in the house. On the sixth night the child's father worships Mother Sixth with the same rites as the maternal uncle used on the fifth night; a light is kept burning the whole night in the lying-in room, and the women of the house pass the two nights awake playing games of chance before the goddess and singing songs, for the fifth and sixth nights are a critical time to the newborn child. The family of the child's father is held impure for ten days after a birth.

On the tenth day both the mother-in-law and the mother of the confined woman present her with sweet fried rice cakes or *ghārgās*, lay in her lap wheat and a cocoanut and a robe and bodice cloth, give her turmeric paste and vermilion to rub on her face



and brow and wave a light round her head. The mother takes her food, dips her fingers in a silver cup with milk, *durva* grass, and silver coin, and thrice touches her left ribs with her fingers. The mother's mother takes the silver coin and leaves the room. On the morning of the eleventh the child is bathed, the house is cowdunged, the mother's clothes are washed, and she is bathed in warm water. Besides by this bath the mother is cleansed from the impurity of childbirth by the priest dropping water from *tulsi* leaves on her head. The men of the house sip water mixed with the five products of the cow and renew their sacred threads. On the twelfth day a feast is given to Bráhmans and married women and friends and kinsfolk are treated to a dinner. Women neighbours are asked to the house to attend the naming or *bársa*. The goldsmith comes to the house and pierces the child's ear lobes. Ornaments and clothes, especially a child's hood or *kunchi* and a small coat, are made ready for the child, and kinswomen drop in each with a bodicecloth for the mother and a hood or *kunchi* for the child. In the lying-in room a cradle is hung to the ceiling and a carpet is spread under it. Women neighbours and relations take their seats on the carpet, and the mother takes her seat on a low stool with the child in her arms. The women one by one fill the mother's lap with wheat and a cocoanut and bodicecloth and the hood for the child, mark her brow with vermilion, present her with turmeric paste which she rubs on her face, and arrange themselves in two groups one on either side of the cradle. They take a cocoanut clad in a child's hood or *kunchi*, cover the bottom of the cradle with a particoloured quilt, and pass the cocoanut over and below the cradle five times. A woman in one of the groups lays the cocoanut in the cradle and says, Take Govind, and a woman in the other group takes it saying, Give Govind. After they have done this five times some matron takes the child in her arms and lays it in the cradle bidding the mother repeat the child's name in its ear. In most cases the women consult the child's mother and settle among themselves what should be the name of the child. The mother then loudly repeats the name in the child's ear, ending with the meaningless sound *kur-r-r*. The guests then gently swing the cradle and sing a cradle song or *pálna* lulling the child to sleep with a chorus, Sleep, my darling sleep.<sup>1</sup> The cradling ends with the distribution of boiled gram and packets of sweetmeat, and the guests retire, after receiving from the houseowner vermilion and turmeric paste which they rub on their brows and cheeks. Widows are not allowed to take any part in a cradling.

When the child is a month old comes the ceremony of growth or *vardhpan* when the mother lays sandal-paste, flowers, and sweetmeat before a pillar in which dwells the deity who presides over the child's growth, bows before it with the child in her arms, and slides the child up the pillar. This is repeated at the end of every month till the child is a year old. The mother keeps her room for three full months. At the end of the third month the mother wears new bangles, dresses

## Chapter III.

## People.

BRÁHMANS.

*Desasths.*

<sup>1</sup> The Maráthi runs : *Jo jo, re, nij bála, jo jo.*



## Chapter III.

## People.

## BRÁHMANS.

*Deshasths.*

her hair, puts on a new robe and bodice, and visits the village temple with the child in her arms. She lays a bodicecloth and a cocoanut before the village god and bows to him with the child in her arms, offers the *shashthi devi* or Satvái another bodicecloth and cocoanut and returns home. Next comes the feeding or *annaprāshan* when some priests, friends and kinsfolk, and married women are treated to a sumptuous dinner. The child's maternal uncle dips a gold ring in a cup holding *khir* or rice boiled in milk mixed with sugar, and lets a few drops of milk fall from the ring into the child's mouth. From this day the child is fed with cooked food. The anniversary of the birth is marked by a feast, and soon after the child is a year old, hair-clipping or *chuda* is performed because a second child may be coming on and it is a rule that no child should see its elder brother's first hair. On a lucky day, a plot in the veranda is coudunged, on it a square is marked with wheat flour, and in the square is set a low stool covered with a bodicecloth which also is marked with a square of wheat. The boy is seated on the bodicecloth and the village barber shaves his hair leaving a lock on the crown and one above each ear and in return is given the bodicecloth and the wheat. The boy is bathed and dressed in new clothes; married women wave lights round his head and the hair-clipping ends with a feast to Bráhmans and married women.

As a rule a boy is girt with the sacred thread in his eighth year. Before the lucky day chosen for the thread-girding the boy's friends and relations give feasts called *gadganers* or *kelvans* meaning merry-makings. The kinsman or friend visits the boy's house and puts a cocoanut into his hands as a sign that he is asked to the dinner. The boy goes to his relation's house, his brow is marked with vermilion, grains of rice are stuck on the vermilion, and he is feasted with a few of his friends. A day or two before the thread-girding an invitation procession consisting of the houseowner's friends and relations of both sexes starts in the evening with music and visits the local temple of Ganpati where the boy's father lays a cocoanut before the god and bows to him, and the priest prays to the god to be present at the ceremony together with his two wives Riddhi and Siddhi the goddesses of plenty and success, and by his holy presence remove obstacles which might come in the way of completing the ceremony. The priest lays yellow rice before the god as a sign of invitation and some married women do the same and ask his attendant goddesses. The procession moves from door to door, the boy's father folding his hands before every houseowner and the priest telling him the day and the hour, asks him with his family and attendants to attend the ceremony at his master's house. The married women who come to ask go into the house, are seated, and ask the women of the family to attend the ceremony. The mistress of the house lays a cocoanut and rice in the askers' laps and marks their brows with vermilion as a sign that the invitation is accepted. In token of accepting the invitation the houseowner presents the boy's father or his priest with a betelnut and the procession leaves the house. The askers do the same at every house, while by degrees the men and women who at first formed part of the procession steal away one by one until the boy's father and his family with the

priest and musicians are alone left. To friends and relations who live in distant villages invitation cards are sent marked with vermilion. A square of earth is raised in the booth built in front of the boy's house and adorned with a canopy. The front of the square is decked with plantain trees set upright at both ends and at each corner five earthen pots smeared with whitewash and red stripes are piled surrounded by sugarcanes. The raised square has an earthen back with steps rising one above the other and a cone of earth at the top. This raised mound or altar they call *vedi* or *bahule*. Then follows the guardian establishing or *devak sthápana*, which, among Rigvedi Smárts, is the same as among the other Bráhmans.<sup>1</sup> On the morning of the lucky day married kinswomen and neighbours meet at the boy's house, where the boy and his parents are dressed in their best and seated each on a low stool covered with a sheet and red cloth marked with a lucky cross or *svastik* strewn in wheat grains. Two pestles are tied together with a bodicecloth and a basket filled with wheat is set before the boy and his parents. The married women then wash the feet of the boy and his parents and wave lights round them. Wheat and fruit are laid in the mother's lap, betel is served to the boy's father, and a cocoanut is put in the boy's hands. Not less than five married women take the two pestles in their hands, set them upright in the basket, and move them up and down as if to pound the wheat in the basket. They sing songs and native music plays. A married woman takes a handful of corn and grinds it in a handmill to which a bodicecloth is tied. Fragrant oil is rubbed on the boy and his parents, and the business of the married women is over. The boy's head is shaved by the barber, he is bathed and taken to the dining hall where his mother seats him on her lap, and feeds him eating from the same plate. After this the boy is not allowed to eat from his mother's plate. The boy's head is again shaved, and he is bathed and taken to his father in the booth. As the lucky moment draws near, the friends and kinspeople asked to the ceremony meet at the house and take their seats in the booth. The father sits on a low stool placed on the altar or *vedi* with his face to the east, while the boy stands before him facing west, and the priests hold between them a curtain marked with a vermilion lucky cross or *svastik*. The boy's sister stands behind the boy with a lighted lamp and a cocoanut in her hands. The priests repeat lucky verses and the guests throw red rice at the boy and his father. At the lucky moment the musicians redouble their noise, the curtain is drawn on one side, and the boy is girt with the sacred thread and dressed in a loin-cloth or *langoti*. The boy is given a deer skin to wear, a *palas* *Butea frondosa* staff is placed in his hands, and a triple sacred-grass cord or *munj* is wound round his waist.

The priests kindle the sacred fire on the altar and throw into the fire offerings of clarified butter sesame and seven kinds of wood.<sup>2</sup>

### Chapter III.

#### People.

BRÁHMANS.

*Deshashis.*

<sup>1</sup> Details are given in the Chitpávan Bráhman customs in the Poona Statistical Account.

<sup>2</sup> These seven kinds are, *palas* *Butea frondosa*, *khair* *Acacia catechu*, *rai* *Calotropis gigantea*, *ashvath* *Ficus religiosa*, *umbar* *Ficus glomerata*, *agháda* *Achyranthes aspera*, and *shami* *Prosopis spicigera*.

## Chapter III.

## People.

## BRÁHMANS.

## Deshasths.

Money presents are given to the priests, and cocoanuts, betel leaves and nuts, flowers, and perfumes are handed among the assembled guests, who take their leave. At noon Bráhmans and married women are feasted. In the evening the *bhikshála* or begging procession goes to the temple of Máruṭi as he is said to be the great bachelor or *brahmachári*, the boy attended by his priest bows before the god, and the procession returns home with music and company. Fire-works are let off. On returning home the boy is seated on the altar or *vedi*, the priest sits near him, and places a bamboo basket or a winnowing fan before him. The mother of the boy comes and stands before him on the altar. The boy says to her in Sanskrit *Bhavati bhikshám dehi*, Lady, give me alms, and holds the bamboo basket before her. The mother blesses him and puts sweet balls, rice, and cocoa-kernel into the basket. Other married women follow her example; the boy repeats the same words to each, and each presents him with sweet balls or money. The contents of the bamboo basket go to the priest who gives part of the sweetmeats to the boy and keeps the rest for himself. The ceremony ends on the fourth day, when, as on the first day, the betelnut Ganpati and the metalpot Varun are invoked and at the end laid on a bamboo winnowing fan and bowed out and the back of the fan is beaten with a stick to show that the ceremony is over, and it is time for friends and kinsfolk to leave. This practice has given rise to the Maráthi phrase *Sup vájle* or the winnowing fan has been struck that is All is over. The boy is now called a *brahmachári* that is an unwed or religious student. Widows and married women lay sandal-paste, flowers, and sweetmeats before him, present him with money, and sip the water in which his feet have been washed. Every morning and evening the boy is taught Vedic texts. After some months the *samávartan* or returning ceremony is performed. The boy puts off the triple sacred-grass waistcord or *mung* and his loincloth or *langoti*, puts on a silk-bordered waistcloth, a coat, a shouldercloth, a turban, and a pair of shoes, takes an umbrella, and sets out as if on a journey to Benares. The priest meets him on the way and promises to give him his daughter in marriage so that the boy may marry and become a *grihasṭh* or householder. Until after the *samávartan* or return ceremony is performed the boy is not affected by birth or death impurities but after the return ceremony is performed he has to remain apart for some days if any of his family had died or given birth to a child between the thread-girding and the *samávartan* or returning. After the return ceremony the boy may marry or not, and is subject to the rules of impurity observed by married Bráhman family men.

Boys are married between eight and twenty-five and girls generally before they are twelve. As soon as a girl is five years old, her parents begin to look out for a suitable husband for her. Whenever the mother meets other women either at home or abroad her chief talk is regarding her daughter's husband and widows who move more abroad than married women are consulted as to the merits of the different boys. When a boy is chosen, the girl's horoscope is put into the hands of the boy's father either by the girl's father or through some common

friend. The boy's father hands the girl's and his son's horoscopes to an astrologer, who, from his almanac tells him whether the boy's and girl's stars are in harmony and if the marriage will be lucky. The custom of consulting and comparing horoscopes is gradually falling into disuse as the parents of the couple hold that considerations of dowry or good looks are more important than the agreement of stars, and settle the marriage according to the *pṛiti vivāh* or love form in which no consultation of horoscopes is required. Thus at present a girl is sometimes chosen for her good looks or for money and sometimes friendship determines the choice irrespective either of money or beauty. The father or some near relation of the boy is asked to the girl's house to see the girl and is welcomed by the girl's father. If any of the boy's kinswomen comes with the father she goes into the house and is received by the girl's mother. The boy's father and his friends are seated on a carpet in the veranda and the girl is called by her father. She comes out dressed in her best and sits near the boy's father with her head hung nearly between her knees through modesty and fear. One of the guests asks her, What her name is, How many brothers she has, How old she is, Whether she goes to school, What her place in the class is, and she is sometimes asked to read a piece from her book. They then tell her to look up and walk away. The boy's kinswoman strips the girl if she is under eight, or takes her bodice off if she is ten or more and examines her closely to see if she is healthy and has no bodily or mental defect. Beauty is specially attended to as it is difficult at so early an age to conjecture what the mental attainments of the girl will be. Betel is served to the boy's father and his relations and they withdraw. As soon as the girl is fixed, the fathers of both the girl and the boy draw up an agreement regarding what money the girl's father should pay to the boy and what ornaments and dresses the boy's father should present to the girl. The lucky day for the wedding is fixed and both the families busy themselves with the wedding preparations raising booths before their houses and buying or procuring rice, pulse, and other provisions. Invitations are sent to friends and relations as before a thread-girding and the boy and girl are feasted by their kinspeople. Two or three days before the wedding day the girl's parents are treated to a dinner at the boy's as they are not to take food at their daughter's unless she is blessed with a son. A day or two before the marriage the guardian-pleasing is performed at the houses of both the boy and the girl when a betelnut Ganpati and a metalpot Varun are worshipped in a winnowing fan with sandal-paste, flowers, turmeric paste, and vermilion and the fan is set before the house gods. Friends and kinspeople meet at the houses of the boy and the girl and are treated to a dinner.

On the marriage eve the bridegroom goes with music and company to the girl's village and halts at the local temple, lays a cocoanut before the god and bows to him. The girl's father meets him at the place with music and a band of friends and both the fathers present each other with cocoanuts. The bridegroom is seated at the temple or taken to the house of some friend of the

## Chapter III.

## People.

BRÁHMANS.

*Deshasthas.*

Chapter III.  
People.

BRÁHMANS.  
*Deshasths.*

girl's father. The guests are welcomed to a seat on the carpet and the bridegroom is worshipped by the girl's father attended by his priest, with sandal-paste, flowers, sweetmeats, and clothes. This they call *simánt puja* or boundary worship. The guests are treated to betel, flowers, and perfumes. The women of the girl's house especially the girl's mother wash the boy's mother's feet and mark her brow with vermilion, laying in her lap a cocoanut and bodicecloth with wheat. Other women guests are given cocoanuts and betel and the girl's party escorts the boy's party to some house in the girl's neighbourhood and return home. On the morning of the marriage, married women pound some wheat in a basket and rub the girl with turmeric paste. The married women take part of the paste that remains to the boy with music and a band of friends and rub him with it. After the turmeric-rubbing the boy is bathed and dressed in new clothes. As the lucky hour draws near the girl's friends and kinspeople, accompanied by a band of kinswomen, visit the bridegroom with music. The bridegroom is dressed in a rich suit, his brow is decked with a marriage coronet, and he and his friends are fed with sweetmeats. The girl's mother gives him a packet of betel leaves and nut which he chews and spits into a dining dish. He mounts the wedding horse and is escorted by the bride's party to the girl's with music and a company of friends and kinsfolk. His mother and her friends and relations follow attended by the girl's mother. On the way cocoanuts are broken and thrown away as offerings to evil spirits. On reaching the bride's the boy dismounts and his feet are washed by one of the women servants of the house. He enters the booth and is led by the bride's father to the raised earth altar or *vedi*. At this time the bridegroom's mother, as she must not see her future daughter-in-law till a particular moment, feigns anger and goes to a neighbouring house. The bridegroom takes off his turban and coat but keeps his marriage coronet on his brow and stands near the raised altar with his face to the east. The bride is clad in a yellow waistcloth called *ashtaputri* and a shortleeved backless bodice and with folded hands is seated before Gauri-har that is an image of Shiv and his wife Gauri whom she prays to give her a good husband. As the lucky moment draws near her maternal uncle takes the bride to the altar and sets her facing the bridegroom with a curtain marked with the lucky cross or *svastik* held between them. The bridegroom's sister stands behind the bridegroom and the bride's sister stands behind the bride as the maids of the pair each with a lighted lamp and a cocoanut. The priest repeats lucky texts, and the guests throw red rice over the pair. The astrologer tells when the lucky moment comes, the musicians play, the curtain is drawn to the north and the couple who up to this time have been silently looking at the lucky cross or *svastik*, throw garlands of flowers and sweet basil or *tulsi* leaves round each other's necks. Thus the pair are husband and wife and the guests are given betel and flowers. The bridegroom's party retire to their place, taking stealthily with them the metal pots used in worshipping Gauri-har. The priest then hands the lucky necklace to the bridegroom who ties it round the bride's neck. This lucky necklace is of two small trinkets and green glass beads strung together by a courtesan who is called *janma savashin*.

or the unwidowed till death. After this the bride's mother prays the bridegroom's mother to go back to the bride's presenting her with a robe and sweetmeats; and the bridegroom's father and his relations are asked to dine at the bride's by the bride's father attended by music and friends. The bride's father is seated and the priest asks the bridegroom's party one by one who, in token of accepting the invitation take a pinch of red rice from the cup which the priest holds before them.

Every day during the ceremony the bride's mother presents the bridegroom's mother with uncooked provisions usually called *ámbon* properly Sanskrit *ámodan* or gladdening. On the marriage-feast day the marriage booth is coudunged and low stools are set in a row, squares of wheat flour and redpowder are traced about the low stools, and plantain leaves are laid one before each low stool with two leaf cups or *drons* one for clarified butter and the other for sauce or curry. When all is ready, the bridegroom's party is brought with friends and music and welcomed by the houseowner. All wash their hands and feet at a place prepared for the purpose, put on their sacred waistcloths, and take their seats on the low stools according to their rank. The bridegroom is seated at the head of the party close to his father or some relation. The bridegroom's mother goes into the house and is seated by the bride's mother on a low stool along with other married women belonging to the bridegroom's party. When all are seated a place is reserved for the bride in front of the bridegroom and frankincense sticks are burnt in the hall. The pair are told to feed each other and all begin to eat. The musicians play and the host moves through the hall praying his guests to pardon the slowness with which the feast is served. When the guests are half done the boys sing verses and the company ends them with a chorus *Sitákánt smaran*, or *Har har Mahádev*. The bridegroom after numerous entreaties from the bride's father, brothers, and other kinsmen has to recite a poem and his mother-in-law stands anxiously behind the door of the hall to applaud him. When the dinner is over, betel is served, and the party of the bridegroom leave, a few of the women remaining at the bride's. In the women's hall, to eat the various dainties the bride's mother constantly presses the bridegroom's mother who is most difficult to please, being ready to take offence at the slightest neglect or want of attention on the part of the bride's mother. The bride is made to eat from the same plate with her mother-in-law who, as a rule, takes two to four hours to finish her meal. The bridegroom's women claiming superiority over the bride's party point out the faults of the girl's household in rhyming couplets called *ukhánás*, and the young girls of the bride's house answer them. The musicians play and at last the bridegroom's mother finishes her meal. She is given sugar to rub on her hands and cloves to cleanse her teeth, and after the service of betel and perfumes she leaves. Every morning during the ceremony the bridegroom and bride are seated face to face in the hall attended by the sisters and friends of each. The bride puts a roll or *vidi* of betel leaf between the teeth of the bridegroom who holds it fast, and the bride tries to bite it off. Some one of the bridegroom's friends gives him a push and the bride

## Chapter III.

## People.

BRÁHMAN'S.

*Deshasths*.



## Chapter III.

## People.

## BRÁHMANS.

*Deshasths.*

fails and is laughed at. Then the bridegroom's turn comes. Pieces of cocoa-kernel and cloves are substituted for rolls of betel leaf and the pair are facetiously warned to take care not to bite off each other's lips. The bridegroom holds fast a betelnut in his left hand and the bride tries to wrest it from him. The bride then holds a betelnut between her two hands and the bridegroom takes it from her using only his left hand. Then follows hide and seek. The bride hides a betelnut in her clothes and the bridegroom tries to find it out. If the bridegroom finds it all is well. If he fails the mischievous girls twit him and advise him to pray his wife to be good enough to give it back. Then the husband hides and the wife seeks it. If the wife finds she is applauded and if she fails she is excused. The pair then put on their bathing dress, and the sisters of each rub turmeric and fragrant oil on them. The pair go to the bathing place and are bathed, first in red water or *kalasarni* from four cups that are specially placed there, and then in warm water. Music plays and the pair are dressed in dry clothes. Then the bridegroom's sister goes home, and the bride's sister goes with her and asks the bridegroom's kinswomen to breakfast at the bride's. They attend and eat with the pair who feed each other from the same dish.

In the evening the bridegroom feigns anger and goes away stealthily to a neighbouring house. The bride's brother or father goes in search of him, presents him with a metal pot and sweetmeats or *lādu gadus*, and brings him back. He sits before the house gods and Gauri-har, and the bride, richly dressed and decked with ornaments stands by him with her left foot on his lap. Saffron water is sprinkled over the mango twigs near the god, and the bridegroom takes one of the images of the house gods, puts it into his pocket, and leaves the place. The pair bow before the house gods and elders and the bridegroom mounts his horse seating the bride before him. Music plays and the procession moves from the girl's to the local temple, bows before the god, and starts for the bridegroom's. Cocoanuts are broken as before in offering to evil spirits, and fireworks are let off. When they reach the bridegroom's, the pair dismount near the door of the booth. The musicians step forward and bar the entry and go on beating their drums until, in addition to their regular wages, they exact a money present from the bridegroom's father. Then the maid who stands at the door with an earthen pot full of water empties it at the feet of the pair who enter the house followed by friends and relations. A measure of corn filled with wheat is placed at the door and the bride oversets it with her foot. The priest conducts the pair through the naming at which the bridegroom gives his wife a new name by which she is hereafter known in his house. Sugar is distributed among the guests, and they are told the bride's new name. The bride is given a cup of milk and the bridegroom drinks what is left from the same pot. Meanwhile his sister has tied the skirts of their garments, and refuses to untie the knot until the pair utter each other's names. The bridegroom at once says his wife's name but the bride hides it in some such couplet, The sweet basil plant lay at the door and I watered it; first I was the darling



of my parents, now I am the queen of Rámráv.<sup>1</sup> The other married women present are not allowed to leave the place until they repeat their husbands' names. A wooden measure or a metal pot is brought from the store room. The bridegroom's mother tries to empty it and the bride to keep it full till at last she lays her hand on an ornament which has been hidden in the grain. The bride's mother leaves one of her relations with the bride because she is very young and a stranger said in jest to be living *sásurvás* that is in the midst of six knives, the father and mother-in-law, the brother and sister-in-law, the husband's sister, and the husband. Next day the couple are bathed at the bridegroom's and the friends and relations of the bride are feasted.

The next is the last day of the ceremony when the bride's mother asks the bridegroom's mother and sisters to her house and bathes them. The married women of the bridegroom's house dress in white and with music and a band of friends go to the bride's accompanied by the bride's mother. As they leave the house, the washerman spreads his cloth or *páyghadi* on the road and the bridegroom's mother and relations walk over it. A long roundabout way is chosen, and, on the way, low stools are placed in order that the bridegroom's mother and her party may rest if weary. If they halt they are given turmeric powder and redpowder to rub on their bodies and cocoanuts and wheat are laid in their laps. Now and then redpowder is thrown over them, and, before reaching the bride's house they are red from head to foot. On reaching the house they are bathed in warm water and new glass bangles are put on their wrists. A piece of silver is put in the metal pot, the water in the pot is boiled, and the coin goes to the servant. All bathe and go home. Sometimes the bridegroom's mother is seated on a swing which is gently swung. As it moves women servants standing on either side pour water over her. She then sings a song with the chorus, The desires of the heart are not fulfilled, oh friend.<sup>2</sup> On that day the bridegroom's party are feasted with stuffed wheat cakes or *karanjás* and *pátvadis* or rolls of gram flour. After dinner the guests dress in rich clothes and seat themselves on carpets. Betel is served and saffron water sprinkled on their shouldercloths. The pair remove each other's marriage-threads and put them in a pot filled with milk. The women take away the earthen pots round the altar or *vedi* and also the canopy over it. The earth altar or *vedi* remains and seeds and creepers are planted on it at the beginning of the rains that the family of the bride and bridegroom may grow and spread like the creepers. Bathings and dinners continue at the bridegroom's on the eighth and sixteenth and at the bride's on the tenth and thirteenth. On the anniversary of the marriage the bride's father gives a dinner to the bridegroom and presents him with a gold ring or a waistcloth. Early marriage and polygamy are allowed and practised among Deshasth Bráhmans, polyandry is unknown, and widow marriage is forbidden on pain of loss of caste.

## Chapter III.

## People.

BRÁHMANS.

*Deshasths.*

<sup>1</sup> The Maráthi runs : *Dári hoti tulas, tila ghálit hote páni ; Pratham hote díbápáchi tánhi, áta jhále Rámráváchi ráni.*

<sup>2</sup> The Maráthi runs : *Náhi manichi haus puráli, sakhí ga.*

## Chapter III.

## People.

## BRÁHMANS.

*Deshasths.*

On the morning of the first Fig Tree or *Jyeshth* that is June-July full-moon after the wedding, when all married women worship the fig tree or *vat* to secure long life to their husbands, the newly married couple are bathed and seated on low stools. The priest attends and music plays. The young wife lays sandal, flowers, turmeric, and vermillion before a picture of the banian drawn on the wall, burns frankincense, presents five special offerings or *váyans* to five unwidowed women, each offering including a wooden comb, two small turmeric and vermillion boxes, a pair of glass bangles, a piece of bodicecloth, and some wheat or rice, all laid in a bamboo tray. If the young wife is at her mother's she has to distribute to Bráhmans five more special offerings or *váyans* given to her by her mother-in-law. In the evening she has to listen to a Bráhman *puránik* or reader who reads the tale of Sávitrí and her husband Satyaván, at the house of some rich lady or at the village temple. The young wife has to eat nothing on that day but light food or *pharál* and next morning after bathing breaks her fast with ordinary food. In the month of *Ashádh* and *Shrávan* or July and August the pair interchange presents of toys. On every Tuesday in *Shrávan* the new wife and her husband worship the goddess of luck or Mangalágauri and Gauri's husband Shiv whom she invokes on the previous day, offering him a handful of grain called *shívmuth* or Shiv's handful. If the young wife meets any unforeseen obstacles, as illness or mourning on the first Monday in *Shrávan*, she puts off the worship till the next *Shrávan*. In the morning, with girl friends she goes to fetch flowers and leaves or *patris*, and a silver image of the goddess Annapurna or the food-supplier is brought from the goldsmith and laid on a low stool. The pair are bathed and seated on two low stools, the girl to the right of the boy in front of the goddess before whom they lay sandal paste, flowers, leaves, and food, burn frankincense, and wave lights. Other married girls join the newly married pair and worship the goddess and are treated to a dinner at the girl's. Before dinner the girls exchange copper coins and plates and remain strictly silent during dinner. Mischievous boys keep coming in and with numberless questions and devices try to make the girls break the golden rule of silence. After the meal is over the girls chew *tulsi* or basil leaves and begin to talk as usual. In the evening the young wife does not eat her usual food but takes a light repast or *pharál* with other girls who are asked to the house and with whom she passes the night repeating the tale or *kaháni* of Mangalágauri and playing games. At dawn all bathe, lay flowers, vermillion, and food before the goddess and bow her out, take a slight breakfast, and sleep. Every girl worships Mangalágauri in *Shrávan* or July-August for five years after her marriage.

On the third day of *Bhádrapad* or August-September, the newly married wife worships Hartálíka, fasts the whole day and night from all food but fruit, passes the night with other girls in playing games, and breaks her fast early next morning. When the sun enters the thirteenth constellation of the Zodiac called *Hast* or the Elephant, newly married girls fasten on a wall in the house a piece of paper marked with pictures of elephants facing each other with garlands in their trunks and with men and women dressed as kings and queens

in cars on their backs. As long as the sun is in the Elephant or *Hast*, married girls meet and sing and dance before a low stool in the hall, marked with wheat or rice figures of elephants. Some day a light feast or *bhātukali* is given to the girl by her friends and relations. On the eighth of *Ashvin* during the first five years after her wedding the young wife has to worship Mahalakshmi. Married girls who are asked to the house meet and worship an embossed image of *Annapurna* or the food-supplier at noon, and at night a large sitting or standing female figure of dough is made, set in the hall, and decked with gold and silver ornaments. Flowers, vermilion, and food are laid before the goddess, and the girls taking small metal or earthen jars make music by blowing across the jar mouths and dance in a circle before the goddess. During the dance, one of the girls begins to blow the jar and dances better than the rest, a sure sign that the goddess has entered into her. She presently sways her hands and is seized with the power of the goddess. Her friends ply her with questions and for some time the goddess in the girl answers the questions. Then the goddess leaves her and the girl falls in a swoon. On the bright tenth of *Ashvin* or September-October, the newly married girl's husband is asked to dine at the girl's father's and presents the girl's family with *āpta* Bauhinia racemosa leaves which on that day are called gold. On his return from crossing the boundary or *simollanghan* the girl waves a light round her husband who presents her with gold ornaments and *āpta* leaves. On *Divāli* in October-November the new son-in-law is asked to bathe and dine at his father-in-law's. On the bright first or *pādva* before or after the meal, the young wife waves a light round her husband and is presented with gold ornaments. Next day he calls his wife's brother to dine at his house, his wife waves a light round her brother, and is presented with a robe and bodice and some money called *ovālni* or the waving gift. On the day of *Makar Sankrānt* or the twelfth of January, for the first five years after her wedding, a newly married girl presents her friends with pieces of sugarcane and sweetmeat called *halva*. Bráhmaṇ un widowed women are asked to the house and each is given an earthen jar or *sugad* covered with a bodicecloth. For nine years after the age-coming ceremony a girl presents five married pairs with five rolls of betel leaves, each roll of nine leaves nine betelnuts nine cloves nine cardamoms nine pieces of mace and nine nutmegs. Next day or *kinkrānt* seven rolls of betel leaves are served to seven married Bráhmaṇ women. On this day all married women meet at the village temple or at the house of some rich lady and present each other with turmeric-paste and vermilion or *halad kunku*. Their laps are filled with wet gram and collyrium is rubbed on their eyes. In the month of *Chaitra* or April, married women hold the ceremony of *halad kunku* or turmeric and vermilion when a female figure or mask is set in the women's hall and called *Annapurna* or the food-supplier. It is decked with flowers and lights are set before it. Women neighbours and friends are asked and presented with vermilion and turmeric, and wet gram and fruit are laid in their laps. This is done at every house. During the whole month women are busy paying visits to neighbours and relations followed by Kunbi maidservants loaded with wet gram. To women

## Chapter III.

## People.

BRÁHMANS.

*Deshashas.*

## Chapter III.

## People.

## BRÁHMANS.

*Deshasths.*

On the morning of the first Fig Tree or *Jyeshth* that is June-July full-moon after the wedding, when all married women worship the fig tree or *vat* to secure long life to their husbands, the newly married couple are bathed and seated on low stools. The priest attends and music plays. The young wife lays sandal, flowers, turmeric, and vermillion before a picture of the banian drawn on the wall, burns frankincense, presents five special offerings or *váyans* to five unwidowed women, each offering including a wooden comb, two small turmeric and vermillion boxes, a pair of glass bangles, a piece of bodicecloth, and some wheat or rice, all laid in a bamboo tray. If the young wife is at her mother's she has to distribute to Bráhmans five more special offerings or *váyans* given to her by her mother-in-law. In the evening she has to listen to a Bráhman *puránik* or reader who reads the tale of Sávitrí and her husband Satyaván, at the house of some rich lady or at the village temple. The young wife has to eat nothing on that day but light food or *pharál* and next morning after bathing breaks her fast with ordinary food. In the month of *Ashád*h and *Shrávan* or July and August the pair interchange presents of toys. On every Tuesday in *Shrávan* the new wife and her husband worship the goddess of luck or Mangalágauri and Gauri's husband Shiv whom she invokes on the previous day, offering him a handful of grain called *shivmuth* or Shiv's handful. If the young wife meets any unforeseen obstacles, as illness or mourning on the first Monday in *Shrávan*, she puts off the worship till the next *Shrávan*. In the morning, with girl friends she goes to fetch flowers and leaves or *patris*, and a silver image of the goddess Annapurna or the food-supplier is brought from the goldsmith and laid on a low stool. The pair are bathed and seated on two low stools, the girl to the right of the boy in front of the goddess before whom they lay sandal paste, flowers, leaves, and food, burn frankincense, and wave lights. Other married girls join the newly married pair and worship the goddess and are treated to a dinner at the girl's. Before dinner the girls exchange copper coins and plates and remain strictly silent during dinner. Mischievous boys keep coming in and with numberless questions and devices try to make the girls break the golden rule of silence. After the meal is over the girls chew *tulsi* or basil leaves and begin to talk as usual. In the evening the young wife does not eat her usual food but takes a light repast or *pharál* with other girls who are asked to the house and with whom she passes the night repeating the tale or *kaháni* of Mangalágauri and playing games. At dawn all bathe, lay flowers, vermillion, and food before the goddess and bow her out, take a slight breakfast, and sleep. Every girl worships Mangalágauri in *Shrávan* or July-August for five years after her marriage.

On the third day of *Bhádrapad* or August-September, the newly married wife worships Hartálika, fasts the whole day and night from all food but fruit, passes the night with other girls in playing games, and breaks her fast early next morning. When the sun enters the thirteenth constellation of the Zodiac called *Hast* or the Elephant, newly married girls fasten on a wall in the house a piece of paper marked with pictures of elephants facing each other with garlands in their trunks and with men and women dressed as kings and queens

in cars on their backs. As long as the sun is in the Elephant or *Hast*, married girls meet and sing and dance before a low stool in the hall, marked with wheat or rice figures of elephants. Some day a light feast or *bhátukali* is given to the girl by her friends and relations. On the eighth of *Ashvin* during the first five years after her wedding the young wife has to worship Mahálakshmi. Married girls who are asked to the house meet and worship an embossed image of *Annapurna* or the food-supplier at noon, and at night a large sitting or standing female figure of dough is made, set in the hall, and decked with gold and silver ornaments. Flowers, vermilion, and food are laid before the goddess, and the girls taking small metal or earthen jars make music by blowing across the jar mouths and dance in a circle before the goddess. During the dance, one of the girls begins to blow the jar and dances better than the rest, a sure sign that the goddess has entered into her. She presently sways her hands and is seized with the power of the goddess. Her friends ply her with questions and for some time the goddess in the girl answers the questions. Then the goddess leaves her and the girl falls in a swoon. On the bright tenth of *Ashvin* or September-October, the newly married girl's husband is asked to dine at the girl's father's and presents the girl's family with *ápta* Bauhinia racemosa leaves which on that day are called gold. On his return from crossing the boundary or *simollanghan* the girl waves a light round her husband who presents her with gold ornaments and *ápta* leaves. On *Diváli* in October-November the new son-in-law is asked to bathe and dine at his father-in-law's. On the bright first or *pádva* before or after the meal, the young wife waves a light round her husband and is presented with gold ornaments. Next day he calls his wife's brother to dine at his house, his wife waves a light round her brother, and is presented with a robe and bodice and some money called *oválni* or the waving gift. On the day of *Makar Sankránt* or the twelfth of January, for the first five years after her wedding, a newly married girl presents her friends with pieces of sugarcane and sweetmeat called *halva*. Bráhmaunwidowed women are asked to the house and each is given an earthen jar or *sugad* covered with a bodicecloth. For nine years after the age-coming ceremony a girl presents five married pairs with five rolls of betel leaves, each roll of nine leaves nine betelnuts nine cloves nine cardamoms nine pieces of mace and nine nutmegs. Next day or *kinkránt* seven rolls of betel leaves are served to seven married Bráhmaun women. On this day all married women meet at the village temple or at the house of some rich lady and present each other with turmeric-paste and vermilion or *halad kunku*. Their laps are filled with wet gram and collyrium is rubbed on their eyes. In the month of *Chaitra* or April, married women hold the ceremony of *halad kunku* or turmeric and vermilion when a female figure or mask is set in the women's hall and called *Annapurna* or the food-supplier. It is decked with flowers and lights are set before it. Women neighbours and friends are asked and presented with vermilion and turmeric, and wet gram and fruit are laid in their laps. This is done at every house. During the whole month women are busy paying visits to neighbours and relations followed by Kunbi maidservants loaded with wet gram. To women

## Chapter III.

## People.

BRÁHMANS.

*Deshashths.*

Chapter III.  
People.

BRĀHMANŚ.  
Desasths.

vermilion or *kunku* is very sacred. If the supply in the vermilion box is finished instead of saying it is done they say it has increased.<sup>1</sup> The bright third of *Vaishākh* or May is the last day of the *halad kunku* or turmeric and vermilion ceremony when the goddess Gauri is said to go to her mother's house or *māher*. On this day a married woman is feasted at every house and women friends and neighbours are presented with turmeric, vermilion, and betel. Next day the goddess is said to go to her husband's and remain there till New Year's Day or *Varsh Pádva* in *Chaitra* or *Āpril*.

When a girl comes of age, a man-servant with a dish filled with packets of sugar is sent to the houses of friends and relations. He visits every house, hands the head of the house one of the sugar packets, and tells him the glad news that the girl has come of age. If the girl is at her father's, a servant carries the news to her husband's with a packet of sugar and a cocoanut and is presented with a turban or waistcloth or some money. As soon as the good news is spread among the girl's husband's friends they tease him with demands of sweetmeats or *pedhās* in honour of the birth of a dumb son or *muka mulga* as the wife's coming of age is generally called. A gaily decked wooden frame is prepared, a square is marked in it, and a low stool set in the square; the girl is decked with jewels and seated in the square, and a Marátha woman attends her day and night. Every morning she is given turmeric and vermilion, music plays, and a cocoanut and wheat are laid in her lap. Women friends and neighbours feed the girl with sweet dishes which they prepare at their homes, and lay a bodicecloth, wheat, and a cocoanut in her lap presenting her with turmeric and vermilion. The girl is rubbed with sweet-scented oil and turmeric and bathed on the morning of the fourth day and is pure. The marriage consummation or *garbhādhán* is performed on a lucky day before the sixteenth day after the age-coming. On the morning of the lucky day, to the sound of music, the pair are rubbed with turmeric and oil and bathed by married women. Both go to the god-room and lay a cocoanut, bow before the gods and the elders, and ask their blessing. Married friends and neighbours are asked to the house. The pair are seated on two low stools the girl to the right of the boy, and by the aid of the priest they lay sandal, flowers, and sweetmeats before the metal-pot Varun and the betelnut Ganpati, and kindle the sacred fire. If the girl's sickness begins at an unlucky time, to remove calamities and troubles, the quieting of Bhuvaneshvari or Bhuvaneshvari *shānti*<sup>2</sup> is performed, and a sacred fire is lit. The pair then make a cooked rice ball, offer it to the spirit, and bathe in water poured by the priest through a sieve or *rovali* from Bhuvaneshvari's pot. They dress in fresh clothes and perform the holy-day blessing or *punyāhaváchan* with the same details as before the marriage, bow to the house gods and elders, and are seated before the sacred fire. The fire is kindled and rice cooked over it, and the boy places the rice with a few mango leaves on his right.

<sup>1</sup> The Maráthi is, *Kunku dabit vādhalē áhe*.

<sup>2</sup> Details are given in the Chitpávan customs in the Poona Statistical Account.



## Chapter III.

## People.

BRÁHMANS.

Deshasths.

The boy feeds the sacred fire with rice and the girl pours clarified butter over it. When the service of the sacred fire is over they wash their hands and sit on the low stools as before. The boy's sister hands the boy a quantity of bent grass or *durva* pounded, wetted, and tied in a piece of white cotton, and he, standing behind the girl and drawing back her head between his knees, with his left hand gently lifts her chin and with his right hand squeezes into her right nostril enough bent grass juice to pass into her throat. The girl leaves her seat, washes her hands and feet, and takes her seat as before to the right of her husband. The boy then touches either her breast or one of her shoulders and lays in her lap a cocoanut, some wheat, a betelnut, and a turmeric root. Women friends and neighbours lay articles in her lap and present her with clothes and ornaments. When the lap-filling is over the boy whispers his name into the girl's right ear, money is presented to the priest who leaves with a blessing on the heads of the pair, and the pair with the hems of their garments knotted together, bow before the house gods and elders. Married men and women are asked to dine at the house at noon. The girl who is considered to be pure, dresses in a silk cloth called *mukta* which she is to wear thenceforth at her every-day meals, is given a cup of butter, and serves its contents to the guests. At night friends and kinspeople meet at the house after supper, and a room is lighted and furnished with cushions and carpets for the guests to sit on. Both the boy and the girl are presented with fine clothes and ornaments which they put on and are seated on the carpet spread in the room. The girl washes her husband's feet in warm water with the aid of her elder sister or some friend and on his feet paints vermilion and turmeric shoes. The women dress a cylindrical stone-pin in a bodice, call it *Gopála*, and bring it in. This they call the future son and ask the girl to hand it to her husband. She gives it to him saying, Please take care of this child, I am going to fetch water. The boy says You keep the child, I am going to my business. Then the married women repeat their husband's names, the stone-pin is placed in the boy's hands, and the guests withdraw. The bedding is spread and water mixed with saffron is sprinkled over it. Close to the bed are set a lamp, a metal waterpot, a metal plate for betel leaves with a nutcracker, a betel-leaf can called *pámpuda*, lime and catechu boxes, betel leaves, nuts, cardamoms, cloves, and nutmeg. The servant who prepared the bedding is presented with a turban. The boy is already in the room and at the lucky moment, the girl who feigns great unwillingness is dragged to the door and pushed in by her female friends, and the door is closed after her. She then drinks a little from a cup of milk and hands the cup to her husband who drinks it and chews the betel which his wife serves to him. Lastly they eat a piece of cocoanut and sugarcandy and go to bed. Next morning the girl's mother brings rice, wheat, a cocoanut, packets of vermilion and turmeric, puts them in the girl's lap, and presents her with uncooked provisions enough to feed twenty people.

During her first pregnancy, the girl is given a longing feast or *dohale jevan* and friends and kinsfolk ask her to dine. When a



Chapter III.  
People.

BRÁHMANS.  
*Deshasths.*

Deshasth is on the point of death, he is laid on a white country blanket or *ghongdi* and a basil leaf or gold and some holy water are put in his mouth. If the son is present he takes the dying head on his lap, and, when all is over, the women sit round the dead wailing and weeping. The dead is laid on a bier and taken to the burning ground by four kinsmen preceded by the chief mourner with the firepot in his hand. If kinsmen are not available Bráhmans are hired to carry the body to the burning ground. As soon as the dead is removed, those who remain at home dig a pit on the spot where the dead breathed his last, set in the hole a lighted lamp facing south, and keep the burning lamp for ten days. The village Mhárs who take cowdung cakes to the burning ground are paid 3s. to 6s. (Rs. 1½ - 3). A pile is heaped, the body is laid on it, and burnt with the same rites as among the Poona Chitpávans. A married woman who dies before her husband is bathed in warm water, her hair is smoothed with butter, her body is rubbed with turmeric, and her brow is marked with vermilion. She is dressed in a new robe and bodice, the lucky necklace is tied round her neck, toerings are put round her toes, and her hair is decked with flowers. A betel roll squeezed between the palms of two hands is put in her mouth, and a cocoanut, wheat, and packets of turmeric and vermilion are laid in her lap. Married women are presented with rice cocoanuts and packets of turmeric and vermilion, and the body is laid on the bier, carried to the burning ground, and burnt. Widows are treated in the same way as men; they are not entitled to the honours shown to married women. Deshasths have a caste council. The Bráhman caste council includes the available men of the Chitpávan, Deshasth, and Karháda castes and settle social disputes at caste meetings or according to the votes of learned men or *shástris*. Smaller breaches of social rules are punished by the caste council and serious breaches are referred to the Smárt Pontiff Shankaráchárya of Sankeshvar. The Pontiff still gets his dues from his followers but his power is growing weaker day by day. They send their boys to school and are a steady class.

VAISHNAVS, or Mádhva Bráhmans, are returned as numbering about 300 and as found in all sub-divisions. They are said to have come from the Bombay Karnátak within the last hundred years. Their home tongue is Kánarese and out of doors they speak Maráthi. They live in one or two-storeyed houses with brick walls and tiled roofs. In look food dress and social and religious customs they do not differ from the Mádhva Bráhmans of Dhárwár.<sup>1</sup> They are landowners and as a class are rich.

*Devrukhas.*

Devrukha's, or People of Devrukh in Ratnágiri, are returned as numbering seventy-six and as found over the whole State except in Alta, Ichalkaranji, and Kágál. Both men and women are dark, strong, regular featured, and well made. They are generally husbandmen and house servants, and most of them are poor. In food

<sup>1</sup> Details are given in the Dhárwár Statistical Account.

dress and customs they are like Karháda Bráhmans. As a class they are hardworking and thrifty. The local Deshasths look down on them as to dine with a Devrukha is considered unlucky. They send their boys to school.

**Dravids**, or Southerners, are returned as numbering thirty-eight, and as found in the town of Kolhápúr. They are said to have come to Kolhápúr within the last hundred years. Their home tongue is Tamil and they speak Maráthi abroad. They are dark strong and well built, and in food drink and dwelling resemble local Deshasths. The men dress in a waistcloth, shouldercloth, shirt, coat, and turban; the women wear a long Marátha robe and bodice with a back and short sleeves. Unlike local Bráhmaṇ women, Dravids do not gather the folds of their robe in front but fasten them to the left of the waistband and let them fall down the left leg. They pass one end of their robe between the feet and tuck it into the waistband behind, covering it with the other end which they pass over the right shoulder and below the left arm. Men whose parents are alive shave the head except the topknot and the face except the moustache, but fatherless men shave the face clean. The women plait their hair in braids like local Bráhmaṇ women and have a similar store of clothes and ornaments. Most are landholders and are well off. Their hereditary calling is to recite the Vēds, and to read Puráns and legends and to practise as priests. A few are moneylenders and medical practitioners, and some are State servants. They worship all Bráhmaṇic and local deities and keep the regular fasts and feasts. Their priests belong to their own class and they do not ask other Bráhmans to conduct their ceremonies. Their customs are the same as Deshasth customs except that Dravids have no raised altars or *bahules* at their thread-girding or marriage, and defer the *samāvartan* or removing of the *kush* grass cord, tied at the time of thread-girding about the boy's waist, to the day of his marriage. They have begun to send their boys to school but not their girls, and are fairly off.

**Golaks**,<sup>1</sup> or Bastards, are returned as numbering 192 and as found all over the State except in Alta and Bhudargad. They are divided into four classes, those born of a Bráhmaṇ widow, those of an unmarried Bráhmaṇ girl, Kund Golaks born of a Bráhmaṇ widow who had remarried, and Rand Golaks of a Bráhmaṇ woman who was guilty of adultery during her husband's life. The first two are now included in the last two. They are middle-sized fair and regular featured, but not so clean as other Bráhmans and are not well-to-do. They are moneylenders shopkeepers and husbandmen.

**Gujarát Bráhmans** are returned as numbering thirty-six and as found in the sub-divisions of Gadinglaj, Ichalkaranji, Kágál, Karvir, and Shirol. They are not permanent residents and have come into the district either for trade or to serve as priests to Gujarát Vánis. They remain in the district for a short time, and return home as soon as their business is over or to marry their children. They are

## Chapter III.

## People.

## BRÁHMANS.

*Dravids.**Golaks.**Gujarátis.*

<sup>1</sup> Details of Golak customs are given in the Sholápur Statistical Account.

## Chapter III.

## People.

## BRÁHMANS.

*Kanaujs.*

servants, beggars, and priests to local Gujarát Vánis. In look food dress and customs they resemble their brethren in Poona and Bombay. They perform the daily worship of their patrons' house-gods and are a poor class.

**Kanaujs** are returned as numbering thirty-two and as found in the town of Kolhápúr. They have come from Upper India and are employed under the State either as soldiers or as watchmen, returning to their native country to marry and when they grow old. They cook their own food and their staple food is wheat flour and clarified butter. They do not allow any one even of their own caste to touch their food and do not eat food cooked by others. They belong to the Panchgaud section of Bráhmans and are faithful and brave.<sup>1</sup>

*Karhádas.*

**Karháda's** are returned as numbering 3659 and as found in small numbers over the whole State. They are new settlers and most of them have come from Belgaum, Ratnágiri, and Sátára. In look food dress and social and religious customs they are the same as Poona Karhádas. They live in one or two-storeyed houses with brick walls and tiled roofs and are State servants, landholders, traders, moneylenders, and beggars. They are fairly off and a rising class.

*Mádhyaandins.*

**Ma'dhyandins**, or Midday Worshippers, are returned as numbering seventy-nine and as found in small numbers in all parts of Kolhápúr. The number given in the census is much below the real number as many return themselves as Deshasths as unless specially questioned they try to pass as Deshasths. The chief of Vishálgad and the hereditary priest or *guru* of the Kolhápúr family are Mádhyaandins. They are so called because while other Deshasths perform their twilight or *sandhya* worship at sunrise, Mádhyaandins as a rule perform it at midday. They are a subdivision of Yajurvedi Deshasths and are darker and stronger than the Rigvedi section of Deshasths. In look food drink and dress they resemble local Deshasth Bráhmans. In character they are like Deshasths except that Mádhyaandins are lazier and more extravagant. They are divided into two sections Vájsaneyas and Kánvas who eat together but do not intermarry, and resemble each other in all points except in their thread-girding and marriage customs. Among the Kánvas, as soon as the bridegroom and bride are brought together, before a metal pot or *kalash* are laid sandal-paste, flowers, and some money in the name of the sage Yájnyavalkya the author of the Yajurved. The priests as a rule are given the money offered to the sage and will not go on with the ritual unless the houseowner lays £1 to £4 (Rs. 10-40) before the metal pot. This takes place at the thread-girding also. The well-to-do among them live in large mansions, use carriages and horses, and have servants and cattle; others live in one or two-storeyed houses with brick walls and tiled roofs and keep cattle. They are landlords, petty traders, moneylenders, State servants, and beggars or priests. Among other Bráhmanic and local gods and goddesses they worship Ambábái, Bahirav, and Vindhyavásini, and keep all Bráhmanic fasts and feasts.

<sup>1</sup> Details of Kananj customs are given in the Poona Statistical Account.

All their social and religious customs are the same as Deshasth customs. They send their boys to school and are a rising class.

**Sava'sha's**<sup>1</sup> are returned as numbering sixty-one and as found only in the sub-divisions of Kágál and Karvir. They say they have come from Sátára but when and why they do not know. They are divided into Smárts and Vaishnavs. The following particulars apply to Vaishnavs as Smárts are seldom found in Kolhápúr. Their names for men are Vyankatesh or Vishnu and for women Lakshmi. They are moneylenders and changers and the men add *náik* or leader to their names. Their surnames are Bhure, Chipde, Inkara, Karnátki, Kolbage, Sarade, Shikhre, and Shirálkar. Their home tongue is Maráthi and their family gods are Khandoba, Narsinh, Sháligrám, and Vyankoba of Tirupati in North Arkot. They are fair strong and middle sized, the women being fairer than the men and graceful. In food and dress they resemble Vaishnav Deshasths and are cleaner and neater than local Deshasths. As a class they are quiet and hardworking, but not thrifty. They are moneylenders and changers and priests and never take to service. They rank below Deshasths and have their own priests to conduct their ceremonies. Their religious teacher is a Vaishnav Pontiff called Rághavendráchárya of Maisur. Like the Vaishnav Deshasths they are branded by their Pontiff with red-hot seals or *tapt mudrás*. In caste matters their pontiff's decision is final. Their social and religious customs are nearly the same as those of Vaishnav Deshasths. They send their children to school, but do not take to new pursuits and are fairly off.

**Shenvis** are returned as numbering 2916 and as found all over the State especially in Ájre and Bhudargad. They are middle-sized, fair, and well made and the women thin, tall, and graceful. Both men and women dress like local Bráhmans, and the women tie their hair in a back knot and are fond of using flowers and false hair. In food character and customs they resemble their brethren in Kánara and Ratnágiri. They are landholders, State servants, and moneylenders, and as a class are well-to-do.

**Telangs** are returned as numbering twenty-eight and as found in Karvir, Gadinglaj, and Ichalkaranji. They are wandering mendicants and none are permanently settled in the State. They are dark like other Yajurvedi Deshasths and speak Telugu at home and a corrupt Maráthi abroad. They do not differ from local Deshasths in food drink or dress, and usually live in some temple or traveller's rest-house. They are great eaters and are specially fond of sour dishes. They earn their living by begging and by selling sacred threads. Some of them are very clever in repeating the Veds and many sing *ashtpadis* or eight-lined sonnets of Jaydev to the accompaniment of the lyre and the double drum called *tabla*, and some are *purániks* or readers, who read and explain Sanskrit legends in temples. Telangs are proverbially unbidden guests. Whenever they hear that a feast is to be given, they appear at the host's without being asked and will not go until the host admits at least one or

### Chapter III. People.

BRÁHMANS.  
*Saváshás.*

*Shenvis.*

*Telangs.*

<sup>1</sup> Details of the origin of the Saváshás are given in the Bijápúr Statistical Account.

## Chapter III.

## People.

## BRÁHMANS.

*Tirguls*.

two of their number to the feast. They show the same sturdiness in exacting money at thread-girdings. The only class whom they are afraid to pester are Karhádas. They have no scruples about accepting any gifts or attending dinners on the eleventh day after a death.

**Tirguls** are returned as numbering 107 and as found scattered over the State. They have no tale either of their origin or of their arrival in Kolhápur. Some say they are degraded Dashasths, while, according to others, they are degraded Shenvis. They are betel vine growers, and in look, food, dress, character, and customs resemble their brethren in Poona and Ahmadnagar.<sup>1</sup>

## WRITERS.

*Prabhús*.

**Prabhús**, or Lords, are returned as numbering 286 and as found scattered over the whole State. They are of two classes Káyasth Prabhús and Pátána Prabhús. Most Kolhápur Prabhús are Káyasths. Shiváji (1627-1680) had great faith in Prabhús and raised them to high military and civil posts. The Kolhápur Káyasth Prabhús are believed to have come from the Konkan and Sátára since the rise of the Maráthas state of Kolhápur (1710). The few Pátána or Bombay Prabhús are said to have come during the last fifty years. Of the origin of the Káyasth Prabhús the books give three accounts. According to the Padma Purán they are descended from Chitrágupt who was created by Brahma to record the actions of mankind; according to the Renuka Mahátmya of the Skand Purán they represent a Kshatriya king of Oudh named Chandrasen; and according to an account given in the Shudra Kamlákar, which is probably a Bráhma play on the word *parbhu* or bastard a corruption of the word *prabhu* or lord, they are descended from a Kshatriya and his mistress. The Pátána Prabhús claim a Rajput origin. It seems probable that they represent Rajput settlements from Anhilváda-Pátan in North Gujarát (A. D. 1139) along the Thána coast near Bombay. The Pátána Prabhús properly have no surnames, though of late they have begun to copy the Marátha practice. Among Káyasth Prabhús Dikshit, Garud, Gholkar, Khátik, Pradhán, Ráje, Shringárpure, Támhne, and other surnames are in use. They have also family names from official titles as Chitnis, Jámnis, Kárkhánnis, Pharasnis, Phadnis, and Sabhásad. The two classes of Prabhús differ little in appearance. As a rule the Pátánás are larger, darker, more robust, and manly; some Káyasths are unusually fair and delicate featured. Their women are middle-sized, fair, and goodlooking. Their home speech is Maráthi. The Káyasth Maráthi differs little from the Chitpávan's and the Pátána's home speech is marked by the use of Gujaráti Portuguese and English words. Though there is no caste objection to the eating of fish and flesh, most Kolhápur Prabhús live like Bráhmans on rice, pulse, and vegetables. They dress like Bráhmans and wear the same ornaments. They are clean, neat, hardworking, and faithful. The Káyasths are given to the worship of local goddesses rather than of the regular deities. In other respects their religious rites, fasts, and feasts, and their social customs differ little from those of Maráthás and Maráthas Bráhmans.

<sup>1</sup> Details of the Tirgul Bráhma customs are given in the Poona and Ahmadnagar Statistical Accounts.

Social disputes are settled by the elders of the caste. They send their boys and some of their girls to school and are well-to-do.<sup>1</sup>

**Fighting Classes** of whom there are two Maráthás and Rajputs have a strength of 63,787 or 8·32 per cent of the Hindu population. The details are :

*Kolhápur Fighting Classes, 1881.*

DIVISION.	Males.	Females.	Total.
Maráthás ...	31,506	30,781	62,287
Rajputs ...	788	712	1500
Total ...	32,294	31,493	63,787

**Maráthas** are returned as numbering 62,287 and as found over the whole State. The Kolhápur Maráthás have a special interest as their head the Maháráj of Kolhápur is the only representative of Shiváji the founder of the Maráthá power. As in other parts of the Bombay Deccan the fighters among the Maráthi-speaking middle classes claim to be called Maráthás. Some families perhaps have an unusually large strain of northern or Rajput blood, but as a class Maráthás cannot be distinguished from Maráthi-speaking Deccan Kunbis with whom all eat and the poorer intermarry. The names in common use among men are Chandraráv, Jánójiráv, Mánájiráv, Pratápráv, Suryáviráv, and Udájiráv, and among women Báyajábái, Hansábái, Lálubái, Pritábái, Rájasbái, and Sakvábái. Many men affect Rajput names as Jaysing, Rámsing, and Phattesing and others have Kunbi names as Esba, Gyánba, and Nárbá. Kolhápur Maráthás claim to belong to four branches or *vanshas*, Brahma *vansh* or the Brahma branch, Shesh *vansh* or the Serpent branch, Som *vansh* or the Moon branch, and Surya *vansh* or the Sun branch. As full a list of Maráthá surnames<sup>2</sup> or *ádnávs* as could be

### Chapter III.

#### People.

#### FIGHTING CLASSES.

#### Maráthás.

<sup>1</sup> A detailed account of Prabhus is given in the Poona Statistical Account.

<sup>2</sup> Several Maráthá surnames are interesting as they include the names, and in some cases apparently preserve the true or un-Sanskritised forms of the names, of many of the early Deccan Hindu dynasties of whom all trace has passed from the Deccan caste lists. Among these dynastic names are Cholke perhaps the original form of Chálukya for long (560-1190) the rulers of the Deccan and Karnátak; Kadam which seems to be the same as Kadamba the name of dynasties, who, at different times between the sixth and the thirteenth century ruled the Karnátak, Kolhápur, and Goa; More who probably represent the Mauryas a branch of the great North Indian family of that name who ruled the Konkan and Deccan in the sixth century; Sálunke, which seems to belong to latecomers, perhaps followers of the Solanki rulers of Gujarát (943-1240); Shelár, which seems to preserve the original form of the name of the Siláhára family who ruled in the Konkan and West Deccan from about 850 to 1275; and Yádav, whose most famous Deccan family was of Devgiri or Daulatabad, who were in power and during much of the time supreme in the Deccan from about 1170 till the Musalmán conquest in 1290. As far as is known the Devgiri Yádavs passed from the south northwards, and it is possible they were not northerners but belonged to some southern Kurubar or other shepherd tribe, who, under Bráhma influence, adopted the great northern shepherd name of Yádav. The preservation of these old dynastic names suggests the hope that an enquiry into the strength and distribution of the clans which bear them might throw light on the strength of the northern element in the Maráthás. This hope seems idle. Almost all the leading tribal surnames Cholke, More, Povár, Selár, and Yádav are found, besides among Kunbis who do not appreciably differ from Maráthás, among Kolis, Dhangers, Rámoshis, Mális (who are Kunbis), Mhárs, Mángs, and several wandering tribes, classes which



## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

procured numbering in all about 500 names, is given in the Appendix. Of these the following are said to be the surnames in commonest use among Kolhápúr Maráthás : Bhonsle, Chaván, Gávde, Ghátge, Ghorpade, Gujar, Ingle, Jagdale, Kadam, Kále, Kharde, Magar, Mohite, Nalávde, Phadtare, Povár, Rananavre, Sálunke, Shende, Sinde, Sisode, Sitole, Suryavanshe, and Yádav. Besides its surname every Marátha family has its *devak* or family guardian, of which as complete a list as could be obtained is given in the Appendix. In matters of marriage the guardian is more important than the surname and sameness of surname alone does not bar marriage. As a rule Maráthás are middle-sized, regular featured, and better made than Marátha Bráhmans, a few are handsome and warlike, but as a rule except that they are fairer and better mannered they cannot be known from Kunbis. The women are often fairer and slenderer than Kunbi women. Both at home and abroad they speak Maráthi almost as correctly as Bráhmans, and some of them speak Kánarese fluently but not correctly. As a rule Maráthás live in fairly aired and lighted middle class houses two or three storeys high with stone and burnt brick walls and tiled roofs. The entrance door, which is often spacious and imposing and furnished with a small room called *devdi* for guards or watchmen, opens on a yard in which is a cattle-shed and a stable for horses. One or two rooms in the upper storey and one or two in the ground floor are whitewashed and well painted and decorated with pictures of Ganpati and Shiv, and fancy pictures of gymnasts wrestling, of a war ship, or two tigers and a huntsman. These rooms are used for receptions and business. Other rooms are set apart for dining, keeping stores, sleeping, and cooking; and at the back of the house is a sweet basil or *tulas* pillar. The privy is sometimes in the back of the yard and sometimes near the entrance. Except a few special apartments the house is seldom clean or tidy. The houses of poor Maráthás are smaller and have fewer rooms. The house goods of the ordinary Marátha include a small store of metal waterpots, dining dishes, and cooking vessels, low wooden stools, cots, and pestles or *musals*, stone slabs or *pátas*, pins

---

seem to be but slightly connected. The existence of the same clan name in most middle and low-class Deccan Hindus might be due to the fact that these clans or tribes came into the Deccan as nations or communities complete enough to spread a fresh layer of people over the whole country. The case of the Vanjáris, whose great bands formerly included many classes of craftsmen and who still have Lohárs and Mhárs among them, shows that this is not impossible. At the same time the evidence against sameness of surname proving sameness of tribe or race is so strong as to make such widespread immigration improbable. The case of the Poona Uchlás or slit-pockets, all of whom are either Gáikváds or Jádavs, proves that sameness of surname by no means implies sameness of tribe or race. Uchlás are recruited from all except the impure classes, being joined, besides by Maráthás and Kámáthís, by Bráhmans Mārwarís and Musalmáns, and all recruits whatever their caste are adopted either into the Gáikvád or into the Jádhav clan. The evidence presented by the Uchlás is supported in a less extreme form by the general Deccan practice of calling a chief's retainers by their chief's surname. This practice, together with the case of the Uchlás who supply almost the last trace of the old system of recruiting predatory tribes, seems to show that the possession of northern surnames is no proof of a northern origin or even of a strain of northern blood. It probably usually arose, like the possession of the Norman names of Gordon and Campbell by the Scotch Keltic highlanders, from the practice of followers taking or being given the name of their chief.



or *varvantás*, and grindstones, beds, blankets, and quilts. Middle class houses have a large store of metal vessels and lampstands, low wooden stools, wooden frames or *devárás* for gods, cots, boxes, bedding, blankets, carpets, mortars and pestles, cradles, and bullock carts. Besides these well-to-do Maráthás have silver cups and plates and scented oil-pots, large metal waterpots, and cooking vessels for grand feasts and brass oil-jars or *budhlis*, chairs, tables, benches, cupboards, stools, palanquins, shigrams or dog-carts or phaetons, bedding, Persian carpets or *gálichás*, bed covers, and pillows of various kinds, candlesticks, wallshades, looking-glasses, wooden and ivory toys, and embroidered wall hangings.<sup>1</sup> Maráthás are fond of pets, and rear dogs monkeys and parrots. The staple food of well-to-do Maráthás is wheat cakes, rice, split pulse, clarified butter, and vegetables and condiments; middle class families on ordinary days eat rice, millet bread, *sámhára* or liquid pulse seasoned with chillies, spices and salt, and vegetables; the daily food of the poor is millet bread, chopped chillies, and pulse sauce. All eat flesh and fish. The well-to-do eat mutton or fowls daily. Middle class families use them about once a week, while the poor use them only occasionally on *Dasara* in September-October and *Shimga* in March, and during marriages. Maráthás seldom use liquor though no caste rule forbids either liquor or narcotics. They eat the usual kinds of flesh except beef and pork. At the houses of the well-to-do the food is cooked and served generally by servants called *savalekaris* or clean men, and in middle and poor families the women cook and serve the food. Before dining Maráthás are careful to bathe and put on a fresh-washed cotton waistcloth. The elderly men of the house lay sandal, flowers, and sweetmeats before the house-gods, water the sweet basil, bow to the sun, and sip a little water in which a basil leaf has been dipped. All the men of the family sit in a line on low stools each with a fresh-scoured metal waterpot or *támbya* and a cup or *pela* to his right, and a metal or leaf plate before him with one or two cups for sauce and clarified butter. At home a Marátha eats bare to the waist; in company and on festive occasions he dines without taking off any article of dress. Women take their food after the men, but the Bráhma practice of eating from their husband's plate is not strictly kept.

The men cut the head hair close and wear the moustache and whiskers but not the beard. Some keep the topknot and earknots and shave the rest of the head leaving a clean shaven passage between the knots gradually narrowing from the brow to the centre

<sup>1</sup> The articles in use in the mansions and palaces of the Marátha chiefs of Kolhápura are: gold and silver waterpots, plates simple and engraven, pots for the worship of the house gods, *attar* pans, staffs carried by bards and mace-bearers or *chopdárs*, tree-like stands with holes for holding cotton soaked in scented oil, twilight or *sandhya* worship pots, spoons, betel cases or *pánpuddás*, flywhisk or *chauri* handles, crest ornaments of royal parasols or *abdágirs*, nutcrackers, lampstands or *samais*, large bathing vessels, chairs, cots, elephant cars or *haudás*, frames for housegods, palanquins with their stands, and horse and elephant housings and trappings. The number of gold vessels is small compared to that of silver, and brass and copper vessels are found in great abundance in addition to a large store of stone and wooden furniture and bedding.

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

and again growing wider till it reaches the back of the head above the neck. In many heads this passage is wholly or partly blocked by the bunch of hair on the crown of the head. The women dress their hair with much care, either tying it in a back knot or *buchada* or plaiting it in a braid which they wear in an open circle at the back of the head. They use false hair and are fond of decking their hair with flowers. The men dress in a turban, a coat, a shouldercloth, and a waistcloth, trousers, or short drawers called *cholnás*. Instead of the turban they often wear a headscarf called *rumál* if about three to four yards or a *patka* if ten to fifteen yards long. Marátha turbans are folded in one of two leading styles *Sindeshái* or Sindia fashion the style in use in the Gwalior court and *Patháni* because it is like the Pathán headdress. The *Sindeshái* turban is an elaborate piece of work, folds arranged so as to present all round a sharp ridge which shades the ears with conical protruding wings. The front is a circular convex ridge wider and more solid near the middle forehead, and sharply depressed near the corners to distinguish it from the adjoining ear wings. The hind part is like the front except that the folds are not twisted and are less elaborately arranged. Twisted bands are passed above, below, and across the surrounding ridge and the two gold ends are fixed at the top near the two wings. Some men wear the turban so that the two wings come within an inch of the ears and many consider it fashionable to place the turban jauntily on the left ear, and make its position secure by passing a twisted band lightly round the side where the ear is left free, allowing the raised wing on that side to show all its twisted and well arranged folds. The folds and twists are fixed by the aid of water or pins so that a turban once folded lasts two to three months. Old and staid men use folds instead of twists. In the *Patháni* turban the twists are not half so rigid as in the *Sindeshái* turban nor are there the wings and the corner depressions which are so notable in the *Sindeshái* turban. It is simpler and smaller and more oval than circular in shape slightly resembling the human head. The front is of partly twisted folds arranged so as to form symmetrical rows of numberless parallelograms one above the other till they reach the middle part of the upper surface. The portion above the right ear is raised slightly higher than the part above the left ear, and most of the back is covered by the two gold ends which reach to the middle of the top where the twisted folds of the front generally end. The *Pathán* fashion is becoming more popular among *Kolhápúr Maráthás*, but, as a rule, on festive occasions and special gatherings the *Sindeshái* mode is adopted. Some *Maráthás* fold their headscarfs called *rumáls* or *patkás*, in the shape of their turbans allowing one of its ends to lie loosely on the top which flutters slightly at every jerk in walking. Some wear a *mandil* or gold turban folded like a loose turban. The *Marátha* coat fits very closely especially the arms and chest. The sleeves are generally longer than the arms, the extra length forming numberless small plaits or folds over the lower arm between the elbow and the wrist. The coat is tied in front below the right shoulder and in the centre of the chest, part of the right chest being left open especially by those who pride themselves on their depth of chest. From the chest the coat falls in long full

folds to the knee and sometimes a few inches below the knee. A Marátha's holiday coat is of silk or cloth of gold. It is not so tight as the every-day white coat and the sleeves have fewer puckers. Maráthás have begun to wear English-shaped coats, shirts, jackets, and boots. The Marátha waistcloth is shorter than the Bráhmaṇ waistcloth and the puckers in front and behind are fewer, the ends hanging and fluttering loose. The Marátha shoe which is finely decorated with silk and gold borders is stained a deep red and differs from the Bráhmaṇ shoe by leaving open the whole except the toes and an inch of the upper part of the foot, and having its small round heel as hard as stone. Formerly a sword was part of the regular Marátha dress. Now a walking stick has taken the place of the sword. They also draw a shawl over their shoulders when they attend the court or *darbár*.

Except that they do not pass the skirt back between the feet and that they draw one end of the robe over the head the indoor dress of the Kolhápur Marátha women is the same as of the Kolhápur Bráhmaṇ women. They mark their brows with vermilion and tattoo a small crescent or *chandra* between the eyebrows, and a small dot on the chin and on each cheek, and figures of sweet basil, lotuses representing the goddess Lakshmi, the words *Shrirám Jayráṁ* in Bálbodh, and pictures of Krishna and his beloved Rádha on their forearms. Both men and women have a large store of valuable clothes and ornaments for great occasions. Almost every married woman has a lucky necklace, a nosering, and toerings which she must wear as signs of her married life. Other ornaments she uses at pleasure especially on holidays and on ceremonial occasions. The wardrobe of a well-to-do Marátha man includes turbans, coats of cotton wool and silk, gold turbans, breeches, silk-bordered shouldercloths and waistcloths, gold-bordered shouldercloths or *dupetás*, and silk girdles or *kāñchás*, trousers made in native fashion, one or two shawls, and shoes or boots. Most of these clothes last for several generations and cost £50 to £100 (Rs. 500 - 1000). Middle class Maráthás do not use gold turbans or *mandils* and shawls and gold-bordered shouldercloths or *dupetás*; their ceremonial dress is worth about £5 to £7 10s. (Rs. 50 - 75). Poor Maráthás wear *patkás* or headscarfs instead of turbans and have a pair of silk-bordered waistcloths and shouldercloths, trousers, and white coats which they keep carefully and use only when they have to pay visits and attend court. Women in high families have in store silk robes or *sádís* worth £1 10s. to £7 10s. (Rs. 15 - 75), Paithani robes worth £30 to £50 (Rs. 300 - 500), short-sleeved silk and gold bodices worth 10s. to £2 (Rs. 5 - 20), and gold upper robes or *dupetás*, and shawls worth £10 to £30 (Rs. 100 - 300). Middle-class families seldom use shawls and *dupetás* and Paithani robes, and have a store of silk-bordered robes worth about £1 to £1 4s. (Rs. 10 - 12), and bodices worth 2s. to 4s. (Rs. 1 - 2), ordinary upper robes worth £1 to £3 (Rs. 10 - 30), and sometimes one or two Paithani robes each worth £5 to £10 (Rs. 50 - 100). Poor women have a pair of robes or *sádís* each worth 6s. to 8s. (Rs. 3 - 4) and bodices each worth 2s. to 4s. (Rs. 1 - 2), and an upper scarf or *shela* worth 4s. to 6s. (Rs. 2 - 3) which they put on while going out of doors on festive

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## Chapter III.

## People.

FIGHTING  
CLASSES,  
Maráthás.

occasions. Maráthás both men and women wear a number of ornaments. Well-to-do men wear earrings with two pearls or an emerald pendant called *bhikbális* and *chaurkadás*, finger rings set with diamonds, and gold bracelets or *kankans*; well-to-do women wear for the head a gold *ketak* or sweet pandanus flower, a *chandrakor* or crescent moon, a *rákhdi* or full-moon, a *mud* or a ball-shaped gold ornament, flowers, *gajarás*, *bindis*, *bijvarás*, and *chandrasins*, all studded with pearls and jewels. *Bindi*, *bijvara* and *chandrasin* are used only by girls after they have come of age; the ear ornaments are *bugdis*, *bályás*, *káps*, and *kuradus* all of gold studded with pearls; *bályás* and *kuradus* of pearls with a jewel in the centre; the wrist ornaments are gold *bángdis* or bangles, *bilvars*, *chhands*, *gorás*, *gots*, *kákans* or wristlets, *pátalis*, and *todás*, ornaments of gold studded with pearls and precious stones; the arm ornaments are *bájubands*, *tolbands*, *velás*, and *vánkis* of gold studded with precious stones; the neck ornaments are *chámpekalis* or champa bud necklaces, *chandrahárs*, *chinchapetis*, *javás* or barley necklace, *kalás* or buds, *kanthás* or necklaces, *lapphás*, *pends*, *putalis* and *saris*, gold necklaces set with pearls and precious stones; pearl noserings with a ruby pendant; gold waistbands or *májpátás* set with precious stones; the foot ornaments are chain anklets *ruls* and *válás* of silver except in the case of the ruling family who alone can wear gold ankle and toe ornaments<sup>1</sup>; and toe ornaments as *gends*, *jodvis* or toerings, *másolis*, *phuls* or flowers, and *virodís*. Marátha women as a rule wear all except foot and toe ornaments of gold and pearls according to their means. Ruling and rich families have a store of ornaments worth £500 to £5000 (Rs. 5000-50,000) and upwards; middle-class Marátha women's ornaments are worth £50 to £200 (Rs. 500-2000); and poor Marátha women have at least the gold lucky necklace or *dorle*, the nosering, and silver toerings worth £5 to £10 (Rs. 50-100).

As a class Maráthás are simple, frank, independent and liberal, courteous, and, when kindly treated, trusting. They are a manly and intelligent race, proud of their former greatness, fond of show, and careful to hide poverty. The Marátha is proverbially *dauli* or fond of show. A Marátha though almost starving will raise a copper's worth of clarified butter and rub his moustache and hands with it, and sit washing his hands and face in front of his house, that passers may think he has had a rich dinner. A Marátha may dress in a rag at home but he has always a spare dress which he himself washes, keeps with great care, and puts on when he goes to pay a visit. He hires a boy to attend him with a lantern at night, or to take care of his shoes when he goes into his friend's house and hold them before him when he comes out. They say that war is their calling and few Maráthás of good family however well educated willingly take service as clerks. They never keep shops. As a rule a well-to-do Marátha has in his service a Bráhman clerk called *divánji* or minister, who often takes advantage of his master's

<sup>1</sup> Gold is Lakshmi and therefore must not be allowed to touch the dust or the goddess will be angry and vanish. As rulers are guardians they are Vishnus or Protectors and therefore lords of Lakshmi and able to treat her as they like.

want of education to defraud him, sometimes ending in making his master his debtor. Marátha women are kind, affable, and simple, and with few exceptions are good wives and managers. Maráthás are husbandmen, grantholders, landowners, and State servants. Besides the Maharáj of Kolhápur several Maráthás are chiefs or *sansthániks*. A Marátha almost never rises early and seldom goes out in the morning. He rises about seven or eight, washes, and attends to business if he has any or idles till ten chewing tobacco, smoking, and talking. About halfpast ten he bathes, dresses in a freshly-washed cotton cloth, marks his brow with white or red sandal, bows before the family gods which the priest has already worshipped, repeats the names of the deities Ambábái, Ganpati, Pándurang, and Shankar, and bows after each name. Religious Maráthás pass an hour or two in reading sacred books as the Gurucharitra or Life of Dattátreya, Jnyánoba's commentary on the *Bhagvatgita*, Shiv's Play or *Shiv Lila*, and Rukmini's Choice or the *Rukmini Svayamvar*. Most of them lay sandal and flowers on their gods and drink the holy water or *tirth* used in washing the god's feet. Then the male members of the family sit in a row and take their food. After dinner they chew betel, smoke tobacco, and enjoy a short midday rest. They rise at three, and play at cards dice or chess. In the evening they drive ride or walk, or visit a friend, return about eight or nine, and retire to bed at ten or eleven. Maráthás who have estates to manage lead regular fairly busy lives; those who have no special business pass a life of monotonous weariness in idle talk, betel-chewing, and smoking. Many are fond of hunting, and hunt and shoot several days in every month. Others spend much of their leisure under the influence of opium and hemp-water. Marátha women seldom leave the house, and in well-to-do families, as they have neither to cook nor to mind the house, they have much leisure. A Marátha matron generally spends her morning in washing combing and decking her hair with flowers, in feeding her children, and in bathing. Elderly Marátha women water the sweet basil plant and lay sandal and flowers before Bákrishna or Mahádev, but young women are generally careless about religious rites. After their midday meal they hear a Purán or holy book read by a priest, take a midday nap, look after the children, talk, play, with dice and sometimes with *ságargotás*, chew betel and tobacco, sup after the men, and retire about ten. Some Marátha women embroider and a few have learnt to read and write.

Maráthás worship all Bráhmanic, local, and boundary gods and keep the usual Bráhmanic fasts and festivals. Their priests are Deshasth Bráhmans who conduct their ceremonies and perform the daily worship of the house gods of the well-to-do. Their chief holidays are the Hindu New Year's Day or *Varshpratipada* and *Rámnavmi* in March-April, *Akshaytritiya* or the Undying Third in May, *Nágpanchami Shrávni-Purnima* and *Gokulashtami* in July-August, *Ganeshchaturthi* in August, *Dasara* in September-October, *Diváli* in October-November, *Sankránt* on the twelfth of January, and *Shimga* in March. Their popular fasts are the Elevenths or *ekádashis* in the bright half of *Ashádh* or July-August and *Kártik* or Octr.-Novr., and Shiv's Night or *Shivráttra* in February. The

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## Chapter III.

## People.

## FIGHTING

## CLASSES.

## Maráthás.

Maráthás, especially the descendants of Shiváji the founder of the Maráthá empire, who was raised to be a Kshatriya on paying £40,000 (Rs. 4,00,000) to Gága Bhatt of Benares,<sup>1</sup> claim to belong to the Kshatriya or second of Manu's classes and say that their ceremonies are the same as those of Bráhmans. Bráhmans admit this claim in the case of the ruling family and perform their ceremonies with Vedic texts. The ceremonies of other Kolhápur Maráthá families are performed according to the Shudra Kamalákar a classical Sanskrit version of the Vedic passages. The well-to-do among the Kolhápur Maráthás claim to perform the sixteen Bráhman sacraments or *sanskárs* but the bulk of the people perform no ceremonies except at birth, threadgirding, marriage, coming of age, and death. A girl goes for her first confinement to her parents and a poor Maráthá midwife waits on the pregnant woman. At the time of her delivery she cuts the navel-cord, bathes the mother and child, and lays them on a cot. When a son is born the joyful news is carried to friends and kinsfolk and packets of sugar are handed among them. The priest, who is asked to repeat *shántipáth* or soothing verses every evening from the first to the tenth day, repeats verses over a pinch of ashes and rice, and hands the ashes to the midwife to be rubbed on the brows of the mother and child. A light is kept burning the whole night for the first ten days. A few days after the birth the *játkarm* or birth ceremony is performed, when the priest and friends and kinsfolk are asked to the house, musicians are engaged to play their instruments, betel is served to men guests and packets of vermilion and turmeric are handed among the women, and a feast to the guests ends the ceremony. Now only a few keep this practice. As a rule all Maráthás are particular about the fifth or sixth day worship, as those days are believed to be full of danger to the newborn child. Maráthás share the common belief that convulsive seizures and most other forms of disease are the work of spirits. They think that only by worshipping Mothers Fifth and Sixth can the child be saved from the attacks of evil spirits which are said to hover about the lying-in-room and lie in wait for the child especially during the fifth and sixth days after birth, probably because from the sloughing of the navel-cord the child is at that time liable to tetanus and convulsions.<sup>2</sup> Elderly matrons in the house take the utmost care to keep a light always burning in the lying-in room day and night especially from the fifth to the tenth day, and during that time never leave the mother alone in her room. On the fifth day a few friends and relations are asked to dine at the house. In the lying-in room a betelnut and a sword or sickle are set on a low stool and flowers, sandal-paste, burnt frankincense, and food are laid before the low stool in the name of Mother Fifth or Páñchvi. The mother bows before the goddess with the child in her arms and prays Mother Fifth to save the child from the attacks of evil spirits. The guests

<sup>1</sup> Before his installation Shiváji seems never to have worn the sacred thread. Details of the ceremony are given under Ráygad in the Kolába Statistical Account.

<sup>2</sup> It is worthy of note that the old English name for convulsion is an attack of dwarfs.



are treated to a dinner and men guests pass the whole night singing ballads or *lávnis* and women guests watch by turns in the lying-in room. Mother Sixth or Satváí is worshipped on the sixth day with the same details as Mother Fifth and a few friends are feasted. The mother is held impure for ten days and no one except the midwife touches her. The midwife rubs the mother and the child with oil and bathes them. Then she bathes, takes her food, and waits upon the mother. During the first ten days the midwife eats nothing unless she has bathed from head to foot both morning and evening. The family are held impure for ten days in consequence of a childbirth. During this time they are allowed to touch others, though they cannot worship the house gods. On the eleventh the clothes of the mother are washed, the room is cowdunged, and the family are purified by drinking water which is given them by the family priest. On the eleventh the men renew their sacred threads and lay sandal, flowers, burnt frankincense, and sweetmeats before the house gods. On the evening of the twelfth a few women are asked to the house, musicians play, and the child is cradled. The women dress the babe in a child's hood or *kunchi* and name it saying, Cut off ties and chains and join the umbrella and palanquin.<sup>1</sup> The anniversary of the child's birthday is kept by a feast to friends and kinsfolk, and on that day the ceremony called *chaul karm* or hair-clipping is performed by the well-to-do, and the child's hair is clipped for the first time. Well-to-do Maráthás especially the families of chiefs and *sardárs* or nobles gird their boys with the sacred thread between ten and twelve with nearly the same ritual as at a Bráhmaṇ thread-girding.

Boys are married between twelve and twenty-five and girls generally before they come of age, though coming of age is no bar to a girl's marriage. A Marátha marriage is very costly. The bride's father must give a large dowry to the bridegroom and in return the bridegroom's father must present valuable ornaments to the bride. So the girls whose fathers belong to high families but cannot offer a large dowry with their daughter's hand remain unmarried after they come of age and have sometimes to marry men who are unequal either in age or social position. Even to the well-to-do to have many daughters is a curse. In proportion to the position of the family, the father has to spend on his daughter's marriage, running into debt from which he seldom frees himself. As a rule the offer of marriage comes from the boy's side. Before the marriage is fixed it must be ascertained that the boy and the girl are not of the same clan or *kul*; they may both bear the same surname but the crest or *devak* on the male side must be different. Sameness of crest on the female side is no bar to marriage. After talking the matter over and fixing on the most suitable girl, the boy's father sends a Rául or Bhát to see the girl. He goes to her house and is treated to a dinner. After a dinner and some betel the Rául or Bhát tells the girl's father why he has come and asks if they are willing to marry their girl. The girl's father answers

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

<sup>1</sup> The Maráthi runs : *Bedi bandhan tod ani chhatri sukhásan jod.*

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

either that they are willing or that they are not willing, and the Bhát or Rául returns home with a present. If the girl's father says he is willing some poor women relations of the boy or a female servant are asked to see the girl. If their report of the girl is satisfactory, the boy's father on a lucky day sends a relation or friend, together with his priest and the Bhát to the girl's to propose the match. They go to the girl's house and are welcomed by the girl's father. They are given water to wash their hands and feet, betel and tobacco are served to them, and they are treated to a dinner. The head of the house kills a goat or at least a fowl, asks a friend or two to dine with the guests, and gives uncooked provisions to the priest who either cooks for himself or has his dinner cooked and served by a Bráhmaṇ. After dinner all sit in the hall, betel is served, and the Bhát formally declares their object in coming. If the girl's father agrees to the match, he calls in his priest and hands him the girl's horoscope. Both priests compare the horoscopes of the boy and the girl, calculate the positions of the stars at the time of their birth, and say whether the match will be lucky. If the astrologers or priests say the match will be unlucky, no further steps are taken. When the boy's and the girl's parents are anxious for the match they do not depend on the words of the astrologer and even do not consult him but at once settle the marriage terms the chief of which are the sum to be paid to the boy by the girl's father at the time of the girl-giving or *kanyáddān*, the clothes and ornaments to be presented to the girl by the boy's father, and the clothes to be presented to the relations of each by the other. Sometimes if the girl is unusually handsome and intelligent the boy's parents bear the whole marriage expenses even of the girl and do not receive a farthing from the girl's parents if they cannot conveniently pay. At other times if the girl's parents are well-to-do and wish to give their daughter to a poor but high family boy they pay the boy's marriage charges and present the girl with ornaments and the boy with a large dowry. A short time before the terms are settled the girl's father sends some relations to see the boy at whose house a feast is held for the guests and they return with presents of turbans and waistcloths or at the least with a waistcloth or cash. At the house of some Maráthás, the presence of a Nhávi is required at the time of settling the marriage. When the terms are settled the fathers exchange cocoanuts, and the barber's duty is to hand the cocoanut to each as the sign of the marriage settlement; for this he is called *mhála* or the marriage settler and both parties present him with cash or a turban. The boy's and girl's fathers ask the village astrologer or *grámjoshi* to name three lucky moments on three different days, for the turmeric-rubbing, marriage, and *varát* or home-taking. As a rule the bridegroom must visit the girl's house for the marriage; but if the girl's parents are poorer than the boy's parents or the boy's parents refuse to visit the girl's but agree to pay her marriage charges, the girl's parents take the girl to the boy's village and lodge at a separate house which has been prepared for them. To take the girl to the boy's house is thought incorrect among Maráthás and forms a special item in the marriage

agreement. A little before the turmeric-rubbing the boy's relations and the priest go with music to the bride's and are received at her house. Music plays and the priest puts a robe and bodice and ornaments and a packet of sugar into her hands. A wheat or rice square is traced round two low stools set in a line close to each other and on another stool before them are placed five waterpots or *kalashas* with cotton thread passed round their necks. The priest repeats verses, lays a betelnut and leaves in each pot, and covers their mouths with half-cocoanuts. He then sets a betelnut on a couple of leaves laid on the low stools and offers sandal, flowers, burnt incense, and sweetmeats to the betelnut Ganpati and the waterpot Varun and waves lights round them. The bride and her mother are rubbed with wet turmeric powder mixed with fragrant oil by the boy's women servants. The girl then comes before the waterpot Varun and the betelnut Ganpati. The priest repeats verses and the girl is told to walk five times round the betelnut Ganpati and the waterpot Varun and sits on one of the two stools in the wheat square; her mother sits on the other stool and while music plays they are again rubbed with sweetscented oil and turmeric and bathed by five women neighbours and relations. The bride is helped to put on a new yellow robe and bodice and her future mother-in-law presents her with ornaments. What remains of the turmeric a party of his friends take with music to the bridegroom's. The boy is rubbed with turmeric and bathed with the same rites as at the girl's house and the turmeric-rubbing ends with a feast at the boy's and girl's.

Next comes the marriage guardian or *devak* worship. A day or two before the marriage a man at the house of the boy and of the girl, bathes, and with music and a band of friends goes to the tree,<sup>1</sup> which is the family guardian, offers sandal, flowers, burnt frankincense and sweatmeats to it, cuts a branch, lays it in a winnowing fan, and brings it home with music. He takes it to his god-room and worships it along with his family gods which are represented by betelnuts in a winnowing fan. Meanwhile five unwidowed girls wash a grindstone or *játe* and lay sandal, flowers, and sweetmeats before it and a family washerwoman worships the stone slab or *páta*, and a feast to married women and a few friends and relations completes the guardian or *devak* worship. Invitation cards are sent to distant friends and the houseowner asks a few of his near relations in person who come to the house on the marriage guardian or *devak* worship day. After dinner the invitation processions start as among Bráhmans, from the boy's and girl's and ask local friends and kinsfolk to the marriage. After dinner the boy is well dressed and seated on a low stool laid in a square marked by the washerwoman with wheat or rice, and married women with a dish of turmeric, vermilion, and rice grains, rub him with turmeric, mark his brow with vermilion, and stick the rice grains on the vermilion. His head is hung with flower garlands or *mundávalis* and he is taken to his family goddess or *kuldevi*, lays a cocoanut and

## Chapter III.

## People.

FIGHTING  
CLASSES.*Maráthas.*

<sup>1</sup> A list of the Marátha *devaks* or marriage guardians most of which are trees or creepers is given in the Appendix.

## Chapter III.

## People.

## FIGHTING

## CLASSES.

## Maráthás.

bows before her, and asks her to be kindly, and starts on horseback for the girl's with friends, relations, priests, and musicians. When they reach the girl's village they stop and visit the village Máruti. The boy dismounts, bows before the god, and asks him to be kindly. Here they are met by the bride's party with music and friends and the *simánt pujan* or boundary worship is performed. If the girl is taken to the boy's village, the ceremony is performed at the house of a friend in the neighbourhood. All are seated and the bride's father marks the boy's brow with sandal and sticks grains of rice on it, burns frankincense before him, gives him sweetmeats to eat, and presents him with a turban and a gold scarf or *shela*. The guests are then escorted to a lodging or *jánvasghar* prepared in the bride's neighbourhood. The Marátha *vágnischaya* or troth-plinghting is the same as among Bráhmans. The boy's father meets the girl's father at his house with his priest and is seated; the girl's father sits near him and his priest attends him. The priests then worship the betelnut Ganpati and the metalpot Varun and repeat verses. The girl's father offers his daughter in marriage to the boy and in presence of his and the girl's relations the boy's father accepts the offer saying, I take her. The fathers change cocoanuts and a distribution of sugar ends the ceremony.

Shortly before the bridegroom starts for the bride's the bride's parents send a feast or *rukhwat* with a few friends and music to the boy's house. The boy is seated on a low stool set in a wheat square, and the sweet dishes brought from the bride's by the village Nhávi are arranged in rows about the stool. The dishes are usually of two kinds, for show and for use. The show dishes include sweet wheat and gram flour balls and sugarcoated betelnut and almond balls, as large as or larger than unhusked cocoanuts; the dishes for use are of ordinary size and are prepared with great care. The bridegroom is presented with a turban, his brow is marked with vermilion to which grain is stuck, lights are waved about him by married women, and he is told to help himself to the dishes. When the boy's feast or *rukhwat* is over, the girl's party with friends and music go to the boy's and tell them that the marriage hour is near. The bridegroom is dressed in rich clothes, his brow is decked with the marriage coronet or *báshing*, a dagger is set in his hands, and he is seated on a horse which is led by the village barber or Nhávi. Musicians walk in front, behind them walk all the men of the bride and bridegroom's parties, and then the bridegroom. Behind the bridegroom walks his sister usually a young girl closely veiled with a gold scarf or *shela* with the *shakundiva* or lucky lamp laid in a dish, and another veiled woman follows her with a metal or earthen pot called *shenskara* holding rice betelnut and water, and covered with a mango branch and a cocoanut and set on a heap of rice in a bamboo basket. If the pair are poor, the women of their house walk veiled behind the bridegroom; if the families are rich the women ride in closed palanquins or walk between cloths which are held round them by women servants. On reaching the bride's the bridegroom dismounts, the priest throws cuminseed or *jiri* on the booth, the bride's mother meets him at the booth door with a dish holding two wheat flour lamps, waves small rice balls and wheat flour lamps round the

bridegroom, throws the rice balls to one side and lays the wheat flour lamps at the bridegroom's feet; another married woman of the bride's house pours a dish full of water mixed with lime and turmeric on his feet. The bridegroom presents the woman with a robe and bodice, the bride's father hands the bridegroom a cocoanut and leads him by the hand to a place prepared for him near the altar. The men guests are seated on carpets in the marriage hall. The women alight from their palanquins hid by curtains held round them by their women servants, and are welcomed to their seats in a hall separated from the men's hall only by a cloth wall near the raised altar or *bahule*. Dancing girls amuse the guests in the marriage hall and the servants load their muskets and hold themselves ready to announce the lucky moment by firing their guns. Shortly before the lucky moment the girl is seated in front of the family goddess or *kuldevi* and throws rice at the *kuldevi* and prays her to grant her a good husband. The astrologer is busy watching his water-clock, and has a horn-blower or *shingi* ready to blow his horn as soon as the astrologer gives the signal by clapping his hands. As the lucky moment draws near the girl is brought out of the house and made to stand before the bridegroom face to face separated by a curtain marked with a lucky cross. The priests stand on either side of the curtain and tell the pair to fold their hands, to look at the lucky cross, and pray to their family gods. The priests repeat lucky verses and throw red rice at the pair, crying *Sávdhán* or Beware, and the musicians play. One of the priests hands red rice to the guests and another holds an empty dish before them and gathers the red rice to be thrown over the pair at the lucky moment. The astrologer tells the moment by clapping his hands, the hornblower or *shingi* blows his horn, the guns are fired, and the musicians redouble their noise. The priests draw aside the curtain, touch the bridegroom's eyes with water, pour red rice over the pair, and they are husband and wife. The bridegroom is taken to a seat near the earthen altar and the bride goes into the house. The bride's father and mother sit on two low stools in front of the bridegroom face to face, the father washes the feet of the boy, and the mother pours water on them. The father marks the brow of the bridegroom with sandal; sticks grains of rice on the sandal, hands him a flower to smell, burns frankincense before him, and pours honey and curds over his hands to sip, and the ceremony of honeysipping or *madhupark* is over.<sup>1</sup> The girl's maternal uncle, or some other near relation, gives the girl's right hand to the boy who clasps it fast in both his hands. The priest lays both his hands over the boy's and mutters verses. The girl's father sets sandal, flowers, burnt frankincense, and sweetmeat before the betelnut Ganpati and the waterpot Varun, and pours water with some coins in it over the clasped hands of the boy and girl and the *kanyádán* or girl-giving is over. The guests in the hall are treated to betel and fragrant cotton sticks called *phávás*, and take leave soon after the girl-giving is over.

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

<sup>1</sup> Formerly any distinguished guest was received with *madhupark* literally honeysipping. The host killed a calf and treated the guest to a dinner but the cow-killing or *gavilambh* was forbidden by the first Shankarácharya on pain of loss of caste. Since that time *madhupark* is performed only at weddings.



## Chapter III.

## People.

## FIGHTING

## CLASSES.

## Maráthás.

The priest then asks the bridegroom to tie the lucky neckthread or *mangalsutra* round the bride's neck, and ties together the hems of the pair's clothes. They are seated on low stools set on the earthen altar, the bride as a rule sitting to the bridegroom's left. The sacrificial fire is lit and fed with clarified butter, sesame seed, cotton sticks, and *palas* or other sacred wood with nearly the same rites as at a Bráhmaṇ marriage. The bride's brother squeezes the bridegroom's ear and is presented with a turban by the bridegroom's party. The pair then leave their seats, walk seven times from right to left round the sacred fire, and the ceremony of Seven Steps or *sapt padi* is over. Turmeric root wristlets are tied to the hands of each of the pair. They bow before the family gods and the first day's proceedings are over. From this day to the hometaking or *varát* the bridegroom stays at the bride's and is feasted. The boy sleeps with the men outside and the girl with the women in the house.

On the next day a sumptuous feast is held in honour of the bridegroom's party. In the morning the pair play at the betelnut hunt and rub each other with turmeric. The boy is seated on the altar and the girl stands behind with turmeric powder in her hand and tries to force some of it into his mouth. The boy keeps his mouth closed tight and tries to prevent her, and if she succeeds in forcing some into his mouth, he is laughed at and asked if he is hungry. Then the boy stands behind the girl and tries with his left hand to force turmeric into her mouth. Next the boy holds a betelnut in his hand and asks the girl to take it from him. They struggle and the girl manages to snatch it away. Then the girl holds a betelnut in her closed fist and asks the boy to take it. If the boy fails, he has to beg it of her, and is laughed at. Lastly the pair bathe, dress in new clothes, and break their fast. Meanwhile the girl's party go with music and friends and ask the bridegroom's party to dine at the bride's. At noon they are asked with music and friends and are treated to a sweet dinner or *godí jevan*. In the evening the boy's mother performs the ceremony of seeing the daughter-in-law's face or *sunmukh darshan*. The bride's mother with music and women friends asks the bridegroom's mother to her house. Accompanied by kinswomen and friends and the family priest and music the bridegroom's mother goes to the girl's bringing bamboo baskets, sesame seed, gram balls, betelnuts, cocoa-kernels, dates, a robe and bodice, and ornaments sweetmeats and fruit. On the way she feigns anger and tries to return home when the girl's mother presents her with a robe and bodice, the washerwoman spreads sheets of cloth on the way, and the bridegroom's mother and her friends go walking over them to the bride's house with music. At the girl's the priest worships the betelnut Ganpati and the waterpot Varun and the boy's mother dresses the girl in the clothes she has brought and sweetens her mouth with sugar. Then comes the basket or *jhál* ceremony. A piece of cloth is spread in a bamboo basket and nine dates, nine cocoa-kernels, and nine lumps of turmeric and a handful of rice and cooked food are laid in it. The priest offers sandal, flowers, rice, and sweetmeats to the basket, and the boy and the girl, with the hems of their garments knotted together, walk five times round it from right to left. The basket is



set on the heads of the nearest relations of the boy and the girl and the ceremony is over. The pair accompanied by friends relations and music start for the boy's. The girl is fully dressed and closely veiled and seated in a palanquin with the boy face to face followed by attendants who wave flywhisks or *chauris* round the pair and hold state umbrellas or *abdágirs* over them. Among poor Maráthás the bride and bridegroom are seated on horseback and the horse is taken by the village Nhávi to the bridegroom's house preceded by musicians and kinsfolk and followed by the bride's sister on horseback or in a closed palanquin. On reaching the house the pair bow before the house-gods and elders, lay sandal and flowers before the goddess Lakshmi, present clothes to the bride's party, and the ceremony ends by a feast at the bridegroom's. Maráthás treat their wedding guests to two sorts of dinners or *mejavánis*, *godí* or sweet and *kháti* or sour. The *godí* feast is given before the marriage guardian is bowed out and the *kháti* which is usually a flesh feast, is given after the marriage guardian is bowed out. At the *kháti* feast Maráthás sit in full dress each with a sword by his side. Maráthás do not allow widow marriage, know nothing of polyandry, and practise polygamy.

Even though the bride is of age, the marriage consummation does not form part of the marriage ceremony. The consummation ceremony is put off till the bride's first monthly sickness after the marriage. In performing the age-coming ceremony, the girl is seated in a gaily decked wooden frame or *makhār* with arches on each side in a specially prepared hall. Plantain stems decked with tinsel and coloured paper are set at each corner of the frame. The girl is dressed in a rich yellow robe and bodice and her brow is marked with vermilion on which rice grains are stuck. Her head is hung with a network of flowers and garlands are tied round her neck and lines of vermilion drawn on her feet. The news is handed round among friends and kinsfolk and sugar packets and cocoanuts are distributed at every house in the neighbourhood. Women friends and relations present the girl with sweet dishes and musicians are engaged to play at the house while the ceremony lasts. The girl is unclean for three days. On the fourth she is rubbed with oil and turmeric and bathed, and a lucky day, between the fourth and the sixteenth, is named for the puberty ceremony. On the morning of the lucky day the pair are rubbed with turmeric and fragrant oil and bathed while music plays. Friends and kinsfolk are asked and the pair are seated on low stools, the girl to the right of the boy. The priest attends and lights the sacred fire as at the Bráhmaṇa puberty ceremony. The pair bow before the gods and elders and the ritual is complete. A grand feast is given to women friends and neighbours at noon and in the evening the ceremony called *otibharan* or lapfilling is performed. The pair are seated on two low stools set in a wheat or rice square, the girl to the left of the boy, and the brows of both the boy and the girl are marked with vermilion. Rice grains are stuck on the vermilion and married women fill the girl's lap with a bodiced cloth, wheat, cocoanut, fruit, packets of vermilion, and betelnuts. Their fathers-in-law present the boy and girl with clothes and ornaments, and the girl's father presents the pair

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

with bedding, lamps, metal waterpots, and betel cases. The rest of the ceremony is the same as the Bráhmán puberty ceremony. During a girl's first pregnancy in the third, fifth, and seventh months, while music plays five unwidowed women fill her lap with wheat, a bodicecloth, a cocoanut, and fruit. She is asked to dine by women friends and relations during the seventh and the eighth months and is presented with robes and bodices. She is taken with women friends and relations to some garden where a longing feast or *dohalejevan* is given her.

When a Maráthá dies the body is bathed and dressed in a white sheet, laid on a bier, and tied fast to the bier with strings. Betel leaves, flowers, and redpowder are thrown on it, and sometimes half a dozen gold or silver flowers are strewn over the bier. The well-to-do Maráthá dead are carried in a palanquin to the burning ground which is generally on the bank of some stream or river accompanied by kinsmen and preceded by Holár or Mhár pipe-blowers. The body is bathed in water, the pile is built, the dead is laid on the pile, and burnt with nearly the same rites as at a Bráhmán funeral. When the body is nearly consumed, the party bathe in the river and return home. On the second third or fourth day the ashes are gathered, and, except a few bones which are buried somewhere near the burning ground they are taken to some holy place or river and are thrown into the water. The rest of the funeral ceremony is performed on the third, fifth, seventh, or ninth at the latest. On the tenth rice or wheat flour balls are offered to the dead. On the eleventh the family, which since the death has been impure, are cleansed by eating the five products of the cow and present Bráhmans with clothes, pots, umbrellas, shoes, cows, and cash in the name of the dead. On the twelfth balls or *pinds* are offered to the dead and his ancestors, and on the thirteenth the *shráddh* or mind-rite is performed in the name of the dead, and friends and kinsfolk are treated to a dinner. On the fourteenth the mouth-sweetening or *god tond karne* is performed, when relations meet and treat the chief mourner to a sweet dinner. At the end of every fortnight, month, and year from the death-day, uncooked provisions are given to Bráhmans in the deceased's name and the anniversary of his death is kept by a *shráddh* or mind-rite, when friends and relations are asked to dine at the house. The dead is remembered every year in the dark half of *Bhádrapad* or August-September on a day corresponding to the death-day in the *Mahálaya Paksh* or All Souls' Fortnight. The chief mourners, out of respect to the dead for one full year avoid gay colours and sweet dishes and do not attend marriage or other festive parties. Maráthás gird their boys with the sacred thread which they renew every year on Cocoanut Day in August. On that day all bathe and sit on low stools and Bráhmán priests attend. One of the priests tells them to sip water three times in the name of Vishnu and pours the five products of the cow on the right palm of each which they sip and again drink water in Vishnu's name. They are then given sacred threads by the priest and put them on. The priests get a cash present and withdraw with uncooked provisions. Some Maráthás of high family perform the sacred thread-renewing or

*shrávni* according to the Bráhmaṇ ritual. On the anniversary of the dead Maráthás lay sandal, flowers, rice, and food before three to thirteen *palas* Butea frondosa leaves and present the officiating and other priests who are generally as many as the number of leaves with uncooked provisions and cash. Maráthas married couples are asked to the house, their feet are washed with water by the deceased's son, and they are feasted. After dinner betel is served to the guests and they withdraw with presents of turbans and robes. Maráthás have a caste council and settle social disputes at meetings of castemen. Breaches of caste rules are punished with fines which generally take the form of caste feasts. They send their boys to school, and except a few are not well-to-do.

The name Marátha, which rose to importance under Sháháji (1594-1664) and his son Shiváji (1627-1680) in the seventeenth century and under the Peshwás became famous throughout India in the eighteenth century, has a threefold application. It is applied First to the section of India south of the Narbada and north of the Karnátaḱ in which the Maráthi language is spoken; Second to the whole Maráthi-speaking population; and Third, in a narrower and more correct sense to the bulk of the old fighting and now cultivating middle class of the country whose language is Maráthi. The generally received origin of the name Marátha, an explanation which has the support of Mr. Fleet and Dr. Bhagvánlál, is that it comes from Maháráshtra the Great Country a name which the early Sanskrit-knowing settlers in Upper India are supposed to have given to the unknown land to the south of Hindusthán.<sup>1</sup> To this explanation the chief objection is the absence of any reason why the people of Northern India should honour the south of India with the name of Great Country, or why, if the name Great Country was at first applied to the whole of Peninsular India it should come to be restricted to the present Maráthi-speaking portions of the peninsula. If any people can be found with a suitable name it seems more likely that the country took its name from the people than that the people took their name from the country. This view was held by the late Dr. John Wilson who proposed to trace Maháráshtra to Mhár-ráshtra the land of the Mhárs. But though the Mhárs are a large and important class in the Maráthi-speaking country their depressed state makes it unlikely that the country should have been called after them. One derivation, which has the approval of Professor Bhándárkar, remains, that Maháráshtra is the Sanskritised form of Mahárattha that is the country of the Maharatthis or Maháratthis that is the Great Rattis,<sup>2</sup> a tribe which, under the name Ratta or Ratthis and its Sanskrit form Ráshtrakas or Ráshtrikas, from very early times have at intervals ruled in the Bombay Deccan Bombay Karnátaḱ.

In the middle of the third century before Christ, in the copy of his rock-cut edicts which is preserved at Gírnár, the Mauryan emperor Ashok (B.C. 245) states that he sent ministers of religion to the Rástikas, the Petenikas, and the Aparántas. According to

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## History.

<sup>1</sup> Fleet's Kánarese Dynasties, 3.<sup>2</sup> Bhándárkar's Early Deccan History, 10.

**Chapter III.****People.****FIGHTING  
CLASSES.****Maráthás.****History.**

Professor Bhándárkar the Aparántas are the people of the Bombay Konkan, the Petenikas are the people of Paithan about fifty miles north-east of Ahmadnagar, and the Rástikas or (Sk.) Ráshtrikas are the people of Maháráshtra.<sup>1</sup> According to Professor Bhándárkar one branch of the tribe of Rástikas or Rattas took the name of Ráshtrakutas and governed the Deccan and Konkan before the fifth century after Christ.<sup>2</sup> They then lost power but won it back about 760 and continued supreme in the Deccan and KarnátaK till about 970.<sup>3</sup> Mr. Fleet<sup>4</sup> favours the opinion that the name Ráshtrakuta was not a Sanskritised form of Ratta but was acquired by the holders in virtue of their office of managers of a *ráshtra* or province. But the case of the Rattas who ruled in the Belgaum district from the ninth to the thirteenth century (875 - 1250) and who claimed to be a branch of the Ráshtrakutas strongly supports the view that Ráshtrakuta is a Sanskritised form of Ratta.<sup>5</sup> In the Kánarese districts the Rattas seem to be now represented by the Raddis one of the leading classes of Kánarese husbandmen.<sup>6</sup> The fact that the list of Maráthá surnames, which includes Cholke that is Chálukya, Selár or Siláhára, Kadam or Kadamba, Yádav or Jádav, and almost all the early rulers of the Deccan, does not include Ratta, favours the view that the memory of the Rattas is preserved in the general term Maráthá. The suggestion that a branch of the Rattas in very early times took the name of Maháratthis or Great Rattas is supported by the practice of the Bhoja rulers of the Konkan and West Deccan who are styled Bhojas in Ashok's thirteenth edict (B.C. 240) and Mahábhojas in rock-cut inscriptions in the Bedsa caves in Poona and the Kuda caves in Kolába of about the first century after Christ.<sup>7</sup> The earliest known mention of the name Maráthá is an inscription of about B.C. 100 over a statue in the Nána pass rest-chamber. This inscription runs *Maháratthágraniho giro*, which probably means The hero, the leader of the Maráthás or Great Rattas.<sup>8</sup> An inscription in the Bedsa caves in the Poona district of about the first century after Christ mentions a gift by a Maháratthi queen and three other inscriptions of the same or of a slightly later date, one at the Bhája caves and two at Kárlé both in the Poona district mention gifts by persons who call themselves Maháratthis.<sup>9</sup> Mahávanso the Ceylonese chronicle of the fifth century

<sup>1</sup> Early Deccan History, 9.

<sup>2</sup> Early Deccan History, 10. Of this Early Ratta or Ráshtrakuta dynasty all that is at present known is that about the fourth century after Christ a chief of this tribe named Krishna ruled whose coins have been found in Násik, South Gujarát, the islands of Salsette and Bombay, and in the South Bombay Deccan. Fleet's Kánarese Dynasties, 31 note 1.

<sup>3</sup> Fleet's Kánarese Dynasties, 31-38; Bhándárkar's Early Deccan History, 10.

<sup>4</sup> Kánarese Dynasties, 32.

<sup>5</sup> Compare Fleet's Kánarese Dynasties, 79-83. The view that Ráshtrakuta is a Sanskritised form of Ratta has the support of Mr. Rice, Dr. Burnell (South Indian Palæography, p. x.), and as noticed above of Professor Bhándárkar.

<sup>6</sup> The 1881 census gives in the Bombay KarnátaK a total of 56,874 Raddis. They are also found in Maisur.

<sup>7</sup> Bombay Gazetteer, X. 336-340; Arch. Survey No. 10, pp. 4, 9, 17, 26. Early Deccan History, 10.

<sup>8</sup> Jour. Bom. Br. Roy. As. Soc. XIII. 311; Early Deccan History, 10. Other interpretations of Maháratthá are the Great Charioteer and the Great Warrior.

<sup>9</sup> Archæological Survey No. 10, pp. 24, 26, 28, 34.

(A.D. 480) twice mentions the country of Mahárattha.<sup>1</sup> About the middle of the seventh century (A.D. 634) the famous inscription at Aihole or Aivalli in South Bijápur notices that the Great Western Chálukya king Pulikeshi II. (610-635) gained the sovereignty of the three Maháráshtrakas which together contained 99,000 villages.<sup>2</sup> About the same time the Chinese pilgrim Hiwen Tshang (629-645) describes the kingdom of Mo-ho-lach'a, apparently Mahárattha or Maháráshtra, as nearly six thousand *lis* or twelve hundred miles in circuit. The capital, which was towards the west near a large river, had a circumference of thirty *lis* or six miles.<sup>3</sup> Hiwen Tshang describes the people, apparently the warlike Marátha tribe, as tall, boastful, and proud. Whoever does them a service, he says, may count on their gratitude, but no one who offends them will escape their vengeance. If any one insults them, they will risk their lives to wipe out the affront. If any one in trouble applies to them forgetful of themselves they will hasten to help him. When they have an injury to avenge they never fail to warn their enemy; after the warning each puts on his cuirass and grasps his spear. In battle they pursue fugitives but do not slay those who give themselves up. When a general has lost a battle, instead of punishing him corporally they make him wear women's clothes, and so force him to sacrifice his life. The state maintains several hundred dauntless champions, who every time they prepare for combat, make themselves drunk with wine; and then one of them, spear in hand, will defy ten thousand enemies. If they kill a man whom they meet on the road, the law does not punish them. Whenever the army goes on a campaign, these braves march in front to the sound of the drum. They also intoxicate many hundreds of naturally fierce elephants. At the time of coming to blows they drink strong liquor. They run in a body, trampling everything under their feet. No enemy can stand before them; and the king proud of possessing these men and elephants despises and slights the neighbouring kingdoms.<sup>4</sup> About 1020 the Arab geographer Al Biruni mentions Marhat Des as a country to the south of the Narbada.<sup>5</sup> In 1320 the French friar Jordanus refers to 'the kingdom of Marátha as very great.'<sup>6</sup> In 1340 the African traveller Ibn Batuta notices that the people of Daulatabad or Devgiri were Marhatahs whose nobles were Bráhmans.<sup>7</sup>

From the beginning to the end of his Deccan history (1290-1600) the historian Ferishta often mentions the Maráthás. In his account of the Musalmán Turk conquest under Alá-ud-din Khilji and his generals, Ferishta refers to the Maráthás as the people of the province of Mhárát or Mherat, dependent on Daulatabad and apparently considered to centre in Paithan or as it is written

## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## History.

<sup>1</sup> Turnour's Mahávanso, 71, 74. The name Mahárattha also occurs in the Dipvanso (Oldenburg's Edition, 54) which is much older. Early Deccan History, 10.

<sup>2</sup> Indian Antiquary, VIII. 244.

<sup>3</sup> Dr. Burgess (Ind. Ant. VII. 290) suggests, though the description hardly suits the site, that this may be Bádámi in South Bijápur.

<sup>4</sup> Julien's Hiwen Tshang, II. 149; Indian Antiquary, VII. 290.

<sup>5</sup> Elliot and Dowson, I. 60. <sup>6</sup> Yule's Jordanus' Mirabilia, 41. <sup>7</sup> Yule's Cathay, 415.



## Chapter III.

## People.

FIGHTING  
CLASSES.

## Maráthás.

## History.

Mheropatán.<sup>1</sup> In 1318 Harapál the son-in-law of the Devgiri chief rebelled and forced the Musalmáns to give up several districts of Maráth.<sup>2</sup> In 1370 Jádhav Marátha, the chief of the Náiks, revolted in Daulatabad, persuaded its Musalmán governor to join him, raised the Ráthod chief of Báglán and other local leaders, and collected a great army at Paithan.<sup>3</sup> Till the end of Bahmani supremacy (1490) some Marátha chiefs, among them the Rájás of Gálna and Báglán in Násik, were practically independent paying no tribute for years at a time. After the close of Bahmani supremacy (1490), under the Ahmádnagar and to a less extent under the Bijápúr kings, one or two Marátha chiefs remained nearly independent.<sup>4</sup> Others were continued in their estates on condition of supplying troops,<sup>5</sup> and others took service with their Musalmán rulers and were granted estates and the Hindu titles of Deshmukh, Sar Deshmukh, Náik, Ráv, and Rája.<sup>6</sup> In several cases the daughters of leading Maráthás were raised to be the wives of Musalmán kings.<sup>7</sup> Of the lower ranks of Maráthás many were employed as mercenary troops, most of them as cavalry<sup>8</sup> but some also as infantry. On one occasion (1507) the bulk of the people between Paithan and Chákan in Poona are spoken of as rebellious Maráthás. Besides by their correct name the Maráthás are often called Bargis, a word of uncertain origin.<sup>9</sup> Shakespeare seems to derive it from the Sanskrit Vargiya as it originally means a man of class (*varg*) or family.<sup>10</sup> Grant Duff describes it as a word of unknown origin apparently a slang term of contempt used of the local levies by the regular foreign cavalry.<sup>11</sup> In another passage Grant Duff states that all the troops

<sup>1</sup> Scott's Deccan, I. 13, 32. Ferishta's Mherat seems closely to correspond with the present Maháráshtra as the two other main divisions of the Deccan were as at present Kar or Karnátak and Telingana. Ditto, I. 10.

<sup>2</sup> Scott, I. 13.

<sup>3</sup> Scott, I. 32.

<sup>4</sup> The Gálna and Báglán chiefs were forced to pay tribute in 1507 and again in 1530. Briggs' Ferishta, III. 204, 226.

<sup>5</sup> Briggs' Ferishta, III. 226.

<sup>6</sup> One Marátha under Bijápúr held the high title of chief of the nobles Omir-ul-omrah. Grant Duff's Maráthás, 39-40.

<sup>7</sup> The daughter of Sábáji Marátha married Amir Berid the son of the Georgian slave Kásim Berid who (1492) became king of Bedar. Briggs' Ferishta, III. 495. Yusuf Adil Sháh's wife (1489-1510) was a Marátha woman of exquisite beauty, great understanding, and engaging manners. Scott's Deccan, I. 226.

<sup>8</sup> In 1507 Maráthás joined the bulk of Malik Ashraf's troops, who for a time held Daulatabad. Briggs' Ferishta, III. 204. In 1535 Ibráhim Adil Sháh of Bijápúr had 30,000 cavalry apparently chiefly Maráthás (Scott's Deccan, I. 262, 278, 302, 303). In 1548 the Bijápúr Marátha horse cut off all supplies from the Ahmádnagar army. Briggs' Ferishta, III. 233, 234. In 1560 Ali Adilsháh I. is mentioned as trusting his family to three Marátha officers. Ditto, III. 432. In 1580 Ibráhim Adil Sháh sent an army of 20,000 Marátha horse to harass the besiegers of Naldurg. Ditto, III. 448. And in 1582 the Abyssinian faction in Bijápúr employed 10,000 Marátha horse against the force that was investing the city. Ditto, III. 153. Grant Duff (History, 40) says, Neither national sentiment nor unity of language and religion, prevented the Maráthás fighting against each other. They fought with rancour wherever there were disputes or family feuds. Their Musalmán rulers used this spirit of rivalry as a means of balancing Marátha families against each other.

<sup>9</sup> Bargi is not to be confounded with the Persian Bárgir literally a rider that is a trooper whose horse and arms are supplied by the chief under whom he takes service. In 1511 most of the Marátha troops under Bijápúr were Bárgirs (Briggs' Ferishta, III. 37, 79), and in later times Shiváji (1680) was very fond of this kind of cavalry. Scott's Deccan, II. 55; compare Grant Duff, 34.

<sup>10</sup> Shakespeare's Hindustáni Dictionary under Bargi p. 319.

<sup>11</sup> Grant Duff's Maráthás, 37.



officered by Maráthás were formerly called Bargis and that when he wrote (1826) in many parts of India the Maráthás were still known by that name.<sup>1</sup> The following are the leading instances of the use of the term Bargi by the Musalmán historians. In the fifteenth century, according to the author of the *Mirát-i-Ahmadi* (1760) the Maráthha chiefs of Báglán in North Násik had for generations borne the title of the Baharji or Bargi chiefs.<sup>2</sup> The word Bargi is applied to the Maráthha cavalry under Bijápur in 1549 and again in 1560.<sup>3</sup> It is frequently applied to Telugu troops and estate-holders under the Kánarese kingdom of Vijayanagar (1330 - 1564),<sup>4</sup> and to the Bijápur troops after Bijápur (1570) extended its power over much of the territory formerly held by Vijayanagar. In 1613 the Emperor Jahangir in his autobiography calls the Maráthha skirmishers of Ahmadnagar Bargiyán.<sup>5</sup> In 1616 the Bargis of Ahmadnagar are described as a very hardy race and Jádhav Rái, apparently Shiváji's maternal grandfather, is called Bargi.<sup>6</sup> These quotations show that the Musalmán historians applied the term Bargi both to Telugu and to Maráthha cavalry. This double use of Bargi suggests that the origin of the word is the Tamil Vaduga that is northern, a term which in the Tamil country is commonly used of the people of Telingana, which is also used of Kánarese immigrants to the Nilgiri hills, and which might, with equal correctness, be used of the people of Maháráshtra.<sup>7</sup>

**Rajputs** are returned as numbering 1500 and as found in all parts of the State. Most of them have been settled in the State for several generations. They believe that their forefathers came south from Upper India in search of military service. Their commonest surnames or clan names are Ahir, Chobe, Kanoje, and Tidhäre. The names in common use among men are Bhimsing, Madansing, and Vijaysing; and among women Durgábái, Gunjábái, and Lakshmibái. They are fair strong and well made, with regular features. The women are short and slightly made, but fair and graceful. Their home speech is Hindi, and out of doors they speak Maráthi. They live in tiled houses and keep cattle and sometimes horses. Their daily food includes rice, Indian millet and pulse, and, on festive occasions, sweet dishes and mutton. They do not eat fowls or eggs. Some of them are excessively fond of opium and of smoking hemp-flower or *gánja*. They take food from no one but Bráhmans. The men wear a waistcloth, jacket, shouldercloth, and headscarf. The women do not appear in public. They wear the full Maráthha robe sometimes passing the skirt back between the feet, and the bodice with a back and short sleeves. They claim, and to a certain extent are given a

## Chapter III.

## People.

FIGHTING  
CLASSES.*Maráthás.**History.**Rajputs.*<sup>1</sup> Grant Duff's *Maráthás*, 37.<sup>2</sup> Bird's *Mirát-i-Ahmadi*, 123.<sup>3</sup> Briggs' *Ferishta*, III. 103 and 432.<sup>4</sup> Compare Scott's *Deccan*, I. 313, 314, 315 and Briggs' *Ferishta*, III. 137, 138, 139, 141, 153, 154, 166, 173, 243. One of these Vijayanagar Bargis bore the Dravidian name Hindeattum (Scott's *Deccan*, I. 305) and some seem to have been Telugu men.<sup>5</sup> *Wákiat-i-Jahangiri* in Elliot and Dowson, VI. 333.<sup>6</sup> *Wákiat-i-Jahangiri* in Elliot and Dowson, VI. 343.<sup>7</sup> Compare Caldwell's *Dravidian Grammar*, ii. The Kánarese Vadugas or northerners of the Nilgiri hills are the people known to the English as Burghers. Ditto, 34.

### Chapter III. People.

#### FIGHTING CLASSES.

##### *Rajputs.*

higher social position than Maráthás. They are faithful, thrifty, hardworking, hospitable, and quick-tempered. They are State servants, traders, and husbandmen. Their ceremonies are performed by North Indian Bráhmaṇ priests called Pandyaś and when Pandyaś are not available by local Bráhmaṇs. They worship the regular Bráhmaṇic gods and pay special reverence to Báláji. They allow widow marriage and some wear the sacred thread. Their birth marriage and death ceremonies do not differ from those performed by Maráthás of good family. Social disputes are settled at meetings of the elders of the caste. Their orders are enforced by putting out of caste or by fine which is spent on a caste dinner. They send their boys to school and are fairly off.

#### TRADERS.

**Traders** include six divisions with a strength of 9876 or 1·29 per cent of the Hindu population. The details are :

##### *Kolhápúr Traders, 1881.*

DIVISION.	Males.	Females.	Total.
Atárs ... ..	4	1	5
Gujarát Vánis ... ..	48	31	79
Komtis ... ..	66	56	122
Marátha Vánis ... ..	4581	4281	8862
Márwár Vánis ... ..	73	25	98
Támbois ... ..	401	359	760
Total ... ..	5123	4753	9876

##### *Atárs.*

**Atárs**, or Perfumers, are returned as numbering five and as found in the town of Kolhápúr. It is doubtful to what class these five Atárs belong. The people generally called Atárs are Musalmáns. It is possible that some individuals either of the Gandhi or Hindu perfumers or of the Lád class who live by selling perfumed oils, powder, and turmeric, returned themselves as Atárs.

##### *Gujarát Vánis.*

**Gujarát Vánis** are returned as numbering seventy-nine and as found chiefly in Alta and Shirol. Most of them are Nágars of the Meshri or Bráhmaṇic division of Gujarát Vánis, who are said to have come from Gujarát, Bombay, and Poona. Few of them are permanently settled in the State; most go to Gujarát Bombay or Poona to marry their children. They are traders and money-lenders and are well-to-do.<sup>1</sup>

##### *Komtis.*

**Komtis**,<sup>2</sup> who are returned as numbering 122, are found in most market towns. They are partly old settlers and partly newcomers. Their home speech shows that they originally belonged to the Telugu country. The men are middle-sized dark and somewhat irregular in features, and the women are short, wiry, strong, and well featured. They are vegetarians and both men and women dress like Bráhmaṇs. They are hardworking, thrifty, and well-to-do dealing in grain, glass beads, and metal ware and sometimes

<sup>1</sup> Details of Gujarát Vánis are given in the Poona Statistical Account.

<sup>2</sup> The fact that several classes are known by the name of Komti suggests that Komti is a country name corresponding to Gujar meaning a Gujarát Váni or to Márwári meaning a Márwár Váni. The home of the Komti Vánis must be in the Telugu country. The similarity in sound suggests Komometh about 120 miles east of Haidarabad. It seems probable that the name Kámáthi is in origin the same as Komti.

lending money. They gird their boys with the sacred thread, and in religious and social customs closely resemble Marátha Bráhmans whom they call to officiate at their houses. They send their children to school and on the whole are a rising class.<sup>1</sup>

**Mara'tha Va'nis**, or Traders, who are also called Vaishya Vánis, are returned as numbering 8812 and as found in Bávda, Bhudargad, Vishálgad, and other sub-divisions bordering on the Konkan from which they seem to have come. They belong to three divisions, Kudál Vánis apparently from Kudál in Sávantvádi, Sangmeshvar Vánis apparently from Sangmeshvar in Ratnágiri, and Pátane Vánis apparently from Pátan in Sátára. All eat together but do not intermarry. They are of middle size, and fairer than Lingáyat Vánis. Their home speech is Maráthi. They eat fish and flesh and drink liquor. They dress like Maráthás except that the men wear a Bráhman-shaped turban. Their ornaments do not differ from those worn by Maráthás. They are shrewd, thrifty, hard-working, and honest, and their chief occupation is grain-dealing. They send grain to the coast on pack-bullocks and bring back salt and other articles. Before cart roads were opened across the Sahyádris they owned large numbers of pack-bullocks. Since cart roads have been opened they have turned their attention to husbandry. They hold much the same position as Maráthás and eat only from Bráhmans. They employ either Konkanasth or Deshasth Marátha Bráhmans and treat them with much respect. Their favourite deities are Ambábái, Máruti, and Vithoba of Pandharpur, and they also worship Jotiba and Ma'hádev. They keep the usual Bráhmanic fasts and feasts and almost all their social and religious customs are the same as Marátha customs. They send their boys to school and teach them to read, write, and work sums in Maráthi. Their condition is middling.

**Mar'war Va'nis**<sup>2</sup> are returned as numbering ninety-eight and as found chiefly in Kolhápur and Shirol. They come from Márwár to trade principally in piecegoods and in their old age retire to their native country. They belong to two main classes Jains or Shrávaks and Meshris or Vaishnavs. Of the seventy-two clans into which the Meshri Márwáris say they are divided in Márwár seventeen are represented in Kolhápur. The seventeen are Bájáj, Baladva, Biavi, Chindah, Gatána, Gilda, Jhándar, Kabra, Kalantri, Malpána, Málv, Marda, Modáni, Porvál, Sárád, Shikji, and Soni. Persons bearing the same surnames cannot intermarry. The names in common use among men are Gavra, Khushál, and Rám; and among women Bani, Náju, and Padma. They are rather tall dark and stout, and as a rule have big faces and sharp eyes. The expression of many is hard and mean, but they are more vigorous than the Lingáyat and other local Vánis. They speak Márwári at home and incorrect Maráthi abroad. They keep their accounts in Márwári. Most of them live in houses of the better class. Their daily food is

## Chapter III.

## People.

## TRADERS.

*Marátha Vánis.**Márwár Vánis.*

<sup>1</sup> A detailed account of Komtis is given in the Sholápur Statistical Account.

<sup>2</sup> A detailed account of Márwár Vánis is given in the Ahmadnagar Statistical Account.

**Chapter III.****People.****TRADERS.****Márwár Vánis.**

wheat pulse and butter. They abstain from flesh and spirituous drink. The men generally wear the back hair long with an upward turn at the tips. They shave the front part of the head leaving a curly lock over each ear. Some wear the beard long and thin, others shave the face except the moustache and eyebrows. The men wear a waistcloth, long coat and shouldercloth, and shoes. They can be known by their two-coloured tightly-wound turban. The women wear the hair in a triple braid without decking it with flowers. They wear a full long petticoat, an openbacked bodice, and an upper robe which they draw over the head like a veil. Some Márwári women wear shoes. Their arms are covered with ivory bracelets. They are shrewd, thrifty, hardworking, and prosperous. Most of them are tradesmen. Their favourite god is Báláji of Tirupati in North Arkot, and their chief festivals are Gaur on the third of bright *Chaitra* or March-April, Tej on the third of bright *Shrávan* or July-August, and *Diváli* on the no-moon of *Ashvin* or September-October. They have priests of their own, and in their absence employ local Bráhmans. Most of them can read and write Márwári and are prosperous.

The Shrávak or Jain Márwáris are a smaller body than the Meshri Márwáris from whom they do not differ in speech, dress, character, occupation, or condition. All Kolhápúr Márwári Jains are said to belong to the Osvál subdivision.

**Támbolis.**

**Támbolis**, or Betel-leaf Sellers, are returned as numbering ten. They seem to belong to a larger class called Pánáris or leaf sellers, who are returned with a strength of 750. These Pánáris used to sell betelnut and some keep to their old calling. The rest have taken to husbandry, betel-leaf growing, parched rice or *poham*-making, and moneylending. In appearance speech and names they do not differ from Maráthás, and in food dress and customs they closely copy Marátha Bráhmans. They send their boys to school and teach them to write, read, and count in Maráthi. They are vigorous and well-to-do.

**HUSBANDMEN.**

**Husbandmen** include four divisions with a strength of 303,696 or 39·65 per cent of the Hindu population. The details are:

*Kolhápúr Husbandmen, 1881.*

DIVISION.	Males.	Females.	Total.
Chhatris ... ..	915	929	1844
Kunbis ... ..	152,113	147,753	299,871
Mális ... ..	713	694	1407
Raddis ... ..	300	274	574
Total ..	154,041	149,655	303,696

**Chhatris.**

**Chhatris** are returned as numbering 1844 and as found in Kolhápúr only. They are apparently of Rajput descent. They are cultivators and resemble Kunbis in appearance, food, dress, and manners and customs.

**Kunbis.**

**Kunbis** are returned as numbering 299,871 and as found over the whole State. They have no divisions, and are dark, middle sized,

well made, strong, and hardy. Except in the south and east where they speak Kánarese, their home tongue is Maráthi. The house of a village Kunbi is about twenty feet square with a tiled or thatched roof and walls of stone, sun-burnt bricks, or wattle and daub. It consists of an enclosed veranda or *sopa* in which he keeps his cattle and a room divided by walls three feet high. Inside it is dark and badly aired. 'If we had windows,' they say, 'the thief's work would be easy.' The Kunbi's ordinary food is *javári* bread, vegetables, salt, and chillies. In the western hills *náchni* is used instead of *javári*. Rice is eaten but very sparingly on account of its high price. All Kunbis to the west of Kolhápúr are fond of *ambil* or gruel a preparation of fermented *náchni* flour and buttermilk. On great holidays banquets and feasts they use animal food and are fond of mutton, fowls, and eggs. They never use beef or pork, but have no objection to boar's flesh. All Kunbis use spirituous liquors, but seldom to excess. Tobacco smoking and chewing are very common, hemp-smoking is not uncommon, but opium-eating is rare. A Kunbi man's usual dress is a white turban and a waistcloth. At home or when at work in the field he wears a piece of cloth passed between his legs and a blanket. Towards the western hills where the climate is colder, Kunbis use a small blanket jacket. On special occasions such as holidays and marriage ceremonies they wear either a waistcloth or loose trousers called *chólnás* reaching a little below the knee and a long white coat hanging to the knee. Poor Kunbis cannot afford to have a coat and wear only a waistcloth. The shoes generally worn by men and women are sandals or *páyants*. Well-to-do Kunbis use a Bráhmaṇ shoe. A Kunbi woman dresses in a robe and bodice. On ceremonial occasions the women wear a silk-bordered robe and bodice and the men a waistcloth. The Kunbis are a hard-working, honest, frank, orderly and contented people, but timid and shy. They are cultivators. Besides managing the house the women aid in the field, picking and cleaning cotton and spinning yarn. They also go to the nearest weekly markets and sell the surplus produce. Kunbis are socially lower than Maráthás. But a well-to-do Kunbi calls himself a Maráthá and poor Maráthás freely and openly marry with rich Kunbis. The men begin work in the field at daybreak and have a light breakfast or *nyáhri* of *javári* or *náchni* which is taken to them by the women at about eight. They work till midday when they have another meal in the field and after a short rest begin again and work till dark, when they return home, sup, and go to bed. The same articles are generally eaten at the midday and evening meals. In the Ghátmátha or hilly west all eat rice and in the Desh or plain instead of rice they use *javári* both in the form of bread and *kanya* that is partially ground *javári* cooked somewhat in the form of rice. Along with this they eat curry made of pounded chillies, flour, and spices, and vegetables. When a Kunbi marriage is settled, both parents go to the village astrologer and ask him whether the stars favour their union. The astrologer asks the boy's and girl's names, and after consulting his almanac generally declares that the stars are favourable and the marriage is settled. The parents ask the astrologer to name lucky days and hours for the turmeric-rubbing, marriage and return procession, and then go to

## Chapter III.

## People.

## HUSBANDMEN.

## Kunbis.

## Chapter III.

## People.

## HUSBANDMEN.

*Kunbis.*

their homes. A little before the hour fixed for the turmeric-rubbing the boy's relations and friends both men and women go to the girl's, taking two robes, sugar, cocoanuts, dates, turmeric, betelnuts, a pair of silver anklets, and a necklace of gold coins or *putlis*, and music. Here while the priest, who is a Bráhmaṇ, repeats verses, the boy's father presents the girl with the robe and puts a little sugar into her mouth. Then the girl's female relations trace a white powder square, set round it five earthen jars and pass a thread round the jars. In the square are set two low wooden stools, and the priest worships the jars by putting water and a betelnut into each jar and closes its mouth with a cocoanut. He lays a betelnut in front, worships it as the god Ganpati, and prays it to be kindly. Both the mother and girl are anointed with turmeric and oil by married women, and the priest, leading the girl five times round the jars, at each turn throws grains of rice over the jars, and at the last turn seats her on one of the low wooden stools. The mother sits on the other stool and both are bathed by married women. After the bath, the boy's relations present the girl with a robe and deck her with ornaments. The girl's relations, taking the remaining turmeric and oil, go along with the boy's relations and music to the boy's, and a similar ceremony is gone through. This is followed by the *devak* or guardian ceremony which consists of worshipping the picture of Ganpati in the priest's almanac; of setting a lucky post outside the house in the booth; and of preparing two bundles of betelnuts, rice, and turmeric to represent the various gods. While this ceremony is going on the women in the house worship the grain grindstone or *játe*, and the village washerwoman lays sandal, rice, turmeric, and vermilion before the grinding-stone slab or *páta*. Next day feasts are held in honour of the family deity Jotiba, Khandoba, or Ambábái. On the third or marriage day, the boy is bathed in the morning, and an hour or two before the hour fixed for the marriage, goes on horseback to the village temple, and thence to the girl's accompanied by men and women relations, friends, and music. When the procession reaches the girl's house, the boy is taken off the horse and the village barber washes his feet. The girl's father approaches the boy and presents him with a new waistcloth shouldercloth and turban. The boy wears them and walking into the booth takes his stand on a heap of unhusked rice. The girl is brought out of the house where she was sitting among women and made to stand on another heap in front of the boy facing him. A cloth is held between them with a lucky red cross or *savastik* properly *svastik* on it. A pinch of cumin seed or *jire* is held by the pair in their mouths, and a near relation holds either a sword or a dagger over the boy's head. The priests and other Bráhmans repeat marriage verses and end with the word *Sávdhán* or Beware. The curtain is pulled on one side, the guests throw rice grains over the pair, and the musicians raise a blast of music. The boy's priest fastens round the girl's neck the marriage string or *mangalsutra*, and one of the elderly male relations ties a cotton thread or *dorla*. The boy and girl are then led by the priest to the house gods and bow before them; while he is bowing the boy steals an image from the god-room and does not give it back till he is paid 2s. (Re. 1). They are next seated on an altar or *bahule* and the girl's brother holds the boy by his right ear, and



does not loosen his hold until he is presented with a new turban. Female relations now approach the couple and drop rice grains from the boy's and girl's shoulders. Then a dish of cooked food such as rice, vegetables, and sweetmeats, served by two or four married women is placed on the altar in front of the boy and girl. A couple of relations from both sides join the pair and all dine from the same plate. A feast to relations and castefellows follows. The boy's parents present the girl with rich clothes and ornaments, and clothes are exchanged between the two houses. The boy and girl are seated on a horse and are taken in procession to the boy's house accompanied by men and women relations, friends, and music. When they arrive at the boy's house, his sister stands in the doorway and does not allow him to enter until he promises to give his daughter in marriage to her son. The pair then enter the house and bow before the house-gods. The village washerwoman, taking a pestle in her hand with the help of the boy, the girl, and some kinswomen beats unhusked rice, singing songs. Kunbis allow their girls to remain unmarried till they are over sixteen. Marriages between Kunbis and Maráthás do not take place unless a Marátha becomes poor and fails to get a Marátha bride. Kunbis allow polygamy, but it is not so common among them as among Maráthás. They also allow widow marriage, but a married widow is considered unclean and cannot take part in any religious family ceremonies. When a Kunbi dies, he is taken out of the house, bathed, dressed in a loincloth, and laid on a bier. He is covered with a sheet and redpowder is sprinkled over the sheet. He is carried on the shoulders of four men to the burning ground. After the body is burnt the mourners return home. On the third day, the chief mourner, accompanied by a few male relations, goes to the burning ground, removes the ashes and unburnt bones, and throws them into water. The family of the dead is unclean for ten days. On the morning of the eleventh they drink water in which a Bráhma's toe has been dipped and become pure. Every year in the month of *Bhádrapad* or August-September they perform the anniversary of the deceased, when they offer cooked food to crows and feast castemen. Kunbis worship all Bráhmaic gods and goddesses, and follow the doctrines of Tukárám, Dnyáneshvar, and Námdev. Others who worship Vithoba of Pandharpur are called *Málkaris* or wearers of basil bead necklaces. The names of their family gods are Bahiroba, Jakoba, Jotiba, Khandoba, Mhasoba, and Narsoba; and of their goddesses Ambábái, Bhaváni, Bhávkái, Chopdái, Ekviri, Jakái, Jugái, Kálkái, Phirangái, Margai, Satvrái, Vithli, and Yallamma. The only animals which Kunbis offer to please their deities are he-goats, cocks, and chickens. They offer them to Mhasoba in the month of *Áshádh* or June-July and to Ambábái in *Áshvin* or September-October on Dasara Day, and on the fifteenth or full-moon of *Mágh* or January-February. Animal sacrifices are not confined to these two deities, they are offered to all house gods. They make vows both to house and village gods, and believe in witchcraft holding witches and sorcerers in great respect. They believe in omens and consider it lucky if a crow flies to the right and a *tás* or the blue jay *Coracias indica* to the left. On going out they think it lucky to meet an unwidowed woman with a full waterpot

## Chapter III.

## People.

## HUSBANDMEN.

*Kunbis.*

## Chapter III.

## People.

## HUSBANDMEN.

## Kunbis.

on her head, a milkmaid with milk pots, or anybody with a dish of cooked food. If a cat, a bareheaded Bráhmán, a barber with his shaving gear, or a widow happen to pass before them while going out, they consider it unlucky and go back. They hold it very unlucky if a lighted lamp falls on the ground and goes out; or if a house-lizard drops in front of them or on them. The only living animal they worship is the cow. They also worship clay images of bullocks on the full-moon of *Āshādh* or June-July, and on that day they paint the horns of their cattle especially of their bullocks, feed them on sweet dishes, and allow them to rest. They worship the sweet basil and the Indian fig tree. Their priests are ordinary village Bráhmans to whom they pay great respect. They go on pilgrimage to Jotiba of Vadi-Ratnágiri nine miles north-west of Kolhápúr in the months of *Chaitra* or March-April and *Shrávan* or July-August; to Narsoba's Vádi on *Guru-dvādashi* in *Āshvin* or Sept.-Oct. and in the month of *Māgh* or January-February; to Pandharpur on the eleventh of the first halves of *Āshādh* or June-July and *Kārtik* or October-November; to Ālandi and Dehu in Poona and Tuljápúr in the Nizám's country, and even to Benares at any time during their lives. The holidays kept by Kunbis are the *Pádva* or New Year's Day which falls in *Chaitra* or March-April. On this day they hoist a flag or *gudhi* in front of their house in honour of the new year. On the fifteenth a feast is held in honour of the god Jotiba when the chief dish is roly polies or *puranpolis*. *Akshayatritiya* which falls on the third of *Vaishákh* or April-May is kept as a feast. The full-moon of *Āshādh* or June-July on which they worship clay bullocks, they consider to be the most important of their holidays. On the fourth of *Bhādrapad* or Aug.-Sept. comes *Ganesh-chaturthi* or Ganpati's Fourth when earthen images of Ganpati are made and worshipped and a dish of rice flour balls stuffed with cocoakernel scrapings and molasses is prepared in their honour. The first nine days of *Āshvin* or September-October are called *Navrátra* when an earthen jar filled with water with a cocoanut on the top is worshipped in honour of the goddess Ambábái. On the tenth they worship weapons and field tools and feast on sweetmeats, flesh, and liquor. In the afternoon villagers go in procession as far as the village boundary or *gāvshinn*. Here the village headman worships the *ápta* or *shami* tree with the help of the village Bráhmán, and on their return they distribute leaves to their relations and friends. On Great *Sankránt* Day or the twelfth of January, they present sugared sesame to their friends and acquaintances, and during *Shimga* in March-April they burn and worship the *Holi* bonfire; and on the following day daub one another with dirt. Four days later on *Rang-panchmi* Day they throw red water over each other and term it *shimpan* or the sprinkling. During these festive occasions Kunbis dress in rich clothes, and those who can afford it eat fowls and mutton and drink liquor. Their fasts are the *Ekādashis* or elevenths of *Kārtik* or October-November and *Āshādh* or June-July, *Shivrātra* in January-February, *Gokulāshtami* in August, *Rám-navmi* in March-April, and all Mondays in *Shrávan* or July-August. The famine of 1876-77 reduced a number of Kunbis to poverty. The western Kunbis are generally in debt and those of the east are better off. Some of them send their boys to school, but their condition on the whole is poor.

**Mális**, or Gardeners, are returned as numbering 1407 and as found chiefly in Karvir and Panhála. They are divided into Lingáyat and Marátha Mális, who do not eat together or intermarry. They are dark and strong. Except a few who speak Kánarese all speak Maráthi. They are hardworking and orderly. They are husbandmen and gardeners, and grow and sell vegetables. They are helped in their calling by their wives and children. Some are moneylenders. The men pass their time in the fields and gardens and the women take the vegetables to market to sell. Most are Lingáyats and their head priest the Svámi of Kadápa's *math* or monastery which is about nine miles from Kolhápúr, attends their marriages. In manners and customs Marátha Mális do not differ from cultivating Maráthás, and though they do not eat or marry with them, Lingáyat Mális resemble Lingáyat Vánis. Some Mális of both classes send their boys to school, but few can be said to be well off.

**Raddis** are returned as numbering 574 and as found mainly in Gadinglaj. They are believed to have come to the State from the south. Their home speech is Telugu. They are husbandmen and resemble Kunbis in all respects. They are Smárts in religion.

**Craftsmen** include twenty-one classes with a strength of 52,574 or 6·57 per cent. The details are :

*Kolhápúr Craftsmen, 1881.*

DIVISION.	Males.	Females.	Total.	DIVISION.	Males.	Females.	Total.
Beldárs ...	397	361	758	Rangáris ...	37	51	88
Buruds ...	469	431	900	Ráuls ...	111	118	229
Gavandis ...	42	45	87	Sangars ...	538	473	1011
Hanbars ...	2122	2040	4162	Shimpis ...	2821	2845	5666
Jingars ...	213	181	394	Sonárs ...	2913	2758	5671
Kásárs ...	220	159	379	Sutárs ...	5960	5491	11,451
Koshitis ...	3350	3081	6431	Támbats ...	73	82	160
Kumbhárs ...	4282	4227	8509	Telis ...	1065	1035	2100
Lohárs ...	1067	1034	2101	Upárs ...	610	602	1212
Otáris ...	118	111	229				
Páñchárs ...	417	402	819				
Pátharvats ...	99	118	217	Total ...	26,929	25,645	52,574

**Beldárs**, or Pickaxe Men, are returned as numbering 758 and as found in small numbers over the whole State. They are tall, dark, robust, strong, hardworking, and quarrelsome. They speak incorrect Maráthi both at home and abroad, and live in dirty clumsy thatched houses. Their chief hereditary calling is working in stone and earth, hewing stone, and building wells. They have a bad name as thieves, with their wives and children attending fairs and river-bank gatherings. The men engage some stranger in talk while the children carry off his property, or one of the gang comes close to women who are seated perhaps cooking on a sandy river side with a box of valuables near, stops as he passes and sits down as if to relieve himself and while the woman turns her head away seizes and hides in the sand any valuables he can lay his hands on. They earn enough to support themselves, but are given to drink and are badly off. They keep all Hindu fasts and feasts and their favourite gods are Khandoba and Jotiba.

**Buruds**,<sup>1</sup> or Basket Makers, are returned as numbering 900 and

### Chapter III.

#### People.

HUSBANDMEN.  
*Mális.*

*Raddis.*

CRAFTSMEN.

*Beldárs.*

*Buruds.*

<sup>1</sup> Details of the Lingáyat Burud ...

## Chapter III.

## People.

## CRAFTSMEN.

*Buruds.*

as found all over the State. They claim descent from Medárket one of the followers of Basav (1100-1168) the founder or reviver of the Lingáyat faith. In look, food, dress, and dwelling they are similar to the Buruds of Ahmadnagar. They are hardworking and fond of drink and spend most of their earnings on liquor and in marriages. They keep all Hindu fasts and feasts and worship Shiv. Their priests are Jangams, but they also ask Bráhmans to their marriages. Their religious teacher is Shiddhgiri of Kanheri in Sátára. They make bamboo baskets, winnowing fans, mats, and cages, and live from hand to mouth. They have a caste council and settle social disputes at caste meetings. Few send their boys to school. They do not take to new pursuits, and are a poor class.

*Gavandis.*

**Gavandis**, or Masons, are returned as numbering eighty-seven and as found in towns. They are said to be the offspring of a Bráhman widow by a *sanyáshi* or Bráhman ascetic. In food, dress, look, and social religious customs they in no way differ from local husbandmen with whom they eat but do not marry. As a class they are quiet, hardworking, clean and neat in their habits, and hospitable. They cut and dress stone and build walls and are well-to-do. They have a caste council and send their boys to school.

*Hanbars.*

**Hanbars**, or Cattlekeepers, are returned as numbering 4162 and as found in Karvir and Gadinglaj. The name *Hanbar* means possessor of cattle with upright horns. According to their religious rules they ought to live in forests, keep herds of cattle, and sell milk and clarified butter, eat only once a day wearing a wet cloth, and never look at a lamp or engage in tillage. Now-a-days they do not keep these rules, many of them till, and a few serve as messengers and labourers or field workers. In look, food, dress, and customs they differ little from ordinary husbandmen. They have their own priests and their favourite gods are Alamprabhu, Krishna, and Sidhoba. They also offer sandal, flowers, and sweetmeats to the serpent or *Nág* on the dark lunar eleventh or *śuklādashi* in *Kártik* or October-November. They have a caste council and settle social disputes at caste meetings. They do not send their boys to school. They are hardworking and thrifty but poor.

*Jingars.*

**Jingars**,<sup>1</sup> or Saddlemakers, are returned as numbering 394 and as found only in towns. In look, food, dress, drink, and dwelling, they are the same as the Sholápur Jingars and Káranjkars. As a class they are clean, neat, hardworking, orderly, and thrifty, and their speech at home and abroad is a corrupt Maráthi. They are saddlemakers, bookbinders, carpenters, copper and brass smiths, landholders, cultivators, and ironsmiths. Those who do not work in leather are called Káranjkars or fountain makers. A few Jingars repair carriages and watches and prepare dolls of paper and earth and sell them at local fairs, and make and sell clay figures of Ganpati in the month of *Bhádrapad* or August-September. Jingars and Káranjkars eat together and intermarry, and their religious and social customs are the same as those of

<sup>1</sup> Details of the Jingar customs are given in the Sholápur Statistical Account.

Sholápur Káranjkars. Their priests are ordinary Marátha Bráhmans. Few among them know how to read and write, but many send their boys to school, and they are a thriving class.

**Ka'sa'rs**, or Bellmetal Smiths, are returned as numbering 379 and as found only in towns. They belong to the Jain sect, and like other Jains wear the sacred thread and worship the Jain deities Kállamma and Párasuáth, eschew flesh, and have their social disputes settled by the Jain pontiff Lakshmisen. They speak Kánarese at home and Maráthi abroad. They deal in copper and brass vessels and glass bangles and fit glass bangles on the wrists of married Hindu women. They are clean neat and orderly, and dress like Bráhmans. They send their boys to school and are in easy circumstances. Their social and religious customs are the same as those of the local Jains.<sup>1</sup>

**Koshtis**,<sup>2</sup> or Weavers, are returned as numbering 6431 and as found in towns and large villages. Kolhápur weavers include six classes, Devángs, Hatkars, Khattris, Koshtis, Láds, and Sális. Of these Koshtis and Sális, though they do not eat together or intermarry, resemble each other in look food dress and customs, and form the bulk of the local weavers. Devángs and Hatkars who are Lingáyats and can be readily known by the *ling* tied round their necks are found in small numbers, and Khattris<sup>3</sup> and Láds are rare. The following details apply to Koshtis and Sális. They say they have come from Paithan on the Godávári but when and why none of them can tell. As a class they are thin and weak, and in look, food, dress, drink, speech, and customs resemble the ordinary local husbandmen. They worship all Bráhmanic gods, keep the usual Bráhman fasts and feasts, and ask local Bráhmans to conduct their marriages. Boys are married between twelve and twenty and girls generally before they come of age. The boy's father pays the girl's marriage charges and makes a money present to her father. Their marriage guardian or *devak* is a mango or *umbar* *Ficus glomerata* twig and boys are given a sacred thread to wear a short time before the marriage by the priest. They bathe daily and offer sandal-paste, flowers, burnt frankincense, and food cooked in the house to their loom which they say represents the *ling* or Shiv's emblem. Widow marriage and polygamy are allowed but polyandry is unknown. Their women help them, but they are badly off owing to the importation of machine-made cotton goods. Some have taken to tillage and many work as labourers. They are a falling class.

**Kumbhárs**, or Potters, are returned as numbering 8509 and as found in small numbers over the whole State. They are divided into Marátha Kumbhárs and Rajput Kumbhárs, who do not eat together or intermarry. Marátha Kumbhárs have no tale of their origin or any memory of former settlement. Rajput Kumbhárs say they came into the State about two hundred years ago. The

### Chapter III. People.

CRAFTSMEN:  
Kásárs.

Koshtis.

Kumbhárs.

<sup>1</sup> Details are given under Jains.

<sup>2</sup> Details of Koshti customs are given in the Ahmadnagar Statistical Account.

<sup>3</sup> Details of Khattris are given in the Ahmadnagar and Sholápur Statistical Accounts.



## Chapter III.

## People.

## CRAFTSMEN.

*Kumbhárs.*

bulk of the Kolhápúr potters are Maráthas Kumbhárs, and the Rajputs are a very small body. The men of both classes shave the head except the topknot and the face except the moustache, and in look, food, dress, and customs the Maráthas resemble local husbandmen. The Rajput Kumbhárs are like local Rajputs in dwelling, food, dress, and look, and in social and religious customs. Both at home and abroad the Maráthas speak a corrupt Maráthi and the Rajputs a corrupt Hindustáni. As a class Kumbhárs are hard-working and thrifty. The Rajputs are brickmakers only and as they find themselves unable to compete with the Maráthas they have taken to fuel-selling and charcoal-burning. The Maráthas enjoy the monopoly of making and selling earth vessels and toys. Marátha Kumbhárs are paid in cash except in villages where they are one among the village staff of servants and are paid in grain at harvest. Their women and children help in their calling. Except that among Marátha Kumbhár mourners men do not shave the face after a death, their social and religious customs are the same as those of local husbandmen. They have a caste council and a headman or *mehtar* and settle social disputes at caste meetings or *pancháyats*. Rajput Kumbhárs are a declining people and Marátha Kumbhárs are fairly off. Bhánda Kumbhárs, seemingly a branch of Marátha Kumbhárs, are found at Panhála. They earn their living by making and selling earthen images. In look, food, dress, and customs they are the same as Marátha Kumbhárs. They practise polygamy and bury their dead. They are a steady class.

*Lohárs.*

**Lohárs,**<sup>1</sup> or Blacksmiths, are returned as numbering 2101 and as found in small numbers over the whole State. They are cultivators and a few hold rent-free land. They worship all Hindu gods and goddesses and keep all their feasts or fasts, and their favourite deities are Khandoba, Sidhoba, and Yallamma. In look, food, dress, and customs they are the same as Ahmadnagar and Poona Lohárs. They employ Bráhmans at their marriages and Jangams at their funerals. They are hardworking and earn enough to support themselves, but are given to drink and are badly off. They settle social disputes at meetings of castemen and seldom send their boys to school.

*Otáris.*

**Otáris,**<sup>2</sup> or Casters, are returned as numbering 229 and as found over the whole State and chiefly in the town of Kolhápúr. They are dark strong and wellmade, their speech both at home and abroad is a corrupt Maráthi, and they live in one-storeyed houses with mud walls and tiled or thatched roofs. They have bullocks for carrying their goods and are fond of pets. In food drink and character they do not differ from the Ahmadnagar Otáris. They make and sell brass and copper vessels, but are badly off on account of the competition of imported goods. Their favourite deity is Kállamma, and they worship all Bráhmanic and local gods and goddesses and keep the usual Hindu fasts and feasts. Their social and religious customs are the same as those of Poona Otáris. They have a caste council

<sup>1</sup> Details of Lohár customs are given in the Ahmadnagar Statistical Account.

<sup>2</sup> Details of Otári customs are given in the Ahmadnagar Statistical Account.



and settle social disputes at caste meetings. Few among them send their boys to school or take to new callings. Though honest and thrifty, they dislike hard work and are poor.

### Chapter III.

#### People.

##### CRAFTSMEN.

##### *Pānchāls.*

**Pa'nchāls**,<sup>1</sup> a name of doubtful origin generally supposed to mean the five craftsmen, are returned as numbering 819 and as found in towns and large villages. They speak Kānarese at home and Marāthi abroad. In look, food, dress, and dwelling, and social and religious customs they are the same as the Sholāpur Pānchāls. They are clean and neat in their habits, hardworking, orderly, and thrifty. They are carpenters, coppersmiths, goldsmiths, and casters of brass and copper vessels. They keep all Brāhmanic fasts and feasts and worship the usual Brāhmanic gods and goddesses. Their family goddess is Kālikādevi and their priests belong to their own caste. They have a caste council and settle social disputes at caste meetings under their headman. A few send their boys to school and as a class are well-to-do.

##### *Pātharvats.*

**Pa'tharvats**, or Stone Dressers, are returned as numbering 217 and as found only in towns. Pātharvats are of several classes Marāthās, Lingāyats, Jains, and Musalmāns. The Marātha Pātharvats dress like Kunbis and do not differ from them in food or in religious and social customs. Their favourite goddess is Kāllamma and they eat but do not marry with Marātha Kunbis. Their calling is well paid but they spend their earnings in liquor. They have a caste council and settle social disputes at caste meetings. Few of them send their boys to school.

##### *Rangāris.*

**Rangāris** or Dyers, including Nilāris or Indigo Dyers, are returned as numbering eighty-eight and as found only in towns. They belong to the Shimpī caste, and in look, food, dress, dwelling, and social and religious customs are the same as Shimpīs. They worship all Brāhman and local gods and goddesses and keep the usual fasts and feasts, and their priests are local Brāhmans who conduct their marriage and death ceremonies. Their calling is well paid and they are fairly off.

##### *Rāuls.*

**Ra'uls** are returned as numbering 229 and as found in all parts of the State. In look, food, drink, dress, and customs they resemble Marātha Kunbis with whom they eat but do not marry. Their favourite god is Mahādev, but they worship all Brāhmanic and local deities and keep the regular fasts and feasts. They are players and beggars, and weave strips of coarse cloth and tape. They have a caste council. They do not send their boys to school, and are poor.

##### *Sangars.*

**Sangars**, or Wool Weavers, are returned as numbering 1011 and as found in small numbers over the whole State. They seem to have been formerly Lingāyats or followers of Basav (1100-1168) whose priests or Jangams they still employ at their marriage and death ceremonies, and to settle their caste disputes. In look, food, dress, dwelling, and customs they do not differ from the Poona Sangars. They weave and sell coarse blankets and the women do as much work as the men. They worship all Hindu gods and

<sup>1</sup> Details of Pānchāl customs are given in the Sholāpur Statistical Account.

## Chapter III.

## People.

## CRAFTSMEN.

*Shimpis.*

goddesses, and keep the regular fasts and feasts. Their favourite gods are Bahiroba, Khandoba, and Mhasoba. They have a caste council, and some of them send their boys to school. Though they are hardworking and thrifty their calling is poorly paid and they live from hand to mouth.

**Shimpis**<sup>1</sup>, or Tailors, are returned as numbering 5666 and as found all over the State but chiefly in towns. They claim descent from the sister of Námdev a staunch devotee of Vithoba of Pandharpur, who is said to have been born of a shell or *shimpi*. Originally it is said Shimpis were both dyers and tailors, but in time, probably from its unpleasantness, dyeing came to be looked down on and is now the calling of a distinct caste called Rangáris. In look, food, dress, and customs the Kolhápúr Shimpis are the same as the Sátára and Ahmadnagar Shimpis. As a class Shimpis are clean and neat in their habits, quiet, orderly, and hardworking, but proverbial cheats. They are cloth-dealers and tailors. They worship all local and Bráhmaic gods and goddesses, and keep the usual fasts and feasts. Their priests are local Bráhmans who conduct their marriage and death ceremonies. They belong to the Vaishnav sect, and their favourite god is Vithoba of Pandharpur. The worshippers of Vithoba wear a *tulsi* bead necklace and on the lunar eleventh or *ekádashis* in *Áshádh* or June-July and *Kártik* or October-November, visit his shrine at Pandharpur in bands carrying yellow flags. When they come back they feast friends and kinsfolk in honour of Vithoba. They have a caste council and send their boys to school. Formerly they received much patronage from the local Marátha noblemen and chiefs and were well-to-do. A few have begun to use sewing machines, but as a class they are not so well off as they formerly were.

*Sonárs.*

**Sonárs**<sup>2</sup>, or Goldsmiths, are returned as numbering 5671 and as found over the whole State. They are divided into Deshasths, Konkanasths, Sádás, Ajhrás, Pardeshis, Vidurs or Dásiputras, and Khándeshis, who neither eat together nor intermarry. Deshasths and Konkanasths, to whom the following details mostly apply, are looked upon as higher than the rest. They look and dress like Bráhmans and speak a corrupt Maráthi with a drawl. In food, dress, house, character, and customs they are the same as Ahmadnagar Sonárs. They are moneychangers and make gold and silver ornaments. They worship all Bráhmaic and local gods and goddesses and keep the usual fasts and feasts. Their priests are men of their own caste who conduct their thread-girding marriage and death ceremonies. The Deshasth and Konkanasth Sonárs, who resemble each other most, gird their boys with the sacred thread between eight and fourteen and marry them before they are twenty-five. Girls are married before they come of age. They forbid widow marriage, know nothing of polyandry, and allow and practise polygamy. All their ceremonies they say are the same as Bráhmaic ceremonies. They are bound together as a body

<sup>1</sup> Details of Námdev Shimpi customs are given in the Ahmadnagar and Sátára Statistical Accounts.

<sup>2</sup> Sonár details are given in the Ahmadnagar Statistical Account.

and settle social disputes at meetings of castemen. They give some elementary schooling to their boys, but as soon as they are of use keep them at home. The other classes of Sonárs resemble local Kunbis in all points and their priests are Deshasth Bráhmans. They do not gird their boys with the sacred thread, and use animal food and drink liquor. The higher classes of Sonárs are fairly off, but the other classes find their calling ill-paid and barely earn a living.

**Sutá'rs**, or Carpenters, are returned as numbering 11,451 and as found over the whole State. They are divided into two classes Maráthás and Kánadá's, the latter looking down on the former with whom they neither eat nor marry. As a class Marátha Sutárs are strong, dark, regular featured, and well built, and live in one-storeyed houses with mud walls and tiled or thatched roofs. In look, food, speech, dress, and customs they resemble the Sutárs of Poona and Ahmádnagar. Their family gods are Jotiba, Khandoba, and Vithoba. Unlike the Kánadá's who have their own priests the priests of Marátha Sutárs are local Bráhmans who conduct their marriage and death ceremonies. At present the work both of Kánada and Marátha Sutárs is in great demand, and they earn enough to keep themselves and their families in comfort. A few are husbandmen and hold rent-free lands in return for their services to villagers as one of the *balutedárs* or village staff.

**Támbats**, or Coppersmiths, are returned as numbering 160 and as found only in towns. They are said to have come from the Konkan about the middle of the eighteenth century. They are middle sized and thin, but strong and muscular. They look and dress like Bráhmans and claim to be Pánc'háls. They speak a corrupt Maráthi and their houses are like those of Sonárs. They say they are vegetarians. They make and sell brass and copper vessels. They worship all local and Bráhmanic gods and goddesses and keep the usual Hindu fasts and feasts. Their family goddess is Kállamma of Shirshingi in Belgaum. They employ their own priests and perform ceremonies like those of Bráhmans. They gird their boys with the sacred thread between eight and fourteen and marry them between fourteen and twenty, the boy as a rule paying the girl's father a sum of money. They have a caste council and settle social disputes at caste meetings. On account of the increasing use of glass and China ware, the Támbats say their goods are in less demand than they used to be.

**Telis**, or Oilmen, are returned as numbering 2100 and as found in small numbers over the whole State. They include two divisions Marátha and Lingáyat Telis. Lingáyat Telis have a separate recognised head of the caste and employ Jangams to conduct their marriages and births. They bury their dead. Marátha Telis eat with local Marátha Kunbis, but marry among themselves only, and employ Bráhman priests to conduct their ceremonies. Telis are hardworking, honest, and thrifty. The growing use of kerosine oil has not yet affected their craft. They are a steady class.

**Upárs**, or Grindstone Makers, are returned as numbering 1212 and as found in small numbers in towns and large villages. In look

**Chapter III.**  
**People.**  
**CRAFTSMEN.**

*Sutárs.*

*Támbats.*

*Telis.*

*Upárs.*

**Chapter III.****People.****CRAFTSMEN.***Upárs.*

food dress and dwelling they do not differ from ordinary Kunbis or Mális. They claim to be mediums and to have intercourse with gods and spirits. Sometimes they put on a Marátha dress and a large bead necklace and sit at a ford or riverside counting their beads as if absorbed in prayer and holy thoughts, but when the chance offers they make away with the property of travellers who happen to halt or rest near them. They are grindstone-makers and cut and dress stone, and make salt from earth. Their family god is Hanu-mán, and they worship all local and Bráhmanic gods and goddesses and keep the usual fasts and feasts. Their customs are the same as Kunbi customs. They allow widow marriage and polygamy but not polyandry. They either burn or bury the dead and mourn them ten days. They have a caste council and settle social disputes at meetings of castemen. Few among them send their boys to school, and as a class they live from hand to mouth.

**MUSICIANS.**

**Musicians** include five classes with a strength of 11,253 or 1·40 per cent of the Hindu population. The details are :

*Kolhápúr Musicians, 1881.*

DIVISION.	Males.	Females.	Total.
Bhát's .. ...	540	592	1132
Dásris ... ..	85	113	198
Davris ... ..	567	557	1114
Ghadshis ... ..	118	95	213
Guravs ... ..	4362	4234	8596
Total ... ..	5662	5591	11,253

*Bhát's.*

**Bhát's**, who are returned as numbering 1132, formerly bards and praisers, are famous for their talkativeness. They eat the flesh of goats and sheep. The demand for their services has to a great extent ceased. Most have taken to tillage. The rest beg and recite the doings and praises of kings. They claim a Kshatriya origin but rank with Maráthás. Their favourite gods are Báláji, Mahádev, Máruti, and Vithoba. They wear necklaces of *tulsi* beads, and allow polygamy and widow marriage. They have no recognized head.

*Dásris.*

**Da'sris**, literally Slaves, are returned as numbering 198 and as found only in Katkol. They are strolling players of two classes one who prostitute and the other who do not prostitute their women. They neither eat together nor intermarry. Their home speech is Telugu. They do not own houses but live in poor tents called *páls* or booths. Their ordinary food is millet bread, pulse, chillies, and salt, but they eat all kinds of flesh except the flesh of the hog and of the cow. They are idle and thriftless and move from village to village begging and performing. Their wives and children help in their calling. Socially they rank below Kunbis. Their favourite gods are Máruti, Vyankatpati, and the goddess Yallamma, whose images they keep in their houses. They worship the usual Bráhmanic gods and goddesses, keep the usual fasts and festivals, and employ as priests the ordinary village Bráhmans whom they treat with respect. They either bury or burn their dead and are poor.

**Davris**, or Players of the *daur* drum, are returned as numbering 1114. Of several divisions Marátha Davris are alone found in Kolhápúr. They eat but do not marry with Maráthás. They have the ancient and still respected privilege of living in the out-houses of the temples of Rankoba and Bahiroba. They eat fish, fowls, and the flesh of goats, wild cats, and foxes, but not of cattle. They wear a thread to which is tied a whistle or *shingi* made of wood or deer's horn. At the houses of Maráthás and others whose family gods are Jotiba and Bahiroba they perform the *gondhal* dance at marriages, or on the fulfilment of vows, and play a small *daur* or drum.<sup>1</sup> They also beg, and are husbandmen and landholders. The names of their family gods are Bahiroba, Jotiba, Mahákáli, Rankoba, and Temblái. Their priests are the ordinary village Bráhmans. In their initiation ceremony holes are made in the lobes of their children's ears and gold rings are put in them. They marry their widows, allow polygamy, and bury their dead. Important disputes are settled by their spiritual guide or *guru*, a slit-eared or Kánphátya Gosávi who lives at Battis Shirála in Sátára.

**Ghadshis** are returned as numbering 213. They are hereditary musicians and some are husbandmen and day labourers. They eat from Kunbis but Kunbis look down on them and do not eat from them or marry with them. Their priests are the ordinary village Bráhmans and their customs are like those of Kunbis. Their social disputes are referred to Bráhman priests whose feet-washings they drink. They do not send their boys to school, and though good musicians, are badly off.

**Guravs**, or Priests, are returned as numbering 8596. They are divided into Nilkanths, Khotásanes, and Lingáyats. The Khotásanes eat flesh and dine with Kunbis and employ Kumbhárs and Davris at their funerals. The Nilkanths and Khotásanes wear the sacred thread, and the Lingáyats the *ling*. Guravs are hereditary worshippers of village gods for which service they generally hold rent-free land. They are also paid in grain by the villagers at harvest time. They have a further source of income in the proceeds of the offerings made to the gods. They also make leaf plates, blow brass horns, and beat drums. They worship Shiv. The priests of Nilkanths and Khotásanes are ordinary village Bráhmans, while those of the Lingáyat Guravs are Jangams.

**Servants** include two classes with a strength of 12,784 or 1·77 per cent of the Hindu population. The details are:

*Kolhápúr Servants, 1881.*

DIVISION.	Males.	Females.	Total.
Nhávis ...	3859	3617	7476
Parits ...	2727	2581	5308
Total ...	6586	6198	12,784

**Nhá'vis** or Barbers, also called Hajáms are returned as numbering 7476 and as found in all towns and villages. They are divided

### Chapter III.

#### People.

##### MUSICIANS.

*Davris.*

*Ghadshis.*

*Guravs.*

SERVANTS.

*Nhávis.*

<sup>1</sup> Details of the *gondhal* dance are given in the Poona Statistical Account.

## Chapter III.

## People.

## SERVANTS.

*Nhavis.*

into Marátha and Lingáyat Nhavis. The home speech of Maráthás is Maráthi and that of the Lingáyats is Kánarese. The Lingáyats are vegetarians, while the Maráthás eat fish and flesh and drink liquor. Though poor the Hajáms take particular care to dress neatly. They are idle but sober and take pains to be agreeable to their patrons. They generally sit and wait for employment at the meetings of roads and streets. When not employed they spend their time in gossip and spreading the stories they hear in the streets or in rich men's houses. In the afternoons they have generally nothing to do. Some have taken to tillage thrashing and selling rice, in which they are helped by their women. Some Nhavi women follow cattle to the grazing grounds to gather cowdung which they dry and use for fuel or sell. In towns barbers are paid in coin and in villages in grain. Unlike the Khándesh barbers they are neither musicians nor torch-carriers. Formerly they practised surgery, but now owing to the spread of European surgery their services are in little demand. Hajáms are supposed to be the offspring of mixed marriages and hold a social position below Kunbis. The priests of the Lingáyat Hajáms are Jangams, and those of Marátha Hajáms ordinary Marátha Bráhmans. The Maráthás rub sandal on their brows and the Lingáyats rub ashes and tie a *ling* round their necks or round their arms above the elbow. Some have lately begun to send their boys to school. As a class they are poor.

*Parits.*

**Parits**, or Washermen, are returned as numbering 5308 and as found over the whole State. They say they came from Sátára with the Maharáj's family in the beginning of the eighteenth century. They are divided into Lingáyat and Marátha Parits. The Lingáyat Parits speak Kánarese and though Lingáyats neither eat nor marry with them, in food customs and religion are the same as Lingáyats. Marátha Parits speak Maráthi, and in food, dress, religion, and customs do not differ from Marátha Kunbis. As a class Parits are clean, quiet, contented, and hardworking. They are washermen and are helped in their calling by their women. They also till and hold rent-free lands. A few are labourers. The priests of the Maráthás are Bráhmans and those of the Lingáyats are Jangams. The social disputes of the Marátha washermen are settled by their headman who is called Mhetar. When a member of the caste has broken one of the leading caste rules, they seek the aid of the village astrologer or Joshi, and the defaulter is let back into caste after drinking the feet-washed water of a Bráhma and feasting the castemen. A few send their boys to school.

## SHEPHERDS.

**Shepherds** include two classes with a strength of 42,150 or 5·86 per cent of the Hindu population. The details are:

*Kolhápúr Shepherds, 1881.*

DIVISION.	Males.	Females.	Total.
Dhangars ...	20,132	18,194	38,326
Gavlis ...	1913	1911	3824
Total ...	22,045	20,105	42,150



**Dhangars**, literally Cowmen, are found all over the State. They are said to have been created from the dust of Shiv's body. They are either an early local tribe or immigrants from the south. In support of their southern origin the division called Kánade Dhangars are said to be the latest settlement. They are divided into Dange or Hill and Mendheor Sheep Dhangars, who eat together but seldom intermarry. Their surnames are Barge, Kambre, Kolekar, Lándge, and Yedge, and parties bearing the same surname do not intermarry. They are dark, strong, and generally lean. They speak Maráthi, and in house, dress, and food are the same as Maráthás. They are dirty, quiet, hospitable, and orderly. They have a great name as weather prophets, foretelling rain and other changes of weather by observing the planets. The Danges who are said to get their name from grazing their cattle in the Sahyádrí forests are cattle dealers. The Mendhes take their name from keeping flocks of sheep and goats, and are professional graziers selling wool and woollen thread and goats and sheep. They collect considerable quantities of grain in return for folding their sheep and goats in fields in want of manure. Their social position is below that of Kunbis. They worship all the Hindu gods and goddesses, and their favourite deities are Vithoba of Pandharpur, Mahádev of Udgiri in Kolhápúr, Bahiroba of Kodoli near Panhála, and Sidhoba and Dhuloba of Chikurde in Sátára. The family priests of the Mendhes are the ordinary village Bráhmans, but the Danges have priests of their own class, who officiate at their marriages. They believe in sorcery and witchcraft, and hold caste councils. They do not send their boys to school. They have suffered by the recent marking off of lands for forest.

**Gavlis**, or Cowkeepers, are found only in towns and large villages. They are divided into Marátha Gavlis, Lingáyat Gavlis, Dhangar or Shepherd Gavlis, Krishna Gavlis, and Rajput Gavlis, who neither eat together nor intermarry. They are clean and their women are generally fat and buxom. Rajput Gavlis speak Hindustáni, Lingáyat Gavlis Kánarese, and Marátha, Shepherd, and Krishna Gavlis Maráthi. The Gavlis are a quiet hard-working people who live by selling milk, curds, and butter, and keep herds of buffaloes and cows. Except of the Lingáyats, the favourite Gavli god is Krishna. The manners and customs of Maráthi-speaking Gavlis are the same as those of Kunbis, keeping the same fasts and feasts and employing Bráhmans in their marriages; the customs of Lingáyat Gavlis are like those of Lingáyats, and Jangams officiate at their marriages and funerals. They seldom send their boys to school and are generally well-to-do.

**Labourers** include ten classes with a strength of 17,534 or 2·27 per cent of the Hindu population. The details are :

Kolhápúr Labourers, 1881.

DIVISION.	Males.	Fe- males.	Total.	DIVISION.	Males.	Fe- males.	Total.
Ambis ...	24	27	51	Khátiks ...	999	986	1985
Berads ...	2723	2554	5277	Kolis ...	3275	2965	6240
Bhandáris ...	215	181	396	Lonáris ...	443	383	826
Bhois ...	926	830	1756	Rámoshis ...	426	350	785
Ghisádis ...	77	76	153				
Kaláls ...	32	33	65	Total ...	9140	8394	17,534

## Chapter III.

## People.

## SHEPHERDS.

## Dhangars.

## Gavlis.

## LABOURERS.

## Chapter III.

## People.

## LABOURERS.

*Ambis.*

**Ambis**, or Watermen, are returned as numbering fifty-one and as found in many river villages. They are ferrymen, taking passengers across the rivers when in flood during the rains for which they are partly paid by the grant of rent-free lands. During the fair season they act as husbandmen. Most of them are Lingáyats with Jangam priests to attend their funerals and marriages, and settle their social disputes. Their manners and customs are the same as those of other Lingáyats.

*Berads.*

**Berads**, apparently Biadarus or Hunters, called by the Musalmáns Bedars the fearless, are returned as numbering 5277 and as found all over the State chiefly in Gadinglaj. They are a settled class and live in regular houses. The Berads seem to be one of the leading early tribes of the Kánarese districts. A book account makes the founder of the tribe a *vyddh* or hunter named Kanayya a great worshipper of Shiv.<sup>1</sup> They seem to have come to Kolhápúr from Belgaum under a chief or *ndik* Gudadapa and settled at the village of Kuldini. Gudadapa gathered a large band of Berads and committed gang robberies in the surrounding districts. The hardheartedness of Berads is proverbial. They formerly moved about the country in gangs committing highway robberies. During the last fifty years they have been steadily hunted down by the Kolhápúr government and forced to change plundering for tillage. The names in common use among men are Ishvara, Lakshman, Malla, Rám, Sidda, Subaya, and Tipya; and among women, Bálái, Lagma, Nilava, and Santa. Their surnames are Goladvár and Phadyálvár. Their home speech is Kánarese, and in look and make they are like the local Mángs and Mhárs. They are dark, strong, muscular, and coarse featured with gray lively eyes, flat nose, round high-boned cheeks, and flabby lips, short and lank head hair, small moustache, and ear-locks. They live in one-storeyed houses with mud and sun-dried brick walls and tiled or thatched roofs. Their house goods include metal and earth vessels, field tools, low stools, one or two cots, quilts, and blankets. They own cattle and rear dogs which are very useful to them in watching their cows and buffaloes and in hunting. Though small and poor their houses are clean and neat. Their staple food is millet bread, pulse sauce seasoned with garlic, onions, salt, chillies, and vegetables. They eat all kinds of flesh except beef and drink liquor. They use animal food particularly on holidays and when they can afford it. They give caste feasts at births, betrothals, marriages, and deaths, when the guests are served with wheat cakes, pulse, vegetables, and mutton, which they wash down with a cup of liquor, and sit all night singing *lávnis* or ballads and beating the *daph* drum accompanied by the one-stringed fiddle or *tuntune*. The men shave the head except the topknot and earknots and face except the moustache and whiskers; the women tie their hair in a back-knot or plait it into braids which hang loose down their back. The men dress in a loincloth or a pair of drawers, a shouldercloth, a shirt, and a coarse Marátha turban. The women wear a Marátha robe and bodice and do not pass the end of the robe back between the feet. Both men

<sup>1</sup> Bijápúr Statistical Account p. 91.

and women have spare clothes for great days and wear ornaments like those worn by Maráthás. As a class they are clean, neat, active, hardworking, simple, and temperate. They are husbandmen and their women and children help in field work. Some of them are day labourers and a few are village watchmen. They work from six in the morning to eleven, take their food, rest for an hour or so, again go to their work, and return home at sunset. Women mind the house and go to the fields after and return before the men; children watch the cattle. They are busy from May to December and during the rest of the year they work as labourers or sell fuel. They earn enough to live on and under ordinary circumstances save. They have good credit, and as a class are not much in debt. They worship all Hindu gods and goddesses, and their family deities are Mahádev, Māruti, and Yallamma. They keep all Hindu fasts and feasts, and their priests are ordinary Bráhmans who conduct their marriages, but at deaths they ask a Lingáyat priest at the house. They have a strong belief in soothsaying witchcraft and spirit-possession, and consult oracles when they are in difficulty. They rank below Kunbis and above Mhárs and Mángs. They marry their girls between five and sixteen and their boys before they are twenty-five. They allow widow marriage and practise polygamy. They either bury or burn their dead and mourn nine days. They are bound together by a strong caste feeling. Their spiritual head or *guru*, whose authority shows no sign of declining, settles their social disputes at caste meetings. They send their boys to school and on the whole are well-to-do.

**Bhanda'ris**, literally Distillers, are returned as numbering 396 and as found in only a few villages. They are said to have come from the Konkan where they are in large numbers especially along the coast. Their surnames are Chaván, Jádhav, More, and Surve. The men are middle-sized, lean, and fairer than Kunbis. The women are fair like the men, short, and goodlooking. They speak Maráthi. In their way of living, food, religious observances, and customs they do not differ from Kunbis. Their name is from the Sanskrit *mand-hárák* or distiller. Their proper calling is palm-tapping; but as the number of palm in Kolhápúr is small they have taken to tillage. Their family gods are Jávadári, Kálái, and Pávadáí. They have a headman who settles social disputes at meetings of the caste.

**Bhois**, or Fishers, are returned as numbering 1756. They are divided into Pardeshi Bhois<sup>1</sup> or Káhárs and Marátha Bhois or more commonly called Bhois who neither eat together nor intermarry. They eat fish and flesh and drink liquor. They are hardworking quiet and contented. They are fishermen, litter-bearers, and husbandmen, and when at leisure busy themselves in preparing fishing nets. They rank below Kunbis and eat from them. Their priests are Bráhmans and their favourite deities Bahiri, Bhaváni, Khandoba, and Māruti. They have a recognized headman who settles their social disputes. They are poor.

## Chapter III.

## People.

## LABOURERS.

*Berads.**Bhandáris.**Bhois.*

<sup>1</sup> Details of Káhár and Marátha Bhois are given in the Ahmadnagar Statistical Account.

## Chapter III.

## People.

## LABOURERS.

*Ghisa'dis.*

**Ghisa'dis**, or Tinkers, who are returned as numbering 153, are believed to have originally come from Gujarát. Their surnames are Chaván, Sálunke, Shelár, Padvalkar, and Khetri. They are generally black and bearded like Musalmáns. They drink to excess. They work in iron, making shields, axes, ploughs, horse-shoes, and ladles. Their women help by bringing coal and blowing the bellows. Socially they rank below Kunbis. Their priests are Bráhmans and their family gods are Jotiba and Khandoba. Their customs are generally like those of Kunbis. They practise bigamy, pay for their wives, and either bury or burn their dead. Caste disputes are settled at meetings of the caste council. Their craft is depressed by the import of iron tools from Bombay and Poona. They cannot read or write, and do not send their children to school.

*Kaláls.*

**Kaláls**, or Liquor Sellers, who are both Hindus and Musalmáns, are returned as numbering sixty-five. Butchers sometimes act as liquor-sellers but they are not called Kaláls. The Kaláls properly Lád Kaláls are a class of Rajputs, who for long have dealt in spirituous liquors and employ Musalmáns and Bhandáris as their agents. They live in thatched houses and own earthen and a few brass vessels. They deal in spirituous liquors and are labourers and field workers. In their social and religious customs they do not differ from Rajputs. Local Bráhmans officiate at their marriages but their spiritual head or *vushtambh* a man of their own caste must also be present. They allow widow marriage and polygamy and burn their dead. Their social disputes are settled by their teacher in the presence of their castemen. They send their boys to school and are generally poor.

*Khátiks.*

**Khátiks**, or Butchers, are returned as numbering 1985 and as found in towns and large villages. Their surnames are Ghátge, Puravalkar, Bhápte, and Shelke. They are active and intelligent. Formerly their business was confined to selling sheep and goats, the slaughtering work being done by Musalmáns. Now Marátha Khátiks act as butchers as well as meat-sellers, while others are husbandmen. Socially Khátiks are lower than Kunbis who neither eat nor drink from their hands. Bráhmans officiate at their marriages, and their manners and customs differ little from those of Kunbis. Their social disputes are settled by a headman or *mehtar*. They seldom send their boys to school, and are a thriving people.

*Kolis.*

**Kolis**, or Ferry-men, are returned as numbering 6240 and as found all over the State. They claim descent from the sage Válmik the reputed author of the Rámáyan. They are divided into Kabir Kolis, Mahádev Kolis, and Ráj-Kolis. Their surnames are Ghutenvar, Hugadvar, and Jatanvar. They are a hardworking, quiet, and hospitable people, but rude dirty and given to drink. They gather slake and sell lime nodules, catch and sell fish, and work ferries on rivers. Some are village servants and labourers and others make and sell sackcloth. Their favourite deities are Bahiroba, Jotiba, Mahádev, and the goddess Yallamma, and their priests are ordinary village Bráhmans. Social disputes are settled

at mass meetings by their head or *guru* called Ganáchár. They do not send their boys to school and are a poor class.

**Lona'ris**, or Cement Makers, are returned as numbering 826 and as chiefly found in the town of Kolhápúr. The first Lonári that came to Kolhápúr is said to have been named Ellapa, and to have come from Mándesh in East Sátára when the Kolhápúr fort was building. In food, dress, religion, and customs, Lonáris are the same as Kunbis. In towns they sell fuel, coal, and lime and the few who live in villages are husbandmen. Their women help in burning and selling lime nodules. Their social disputes are settled at meetings of the leading members of the caste. They do not send their boys to school. Their calling is less thriving than it was partly from forest restrictions on the cutting of fuel and partly from the competition of a class of Rajputs called Balvars.

**Ra'moshis** are returned as numbering 785 and as found chiefly in Alta and Panhála. They claim descent from Rám, who they say created them when he passed through the Deccan to Ceylon. Their rites, ceremonies, and home speech seem to show a Telugu origin. They are divided into Chaváns and Jádhas. Like Kunbis they eat fish, fowls, and the flesh of goats and deer, and differ little from them in house, dress, or customs. They have a bad name for committing thefts burglaries and gang and highway robberies, and stealing cattle and crops. Their children are petty thieves and robbers. They act as village watchmen and in return for their services hold rent-free lands and receive grain allowances. Some are labourers and others husbandmen. Their favourite god is Khandoba, but they worship the usual Bráhmānic gods and goddesses. Their priests are ordinary village Bráhmāns. They practise bigamy and have to pay for their wives. They bury their dead.

**Unsettled Tribes** include four divisions with a strength of 5165 or 0·67 per cent of the Hindu population. The details are:

*Kolhápúr Unsettled Tribes, 1881.*

DIVISION.	Males.	Females	Total.
Kaika'dis ... ..	72	73	145
Korvis ... ..	629	693	1267
Lamáns ... ..	144	99	243
Vadárs ... ..	1868	1642	3510
Total ... ..	2713	2452	5165

**Kaika'dis**, or Basket Makers, are returned at 145 and as found all over the State wandering in search of work. At home they speak a mixed Kánarese and Telugu and abroad an incorrect Maráthi or Kánarese. In the rainy season they live in the skirts of villages in wretched leaf and branch huts and under trees during the dry months. They eat almost all kinds of flesh except beef, and drink liquor. They are dirty and poor but hardworking. They make baskets of *bábhul* twigs and cotton and *tur* stalks, and are day labourers. They rank below Kolis and are said to belong to the same tribe. They are Bráhmānic Hindus, and their favourite deities are

### Chapter III.

#### People.

#### LABOURERS.

##### *Lonáris.*

##### *Rámoshis.*

#### UNSETTLED TRIBES.

##### *Kaika'dis.*

## Chapter III.

## People.

## UNSETTLED

## TRIBES.

*Korvis.*

Khandoba and Máyákka. They practise polygamy, allow widow marriage, and pay for their wives. They bury their dead, raise tombs over their graves, and worship the tombs for three days.

**Korvis**, or Basket Makers, are returned as numbering 1267. They are a wandering tribe who make baskets and brooms from *tur* Cajanus indicus and cotton stems. They rear pig, play music, and when the chance offers, commit thefts and gang robberies. Their favourite deities are Hanumán, Vyankoba, and Yallamma, and their favourite month is *Shrávan* or July-August. The priests who conduct their marriages belong to their own caste, and except in *Bhádrapad* or August-September and the month in which the Musalmán *Muharram* falls they marry their children at any time. They practise polygamy, allow widow marriage, and pay for their wives. They either bury or burn their dead.

*Lamáns.*

**Lama'ns**, or Caravan Men, who are returned as numbering 243 are said to have come from Khándesh about two hundred years ago. They eat most kinds of flesh except the flesh of cattle. Their women wear the petticoat and short-sleeved bodice and bone ornaments. They are a wandering tribe and trade in grain and salt moving about during the fair season with large droves of pack bullocks, buffaloes, cows, and sheep, and sometimes camels. During the rains they live in the forests. Their chief holidays are *Shimga* in February-March, *Dasara* in September-October, and *Diváti* in October-November. Their priests are the ordinary village Bráhmans, and their favourite gods are Báláji and Vyankatesh. They name their children on the twentieth day after birth and their marriages cost not less than £10 (Rs. 100). They burn the dead and have their social disputes settled by their headman in presence of the caste men. Since the opening of cart-roads the demand for their services has greatly declined.

*Vadárs.*

**Vadárs**, or Quarrymen, are returned as numbering 3510. They are divided into Gádi or Cart Vadárs and Máti or Earth Vadárs, who eat together but do not intermarry. They are black, strong, well-built, and generally spare, and their home speech is Telugu. They live outside of villages in rude huts made of sticks mats and sugarcane leaves. Their staple food is millet, but they eat fish fowls and flesh of all kinds, being specially fond of rats. Their women do not wear the bodice, but are careful to wear glass and brass bangles round the left and right wrists. Though dirty and intemperate they are hardworking, thrifty, and hospitable. Gádi Vadárs are quarrymen, making grindstones and carrying stones on low solid wheeled carts; the Máti or Earth Vadárs dig wells and ponds. Their favourite gods are Máruti and Vyankoba, and they keep the usual Bráhmanic fasts and festivals. Their marriages occupy two days Sunday and Monday. On Sunday the turmeric ceremony takes place. On Monday morning an iron post is fixed in the ground and the bride and bridegroom are made to stand near it. Rice and holy water given by the *guru* or teacher are thrown over the pair but no texts are repeated. A dinner party on that day ends the ceremony. Vadár women are impure for thirty days after childbirth. They either bury or burn their dead. They do not send their boys to



school, but from their early years employ them to tend sheep and goats. As a class they are fairly off.

**Depressed Classes** include five divisions with a strength of 90,150 or 11·77 per cent of the Hindu population. The details are :

*Kolhápur Depressed Classes, 1881.*

DIVISION.	Males.	Females.	Total.
Bhangis	66	62	128
Chámhbárs ... ..	5248	4971	10,219
Dhors ... ..	617	549	1166
Mángs ... ..	6779	6544	13,323
Mhárs ... ..	32,510	32,804	65,314
Total ... ..	45,220	44,930	90,150

**Bhangis**, or Nightsoil Men, are returned as numbering 128 and as found chiefly in Kolhápur town. They are dark and strongly built, and both at home and abroad speak an incorrect Hindustáni. They live in clean one-storeyed houses, and eat better food than other depressed classes. Their staple food is millet, rice, wheat, split pulse, vegetables, and occasionally fish and flesh. They smoke tobacco, hemp, and opium, and drink liquor. In the morning when they go their rounds the men wear tight trousers, a jacket, and a cap. The women wear either the petticoat, open-backed bodice and head-scarf, or the robe reaching to the knee with the skirt tightly drawn back between the feet and a small tightfitting bodice with short sleeves and a back. They are generally sluggish, weak, timid, and drunken, but contented and orderly. The men are fond of show and pleasure. When a Bhangi is dressed in his best it is hard to say to what caste he belongs. He wears a white or red turban, a white coat and jacket, and a silk-bordered shouldercloth with a silk handkerchief in his hand. They are scavengers and nightsoil men, cleaning the town from daybreak to ten. They are paid £1 to £1 4s. (Rs.10-12) a month. In religion they are half Musalmáns half Hindus, repeating prayers from the Kurán and at the same time worshipping Hindu gods. They rank as the lowest of all Hindu castes. Their social disputes are settled at caste meetings. They do not send their children to school, and show no signs of bettering their condition.<sup>1</sup>

**Cha'mbha'rs**, or Leather Workers, are returned as numbering 10,219 and as found over the whole State. They claim descent from Arálaya, one of the sons and great worshippers of Shiv, who incurred Shiv's displeasure by making a pair of shoes of his own skin which he presented to the god. As a punishment he was doomed to be a cobbler for life. They have no memory of any former home. The names in common use among men are Ápya, Haibati, Mahádu, and Ráma; and among women, Ahilya, Dhondu, Lakshmi, and Rukmini. They belong to two divisions those that make shoes for the higher classes, and those that make shoes for Berads, Mángs, and Mhárs. Though they neither eat together nor intermarry these two classes are similar to one another in every respect. As a class

### Chapter III.

#### People.

#### DEPRESSED CLASSES.

*Bhangis.*

*Chámhbárs.*

<sup>1</sup> Details of Bhangis are given in the Poona Statistical Account.

## Chapter III.

## People.

DEPRESSED  
CLASSES.*Chámbhárs.*

Chámbhárs are fair, middle-sized, a little round-shouldered, and weak with large gray eyes, gaunt cheeks, thin lips, and lank head and face hair. Their women are well built with regular features and fairer than Kunbi women. Both at home and abroad they speak a corrupt Maráthi and live in one-storeyed houses with mud and sun-dried walls and tiled or thatched roofs, with a small open veranda and courtyard where they tan hides and work in leather. Besides their working tools and a store of hides their house goods include metal and earth vessels, quilts, low stools, and blankets. They rear cows and buffaloes and poultry. Their staple food includes millet bread, pulse, and a pounded mixture of onions garlic and chillies. They eat flesh except beef and pork. They eat flesh whenever they can afford it, and drink liquor. Except by being less clean their dress does not differ from the Kunbi dress. As a class Chámbhárs are quiet, honest, hardworking, even-tempered, and free from crime. They make shoes, water-bags, and harness work to order, and sometimes take job work by contract. They work from six to ten in the morning, breakfast, and again work till two in the afternoon when they again eat and work till eight at night. The Chámbhár's is one of the few callings that have not suffered from European competition. On the contrary they are better paid than they formerly were. Besides by making shoes a few Chámbhárs earn their living as husbandmen. Chámbhárs rank above Mángs and Mhárs. They worship all local and Bráhmanic gods and goddesses, chiefly Mahádev and Yallamma, and they keep the usual Bráhmanic feasts and fasts. Their priests who are Bráhmans name the lucky day for the marriages and conduct the ceremony<sup>1</sup> standing at a distance. They make pilgrimages to Singanápúr in Sátára, to Yallamma in Belgaum, and to Jotiba's hill in Vádi-Ratnágiri nine miles north-west of Kolhápúr. They have a religious teacher to whom they pay a yearly money tribute, but whom they do not ask to settle social disputes which are referred to a council of elder castemen. An appeal from the caste lies to a Chámbhár of Sidi at Siddhgiri whose decrees are final. Smaller breaches of caste rules are punished with fines which take the form of a caste fine, and no one is allowed to smoke, drink, or eat with any one who is out of caste. They do not send their boys to school or take up new pursuits, but their calling is well paid and they earn enough to live on and to save.

*Dhors.*

Dhors,<sup>2</sup> or Tanners, are returned as numbering 1166 and are in towns and large villages. Their names and surnames are the same as those among Mhárs, and in food, look, dress, and habits they do not differ from the Dhors of Ahmadnagar and Bijapur. They eat flesh except beef and drink liquor. They tan hides and repair water-bags. The women mind the house and help in their calling. Besides as tanners Dhors work as hatters. Though they rank above Mhárs and Mángs their touch is not allowed to pollute high and middle class Hindus. They

<sup>1</sup> Details of Chámbhár customs are given in the Ahmadnagar Statistical Account.

<sup>2</sup> Details of Dhor customs are given in the Bijapur Statistical Account.



### Chapter III. People.

#### DEPRESSED CLASSES. *Chámbhárs.*

Chámbhárs are fair, middle-sized, a little round-shouldered, and weak with large gray eyes, gaunt cheeks, thin lips, and lank head and face hair. Their women are well built with regular features and fairer than Kunbi women. Both at home and abroad they speak a corrupt Maráthi and live in one-storeyed houses with mud and sun-dried walls and tiled or thatched roofs, with a small open veranda and courtyard where they tan hides and work in leather. Besides their working tools and a store of hides their house goods include metal and earth vessels, quilts, low stools, and blankets. They rear cows and buffaloes and poultry. Their staple food includes millet bread, pulse, and a pounded mixture of onions garlic and chillies. They eat flesh except beef and pork. They eat flesh whenever they can afford it, and drink liquor. Except by being less clean their dress does not differ from the Kunbi dress. As a class Chámbhárs are quiet, honest, hardworking, even-tempered, and free from crime. They make shoes, water-bags, and harness work to order, and sometimes take job work by contract. They work from six to ten in the morning, breakfast, and again work till two in the afternoon when they again eat and work till eight at night. The Chámbhár's is one of the few callings that have not suffered from European competition. On the contrary they are better paid than they formerly were. Besides by making shoes a few Chámbhárs earn their living as husbandmen. Chámbhárs rank above Mángs and Mhárs. They worship all local and Bráhmanic gods and goddesses, chiefly Mahádev and Yallamma, and they keep the usual Bráhmanic feasts and fasts. Their priests who are Bráhmans name the lucky day for the marriages and conduct the ceremony<sup>1</sup> standing at a distance. They make pilgrimages to Singanápúr in Sátára, to Yallamma in Belgaum, and to Jotiba's hill in Vádi-Ratnágiri nine miles north-west of Kolhápúr. They have a religious teacher to whom they pay a yearly money tribute, but whom they do not ask to settle social disputes which are referred to a council of elderly castemen. An appeal from the caste lies to a Chámbhár Gosávi at Siddhgiri whose decrees are final. Smaller breaches of caste rules are punished with fines which take the form of a caste feast and no one is allowed to smoke, drink, or eat with any one who is out of caste. They do not send their boys to school or take to new pursuits, but their calling is well paid and they earn enough to live on and to save.

#### *Dhors.*

Dhors,<sup>2</sup> or Tanners, are returned as numbering 1166 and as found in towns and large villages. Their names and surnames are the same as those among Mhárs, and in food, look, dress, and customs they do not differ from the Dhors of Ahmadnagar and Bijápúr. They eat flesh except beef and drink liquor. They tan hides and make and repair water-bags. The women mind the house and help the men in their calling. Besides as tanners Dhors work as husbandmen. Though they rank above Mhárs and Mángs their touch is thought to pollute high and middle class Hindus. They worship all

<sup>1</sup> Details of Chámbhár customs are given in the Ahmadnagar Statistical Account.

<sup>2</sup> Details of Dhor customs are given in the Bijápúr Statistical Account.

Hindu gods and goddesses and keep the regular fasts and feasts. Their family gods are Jotiba, Náikoba, and Yallamma, and their priests are village Bráhmans who name a lucky day for their marriages and repeat verses at the lucky moment standing at a distance from the Dhor marriage booth. Dhors settle caste disputes at meetings of castemen subject to the decision of the Lingáyat Jangam at Siddhgiri. They do not send their boys to school. Their calling is well paid but they spend their earnings on liquor. Of late years their condition has changed a little.

**Mángs** are returned as numbering 13,323 and as found all over the State. They have no memory of any former home. They are divided into Dukalvals or begging bards, Gárudis or snake-charmers now cattle-dealers, Nádás or rope-makers, Páthantánás or Shívtás or cobblers, and Vájantris or musicians. Of these five divisions the Nádás think themselves highest and do not eat with the rest. Most Mángs speak Maráthi and a few who live on the borders of the Kánarese districts speak Kánarese. They are darker than Kunbis and have a strongly built athletic frame with a fierce look, dark or gray eyes, straight nose, gaunt cheeks, and lank and thick head and face hair. They live in dirty ill-kept one-storeyed houses with stone or sun-burnt brick and mud walls and tiled or thatched roofs. Their house goods include a few brass and copper vessels, bellmetal dining plates, cooking earthen pots, and a few dirty clothes. Their staple food is millet bread and split pulse with a relish of chillies, salt, onions, and garlic. They eat all kinds of flesh including carrion. When they can afford it they drink country liquor. The men wear a pair of reddish knee-breeches, a jacket, a shouldercloth, and a ragged turban, and gird their loins with a waistband. The women dress in the ordinary full Marátha robe without passing the skirt back between the feet, and bodice with short sleeves and a back. They wear few brass and zinc ornaments. Mángs both men and women are proverbially dirty. They are faithless, passionate, drunken, and fond of thieving. Dukalvals are Máng bards who move from place to place begging from Mángs. Gárudis under the pretence of begging and cattle-dealing are cattle-lifters and sheep and goat stealers which they catch at night or kill while grazing during the day. Nádás are tanners and make hide and hemp ropes, brooms, and bamboo baskets. Páthantánás or Shívtás are cobblers. Vájantris are Máng musicians who play on the tabor and clarion. Besides their special occupations many Mángs of all classes work as day labourers and village watchmen. A Máng is also the State executioner whose dearest pleasure is said to be adjusting the noose round the neck of a Mhár the hereditary rival of their tribe. They are poor and live from hand to mouth. They rank below Mhárs and above Bhangis. They are Bráhmanic Hindus and adore Bráhmans whom they call to conduct their marriages. They worship all local and Bráhmanic Hindu gods and goddesses and keep some of the leading fasts and feasts. Their favourite deities are Jotiba in Vádi-Ratnágiri nine miles north-west of Kolhápura and Yallamma of Parasgad in Belgaum whose shrines they sometimes visit. They have a strong faith in soothsaying sorcery and witchcraft. They allow widow

**Chapter III.****People.****DEPRESSED  
CLASSES.***Dhors.**Mángs.*

## Chapter III.

## People.

DEPRESSED  
CLASSES.*Mángs.*

marriage and polygamy, but forbid polyandry. As among Mhárs the husband has to pay the bride's father a sum of money, and their marriage ceremony does not differ from that of Mhárs. Mángs either burn or bury their dead and are impure for ten days after a death. On the twelfth they take holy water from the village astrologer and give a caste dinner. They are bound together by a strong caste feeling and have headmen called Mhetars. The Mhetars with the chief Máng inhabitants of the surrounding five villages settle social disputes. Breaches of social rules are punished by putting the offender out of caste. They do not send their children to school, but their condition of late years shows some signs of improving.

*Mhárs.*

**Mhárs** are returned as numbering 65,314 and as found in considerable numbers all over the State. They have no memory of any former settlement. The names in common use among men are Kondunák, Limbnák, Masnák, and Rámnák; and among women Bhimi, Iji, Ráni, Taini, and Yelli. Like South Konkan Mhárs the men take the word *nák* apparently a corruption of *nák* or leader after their names. Of the many divisions into which Mhárs say they are divided, thirteen are represented in Kolhápúr. The thirteen are Andvon or virgin-born, Beles or broom basket and mat makers, Jhádes or sweepers, Ghadshis or musicians, Ghátkamblis, Gondváns or beggars, Hedshis, Kabules, Kudváns, Ládvans, Páns or flute-players, Sankamblis, and Saladis. The members of these divisions neither eat together nor intermarry. Except those living in the villages bordering on the Kánarese country who speak Kánarese, most Mhárs speak an incorrect and oddly pronounced Maráthi both at home and abroad. When he meets a man of his own caste a Mhár says *Namastu* or A bow to you, and when he meets any one other than a Mhár he says *Johár*, said to be from the Sanskrit *yoddhár* or warrior. They are darker than Kunbis, with gaunt cheeks, irregular features, a dreamy expression, and flat noses, still except in colour they differ little from Kunbis. They live on the skirts of towns and villages in dirty ill-kept one-storeyed houses with sun-burnt brick or stone and mud walls and tiled or thatched roofs. Mhárs consider it wrong to live in a house for which rent has to be paid. Their house goods include a few brass drinking vessels, bellmetal dining plates, earthen cooking dishes, and a few clothes. Only husbandmen own bullocks and field tools. Mhárs are great eaters but poor cooks. Their staple food is millet bread and cheap vegetables and, when they can get it, carrion. Except the flesh of the peacock, hog, and cat, they say they may use any kind of flesh. They are very fond of mutton and eat it with rice and pulse and wheat bread on holidays. They smoke tobacco and hemp and drink liquor. The men dress in a loincloth, a waistcloth, a jacket, a blanket as a shouldercloth, and a white or red turban. The women plait their hair in a braid which hangs down the back. They wear the full Maráthi robe without passing the skirt back between the feet and a bodice with short sleeves and a back. Except that it is somewhat richer, the Mhár's holiday dress is the same as his every-day dress. They are hardworking and fairly honest, but careless and unclean. They are often accused of poisoning village cattle, and the village headman keeps a list of all



the village Mhárs, does not allow them to go out of the village without his leave, and every evening sees that all are present in the village.

They are village servants, street-sweepers, and dead cattle carriers. They act as guides and messengers to public officers travelling on duty being rewarded by the grant of *inám* or rent-free lands. A few are husbandmen and a few bricklayers. The chief dues for Mhárs' services to villagers which were allowed by the Muhammadan and Marátha governments are *Sita-devi* or a part of a standing sugarcane crop, village or town gate offerings, *Holi* food offerings on the full-moon of *Phálgun* in March, *bendur* grain gifts on the full-moon of *Ashádh* or June-July, hides of dead cattle, *hát-shekne* or hand-warming, a money gift for watching the fire made for boiling sugarcane juice, *ghar-takka* or home-money, money paid for digging graves, grain lying on and about the thrashing floor when the floor is used for the first time, grain at the bottom of a *pev* or grain pit, the rice strewn on the two low stools which are set for the bride and bridegroom, a yearly pair of sandals for watching the village or town gate, *rukha* or marriage gift including two coppers in cash, a piece of cocoa-kernel and a handful of rice, *oti-pati* or lap-tax that is handfuls of grain put into the laps of Mhár women at the first treading of the grain, money thrown into her platter when a Mhár woman comes to wave a lamp round the head of the bride's or bridegroom's mother, *madhe-pade* or carcass-tax, *manguli* or gifts for winding a string round the village on the no-moon of *Ashádh* in June-July and of *Kártik* in October-November, *rán-sodvan* or forest-leaving that is grain ears given to Mhárs on the first cutting and stacking, *pendha* or straw, and *lagin takka* or marriage-rupee that is 6d. (4 as.) given to the village Mhár when the booth is raised. Of late years regular employment in State public works has improved the condition of the Mhárs and they are less in debt than Kunbis. They have no credit and can borrow only at twenty-five to fifty per cent. They work from six to twelve and from two to nine. Village watchmen sleep by day and stay awake all night. Their busy season is from January to June. Besides the ordinary Bráhmanic holidays they take a holiday on the *Rede Jatra* or Buffalo Fair that is when buffaloes are killed in honour of the cholera goddess. They rank first among the depressed classes and do not eat from Mángs. When a Kunbi is buried or burnt without a Bráhman priest, a Mhár is asked to say, Ye great angels, free *Bápu* son of *Ráma* from worldly affections. His sin and his merit have been balanced, he is gone to Shiv's heaven by holding the sacred bull's tail, Shiv, Har Har.<sup>1</sup> A family of five spend about 10s. (Rs. 5) a month on food and dress. A boy's marriage costs £5 to £6 (Rs. 50-60) including all the girl's father's expenses and a special payment of £2 8s. (Rs. 24), and a death 10s. to £3 (Rs. 5-30). Mhárs are Bráhmanic Hindus, but they cannot tell whether they are

## Chapter III.

## People.

DEPRESSED  
CLASSES.

## Mhárs.

<sup>1</sup> The Maráthi runs: *Jháda jhuda sansár toda, pápa punyácha jháta niváda, dev-ganche devgan miratche mahágan* (he says deceased's name) *basvyáchi shep dharan kailásás gela, Shiv, Har Har.*

## Chapter III.

## People.

DEPRESSED  
CLASSES.*Mhárs.*

Bhāgvats or Smārts. They revere Brāhmans and have also teachers or *gurus* of their own caste. The head of their teachers is called Dheguji Meghuji or Cloud of Clouds. There are three Clouds of Clouds, of one of whom Kolhāpur is the see.<sup>1</sup> The jurisdiction of the Kolhāpur Cloudy Highness passes as far south as the Tungbhadra, and his yearly dues, which are collected at the rate of 4s. (Rs. 2) a village amount to about £300 (Rs. 3000). His office is hereditary. The Dheguji Meghujis are much respected; they eschew beef and do not allow other Mhárs to touch their food. Mhárs worship all Brāhmanic gods and goddesses, their favourite deities being Bahiroba, Khandoba, Mhasoba, and Vithoba. Their peculiar deities are the cholera goddess or Mari, Pándhar or the village site goddess, and Thal or the settlement place-spirit. Besides these gods and goddesses they worship their ancestors' brass images as house gods, and they have strong faith in soothsaying sorcery and witchcraft.

A Mhár woman is held impure for eight days after childbirth. On the fifth a few spots of sandal and turmeric paste are daubed on the wall near the mother's cot. The spots are marked with sandal paste and rice, and a lamp is waved round them. Mhár children are named on the ninth day. Polygamy and widow-marriage are allowed and polyandry is forbidden. Mhár girls who are devoted to Khandoba remain unmarried and become their fathers' heirs. When a marriage is settled the boy's father asks the village astrologer to fix the marriage day. On the day before the marriage day the boy is rubbed with turmeric paste and bathed, and his kinspeople and friends take the rest of the paste to the girl's house, rub the girl with the paste, and present her with a robe and a few ornaments. In the evening of the marriage day an hour before the time fixed the boy goes on horseback in procession to the girl's, where the village astrologer gives the boy and girl two yellow strings with bits of turmeric roots fastened to them to tie round their wrists. The boy and girl are then taken to the marriage altar and seated on two low wooden stools, the girl to the right and the boy to the left. The village astrologer and the kinspeople and friends of the pair throw yellow rice on the pair and they are wedded. Betel is handed to all present and friends and kinspeople are feasted. After the feast the boy and girl are taken on horseback to the village Máruti, where they break a cocoanut and go to the boy's house. The ceremony ends with two feasts one given by each party. Mhárs bury their dead and mourn three days. On the third day the chief mourner shampoos the bearers' shoulders, and gives them food before any of the family eats and while the bearers are eating every one leaves the house. Mhárs are bound together by a strong caste feeling and have headmen or *Mhetars*. Breaches against caste rules are punished by putting the offender out of caste. A *nimb* twig is thrown on the offender's house and all are enjoined to keep aloof from the offender's family on pain of losing caste. When an offender is let back, he has to spend 4s. to £1

<sup>1</sup> The other two sees are at Dombingaon on the Godávri and Vasi the position of which the Kolhāpur Mhárs do not know.

(Rs. 2 - 10) on a caste dinner. The high priest gives him *tirth* or holy water to sip and he is allowed to eat in the same row with his castemen. *Mhárs* seldom send their boys to school, but of late years their condition has shown signs of improving.

**Beggars** include nine classes with a strength of 3504 or 0.46 per cent of the Hindu population. The details are :

*Kolhápur Beggars, 1881.*

DIVISION.	Males.	Females	Total.	DIVISION.	Males.	Females	Total.
Bairágis...	64	42	106	Gosávis ...	989	807	1796
Chudbudke Joshis	129	139	268	Valhárs ...	149	121	270
Dombáris ...	71	108	179	Vásudevs ...	13	13	26
Gárudis ...	31	22	53				
Gondhlis ...	384	366	750				
Gopáls ...	29	27	56	Total ...	1859	1645	3504

**Bairágis**, properly *Vairágis* or Ascetics are returned as numbering 106 and as found wandering all over the State. As all Hindus except the depressed classes are allowed to become *Bairágis*, the class varies greatly in appearance. They speak *Hindustáni* among themselves. They are vegetarians and keep from flesh fish and liquor, but freely use hemp. They dress in ochre-coloured clothes. They smear their bodies with ashes and grow their hair long, wearing it either dishevelled or coiled round the head. *Bairágis* are passionate and idle and almost always under the influence of hemp. They are religious beggars and wander all over the country sometimes in bands and sometimes singly. On the third Monday of *Shrávan* or July-August the State gives a dinner, clothes, and money to *Bairágis*. They are devotees of Vishnu and visit many of the famous Vishnu shrines. Their *gurus* or teachers who are also *Bairágis* have *maths* or monasteries in different holy places in India. The *guru* is succeeded by his favourite disciple. When a Hindu wishes to become a *Bairági*, he tells a distinguished *Bairági* that he wishes to become his *chela* or disciple. A day is fixed on which the novice is stripped of his clothes and is given a loincloth to wear and a *hom* or burnt-offering is made. The novice then takes a vow of poverty, celibacy, and pilgrimage to all holy places in India. The vow is not always kept. Only a few of them refrain from cutting their hair and nails, and undergo bodily tortures. They worship all *Bráhma*nic gods and keep most fasts and feasts. They believe in witchcraft and soothsaying. They bury their dead and do not mourn. On the thirteenth a feast is given to *Bairágis*.

**Chudbudke Joshis**, or Hourglass-drum Astrologers, are returned as numbering 268 and as found in small numbers in some of the eastern and southern villages of Kolhápur. They take their name from the little hourglass-shaped drum or *chudbudke*. In name house food and dress they do not differ from *Kunbis*. A *Chudbudke Joshi* got up for his begging tour is a quaint figure. He is dressed in a large dirty white turban with a red cloth turned over it, a long white coat reaching below his knees, and a tattered silk-bordered shouldercloth. In one hand is a book by referring to which they pretend to foretell fortunes, and in the other is the name-giving hourglass-shaped drum. As they are generally unable to

### Chapter III. People.

#### BEGGARS.

#### *Bairágis.*

#### *Chudbudke Joshis.*

## Chapter III.

## People.

## BEGGARS.

*Chudbudke*  
*Joshis.*

read, they do not tell fortunes by almanacs and books, but judge by the face and the lines on the hands. They have good fortune in store for every one who asks them. Their usual blessing is Brother, thy belly will grow large, that is You will become a big man.<sup>1</sup> They beg from morning to evening. The harvest is their busy time when they lay in grain for the rainy season. Their favourite goddesses are Yallamma and Margai. In other points of religion and in customs they do not differ from Kunbis. Their social disputes are settled by a headman or *Mhetar* who lives at Kolhápúr. They do not send their children to school nor take to new pursuits. On the whole they are a falling class.

*Dombáris.*

**Dombáris**, or Tumblers also called Kolhátis, are returned as numbering 179 and as found wandering all over the State. They have no memory of any former settlement. They are generally dark, strong, and well made with regular features. Their home speech is a mixed Maráthi Hindustáni and Kánarese. They live in small huts of grass matting and own donkeys to carry their kit, dogs for watching, and she-buffaloes for milk. The men's dress includes a loincloth, *cholmús* or knee-breeches, a tattered turban, and a piece of cloth thrown loosely over the shoulders. The women dress in a full Maráthi robe without passing the skirt back between the feet and a bodice with short sleeves and a back. The women who tumble are careful about their dress and appearance, and wear a few ornaments. They are a wandering tribe of tumblers and rope-dancers of bad character, the women prostitutes, and all when they get the chance thieves. They are under the eye of the police. They worship both Hindu gods and Musalmán saints and have no regular rites. They have neither priests nor headmen: the most influential among them advises the community. They believe in witchcraft and ghosts. They have no fixed customs. Their marriage ends with a procession from the bridegroom's house to the bride's and a caste feast. They do not send their children to school and show no signs of bettering their condition.

*Gárudis.*

**Gárudis**, or Jugglers and Snakecharmers, are returned as numbering fifty-three and as found wandering with their families in all parts of the State. They are Bráhmanic Hindus and ask Bráhmans to conduct their marriages. They fast on the eleventh of each fortnight and on the first day of *Ashvin* or September-October. They practise bigamy and pay for their wives. They either burn or bury their dead.

*Gondhlis.*

**Gondhlis**, or Performers of the *gondhal* dance, are returned as numbering 750 and as found all over the State. Except that they are poorer, they differ little from Kunbis in name, house, food, or dress. They are beggars begging from door to door for grain clothes and money, singing dancing and playing on a drum called *sambal*, on the one-stringed fiddle or *tuntune*, and on metal cups or *táls*. They beg on Tuesdays and Fridays, days sacred to Bhaváni. They also perform the *gondhal* dance, and entertain

<sup>1</sup> The incorrect Maráthi runs : *Tujhe dvánd mothe hoil ga dáda.*

people with their songs. The *gondhal* dance<sup>1</sup> is generally performed among Deshasth Bráhmans and among Maráthás and Kunbis in honour of Bhaváni on the occasion of a thread-girding, of a marriage, or of a birth. The dance always takes place at night. During the day the host gives a feast to dancers, who generally perform in a band of three to five. At night the dancers come back bringing their musical instruments, a torch or *divti*, and the dress of the chief player. The dance begins between nine and ten at night and with good performances ends between four and five in the morning. On a wooden stool in the largest room of the house they set a brass water-pot or *támbya*. In the mouth of the water-pot betel leaves are laid and the whole is closed with a cocoanut. The water-pot with the cocoanut represents the family goddess Bhaváni. On either side of the pot are set two lighted torches which are fed with oil from time to time. The head dancer is dressed in a long white robe reaching to his ankles fringed with red or gold and gathered in puckers a little above the waist and wears cowry shell necklaces and jingling bell anklets. He takes his stand in front of the goddess and his companions stand behind him playing on the double drum or *sambal* and one-stringed fiddle called *tuntune*. The head dancer dances and sings hymns in praise of Bhaváni and his companions repeat a refrain. After Bhaváni's praise is over the rest of the time is spent in reciting and explaining historical ballads and singing love songs. They are idle and many consider it a degradation to work as labourers. They are not so well off as they used to be. Owing to the want of patronage skilled Gondhlis are disappearing. In religious and social customs they do not differ from Kunbis. They seldom send their children to school and on the whole are a falling class.

**Gopa'ls**, literally Cowkeepers, are returned as numbering fifty-six and as found wandering over the State. They are Mhár beggars who wear a woollen necklace, clash cymbals, and ask blessings on the almsgiver. Though Mhárs by birth and in social customs, they do not eat from Mhárs.

**Gosa'vis**, or Passion Lords, are returned as numbering 1796 and as found either wandering or settled all over the State. They are divided into five classes Ban, Bhárti, Giri, Puri, and Sarasvati, who, except Bhártis and Puris, eat together and intermarry. They are recruited from all Hindus except the depressed classes. The body of Gosávis include those who willingly become Gosávis, children bought by Gosávis, and children presented to Gosávis by their parents. Those who are married generally live in one-storeyed houses. Among themselves they speak Hindustáni and Maráthi with others. Gosávis wear ochre-coloured clothes. They dine with Kunbis, eat goats sheep and fowls, smoke tobacco and hemp, and some drink country liquor. They are passionate and idle. They are religious beggars. On the third Monday of *Shrávan* or July-August the State gives a dinner, clothes, and money to Gosávis. Though at the initiation they take a vow of poverty and celibacy,

## Chapter III.

## People.

## BEGGARS.

*Gondhli*.*Gopáls*.*Gosávis*.

<sup>1</sup> Details are given in the Poona Statistical Account.

## Chapter III.

## People.

## BEGGARS.

*Gosávis.*

most of them are traders, moneylenders, soldiers, and a few are *inám* or rent-free landholders. They formerly wandered in armed bands, waged war with Bairágis, and plundered the country they passed through. They are devotees of Shiv, worship all regular Bráhmánic gods, and keep most fasts and feasts. Some marry and some keep mistresses. Those who live a single life are generally attended by a disciple who is their heir and successor. They bury their dead and do not mourn. On the thirteenth they give a feast to Gosávis.

*Valhárs.*

**Valhárs** are returned as numbering 270 and as found only in some villages of the State. In name, house, food, dress, religion, and customs they do not differ from Kunbis. They play on flutes and drums and beg. Some are husbandmen, some make horse whips, and some are day-labourers. They do not send their children to school and are a steady class.

*Vásudevs.*

**Vásudevs** are returned as numbering twenty-six and as found wandering all over the State. In name, house, food, dress, religion, and customs they do not differ from Kunbis. The men beg dressed in trousers, a long white coat, and a long crown-like hat with a brass top surrounded with peacock feathers. While begging three or four dance in a circle striking together their metal cups or *táls* and castanets or *chiplis*.

## LINGÁYATS.

**Lingáyats**,<sup>1</sup> properly Lingvats or *Ling* Wearers, are returned as numbering 75,212 of whom 39,571 are males and 35,641 females. They are chiefly found in the Alta, Gadinglaj, and Shirol subdivisions. Of the whole number 27,148 or more than one-third are in Gadinglaj on the south-east bordering on Belgaum. The Lingáyat sect rose to importance during the twelfth century. Basav, the founder of the sect was the son of an Árádhyá or Shaiv Bráhmán of Ingleshvar near Bágévádi about twenty-two miles south-east of Bijápúr. The worship of the *ling* as a home or shrine of Shiv is generally admitted to have belonged to the tribes who held the south of India before the arrival of the Bráhmans. The Lingáyats claim the *ling* as the earliest object of worship and look on Basav as the restorer not the author of the faith. It is not unlikely that like other guardian emblems or objects the *ling* has from very early times been worn by the people of the Deccan.<sup>2</sup> Guravs, not Bráhmans, are the proper ministrants in Shaiv shrines, who often wear the *ling*, though most of them are not followers of the Lingáyat faith. From them or some other local classes the

<sup>1</sup> Detailed accounts of Lingáyats are given in the Dhárwar and Bijápúr Statistical Accounts.

<sup>2</sup> In Egypt, in Rome, and still in Italy a small *ling* or phalus is hung round a child's neck to ward off the evil eye. For the same reason a phalus was tied under a Roman warrior's triumphal car. The Bráhmán story of the origin of the wearing of the *ling* is that Brahma asked Rudra or Shiv to plan a world. Rudra disappeared into the lower world and remained so long thinking how to devise an everlasting world that Brahma weary of waiting himself completed the universe. News came to Rudra that a world had been made. In a fit of passion he forced his way through the earth and determined to destroy all that Brahma had done. The gods prayed him to spare it and he relented. He took from the gods their power and made an animal with three horns one of Vishnu's power, one of his own, and the third of Brahma's. Rudra afterwards restored their power to Brahma and Vishnu and wore the third horn round his own neck calling it *átma ling* or soul-essence.



Árádhya Bráhmans seem to have adopted the practice of wearing the *ling* round the arm. This practice Basav extended to all members of his sect. His followers consider Basav an incarnation of Nandi or Shiv's bull. According to tradition his father was a worshipper of *párlhiv* or earth *lings*, which he made daily with his own hands. Basav is said to have refused to be girt with the sacred thread, or, according to another account, refused to repeat the *gáyatri* or sun-hymn and was forced to leave his father's house. He went to Kalyán in the Nizám's country about a hundred miles north-west of Haidarabad then the seat of the usurper Vijjal or Bijjal of the Kalachuri family, who was a Jain by religion. Basav's cleverness attracted the notice of Baldev the prime minister, who gave him his daughter in marriage, and his advancement was further hastened by the beauty of his sister Akka Nágamma with whom king Bijjal fell in love. After the death of his father-in-law, Basav became prime minister, and in time rose to the command of the army and the control of the finances. When he rose to power Basav took great pains to spread his new religion. He filled all the offices of the State with adherents of the new sect.<sup>1</sup> At length his power became so formidable that Bijjal determined to seize him. Basav fled, and gathering a large body of his followers turned on the king who was in pursuit of him and defeated him. This happened in 1168. He returned in triumph to Kalyán with the king as his prisoner. According to the Basav Purán, because the king had put out the eyes of two pious Lingáyats, Basav ordered him to be killed. He cursed Kalyán and retired to Sangameshvar about ten miles north of Hungund in Bijápur, the meeting of the Malprabha and Krishna. When Basav heard that the king was dead he prayed Shiv to receive him, the *ling* opened and Basav passed into it. According to Jain histories after the murder of his king Basav was seized with panic. He fled from the king's son and sought refuge in Ulvi in North Kánara about twenty miles south of Supa. Finding that the town could not stand against the besieging army, Basav leapt into a well and perished. Lingáyats still go on pilgrimage to Ulvi in *Mágh* or January-February. After Basav's death the sect made rapid progress. According to the theory of the faith the wearers of the *ling* are equal and distinctions of caste cease. It is said that Basav allowed people of even the lowest classes to join the new sect. According to some accounts, the bulk of the early adherents were men of low caste. In support of this it is said that the bulk of Lingáyat saints are outcastes and women and that there is not a Bráhman among them.<sup>2</sup> Soon after Basav's death, the lower or impure classes were not allowed to join and all other classes who wished to join had to pass a term of proving before they were admitted to be members. Like the doctrine of the equality of believers many of Basav's other doctrines, if they ever passed beyond theory, are no longer practised. One of his leading doctrines was that there was one God who required neither

## Chapter III.

## People.

## LINGÁYATS.

<sup>1</sup> According to Jain traditions Basav started his new religion because he had been put out of caste for taking food from the hands of a woman in her monthly sickness.

<sup>2</sup> Madras Journal of Literature and Science, II. 146.

## Chapter III.

## People.

## LINGÁYATS.

mediators, fasts, nor pilgrimages. The Kolhápúr Lingáyats worship several gods, among them Basav the founder of the faith whom they consider an incarnation of Nandi or Shiv's bull, Ganpati and Virbhadrá the sons of Shiv, and Ganga and Párvati the wives of Shiv. Besides the members of Shiv's family Kolhápúr Lingáyats worship Yallamma of Hampi in Belári and Tuljábhaváni of Tuljápúr in the Nizám's country. The Kolhápúr Lingáyats fast on *Shivráttra* or Shiv's Night in January-February, and make pilgrimages to Ulvi in North Kánara and Sangameshvar in Bijápúr, and the Jamgam in practice is no less a mediator than the Bráhman. One of the leading doctrines of Basav's faith was that nothing could make the bearer of the *ling* impure. To the true believer the observance of ceremonial impurity in consequence of a woman's monthly sickness, a birth, or a death was unnecessary. In practice the Kolhápúr Lingáyats are little less careful to observe ceremonial uncleanness in connection with monthly sickness, births, and deaths than their Bráhmanic neighbours. Another of Basav's leading doctrines was that as she wore the *ling* the Lingáyat woman was the equal of the Lingáyat man; that therefore she should not marry till she came of age; that she should have a say in the choice of her husband; and that she, equally with the man, might be a *guru* or Lingáyat teacher. Lingáyat women in Kolhápúr are married in their childhood, they have nothing to say to the choice of their husband, and except that the widow's hair is not shaved and that she is not stripped of her bodice, her position differs in no way from the position of a widow in a Bráhmanic Hindu household. According to the theory of the Lingáyat faith the wearer of the *ling* is safe from all evil influences, neither stars nor evil spirits can harm him. In practice Kolhápúr Lingáyats consult astrologers and fear and guard against evil spirits little less constantly and carefully than their Bráhmanic Hindu neighbours. The chief points of difference between a Kolhápúr Lingáyat and Bráhmanic Hindu is that the Lingáyat worships fewer gods, that he has fewer fasts and feasts and fewer ceremonies especially death ceremonies and purifying ceremonies; that both men and women wear the *ling* and neither man nor woman the sacred thread; that both men and women rub their brows with cowdung ashes; that as a rule men shave the whole head, and that neither a widow's head nor a mourner's lip is shaved; that they neither eat animal food nor drink liquor; and that they show no respect to Bráhmans and show high respect to Jangams their own priests. In having a *ling*-binding, an initiation for priests, and a purifying ceremony for all instead of the sixteen sacraments or *sanskárs*, Lingáyats differ both from Bráhmanical and Jain Hindus. In their respect for life, in the strictness of their rules against the use of animal food and liquor, and in the little regard they show to the dead the Lingáyats are like the Jains.<sup>1</sup>

<sup>1</sup> In connection with the Buddhist and Jain element in the Lingáyats it is worthy of note that one of the latest buildings raised to Buddhist gods about 1095 was built at Dambal in Dhárwár by traders of the Vira Balanja sect who afterwards became great supporters of the Lingáyat faith.

Kolhápúr Lingáyats belong to four classes Jangams or priests, Vánis or traders, Panchams or Panchamsális,<sup>1</sup> craftsmen husbandmen and herdsmen, and a fourth unnamed class including servants barbers washermen and Mhárs. The Lingáyat priests of Kolhápúr include five sects or schools Ekorámárádhyā, Marulárádhyā, Panditárádhyā, Revanárádhyā, and Vishvárádhyā. The founders of these schools Ekorám, Marul, Pandit, Revan, and Vishva, are believed to have sprung from the five mouths of Shiv and to have been great spreaders of the Lingáyat faith.

They seldom meet and there is no show of rivalry. To laymen all Jangams are holy and they worship all without much inquiry as to their school. Each of the five schools includes thirteen divisions or *bagis*. The divisions or *bagis* of the Ekorámárádhyā school are Bhasma, Chandragundi, Katiyemba, Khadgi, Khastak, Lambonemba, Mrityakánti, Rajyu, Rámgi, Raupya, Shikhari, Triputi, and Vasam. The divisions of the Marulárádhyā school are Bilvasutra, Bhaitraya, Chakari, Kattar, Kavach, Koraban, Kukshakanta, Kutar, Malli, Masani, Nilkanti, Singi, and Svarnakanthi. The divisions of the Panditárádhyā school are Bedadi, Bhagini, Danti, Gonikati, Jálkanti, Jathar, Keshkanti, Lallat, Lochan, Muktaguchha, Natija, Trigun, and Vijaprakanti. The divisions of the Revanárádhyā school are Bhikti, Digambar, Mahni, Murath, Musadi, Nat, Pachhakanti, Padvidi, Puran, Shadga, Shori, Surgi, and Veni. The divisions of the Vishvárádhyā school are Dashmukh, Gagan, Gochar, Guhágra, Gurjarkanti, Kamblí, Panchvaktu, Panchvani, Lagudi, Musali, Pashupati, Shitali, and Vrishabh. The chief details of the five leading schools are:

*Lingáyat Sects, 1881.*

SCHOOL.	ORIGIN.	CENTRE.	STOCK.	Sutra OR BRANCH.	Pravar OR FOUNDER.
Ekorámárádhyā ...	Drá k s h á r á m Kshetra.	Kedár <sup>2</sup> ...	Bhringi ...	Lambak ...	Virshaiv.
Marulárádhyā ...	Shri Sidhavata.	Ujjain ...	Nandi ...	Vrishtika ...	Vireshvar
Panditárádhyā ...	Shuddhakundi...	Shrishail Parvat	Vrishabh ...	Muktaguchha .	Virshaiv.
Revanárádhyā ...	Kolupakish ...	Kadalipur (Bá-lehalli).	Vir... ..	Padvidi ...	Virshaiv.
Vishvárádhyā ...	Vishvesha Ling.	Kollipáke ...	Skand ...	Panchvarna ...	Virshaiv.

Jangams of the same school division or *bagi* do not intermarry. Jangams include five classes, Virakts or renouncers of worldly pleasures, Pattadevru or head priests, Ayyás or teachers, Charantis or wanderers, and Maris or acolytes.<sup>3</sup> The Virakts wear the loincloth

<sup>1</sup> Panchamsális seem to mean Jain weavers. The Panchams are the fifth or lowest class of Jains whom all who marry widows have to join. Compare the account of Lingáyats in the Statistical Account of Dhárwár.

<sup>2</sup> Kedár is in the Garhwál district of the North-West Provinces, Ujjain in Málwa, Shri Shail Parvat in North Arkot, Kadlipur the modern Bálehali in Dhárwár, and Kollipáke an unidentified Western Chálukya capital in Southern India (Fleet's Dynasties of the Kánarese Districts of the Bombay Presidency, 44).

<sup>3</sup> *Virakti* is from the Sanskrit *vi* without and *ranj* to please; *Pattadevru* is from the Sanskrit *pát* cloth through *patt* clothed hence honoured, and *dev* shining hence worshipful. *Devru* is the Kánarese plural of *dev*. *Ayya* means spiritual guide and is often applied to common teachers.

## Chapter III.

## People.

## LINGÁYATS.

and short loose shirt, and spend most of their time in devotion and study. The Pattadevurus wear a waistcloth instead of a loincloth and are less retired than the Virakts. The Ayyás are married and live chiefly by begging. When begging they wear the bell-garter or *jang* below the right knee, wear ochre-coloured clothes, and carry a cane staff.<sup>1</sup> The Charantis or wanderers go from place to place and gather contributions from the Lingáyat laity for the support of monasteries or *maths*. Maris or acolytes are celibates and wait on the Virakts. After the death of a Virakt, the most learned and fittest among his Maris or attendants is raised to his seat. Unlike Bijápur Lingáyats, Kolhápur Lingáyats have no Ganácháris or monastery managers, Mathpatis or Lingáyat beadles, and Chalvátis or Mhár standard-bearers. In Kolhápur the heads of small monasteries are called Mathadayyas. Vánis and Panchams or Panchamsális can become Jangams but it is only when a Jangam has no child or relation that he adopts a boy from these classes. The boy must be unmarried and must not be the child of a widow by her second husband. Ayyás or married Jangams may take food from any Lingáyat except from members of the barber washerman and Mhár classes, and in some cases from oilmen and ferrymen. When a Jangam gives a feast, all except these three classes come and eat together. The same freedom is observed when a feast is given in a monastery or *math*. In Kolhápur the word Jangam is generally applied to the Jangam's assistants, the Mathpatis or Lingáyat beadles of Belgaum and other Kánarese districts, who in all religious ceremonies act under the Jangam's orders. In Kolhápur the head local Jangam is called *svámi* or lord a title which in other districts belongs to the provincial high priest. The house in which the Mathadayya or local head priest lives is called a *math* or monastery. In places where there are many Lingáyats the monastery is a large building of stone or burnt brick, an open quadrangle generally shaded with trees among which the *bel* *Ægle marmelos* is conspicuous. The four verandas of the quadrangle are covered with tiled roofs one of which is set apart as a *ling* shrine with a Nandi or bull in front. In the central hall a place is set apart for the *svámi* or chief priest, whose authority extends over several villages. On the space set apart for the *svámi* a cushion with pillows on three sides of it is always spread. Several small rooms are used as a cook-room for the *svámi*, a worshipping-room, a study, and a sleeping-room. In the outer verandas a school is generally held where Kánarese and sometimes Sanskrit are taught. In the open ground behind the monastery are generally a well, and at some distance the tombs of previous *svámis*, cube-shaped stone structures with a *ling* on the top. The hindpart of the enclosure is generally surrounded with a wall. At each corner of the building is a stone called the *lingmudrikallu* or ling-marked stone. Lingáyat strangers can almost always find a meal at a monastery. No Bráhmanic Hindu

<sup>1</sup> Kolhápur Lingáyats do not carry the cobra-cane or *nágbet* and do not know why the cane carried by Bijápur Jangams is called *nágbet* or cobra-cane.

can get a meal at a monastery and no Lingáyat stranger can remain at a monastery more than two days. The income of the head of the monastery is generally partly paid by the State, most of it is collected from the local Lingáyats chiefly on marriage and other festive occasions, from trade fees, and from gifts at religious ceremonies. The head of the monastery often gets presents of cloth from cloth dealers and grain from husbandmen and landowners. A stranger who visits the head of a monastery is generally requested to lay some silver coins before his feet. If the *svámi* expresses a wish for anything his wish is promptly gratified by one of his followers. He generally takes his midday meal at a follower's house and sometimes takes a little at several houses; his evening meal he takes in the monastery. He has servants and attendants who exact prompt obedience from the *svámi's* followers. The *svámi* is always careful on all occasions to press on his followers the need of keeping their faith and of unquestioning obedience to all its rules. In the afternoon he generally reads some sacred book, old people almost always coming to hear. In *Shrávan* or July-August the congregation is specially large and is generally chiefly composed of old women. The Purán is finished in *Bhādrapad* or August-September, when the hearers give cash and clothes and a feast is held.

The class of Lingáyats who rank next to Jangams are the Vánis or traders. They are divided into Shilvants or rule-keepers and Lokvants or common people.<sup>1</sup> Shilvants rank next to Jangams and can become Jangams by passing the purifying ceremony called *diksha*. Lokvants who rank next to Shilvants can also become Jangams. Except when a Jangam is the host or when the feast is held in a religious house neither Shilvants nor Lokvants eat with members of the lower classes. The third division includes Panchams or Panchamsális, oilmen or Telis, ferrymen or Ambis, cowherds or Gavlis, gardeners or Mális, and potters or Kumbhárs. A Jangam may adopt a Pancham boy. The fourth or lowest class includes Nhávis or barbers, Parits or washermen, and Mhárs.

The names in common use among men are generally taken from the names of Shiv as Rudráppa, and Shivlingáppa, some from Basav and Guru as Basáppa, Vir Basáppa, and Gurusidháppa. If a woman has lost several children she gives her next child a mean name, as Kalláppa from *kallu* (K.) stone and Kadáppa from *kad* (K.) forest. The names in common use among women are Basavva from Basav, Gangavva from the heavenly Ganges, Kallavva from *kallu* (K.) stone, and Párvativva from Párvati the wife of Shiv. Their surnames, when they have surnames, are place and calling names as Lokápurí a dweller in Lokápur or Tenginkai a cocoanut seller. The lay followers of a *guru* or teacher adopt his family stock or *gotra*.

The Lingáyats of Gadinglaj in the south speak correct Kánarese. The home tongue of the rest is a somewhat impure Kánarese spoken in a Maráthi tone. Out of doors most speak a fairly correct Maráthi.

<sup>1</sup> Shilvant is said to come from the Sanskrit *śīl* good disposition and to mean those who obey religious rules. The word Lokvant is from the Sanskrit *lok* people and means of the masses.

## Chapter III.

## People.

## LINGÁYATS.

So large a body as the Lingáyats, including persons of almost all callings differ considerably in appearance, height, and colour. Still, except that they are slighter and cleaner, Kolhápúr Lingáyats as a class differ little from Maráthás. The men are dark-brown and the women are often fair and handsome. Their houses are simple and clean and are occasionally two-storeyed. They are divided into several dark and ill-aired rooms, a cooking and a store-room, a sitting and office room, and bed rooms. Near the cook-room are niches in the wall with folding doors where pickles and sun-dried pulse and rice called *sándge pápad* are kept. A portion of the centre hall is set apart as a shrine where the Jangam is worshipped. No one but a Lingáyat may go into the cook-room or into the Jangam shrine. Lingáyats have a great dislike to leather. They allow no leather in their saddles; no shoe may be brought into the inner part of the house, and if any one touches a shoe he must wash.<sup>1</sup> The privy, if there is a privy, is at some distance from the house. Cattle are not kept in the house but in a separate shed. A Lingáyat's house goods include cots, low wooden stools, boxes, iron or brass tripods to hold dining plates, and metal and earthen vessels required for family use. Few have vessels enough for a caste feast. Givers of caste feasts borrow the public vessels from a monastery. Silver vessels are used by the rich, brass and copper vessels by middle class people, and wooden and earthen vessels by the poor. Lingáyats never use animal food or spirituous drink. Their daily food includes rice, millet bread, pulse curry, vegetables, and milk, whey, curds, butter, and clarified butter. No one but a *ling*-wearer may touch or even see a Lingáyat's food. On holidays and at small parties they have rich dishes. Their caste feasts are plain. The two chief dishes are *huggi* that is wheat and milk boiled together and seasoned with raw sugar and *holagis* or roly-polies, that is wheat cakes stuffed with gram flour and raw sugar. A caste feast costs about 6d. (4 as.) a head. A Lingáyat when alone or one of a small party sits to eat on a low wooden stool and generally eats his food off a brass plate set on an iron or brass tripod. Except in travelling when metal plates are not easily got and leaf plates are used, Lingáyats never use leaf plates. At dinner, before he eats a Lingáyat holds his *ling* in his left hand and bows to it. At caste dinners the guests sit on matting instead of on stools, and except Jangams lay the plate on the ground not on a tripod. At caste dinners before guests have sat to it, *tirth* or holy water, that is water in which a Jangam's feet have been washed, is poured over the guest's hands. The guests sip the holy water, shout *Har Har Mahádev*, and begin to eat. In eating the right hand is alone used. The small waterpot which must never touch the lip is raised in the left hand. Women dine after the men. They sometimes sit on stools, never on mats, and generally lay their plates on the ground. Among Lingáyats a young married couple never talk together in the presence of

<sup>1</sup> The Lingáyat dislike to leather is stronger than the Deccan Bráhmaṇ's dislike. When they go out well-to-do Deccan Bráhmaṇ women put on shoes; and during her lying-in a Bráhmaṇ woman with her shoes on is allowed to walk over great part of the house.



elders. Except a few who grow short topknots the men shave the whole head and face except the moustache and eyebrows. They mark the brow with white ashes called *vibhuti* literally the great power.<sup>1</sup> The ashes which are rubbed on the brow are specially prepared by the Jangams or priests. Pure cowdung is dried and burnt and the ashes soaked in milk for six or seven days and rolled into balls about the size of a mango. Before they are used, the Jangam purifies the ball by sprinkling it with sacred water and saying texts over it. They cannot be sold by the person who gets them from the Jangam, and they cannot be passed to any one else. Virakt or unwed Jangams wear a loincloth hung from a waistband and ochre-coloured shoulder and head cloths. Laymen and married priests generally wear a somewhat scrimp waistcloth, a headscarf or a Bráhmaṇ turban. They do not colour their clothes with ochre. Husbandmen generally wear a loincloth or short trousers, a blanket, and a headscarf. Lingáyats women tie the hair in a knot at the back of the head but with less care than Bráhmaṇ women. They never use false hair or deck their hair with flowers or ornaments. Their wives and widows wear the ordinary Marátha bodice with a back and short sleeves and the ends tied in front under the bosom. The robe is like the Marátha Bráhmaṇ woman's robe except that the skirt falls like a petticoat and is seldom drawn back between the feet. Lingáyats women are also more careful than Bráhmaṇ women always to draw the upper end of the robe over the head. Like the men, women mark the brow with white cowdung ashes. Except that the women wear no head ornaments, the ornaments worn both by men and women are the same as those worn by Marátha Bráhmaṇs. On holidays Lingáyats women dress and adorn themselves richly.

Lingáyats are a quiet satisfied class wishing neither change nor power. Few are in the service of the State and almost none are messengers, constables, or soldiers. A large number of Lingáyats are weavers, several are retail dealers, and some are husbandmen. In Gadinglaj and in the Kágál State a few rich traders have large dealings with Belgaum, Dhárwár, and other Kánarese districts. A few estate-holders or *jágirdárs* and proprietors and *indmdárs* as the Desáis of Terni and Bhodgaon, are Lingáyats. Except the priests no Lingáyat lives on alms, and few are labourers. A Lingáyat rises early, marks his brow with ashes, and goes to the monastery to pay his respects to the lord or *svámi*. He works till eleven, bathes, and, sitting on a white blanket in the central hall near the Jangam shrine, worships the *ling* for about half an hour. He then dines. After dinner, over which he spends twenty to thirty minutes, he washes his hands and mouth and chews betel. If well-to-do he rests after his dinner and goes back to work. In the

<sup>1</sup> Among Kolhápur Lingáyats, according to the time when they are used, the cowdung ashes have different degrees of holiness. The ashes which Lingáyats rub without bathing are simple ashes, have no texts said over them, and can be touched by any Lingáyat. The ashes rubbed after bathing are holier, have texts said over them, and can be touched only by Lingáyats who have bathed. The ashes rubbed at the time of the *ling* worship are still holier, have many texts said over them, and can be touched only at the time of *ling* worship.

## Chapter III.

## People.

## LINGÁYATS.

evening he visits the monastery and bows to the head priest.<sup>1</sup> Priests and a few pious laymen worship the *ling* in the evening with the same details as in the morning. But the bulk of the laity simply wash their hands and feet and then wash the *ling* and eat their supper. After supper they chew betel, smoke tobacco, and talk for an hour or so and then go to bed. In theory as a fellow-wearer of the *ling* the Lingáyat woman is equal to the Lingáyat man. In practice her position in the family does not vary from the position of a woman in a Bráhmānic Hindu family. She has no voice in choosing her husband. She is married about ten and contrary to book rules must be married before she comes of age. She rises early and marks her brow both with ashes and with redpowder. The higher class women do no work except minding the house. The wives of potters and weavers help their husbands at home, and the wives of husbandmen work in the fields and sell vegetables. Elderly women go in the morning to the monastery to pay their respects to the *svāmi*. The three watchwords of the Lingáyat faith are the *ling* the *Jangam* and the *guru*. The *ling* is the stone home of the deity, the *jangam* is the human abode of the deity, and the *guru* is the teacher who breathes the sacred spell into the disciple's ear. All Lingáyats both men and women from childhood to death wear hung to a string passed round the neck a small slate-stone *ling*, a double disc with a small pea-like knob on the upper disc, hid under a betelnut-like coating of cowdung earth and marking-nut, and wound in a cloth or laid in a silver or rarely in a gold box.<sup>2</sup> A Lingáyat is very careful not to lose his *ling*. In theory a man who

<sup>1</sup> When a Lingáyat layman pays his respects to his head priest, he prostrates himself before him; and when he meets an ordinary Jangam he places both his palms on his head and the head on the Jangam's feet. Neither the head priest nor an ordinary Jangam does or says anything. When a Lingáyat layman meets another Lingáyat layman, both of them join their hands, raise them to their heads and say *Sharandṛth* probably from *sharandṛthi* that is asking refuge. When two Jangams meet they salute each other like laymen. Laywomen do not salute each other; but if she meets a Jangam woman a laywoman salutes her as a layman salutes a Jangam. Like laywomen Jangam women do not salute one another. Before he starts on a journey a Lingáyat prostrates himself before his gods and elders and his younger relations prostrate themselves before him. In a bargain a Lingáyat buyer strikes the four fingers of his right hand on the four fingers of a Lingáyat seller's right hand.

<sup>2</sup> The *lings* worn by Lingáyats are generally of a light gray slate brought from Parvatgiri in North Arkot. The *ling* which is turned on a lathe is of two discs one lower circular about an eighth of an inch thick the upper slightly elongated, each disc about three-quarters of an inch in diameter and separated by a deep groove about an eighth of an inch broad. From the centre of the upper disc, which like the lower disc is slightly rounded, rises a pea-like knob about a quarter of an inch high and three-quarters of an inch round, giving the stone *ling* a total height of nearly three quarters of an inch. This knob is called the *bān* or arrow. The upper disc is called *jālhāri* that is the water-drawer because this part of a full-sized *ling* is grooved for carrying off the water which is poured over the central knob. It is also called *pīth* that is the seat and *pīthak* the little seat. Over the stone *ling* to keep it from harm is plastered a black mixture of clay cowdung ashes and marking-nut juice. This coating, which is called *kanthi* or the cover, entirely hides the shape of the enclosed stone *ling*. It forms a smooth black slightly truncated cone, not unlike a dark betelnut, about three-quarters of an inch high and narrowing from three-quarters of an inch at the base to half an inch across the point which is cut flat and is slightly hollow. The simplest *ling* costs 1½d. (1 a.) and its usual price is 3s. (Rs. 1½). To the clay, ashes, and marking-nut juice the rich add powdered gold, silver, coral, pearls, even diamonds, raising the value of the *ling* sometimes to £5 (Rs. 50). Statistical Account of Bijāpur.

## Chapter III.

## People.

## LINGÁYATS.

loses his *ling* is degraded and cannot again become a Lingáyat. In practice if the *ling* is accidentally lost the loser has to give a caste dinner, go through the ceremony of *shuddhi*<sup>1</sup> or cleansing, and receive a new *ling* from the teacher or *guru*. Jangams or Lingáyat priests are as much respected by Lingáyats as Bráhmans are by Bráhmanic Hindus. They marry and bury Lingáyats and conduct almost all Lingáyat rites and ceremonies. The Jangam is succeeded by his son or near kinsman, or if he has no near kinsman by a disciple. The head Pontiff of the Lingáyats is the Ayya or teacher of the Chitrakaldurga monastery in north-west Maisur. He is greatly respected and when he visits Kolhápura is received with enthusiasm. The *guru* is a married Jangam and seems to be the direct descendant either by birth or by adoption, of the first head of several families. The *gotra* or stock of these families and of their *guru* or teacher is the same and the families cannot intermarry. The *guru* or teacher is required to be present at every family ceremony. If he is not present his place is taken by an ordinary *ayya* who conducts the ceremony. Besides everybody's own *ling* which is worshipped by the wearer at least once a day, in Kolhápura almost every Lingáyat household has a wooden shrine for the house gods, who are worshipped every morning by a man of the house. The shrine is placed in *májghar* or central hall close to the Jangam shrine. The house gods are small brass images generally representing Shiv's family, Shiv himself, his two wives Ganga and Párvati, his two sons Ganpati and Virbhadrá, and his bull the Nandi. The worshipper bathes, wears a silk, woollen,<sup>2</sup> or freshly-washed cotton waistcloth, marks his brow with cowdung ashes, and begins the worship. He bathes the images in a brass or copper saucer, wipes them with a piece of cloth, and sets them on their proper seats in the shrine. He marks the images with cowdung ashes, lays flowers on them, throws coloured rice on their heads, burns frankincense before them, waves a small lamp fed with clarified butter about them, and offers them sugar, milk, or molasses. He repeats different texts during the different parts of the worship. The *ling* worship is performed close to the shrine of the house gods. The worshipper bathes, puts on a sacred cloth, marks his brow with cowdung ashes, and produces a cane basket. From the cane basket he takes a white blanket which is wrapped round a number of small worship pots, a number of large and small *rudráksh* bead strings, and a bag of cowdung ashes. He sits on the white blanket, marks his brow and generally smears his whole body with ashes, and in the small pots which are shaped to hold the different articles of worship, puts flowers, red rice, and other articles. He puts the *rudráksh* bead strings round his neck, wrists, ears, and arms, and a small string round the *ling*. He worships the *ling* in the same way as he worships his house gods. After worship he folds the pots, the bead strings, and the ash-bag in the white blanket, puts them in the cane basket, and places the

<sup>1</sup> Details of *shuddhi* are given in the Bijápura Statistical Account.

<sup>2</sup> Unlike Jains and like Bráhmans Lingáyats hold that silk and woollen cloths are not made impure in touch.

## Chapter III.

## People.

## LINGÁYATS.

cane basket in the niche. Except that she says no texts a woman in worshipping her *ling* goes through all the details given above. Most Kolhápúr Lingáyats, if they happen to pass by Rám's, Vithoba's, Māruti's or a boundary god's, or Lakshmi's or a village goddess' temple, bow to the deity. Lingáyats fast on *Shivrātra* in *Māgh* in February. On *Shrāvan* or July-August Mondays they take only one evening meal. Most Kolhápúr Lingáyats go on pilgrimage to Kedārling on Jotiba's hill in Vādi-Ratnāgiri about nine miles north-west of Kolhápúr, to Nidsushi near Sankeshvar in Belgaum, to the *math* or monastery of Siddhgiri in Kadāppa about six miles south of Kolhápúr, and to Yedur in Chikodi in Belgaum. A few go to Gokarn in North Kánara and Ulvi twenty-five miles south of Supa in North Kánara. In theory the Lingáyat has no good or bad days. In practice Kolhápúr Lingáyats have a belief in good and bad luck and often consult Jangam astrologers to find a lucky day to perform a ceremony. They fast on eclipses and bathe before and after the eclipse. They openly consult astrologers and their Jangams study the same books as Bráhmans and are consulted by Lingáyats as much as Bráhman astrologers are consulted by Bráhmanic Hindus. Jangams and a few pious laymen pretend not to believe in ghosts and witchcraft, but women and ordinary people have a strong faith in witchcraft. Some Lingáyats pretend to cure diseases by saying texts or *mantras* of Shiv over the diseased part and by tying on the person of the sick a magical design or *yantra* drawn on paper with the name of the god Dattātreyā and some other letters on it. Unlike Bráhmans Lingáyats have no separate lying-in room, any suitable room in the house being used for the purpose. When a woman is in labour a Lingáyat and in her absence a Jain or a Marátha midwife is sent for. If the labour is long and trying Jangams are called to say texts. After birth the room is purified by sprinkling water in which a Jangam's foot has been washed. The birth-time is noted and a Jangam astrologer is asked to prepare a birth paper and is paid according to the means of the family. If a birth takes place at an unlucky time, the evil stars are humoured with offerings. On the fifth day after the birth of a child a Jangam comes, repeats verses, takes a *ling*, winds it in a piece of silk cloth, and ties it round the child's neck or its upper right arm. The *ling* is soon after taken off and tied to the child's cradle. In the evening women neighbours come and perform rites in honour of Mother Sixth or Sati to keep off evil spirits. Sati is represented by a sickle with a bodicecloth wound round it. Near the goddess are laid a cocoanut, and a piece of blank paper, a pen, and an inkstand to write the destiny of the child. The paper pen and ink are kept there during the night. On the twelfth the child is laid in the cradle and named. Unlike Bráhmans, among whom the name is generally fixed by an astrologer Lingáyats themselves fix the name of the child. It is generally chosen by the parents or by some elder of the family and is given by women neighbours who come to witness the ceremony. The women fill the mother's lap with wheat, betelnuts, a cocoanut, dry dates, and a bodicecloth; and the women are given betel and turmeric and vermilion paste to rub on their cheeks and mark their brows. Among priestly

Lingáyats when a boy is between seven and nine years old the initiation or *aitan*,<sup>1</sup> literally priest's state from the Kánarese *ayya* priest and *tan* state, is performed. A Jangam astrologer is asked to choose a lucky day. The *guru* or teacher comes early in the morning of the day fixed, a square is made with a waterpot in the centre and one in each corner, each standing on a small heap of rice. White thread is passed round the necks of the pots. The boy's head is shaved, and he is bathed and seated on a small wooden stool in front of the pot square. The teacher repeats several texts, whispers into the boy's ear, and makes him recite a short hymn. During the ceremony the pipe and drum are played and at the close a feast is given and alms are distributed. After his initiation the boy is a priest and may not eat food without bathing and performing regular *ling* worship. *Diksha* which means purification, may be undergone by any class of Lingáyats except Jangams. A *diksha* raises a Pancham to be a Lokvant, a Lokvant to be a Shilvant, and a Shilvant to be a Jangam. By performing *diksha* girls of the Pancham, Lokvant, and Shilvant classes may marry into the classes above them. Many Lingáyat men and women perform *diksha* before marriage or at any time before death to cleanse them from sin. As in *aitan* so in *diksha* the day is fixed by a Jangam astrologer, and except that *diksha* texts are different from *aitan* texts, the ceremony differs little from *aitan*. Five metal jars are set on the ground four of them one at each corner of a square and the fifth in the centre each on a small heap of rice. A white thread is wound round the necks of the pots and betel and leaves and vermillion are set in their mouths. The man or the woman on whose account the ceremony is performed is bathed and made to sit on a woollen carpet in front of the pot square. The Jangam recites verses and all present throw grains of rice mixed with vermillion over the person's head. The ceremony ends with a feast and the distribution of alms.

Girls are married before they come of age. When the parents of the boy and girl agree to marry their children, the marriage day is fixed by a Jangam astrologer and marriage booths are raised in front of the boy's and girl's houses. The first pole of the booth is driven in at a lucky moment. A marriage ceremony generally lasts for four days. On the first day comes the *videghálne* or betel-serving in token that the marriage settlement is made and is binding. The bride is decked with ornaments, and in the presence of Jangams and other respectable members of the caste is given pieces of sugarcandy. On the second day come the Ganpati worship, the turmeric-rubbing, and the *gugul* or bdellium gum ceremony in honour of Virbhadrá. In the gum ceremony, which either the bride or bridegroom and their mothers must attend, two white-washed earthen jars, in form and size like those in which women fetch water, are cut in two a little below the middle where they are widest. The upper halves are turned upside down standing on their mouths and into the upper half the lower half is dropped so

## Chapter III.

## People.

## LINGÁYATS.

<sup>1</sup> Full details are given in the Bijápur Statistical Account.

## Chapter III.

## People.

## LINGÁYATS.

that the open side is upward. The wide-mouthed vessels thus prepared are filled with ashes. The ashes in the middle of each pot are damped and a stick about six inches long is fixed and wrapped round with a piece of cloth like a small torch. The two torches are lighted and the redpowders *gulál* and *kunku*, sandal-paste or *gandh*, and flower wreaths are thrown over them. Two Jangams or priests or two kinsmen dancing as they go carry the pots either in their hands or on their heads in procession, with pipes and drums, to a river or well outside of the village. When the pots are placed on the ground near the river or well, the head of the family washes the feet of the *svámi* or monastery head who goes with the procession, puts flowers on his feet, gives him a cocoanut and money, and prostrates himself before him. After the *svámi* worship the torches are put out and the pots are broken. Betel is served to all present and money is given to the priests or Jangams. The party go home silently without music. The gum or *gugul* ceremony was formerly performed only when a vow was made to Virbhadrá, but in most Lingáyat families it has become a regular part of the marriage ceremony. It is also performed by several Marátha and by a few Bráhma families,<sup>1</sup> with the same details, except that in Marátha and Bráhma *gugul* processions the pots are borne by kinsmen and no *svámi* is worshipped. On the third day comes the *devak* or marriage guardian ceremony. All Lingáyat families have the same *devak*. It is a winnowing bamboo basket containing rice, turmeric, betel leaves and nuts, and a closed earthen pot whose lid is tied on with cotton thread. The pot contains water and a few copper coins. Sometimes the *devak* ceremony takes place a day or two before the marriage. After the guardian is in his place the bridegroom is bathed and his brow is marked with ashes. He is dressed in rich clothes and a marriage coronet of *bhend* or water hemp is tied on his brow. An hour or two before the marriage which is generally in the evening, the bridegroom starts in procession with music for the bride's. In a Lingáyat marriage no water-clock is set to note the exact time, and the proper time is guessed by one of the elders. At the bride's, the bride and bridegroom sit side by side on ordinary low wooden stools set in the centre of a square of metal pots like the square made for the purification or *diksha*. The bride is dressed in a simple white robe and her brow is decked with a *bhend* or water-hemp marriage coronet. The hems of the garments of the pair are tied together. The *ayya* hands rice mixed with vermilion to the guests, and recites verses. The guests throw the red rice on the pair's heads

<sup>1</sup> This *gugul* is interesting from the early character of its details. It seems to be an old spirit-scaring practice handed down from times before the higher ideas of Lingáyatism or Bráhmaism. The idea seems to be to collect evil influences in the torch and make it a scape-torch like the Jewish or early Hindu scapegoat or buffalo and carry the evil spirits beyond the village limits and leave them there. The device of asking the *svámi*'s blessing and paying him a fee seems to have saved the old practice from perishing. The service is said to be in honour of Virbhadrá an early spirit of the Kánárese country who has been identified with Shiv's son. The root of the fear of Virbhadrá seems to be the fear of the *Virs* who are chiefly the angry ghosts of the unwed dead.



as long as the *ayya* recites verses. All this time music is played and muskets are fired. At the close of the recitation the lucky black glass bead string is tied round the bride's neck, the wedded pair are taken to bow to the house-gods, and the knot of their garments is loosened. On the fourth night the bridegroom goes to a *math* or monastery with his wife in a great procession both riding on the back of a bullock, or of late, though the change is a grief to the old and strict, on horseback. At the *math* or monastery the pair lay a cocoanut before the *svāmi* or head priest and prostrate themselves before him. From the *math* the procession goes to the bridegroom's house, where the ceremony ends with a feast and the distribution of alms. On the way they break coconuts at places supposed to be haunted by evil spirits and throw the spirits pieces of cocoanut. In a wealthy family a boy's marriage costs about £200 (Rs. 2000). Of this £100 (Rs. 1000) go in ornaments for the bride, £30 (Rs. 300) in clothing, £30 (Rs. 300) in charity, and £40 (Rs. 400) in food and other charges. In a middle class family a boy's marriage costs about £40 (Rs. 400) of which £20 (Rs. 200) go in ornaments, £10 (Rs. 100) in clothing, £2 10s. (Rs. 25) in charity, and £7 10s. (Rs. 75) in food and other things. In a poor family a boy's marriage costs about £20 (Rs. 200), of which £5 (Rs. 50) go in ornaments, £7 10s. (Rs. 75) in clothing, £1 (Rs. 10) in charity, and £6 10s. (Rs. 65) in food and other charges. A girl's marriage costs less than a boy's, the total varying from £2 10s. to £30 (Rs. 25-300). The charges include a dowry of £2 10s. to £5 (Rs. 25-50), a suit of clothes, and a necklace and ring to the bridegroom, robes and bodices for the bridegroom's mother and other kinswomen, and turbans for his father and brothers.

Widow marriage is forbidden among Jangams, Shilvants, and Lokvants. Panchams occasionally marry widows. Barbers, oilmen, potters, washermen, and Mhārs allow and practise widow marriage. Unlike the high class Brāhmanic widow the Lingāyat widow may use a robe of any colour, continues to wear the bodice, is not shaven, and may wear ornaments except the nose-ring, the lucky neck-thread, and toe-rings. Still a widow is held unlucky and is not asked to marriage and other festive ceremonies.

When a Lingāyat is on the point of death he is advised to distribute money in charity and present a Jangam with a cow. His body is covered with sacred ashes. If he is well-to-do, the dying man performs the *vibhutiville* or ashes and betel-giving at a cost of £2 to £2 10s. (Rs. 20-25). This rite is believed to cleanse the sin of the performer and is generally performed by old men and women. If a performer survives the rite he or she has to leave his or her house and pass the rest of their lives in a *math* or monastery. Jangams are not required to undergo this rite as they are considered holy and not to need purifying. Sometimes a Jangam is asked to recite verses. A few minutes before death the dying person is laid on a white blanket and a little holy water is put into the mouth. After death the ornaments, if there are any, are removed from the body, and the body washed in cold water in an open space near the house, and is clad in full dress. The body is

## Chapter III.

## People.

## LINGĀYATS.

## Chapter III.

## People.

## LINGAYATS.

laid crosslegged slightly leaning against a wall for two to eight hours, or even longer if the dead is an old and influential person. During this time kinsmen and kinswomen sit near and bewail the dead. If the dead is a Jangam or an old man or woman Jangams are asked to recite verses, and the recitation is accompanied with music. If the dead has a wife, his wife's lucky thread, glass bangles, and toe-rings are taken off her body and laid in the canopied chair specially prepared for the occasion. Plantain stems are tied to the upright poles of the chair, the leaves are fastened together into arches, and the whole chair is decorated with flower wreaths. The dead body is seated crosslegged in the chair, and the chair is borne by four friends or kinsmen. No fire is taken with the procession, and no women go with it. If the family is well-to-do, musicians play before the body; and music is always employed when a Jangam dies. As the body is borne to the grave the men in the procession cry out Shiv Shiv, or Har Har, and at intervals betel-leaves and copper coins are thrown on the road. Meanwhile the grave is being dug by labourers of any caste. The grave is  $4\frac{1}{2}$  feet long  $2\frac{3}{4}$  feet wide and three feet deep. In the east side of the grave a niche large enough to hold the dead body is cut, and the inside of the grave is cowdunged and purified with *pádodak* that is water in which a Jangam's feet have been washed. On the outside of the grave, at each corner is set an earthen *ling* with an earthen bull in front of each *ling*. The dead is lowered into the grave by his friends and kinsmen, and laid in the niche facing west. The *ling* is taken out of its case, which is kept by the heirs, and laid in the body's left hand. The priest washes the *ling*, rubs ashes, and lays *bel* leaves on it. He hands *bel* leaves to all present, and drops some on the head of the dead and all drop their leaves after him. If the dead is a *svámi* or head priest a note signed by his successor asking that the doors of heaven may be opened to let the dead into the presence of Shiv is tied round the neck. The grave is filled with salt and ashes till the body is covered, and then with earth, and over the earth one or two slabs of stone are laid. The priest stands on the stone and the mourners wash his feet, lay flowers and *bel* leaves on them, and give him money. Money is also given to beggars. When there is music the music goes on till after the priest's feet are worshipped. The whole party go to a river or well, bathe, and return in wet clothes to the house of mourning, where each of them sips a little *karuna* literally grace, which is of higher efficacy than *pádodak* or foot-water and over which a larger number of texts have been repeated. Jangams are fed and alms are given to the poor. On the first and sometimes on the fifth the old clothes of the dead are given to priests and poor men. To the *svámi* are given a cow, a pair of shoes, an umbrella, and pots. On the third, fifth, or seventh day after death Jangams and the near kinsmen of the dead are asked to dinner, and after this the family are considered pure, and strangers may take food in the house. No monthly or yearly mind-rites are performed in honour of the dead. If the family is well-to-do, a tomb is built with a masonry *ling* and *nandi* or bull on it, and the *ling* and the bull are worshipped daily by some

member of the family. Lingáyats are bound together by a strong fellow-feeling. Social disputes are referred to the *svámi* or monastery head whose decision is generally accepted. An appeal lies to the head of the Kadáppa *math* or monastery on a hill six miles south of Kolhápur, who is the head Jangam of the province. Kolhápur Lingáyats have not begun to make much use of State schools, the total number of Lingáyat boys in the Kolhápur schools in March 1883 was 1478. Girls are seldom sent to school. The Lingáyat faith seems to keep its hold on the minds and affections of the people. They may have to be a little more careful than formerly in the punishments they inflict for caste rules, and with this exception the influence of the priests shows no sign of declining.

**Jains** are returned as numbering 46,732 or 6·02 per cent of the Hindu population and as found over the whole State. They take their name from being followers of the twenty-four Jins or conquerors the last two of whom were Párasnáth and Mahávir who was also called Vardhmán. Párasnáth or Párshavanáth literally the *náth* or lord who comes next to the last Jin Vardhmán is said to have been the son of king Ashvasen by his wife Váma or Báma Devi of the race of Ikshváku. He is said to have been born at Benares, to have married Prabhávatí the daughter of king Prasén Jit, to have adopted an ascetic life at the age of thirty, and to have practised austerities for eighty days when he gained perfect wisdom. Once while engaged in devotion his enemy Kamath caused a great rain to fall on him. But the serpent Dharanidhar or the Nág king Dharan shaded Párasnáth's head with his hood spread like an umbrella or *chhatra*, whence the place was called Ahichhatra or the snake umbrella.<sup>1</sup> Párasnáth is said to have worn only one garment. He had a number of followers of both sexes, and died performing a fast at the age of 100 on the top of Samet Shikhar in Hazáribágh in West Bengal. His death occurred 250 years before that of the last or twenty-fourth Jin Mahávir. Mahávir or Vardhmán, who was also of the Ikshváku race, is said to have been the son of Siddhárth prince of Pavan by Trisala and to have been born at Chitrakut or Kundgrám perhaps the modern Chitarkot a great place of pilgrimage seventy-one miles west of Allahabad. He is said to have married Yashoda the daughter of prince Samarvir, and to have by her a daughter named Priyadarshana, who became the wife of Jamáli, a nephew of Mahávir's and one of his pupils who founded a separate sect. Mahávir's father and mother died when he was twenty-eight, and two years later he devoted himself to austerities which he continued for twelve and a half years, nearly eleven of which were spent in fasts. As a Digambar or sky-clad ascetic he went robeless and had no vessel but his hand. At last the bonds of action were snapped like an old rope and he gained *keval* or absolute unity of spirit and became an Arhat that is worthy or Jin that is conqueror. He went to Pápauri or Apápuri in Behár and taught his doctrine. Of several eminent Bráhmans who became converts and founded schools or *ganas*, the chief was Indrabhuti or Gautam,

## Chapter III.

## People.

## LINGÁYATS.

## JAINS.

<sup>1</sup> General Cunningham has identified the ancient Ahichhatra with the present Rámnagar in Rohilkhand in Upper India. Cunningham's Ancient Geography, I. 359.

Chapter III.  
People.  
JAINS.

who preached his doctrines at the cities of Kaushāmbi and Rājgrih and died at the age of seventy-two at Apāpuri in South Behār between B.C. 663 and 526.<sup>1</sup>

Like the Buddhists, the Jains reject the Veds which they pronounce apocryphal and corrupt and to which they oppose their own scriptures or Angas. As among Buddhists confession is practised among Jains. Great importance is attached to pilgrimage and four months or the *chāturmās* that is four months from the eleventh of *Āshādh* or July-August to the eleventh of *Kārtik* or October-November in the year are given to fasting, the reading of sacred books, and meditation. They attach no religious importance to caste. Jains like Buddhists are of two classes *yatis* or ascetics and *shrāvaks* or hearers. Jains like Buddhists admit no creator. According to them the world is eternal and they deny that any being can have been always perfect; the Jin became perfect but he was not perfect at first. Both Buddhists and Jains worship though under different names twenty-four lords each with his sign and his attendant goddess or *shāsana devi* :

*Jain Saints.*<sup>2</sup>

NAME.	SIGN.	Shāsandevis OR ATTENDANT GODDESS.	NAME.	SIGN.	Shāsandevis OR ATTENDANT GODDESS.
Rishabh or A'dināth.	Bull ...	Chakreshvari.	Vimalnāth ...	Boar ...	Vidita.
Ajītnāth ...	Elephant ...	Ajitbala.	Anantnāth ...	Falcon ...	Ankusha.
Shāmbhav ...	Horse ...	Duritāri.	Dharmanāth ...	Thunderbolt ...	Kandarpa.
Abhinandan ...	Monkey ...	Kālīka.	Shāntināth ...	Antelope ...	Nirvāni.
Sumati ...	Curlew ...	Mahākālī.	Kunthunāth ...	Goat ...	Bala.
Padmaprabh ...	Lotus ...	Shyāma.	Arnāth ...	<i>Nandyāvart</i> or pleasing jewel.	Dhāriṇi.
Supārshv ...	Lucky Cross or <i>Svastik</i> .	Shānta.	Mallināth ...	Water Jar ...	Dharanpriya.
Chandraprabh ...	Moon ...	Bhrikuti.	Muni Suvrat ...	Tortoise ...	Naradatta.
Pushpadant ...	Crocodile ...	Sutāraka.	Nimināth ...	Blue Water Lily.	Gāndhāri.
Shital ...	Cruciform Symbol or <i>Shrivats</i> .	Ashoka.	Nemināth ...	Conch Shell ...	Ambika.
Shreyānsh ...	Rhinoceros ...	Mānavi.	Pārshvnāth ...	Cobra ...	Padmāvati.
Vāsupujya ...	Buffalo ...	Chanda.	Vardhmān or Mahāvīr.	Lion ...	Siddhayika.

On the whole Jainism is less opposed to Brāhmanism than Buddhism is, and admits some of the Brāhman deities, though it holds them inferior to their *chovishi* or twenty-four saints. Jainism, of which there are traces in South India as early as the second century before Christ and to which the great stone figure of Gomateshvar at Shrāvan Belgola in Maisur is believed to belong, was a ruling religion in the Deccan at least as early as the fourth or fifth century. Kolhāpur seems to have been a Jain settlement before the time of the Silahāras. It is once called Padmālaya or the abode of Padma the Jain name for Lakshmi apparently from the temple of Mahālakshmi which has since been used by Brāhmins. During the time of the Silahāras (1050 - 1210) Jainism was the prevailing religion in Kolhāpur and the country round.<sup>3</sup> It gradually gave way to Shankarāchārya the founder of the Smārts, Rāmānuj the great Vaishnav (A.D. 1130), and Basav the first of the Lingāyats (1150-1168).

<sup>1</sup> Rice's Mysore and Coorg, I. 374, 375.

<sup>2</sup> Rice's Mysore and Coorg, I. 374.

<sup>3</sup> Fleet's Kānarese Dynasties pp. 102-103.

Jains name their children after the *arhats* or worthies of the present past and future ages, after the parents of the *arhats*, after the pious and great men, and after Bráhmānic gods and local deities. Like Bráhmānic Hindus Jain parents sometimes give their children mean names to avert early death as Kalláppa from *kallu* (K.) stone, Kadáppa from *kad* (K.) forest, Dhondu from *dhonda* (M.) and Dagadu from *dagad* (M.) stone.

Kolhápura Jains are divided into Upádhyás or priests, Panchams or traders, Chatúrthas or husbandmen, Kásárs or coppersmiths, and Shetváls or cloth-sellers. These classes eat together but do not intermarry. Formerly the sect included barbers, washermen, and many other castes who have ceased to be Jains. Properly speaking there is no separate priestly caste among the Jains, the Upádhyás or priests are usually chosen from among the learned Panchams or Chatúrthas subject to the recognition of their principal *svámis* or head priests called Pattáchárya Svámis.

The men are dark, middle sized, strong, and well built, and the women slender, fair, and graceful. They speak Kánarese at home and Maráthi abroad, which they call Áre Mátu or the language of the Áres. In their Kánarese the last syllable is always very indistinct. The sacred literature of the Jains is in a dialect of Sanskrit called Mágadhi. They keep cattle, but are not allowed to have pet birds in cages. Jains are strict vegetarians and do not use animal food on pain of loss of caste. Every Jain filters the water he uses in drinking or cooking for fear of killing insect life. He also takes his food before sunset in case of destroying any animal life by eating in the dark. No Jain tastes honey or drinks liquor, and monks and religious Jains abstain from fresh vegetables. The men wear the waistcloth, jacket, coat, shouldercloth, and the Kánarese headscarf. The women wear the hair in a knot at the back of the head, and dress in the full Maráthi robe with or without passing the skirt back between the feet, and a bodice with a back and short sleeves. Young widows may dress in the robe and bodice and their hair is not shaven. Old widows generally dress in white and never put on bodices. As a class Jains are orderly and law-abiding and seldom appear in criminal courts. In spite of political changes many Jains are hereditary village and district officers. Strict Jains object to tillage because of the loss of life which it cannot help causing. Still they do not carry their objection to the length of refusing to dine with Jain husbandmen. Among Kolhápura Jains the husbandmen are the largest and most important class with a head priest of their own who lives at Nándni about eighteen miles east of Kolhápura. Except some of the larger landholders who keep farm servants, the Jain landholders, with the help of their women do all parts of field work with their own hands. They are the hardest working husbandmen in the State, making use of every advantage of soil and situation. In large towns like Kolhápura and Miraj Jains are merchants, traders, and shopkeepers dealing chiefly in jewelry, cotton, cloth, and grain. Most Kásárs deal in bangles or work as coppersmiths, and others weave and press oil. Some Jains live by begging, but any one who

### Chapter III.

#### People.

#### JAINS.

## Chapter III.

## People.

## JAINS.

asks alms from a man who is not a Jain is put out of caste. To every Jain temple one or more priests or *Upādhyās* are attached. They belong to the Chaturth or the Pancham division and are supported by the Jain community, taking the food offerings, cloth, and money presents which are made to the gods and goddesses. Besides temple priests every village which has a considerable number of Jains has an hereditary village priest called *grāmopādhyā* who conducts their ceremonies and is paid either in cash or in grain. These village priests, who are married and in whose families the office of priest is hereditary, are under a high priest called *dharmādhikāri* or religious head a celibate or ascetic by whom they are appointed and who has power to turn out any priest who breaks religious rules or caste customs. The village priest keeps a register of all marriages and thread-girdings in the village, and the high priest whose head-quarters are at Nāndni about eighteen miles east of Kolhápur and whose authority extends over all Kolhápur Jains, makes a yearly circuit gathering contributions, or sends an agent to collect subscriptions from the persons named in the village priests' lists. The office of high priest is elective. The high priest chooses his successor from among his favourite disciples.

As a class the Kolhápur Jains are backward in education and few are in the service of the State. Still their diligence and orderliness make them a prosperous and important class. In the early morning before he gets up a Jain rests his right shoulder on the ground. He then sits facing the east and repeats verses in praise of Jindev the victorious. He leaves his seat and sets out for the temple to see the image of Párasnāth, on his way as far as possible avoiding the sight of man or beast. On his return from the temple he retires, cleanses himself with earth, and washes his hands feet and face. After washing he bathes in warm water which he first purifies by repeating verses over it. When his bath is finished he puts on a freshly washed cotton cloth, sits on a low wooden stool, and for about an hour says his morning prayer or *sandhya*. He lays sandal flowers and sweetmeat before the house gods and then goes to the temple to worship Párasnāth, where the head ascetic or *svāmi* reads the Jain Purán, tells his beads, sips a little of the holy water or *tirth* in which the image has been bathed, and returns home. He washes his hands and feet, performs a fire worship, and feeds the fire with cooked rice and clarified butter in the name of all the Vedic gods or *Vishvedevs*. He usually dines between eleven and one. If a stranger happens to visit the house at dinner time, he is welcomed and asked to dine. If the guest belongs to the same class as the houseowner they sit in the same row and eat like local Bráhmans. After dinner he chews betel, and then either goes to his business, or takes a midday rest and reads his holy books. As a rule he sups an hour at least before sunset, repeats his evening prayer, visits the temple and hears a Purán, returns about nine and goes to bed. Women as soon as they rise, go to the temple to have a sight of Párasnāth, return home and mind the house sweeping and cowdunging the kitchen and dining place. They then bathe, dress in a freshly washed cotton robe and bodice, rub their brows and cheeks with



vermilion and turmeric, again visit the temple, bow before the god, and sip and throw over the head water which has been used in bathing the god. On returning home, they fetch water and wash clothes, cook, and after serving the men with food, take their dinner. After dinner they grind corn and do other house work, prepare supper, sup after the men before sunset, visit the Jain temple, listen to a Purán, return home, and retire for the night. As a rule young women neither go so often to the temple nor stay there so long as elderly women.

The religion of the Kolhápúr Jains may be treated under five heads: the temple worship of the twenty-four saints and their attendant goddesses; holy places and holy days; the worship of house gods; the worship of field guardians; and the irregular worship of evil disease-causing spirits. The chief Jain doctrine is that to take life is sin. Like Buddhists they believe that certain conduct has raised men above the gods. Twenty-four saints have gained perfection. To each of these a sign and an attendant goddess have been allotted and these form the regular objects of Jain temple worship. The Jains belong to two main sects the *shvetámbar*s or white-robed and *digambar*s or sky-clad that is the naked saint worshippers. The bulk of the Kolhápúr Jains are Digambar. Temple worship is the chief part of the Jain's religious duties. Their temples are called *bastis* or dwellings, but can easily be known from ordinary dwellings by their high plinths. The temple consists of an outer hall and a shrine. The walls of the outer hall are filled with niches of the different Bráhmanic deities and attendant goddesses. In the shrine is an image generally of the twenty-third saint Párasnáth, which in Kolhápúr temples is generally naked. The images in most cases are of black polished stone two feet to three feet high either standing with the hands stretched down the sides, or in the seated cross-legged position. Temple worship is of four kinds, daily worship, eight-day or *ashtánhiki* worship, wish-filling or *kalp* worship, and the five-blessing or *panch kalyáni* worship. In the daily temple worship the image of the saint is bathed by the temple ministrant in milk and on special days in the five nectars or *panchámrits* water, tree sap or *vriksh ras* that is sugar, plantains, clarified butter, milk and curds. The priest repeats sacred verses, sandal paste is laid on the image, and it is decked with flowers.

Jains perform the *ashtánhiki* or eight-day worship three times in a year from the bright eighth to the full-moon of *Shrávan* or July-August, in *Kártik* or October-November, and in *Phálgun* or February-March. Only the rich perform the wish-filling or *kalp* worship as the worshipper has to give the priest whatever he asks. Except the goat-killing the five-blessing or *panchkalyáni* worship is the same as the Bráhmanical sacrifice. According to the Jain doctrine bathing in holy places does not cleanse from sin. Kolhápúr Jains make pilgrimages to Jain holy places, Uru Jayantgiri or Girnár in South Káthiávár sacred to Nemishvar or Nemináth, Pavápur near Rájagriha or Rájgir about fifty miles south of Patna sacred to Vardhmán Svámi, Sammedhgiri properly Samet Shikhar or Párasnáth hill in Hazáribágh in West Bengal sacred to Párasnáth where are feet symbols or *pádúkás* of the twenty-four Jain *arhats* or

## Chapter III.

## People.

## JAINS.

Chapter III.  
People.  
JAINS.

worthies, and in the south, the stone figure of Gomateshvar in Shrāvan Belgola in Maisur, and Mudbidri in South Kánara. They make pilgrimages to Benares which they say is the birthplace of Párasnāth who was the son of Vishveshvar the chief Bráhmaṇ deity of the place. The leading religious seats of the Jains are Delhi, Dinkānchi in Madras, Vingundi in South Kánara, and Kolhāpur. Any poor Jain may visit these places and is fed for any number of days, but on pain of loss of caste he must beg from no one who is not a Jain.

Jain ascetics keep ten fasts in every lunar month, the fourths, the eighths, the elevenths, the fourteenth, and the full-moon and no-moon. They keep all Bráhmaṇic holidays and in addition the week beginning from the lunar eighth of *Āshādh* or June-July, of *Kārtik* or October-November, and of *Phālgun* or February-March, and they hold a special feast on *Shrut Panchmi* or Learning's Fifth on the bright fifth of *Jyeshth* or May-June. Of the twenty-four minor goddesses who attend on the twenty-four saints the chief are Kālika or Jvālāmālīni and Padmāvati who probably are the same as the two popular Bráhmaṇ goddesses Bhavāni and Lakshmi.

Besides in the twenty-four attendant goddesses Jains believe in all Bráhmaṇic deities placing them below their saints or *tirthankars*. They pay special respect to the Bráhmaṇ goddess Sarasvati who is represented by a sacred book resting on a brazen chair called *shrut skandh* or learning's prop and in whose honour in all Jain temples a festival is held on the bright fifth of *Jyeshth* or May-June. To these guardian goddesses and saints two beings are added Bhujval or Goval of Shrāvan Belgola in Maisur distinguished by the creepers twining round his arms and Nandishrami a small temple like a brass frame. Besides these they worship a brass wheel of law or *dharm-chakra* which is said to represent five classes of great deities or *Parameshthis* a verbal salutation to the whole of whom forms the Jain's daily prayer. The Jains think their book and temple gods the *arhats* or worthies, the *siddhs* or perfect beings, the *āchāryas* or godfathers, the *upādhyās* or priests, and the *sādhus* or saints are too austere and ascetic to take an interest in every-day life or to be worshipped as house guardians. For this reason their house deities are either Bráhmaṇic or Lingāyat gods.

As among Bráhmaṇic Hindus the house deities are kept in a separate room generally next to the cooking room in a *devāra* or shrine of carved wood. The images are generally of metal three to four inches high. Among the images is not unusually the mask or bust of some deceased female member of the family who has afflicted the family with sickness and to please her had her image placed and worshipped among the house gods.<sup>1</sup> Besides the usual Bráhmaṇic or Lingāyat house deities several families have a house image of Párasnāth but the worship of Párasnāth as a house image is not usual. As among Bráhmaṇic Hindus the daily worship of the house gods is simple chiefly consisting in a hurried decking with flowers. On holidays the images are bathed in milk, and flowers,

<sup>1</sup> Details are given below under Jakhin.

## Chapter III.

## People.

## JAINS.

sandal-paste, rice, burnt frankincense, and camphor and cooked food are laid before them. Women are not allowed to touch the house gods. During the absence of the men of the house the temple priest is asked to conduct the daily worship. Another class of Jain deities are the *kshetrapáls* or field guardians the chief of whom are Bhairav and Brahma. In theory Jains do not believe in spirits. The learned are particularly careful to disavow a belief in spirits and even ordinary Jains dislike to admit the existence of such a belief. Still enquiry shows that a belief in spirits is little less general than among the corresponding Bráhmanic classes. They believe in spirit-possession and call their family spirits *pitrád* or fathers. Though they profess not to believe that infants are attacked by spirits they perform the ceremonies observed by Bráhmanic Hindus in honour of Mothers Fifth and Sixth which seem to form a part of the early rites on which the customs of all Hindu sects are based. Besides the spirit attacks to which children are specially liable on the fifth and sixth days after birth, Jain children are liable to child-seizures or *bál grahas* probably a form of convulsions which Jain women say is the work of spirits. Educated and religious Jains who object to the early or direct form of spirit action believe in the more refined *drisht* or evil eye as a cause of sickness. According to the popular Jain belief all eyes have not the blasting power of the evil eye. Care must be taken in cutting the child's navel for if any of the blood enters its eyes their glance is sure to have a blasting or evil power. Unlike most Bráhmanic Hindus, Jains do not believe that a woman in her monthly sickness is specially liable to spirit attacks. In their opinion a woman runs most risk of being possessed when she has just bathed and her colour is heightened by turmeric, when her hair is loose, and when she is gaily dressed, and happens to go to a lonely well or river bank at noon or sunset. Boys also are apt to be possessed when they are well dressed or fine-looking or when they are unusually sharp and clever. Jains profess not to hold the ordinary Bráhmanic belief that the first wife comes back and plagues the second wife. Still they hold in great terror Jakhins that is the ghosts of women who die with unfulfilled wishes. Among Jains as among other Hindus, Jakhins plague the living by attacking children with lingering diseases. When a child is wasting away Jain parents make the Jakhin a vow that if the child recovers the Jakhin's image shall be placed with their family gods. If the child begins to recover as soon as the vow is made the house people buy a silver or gold mask or *ták* of Jakhin, lay sandal-paste and flowers on and sweet-meats before it, and set it in the god room with the other house gods. Five married women, who are asked to dine at the house are presented each with turmeric, vermilion, betel, and wet gram, and a special offering or *váyan* consisting of five wheat cakes stuffed with sugar clarified butter and molasses is made in the name of the dead woman who is believed to have turned Jakhin and possessed the child. The women and men guests dine with the family and take the special offering or *váyan* home. The image is daily worshipped with the house gods with great reverence as it generally represents the mother or some near relation of the worshipper. This Jakhin worship is common among Jains. Jains have no professional exorcists or

## Chapter III.

## People.

## JAINS.

charmners chiefly because their place is filled by the Jain priests. When sickness is believed to be caused by spirit-possession the priest is consulted. He worships the goddess Padmavati or Lakshmi and gives the sick holy water or *tirth* in which the goddess' feet have been washed. If the holy water fails to cure, the priest consults his book of omens or *shakunvanti*, adds together certain figures in the book and divides the total by a certain figure in the tables of the book, and by referring to the book finds what dead relation of the sick person the quotient stands for. If it is a woman she has become a Jakhin and should be worshipped along with the family gods. The priest then mutters a verse over a pinch of frankincense ashes or *angúra* burnt before the gods and hands it to the sick to be rubbed on his brow. If the ash-rubbing and the Jakhin worship fail to cure the sick, the priest prepares a paper or *bhoj* or birch leaf called a *yantra* or device marked with mystic figures or letters and ties it in a silk cloth or puts it in a small casket or *táit*, mutters verses over it, burns frankincense, and ties it round the possessed person's arm or neck. If the amulet is of no avail the priest advises an *anuskhán* or god-pleasing. The head of the house asks the priest to read a sacred book before the temple image of one of the saints or to repeat a text or *mantra* or a sacred hymn or *stotra* some thousand times in honour of one of the saints. The priest is paid for his trouble, and when the sick is cured the god-pleasing ends with a feast to priests and friends. If even the god-pleasing fails, the sick, if he is an orthodox and particular Jain, resigns himself to his fate or seeks the aid of a physician. Unlike the men Jain women are not satisfied without consulting exorcists and trying their cures. Exorcists are shunned by men Jains because part of the exorcists' cure is almost always the offering of a goat or of a cock. A Jain man will seldom agree to such a breach of the chief law of his faith, but Jain women secretly go to the exorcists and do as they are advised. When all remedies are of no avail Jains sometimes take the sick to a holy place called Tavnidhi fifteen miles south-west of Chikodi, and the sick or some relation on his behalf worships the spirit-scaring Brahmanidhi until the patient is cured. The Jains profess to have no sacred pools, animals, or trees that have a spirit-scaring power. When an epidemic rages a special worship of Jindev is performed.

Of the sixteen sacraments or *sanskárs* which are nearly the same as the sixteen Bráhmaṇ sacraments, Kolhápur Jains perform thread-girding, marriage, puberty, and death. Except that the texts are not Vedic the rites do not differ from those performed by Bráhmans. Their birth ceremonies are the same as those of Bráhmans like whom on the fifth day they worship the goddess Satvái. Boys are girt with the sacred thread between eight and sixteen. A boy must not be girt until he is eight. If, for any reason, it suits the parents to hold the thread-girding before the boy is eight, they add to his age the nine months he passed in the womb. A Jain astrologer names a lucky day for the thread-girding, a booth is raised before the house, and an earth altar or *bahule* a foot and a half square is built in the booth and plantain trees are set at its corners. Pots are brought from the potter's and piled in each corner of the altar and

Chapter III.  
People.  
JAINS.

a yellow cotton thread is passed round their necks. Over the altar is a canopy and in front is a small entrance hung with evergreens. Invitation cards are sent to distant friends and kinsfolk. A day or two before the thread-girding the invitation procession consisting of men and women of the boy's house with music and friends starts from the boy's. They first go to the Jain temple and the father or some other relation with the family priest lays a cocoanut before the god, bows before him, and asks him to the ceremony. They visit the houses of their friends and relations and ask them to attend the ceremony. The Jains have no *devak* or family guardian worship. The boy and his parents go through the preliminary ceremonies as at a Bráhmañ thread-girding. The boy's head is shaved and he is bathed and rubbed with turmeric. The astrologer marks the lucky moment by means of his water-clock or *ghatka* and as it draws near music plays and guns are fired. The priest repeats the lucky verses and throws red rice over the boy. The boy is seated on his father's or if the father is dead on some other kinsman's knee on a low stool. The knot of his hair is tied and he is girt with a sacred thread or *jánve* and a string of *kush* grass is tied round his waist. The priest kindles the sacred fire, betel is served to the guests, and money gifts are distributed among priests and beggars. The boy has to go and beg at five Jain houses. He stands at the door of each house and asks the mistress of the house to give him alms saying Oh lady be pleased to give alms.<sup>1</sup> The alms usually consists of a waistcloth, rice, or cash. Great merit is gained by giving alms to a newly girded boy, and many women visit the boy's house for three or four days to present him with silver or clothes. After begging at five houses the boy returns home and a feast to friends and kinsfolk ends the first day. The *sodmunj* or grass-cord loosening is performed usually after a week and sometimes between a week from the thread-girding and the marriage day. The loosening is generally performed near a *pimpal* *Ficus religiosa* tree. The boy is bathed, the rite of holiday calling or *punyáhaváchan* is gone through as on the first day, music plays, and flowers, sandal-paste, burnt frankincense, and sweetmeat are offered to the *pimpal* tree. The boy bows before the tree and the priest unties the cord from round his waist. The boy is dressed in a full suit of clothes, declares that he means to go to Benares and spend the rest of his life in study and worship, and sets out on his journey. Before he has gone many yards, his maternal uncle meets him, promises him his daughter's hand in marriage, and asks him to return home and live among them as a householder or *grihasth*. The boy is escorted home with music and a band of friends and a small feast to friends and kinsfolk ends the ceremony.

Boys are married between fifteen and twenty-five and girls before they come of age. As a rule the boy's father proposes the match to the girl's father and when they agree, an astrologer is consulted, who compares the birth papers of the boy and the girl and approves the match if he thinks the result will be lucky and if the family

<sup>1</sup> The Sankrit runs ; *Bhavati bhiksham deli.*

## Chapter III.

## People.

## JAINS.

stocks and branches or *shákhás* of the boy and the girl are different. Then on a lucky day the boy's father visits the girl's house with a few friends, including five kinswomen, and are received by the girl's father and mother. The girl is seated on a low stool in front of the house gods, and the boy's father presents her with a robe and bodice and a pair of silver chains or *sánkhkhis* and anklets or *válás*. Her brow is marked with vermilion and decked with a network of flowers. The women of the boy's house dress the girl in the clothes and ornaments brought by the boy's father, and the boy's father puts a little sugar in her mouth. Packets of sugar and betel are handed among the guests and the asking or *mágni* ends with a feast to the guests. As a rule marriage takes place two or three years after betrothal. Every year the boy's parents have to send a present of a string of cocoa-kernel and some fried rice on the Cobra's Fifth or *Nágpanchmi* in July-August and this they have to continue to do till the girl comes of age. When the boy is fifteen or sixteen and the girl is ten or eleven the parents think it is time they were married and send for and consult an astrologer. He compares their horoscopes, consults his almanac, and names a lucky day for the marriage. The ceremony as a rule lasts five days. On the first day two married girls in the bride's house bathe early in the morning, wear a ceremonial dress, and with music and a band of friends go to a pond or a river with copper pots on their heads, lay sandal-paste, flowers, rice, vermilion, burnt frankincense, and sweetmeats on the bank in the name of the water goddess, fill the pots with water, and mark them with vermilion, set a cocoanut and betel leaves in the mouth of each, cover them with bodicecloths, and deck them with gold necklaces. They then set the waterpots on their heads, return home, and lay them on the earthen altars. Flowers, vermilion, burnt frankincense and sweetmeat are offered to the pots and five dishes filled with earth are set before them, sprinkled with water from the waterpots, and mixed seed grain is sown in the earth. Friends and kinsfolk are asked to dine at the house and the sprout-offering or *ankurárpan* is over. The bridegroom is bathed at his house and lights a sacred fire or *hom*, puts on a rich dress, and goes on horseback with music and friends carrying clothes, ornaments, sugar, and betel packets to the bride's house. The bride's party meet him on the way and the bridegroom is taken to the bride's house and seated outside of the house on a seat of *audumbar* or *umbar* *Ficus glomerata*. The bride's parents come out with a vessel full of water, the father washes his future son-in-law's feet and the mother pours water over them. The bridegroom is then taken to a raised seat in the house, seated on it, and presented with clothes, a gold ring, and a necklace. The bridegroom's parents present the ornaments and clothes they have brought for the bride, packets of betel and sugar are handed among friends and kinspeople, and the first day ends with a feast to the bridegroom's party. The bridegroom returns home with his party, is rubbed with turmeric and clarified butter, and bathed by five married women, seated in a square with an earthen pot at each corner and a yellow thread passed five times round their necks. The bride is bathed in a similar square at her house. On the third day the bride and bridegroom bathe, dress in



## Chapter III.

People.

JAINS.

newly washed clothes, and starting from their homes meet at the Jain temple. The priest attends them and the pair bow before the idol. The priest makes them repeat the five-salutation hymn which every Jain ought to know and warns them to keep the Jain vow or *Jain vrat* of not-killing or *ahinsa* and of leading a pure moral life. The pair are treated to sweetmeats each by their own people, and the family gods and the cork marriage coronet or *báshing* are worshipped at both houses. Men and women from both houses go with music and ask their friends and kinspeople. In the afternoon, when all meet, the women take their seats in the booth and the men inside of the house and all eat at the same time. On the fourth day the actual marriage ceremony begins. Friends and relations are asked to both houses. The bridegroom is rubbed with fragrant oil, and with about fifteen of his relations again kindles the sacred fire, dresses in rich clothes, and goes to the bride's house on horseback with music and friends. On the way he is met by the bride's party and taken to a raised *umbar* *Ficus glomerata* seat. While he is seated on the *umbar* seat a couple from the bride's house, generally the bride's parents, come and wash his feet. The bridegroom thrice sips water, puts on the new sacred thread offered him by the bride's priest, and swallows curds mixed with sugar which the couple have poured over his hands. The father-in-law leads the bridegroom by the hand to a ready-made seat in the house. Before the seat a curtain is held and two heaps of rice, one on each side of the curtain, marked with the lucky cross or *svastik* and crowned with the sacred *kush* grass. A short time before the lucky moment the bride is led out by her friends and made to stand on the rice heap behind the curtain, the bridegroom standing on the rice heap on the other side. The guests stand around and the priests recite the nine-planet lucky verses or *navgrah mangaláshtaks*. The astrologer marks the lucky moment by clapping his hands, the musicians redouble their noise, the priests draw aside the curtain, and the pair look at each other and are husband and wife. The bridegroom marks the bride's brow with vermilion and she throws a flower garland round his neck. They fold their hands together and the bride's father pours water over their hands. They then throw rice over each other's head, and the priests and guests throw rice at the pair. The priests tie the marriage wristlets on the hands of the pair. The bridegroom then sits on a low stool facing east and the bride on another stool to his left. The priest kindles the sacred or *hom* fire and the bridegroom feeds the fire with offerings of parched rice held in a dish before him by the bride. Then the priest lays seven small heaps of rice each with a small stone at the top in one row. The bridegroom, holding the bride by the hand, touches the rice and the stone on each heap with his right toe, moves five times round the heaps, the priest shows the pair the Polar star or *dhruv*, and the payment of a money gift to the priest completes the day's ceremonies. The hems of the pair's garments are knotted together and they walk into the house and bow before the waterpots which are arranged on the first day, and are fed with a dish of milk and clarified butter. Next day the bride's parents give a feast to the bridegroom's party and to their own kinspeople. In the morning

## Chapter III.

## People.

## JAINS.

the pair are seated in the booth and young girls on both sides join them. The pair first play with betelnuts for a time and the bridegroom takes some wet turmeric powder and rubs it five times on the bride's face, who gathers it and rubs it on the bridegroom's face. The bridegroom is given a betel packet to chew, chews half of it and hands the rest to the bride. Thus he chews the five betel packets, and the bride in her turn chews another five each time handing half of the betel packet to the bridegroom to chew. Next morning the sacred fire is again kindled and the serpent is worshipped. The pair then dine at the bride's and play with betelnuts. The pair are seated on horseback, the bride before the bridegroom, and taken to the Jain temple where they walk round the god, bow before him, and ask his blessing. They then walk to the bridegroom's with music and friends. Before they reach every part of the house is lighted and a long white sheet is spread on the ground from the booth door to the god-room. When the pair attempt to cross the threshold the bridegroom's sister blocks the door and does not allow them to enter. The bridegroom asks her why she blocks the door. She says, Will you give your daughter in marriage to my son? He answers, Ask my wife. The sister asks the wife and she says, I will give one of my three pearls in marriage to your son. Then she leaves the door, the pair walk into the house, bow before the house gods, and a feast of uncooked provisions to those that do not eat from them and of cooked food to friends of their own caste and to kinspeople ends the ceremony. Though forbidden by their sacred book, all Jains except Upādhyās or priests allow widow marriage. They say the practice came into use about 200 years ago. If a woman does not get on well with her husband, she may live separate from him but cannot marry during her husband's lifetime. When a girl comes of age she sits apart for three days. On the fourth she is bathed and her lap is filled with rice and a cocoanut, and the rest of the age-coming does not differ from a Brāhman age-coming.

When a Jain is on the point of death, a priest is called in to repeat verses to cleanse the sick person's ears, to quiet his soul, and if possible to drive away his disease. When recovery is hopeless, a ceremony called *sallekhan vidhi* or tearing rite is performed to sever the sick person from worldly pleasures and to make him fit for the life he is about to enter. Sometimes the sick man is made to pass through the ceremony called *sannyās grahan* or ascetic vow-taking with the same rites as among Brāhmins. When these rites are over and death is near, the dying man is made to lie on a line of three to four wooden stools and the names of gods and sacred hymns are loudly repeated. After death the body is taken outside of the house, bathed in warm water, dressed in a waist and a shouldercloth, and seated cross-legged on a low stool leaning against the wall. A bier is made and the dead is laid on it, and the whole body including the face is covered with a white sheet. Jewels are put into the dead mouth and fastened over the eyes. Four kinsmen lift the bier and followed by a party of friends, walk after the chief mourner who carries a firepot slung from his hand. To perform Jain funeral rites, from the first to the thirteenth day, six men are required, the chief mourner who carries fire, four

## Chapter III.

## People.

## JAINS.

corpse-bearers, and a body-dresser. Music is played at some funerals, but on the way no coins or grain are thrown to spirits and no words uttered. The party moves silently to the burning ground and the chief mourner is not allowed to look behind. About half-way the bier is laid on the ground and the cloth is removed from the dead face apparently to make sure that there are no signs of life. They go on to the burning ground and set down the bier. One of the party cleans the spot where the pyre is to be prepared and they build the pyre. When it is ready the bearers lay the body on the pile and the chief mourner lights it. When the body is half consumed the chief mourner bathes, carries an earthen pot filled with water on his shoulder, and walks three times round the pile. Another man walks with him and at each turn makes a hole in the pot with a stone called *ashma* or the life-stone. When three rounds and three holes are made, the chief mourner throws the pot over his back and beats his mouth with the open palm of his right hand. The *ashma* or life-stone is kept ten days and each day a rice ball is offered to it. As a rule the funeral party stops at the burning ground till the skull bursts. If they choose some of the party may go home, but as a rule the six mourners must remain there till the body is consumed when each offers a flour-ball and a handful of water to the life-stone and returns home. A lamp is set on the spot where the dead breathed his last, and kept there burning for at least twenty-four hours. On the second day the six chief mourners go to the burning ground and in the house put out the fire with offerings of milk sugar and water. On the third day they gather the deceased's bones and bury them somewhere among the neighbouring hills. Except offering a rice ball to the life-stone from the first to the tenth day nothing special is performed from the fourth to the ninth day. The family are held impure for ten days. On the tenth the house is cowdunged and all members of the family bathe and each offer a handful of water called *tilodak* or sesame water to the dead. The house is purified by sprinkling holy water and the sacred or *hom* fire is lit by the priest. On the twelfth the clothes of the deceased are given to the poor, and rice balls in the name of the deceased and his ancestors are made and sandal-paste, flowers, vermilion, frankincense, and sweetmeat are offered them. The temple gods are worshipped and a feast to the corpse-bearers and dresser ends the twelfth day ceremony. On the thirteenth the *shrāddh* or mind-rite is performed and a few friends and relations are asked to dine. A fortnightly and monthly ceremony is performed every month for one year and a feast is held every year for twelve years. According to rule the widow's head should be shaved on the tenth, but the practice is becoming rare, still her lucky thread and toe ornaments are taken away and she is not allowed to wear a black bodice or robe. When a *sanyāshi* or ascetic dies his body is carried in a canopied chair instead of an ordinary bier. The body is laid on the pyre and bathed in the five nectars or *pañchāmrits* milk, curds, clarified butter, plantain, and sugar. Camphor is lighted on the head and the pile is lit. At a *sanyāshi's* funeral only five men are required. A fire-carrier is not wanted as fire can be taken from any neigh-

Chapter III.  
People.  
JAINS.

bouring house to light the pile. The family of the dead are impure for only three days, and no balls are offered to the dead. When an infant dies before teething it is buried, and boys who die before their thread-girding are not honoured with the rice-ball offering. No special rites are performed in the case of a married woman, a widow, or a woman who dies in childbed. No evil attaches to a death which happens during an eclipse of the sun or the moon. In the case of a person who dies at an unlucky moment, Jains perform the same rites as Bráhmānic Hindus.<sup>1</sup> Jains are bound together by a strong caste feeling and settle social disputes at caste meetings. Appeals against the decisions of the caste council lie to their *svāmi* or religious head who with the two titles Jinsen Svāmi and Lakshnisen Svāmi, and with jurisdiction over the Jains of almost the whole Bombay Karnātak, lives at Kolhāpur. Small breaches of caste rules are punished with fines which take the form of a caste feast, and the decisions of the *svāmi* are held final and are enforced on pain of expulsion from caste. The bulk of the Kolhāpur Jains set little value on schooling, yet they give their sons primary schooling and the majority of them are able to read and write and cast accounts. The knowledge of Sanskrit for which the Jains were once famous has now sunk to a low ebb. Though they are wanting in enterprise and do not take to new pursuits, a gradual change for the better has passed over the caste during the last twenty years.

Non-Kolhāpur Jains include a considerable number of Jain Mārvaris and of Jain Gujarāt Vānis who have come from Mārvar and Gujarāt for trade and who settle in the State for a time and return to their homes when they have collected money enough. They do not marry with the Jains of Kolhāpur, and unlike the Jains of Kolhāpur they have no objection to take water from the hands of the Marátha Kunbis and to take food from non-Jains. Their favourite place of pilgrimage is Mount Ábu. They are moneylenders and dealers in piece-goods and jewelry. They live in well built houses, send their children to school, and are a prosperous class.<sup>2</sup>

MISCELLANEOUS.

Miscellaneous Hindus included thirty castes with a total strength of 903, of whom 444 were males and 459 females. Of these 375 (males 191, females 184) were Bágadis; 5 (males 3, females 2) Chhatti Balajvárs; 22 (males 14, females 8) Devils; 2 (females) Gábids or Fishers; 9 (males 6, females 3) Gollas; 20 (males 8, females 12) Gantnichors or Pickpockets; 2 (male 1, female 1) Halvais or sweetmeat makers; 33 (males 19, females 14) Helvis; 8 (males 2, females 6) Jhāris or dust sifters; 3 (male 1, females 2) Kalāvants or dancing girls; 4 (males 3, female 1) Kulkutkis; 6 (males 4, females 2) Khurkhurmundis; 10 (males 7, females 3) Kilikyats; 11 (males 7, females 4) Konges; 8 (males 6, females 2) Kadvechātis; 53 (males 26, females 27) Manvars; 23 (males 11, females 12) Mitkaris or salt-makers; 2 (males) Mudlyárs or Madras traders; 1 Náth (male); 47 (males 23, females 24) Natkars or actors; 1 (male) Patvekari or silk tassel twister;

<sup>1</sup> Details of these rites are given in the Poona Statistical Account.

<sup>2</sup> Details of Mārvar Jains are given in the Ahmadnagar Statistical Account.

144 (males 55, females 89) Pichatis; 2 (males) Pendhárís or pony-keepers and grass-cutters; 33 (males 13, females 20) Saibars; 3 Salmandupes (males); 28 (males 14, females 14) Shindis; 28 (males 10, females 18) Takárs or grind-stone makers; 1 Thákur (male); 9 (male 1, females 8) Vaivarís; and 10 (males 9, female 1) unspecified.

**Musalma'ns** are returned at 33,022 or 4·12 per cent of the population. They include thirty-eight subdivisions, twelve of which, all with a foreign element, marry together and form the main body of regular Musalmáns, and twenty-six form distinct and irregular communities. The foreign element includes strains of Arab, Abyssinian, Persian, Moghal, and Upper and South Indian blood. The sources of the foreign element are numerous, Turk immigrants of the fourteenth century and Arab, Persian, and Upper Indian soldiers and commanders who took service under the Bahmani (1347-1490), Bijápur (1490-1686), and Moghal kings (1686-1710). The fall of Bijápur in 1686 introduced two new Musalmán elements one foreign the Moghal from Upper India, the other local Hindu converts due to the zeal of Aurangzeb (1658-1707). A large number of local classes trace their conversion to Aurangzeb. But it seems probable that in many cases the date of their conversion is earlier and that they trace their conversion to Aurangzeb as the most famous of modern proselytising Musalmáns. Except that the men wear the beard, the local converts differ little in appearance from the corresponding classes of Kolhápúr Hindus. All regular Musalmáns speak Hindustáni at home and Maráthi with others. In food, house, dress, drink, and customs they do not differ from the Sátára Musalmáns.<sup>1</sup> They are landowners, grantholders, husbandmen, and traders. They send their boys to school and teach their boys to read the Kurán and Maráthi. Few among them have risen to any high position. The main body of regular Musalmáns who intermarry and are similar to one another in appearance and customs, besides the four general divisions Moghals, Patháns, Shaikhs, and Syeds, include eight classes, Atárs, Barutgars, Kágzis, Manyárs, Maháwats, Nálbands, Rangrezs, and Sárbán's.

**Moghals** claim descent from the Moghal leaders and soldiers who came to the Deccan chiefly during the seventeenth century. They are found in towns and large villages. They speak Hindustáni at home and Maráthi abroad, and in appearance and customs do not differ from the local Shaikhs and Syeds. Except that they wear full beards they look like local Maráthás, and as a class are clean and neat in their habits, honest, hardworking, and thrifty. Town Moghals are constables, soldiers, and messengers, and village Moghals are husbandmen. They belong to the Hanafi Sunni sect, say their prayers regularly, and teach their boys to read the Kurán. They send their boys to school, but none of them learn English.

**Patha'ns**, or Warriors, are the followers of Afghan mercenaries and military leaders who conquered and took service in the Deccan. They speak Hindustáni among themselves and Maráthi

### Chapter III. People.

#### MUSALMÁNS.

#### Moghals

#### Patháns.

<sup>1</sup> Details are given in the Sátára Statistical Account.

## Chapter III.

## People.

## MUSALMÁNS.

with others. In look, dress, food, and customs they are the same as Poona and Sholápur Patháns. The town Patháns are soldiers, constables, and messengers, and the villagers are husbandmen. Though hardworking and thrifty most of them are deeply embarrassed from the effects of the 1876-77 famine. They belong to the Sunni sect of the Hanafi school and ask the *kázi* to conduct their marriages and deaths. They are careless about saying their prayers and seldom give their boys any schooling.

*Shaikhs.*

**Shaikhs**, in theory descendants of Sidiks and Fárúks, are chiefly if not entirely of local origin. They do not differ from local Syeds in look, food, dress, or customs, and like them speak Hindustáni at home. As a class they are hardworking, thrifty, neat, and clean in their habits, and most of them are orderly and sober. The town Shaikhs are soldiers, constables, and messengers, and the villagers are husbandmen. Numbers of them were reduced to poverty by the 1876-77 famine. Like Syeds they are Sunnis of the Hanafi school, repeat their prayers, and teach their sons to read the Kurán. Many of them send their boys to local schools.

*Syeds.*

**Syeds**, or Descendants of Fatima and Ali, are found in towns and large villages. Their home tongue is Hindustáni and they speak Maráthi abroad. In look, food, dress, and customs they are the same as the Syeds of Poona and Sholápur. They are honest, clean, and neat in their habits and orderly. They earn their living as landholders, husbandmen, soldiers, constables, and messengers. In religion they are Sunnis of the Hanafi school, they teach their children to read the Kurán, and are careful to say their prayers. The town Syeds are lazy and unthrifty, but the villagers are hardworking thrifty and well-to-do. They send their boys to school.

Special  
Communities.

The eight classes who are separate in name only and marry with the four general divisions and with each other and form part of the main body of the Kolhápur Musalmáns are :

*Atárs.*

**Atárs**, or Perfumers, are said to represent members of the Hindu caste of the same name who were converted by Aurangzeb (1658-1707). They are found only in towns. In look, food, dress, speech, and customs they do not differ from regular Musalmáns. They sell both flowers and perfumes. They have fixed shops and deal in redpowder or *kunku*, *attars* or fragrant oils, frankincense-sticks, dentrifice, spices, fragrant plants, and flowers, which they hawk from village to village. They are hardworking and thrifty, but they say their goods are not in so great a demand as formerly owing to the competition of Upper Indian and English perfumes. They belong to the Hanafi Sunni sect, but are careless in saying their prayers. A few send their boys to school, but as a class they are not well-to-do.

*Barutgars.*

**Barutgars**, or Firework-makers, are said to represent Hindus of different castes converted by Aurangzeb (1658-1707). They speak Hindustáni among themselves and Maráthi with others. In look, food, dress, and customs they do not differ from regular Musalmáns. As their hereditary calling is not now well paid, some earn their living as constables and messengers. They are Hanafi Sunnis



and are careful to say their prayers. They send their boys to school and are a falling class.

**Ka'gzis**, or Paper Makers, said to represent the local converts of different Hindu castes, are found in Kolhápur town. In speech, look, food, and dress they resemble Atárs and their customs do not differ from those of regular Musalmáns. They are rather dirty and untidy in their habits, but hardworking and thrifty. The universal use of European steam-made paper has much lessened the demand for their coarse paper and they are now in a falling state. Many of them are in debt and have taken to other pursuits. They belong to the Hanafi Sunni sect and ask the *kázi* to conduct their marriage and death ceremonies. They do not send their boys to school and are a poverty-stricken class.

**Manya'rs**, or Glass Bangle Sellers, probably representing Hindu converts of the same caste, are found in towns and large villages. In look, food, dress, speech, and customs they are the same as the regular Musalmáns, and are hardworking, thrifty, and orderly. They are bangle-sellers and are well-to-do. They have no organized body and no headman, and the local *kázi* settles their caste disputes. They are Sunnis of the Hanafi school, and seldom say their prayers or teach their sons to read the Kurán.

**Maha'wats**, or Elephant Drivers, are said to represent local converts of the Hindu caste of the same name and found in small numbers in towns. They do not differ from regular Musalmáns in look, dress, food, or customs. Their calling is not so well paid as formerly and many have become constables, messengers, and servants. They are Hanafi Sunnis, are not careful to say their prayers or send their boys to school, and are a poor class.

**Nálbands**, or Farriers, believed to represent Hindu converts of the same name, are found in towns only. They differ in no respects from the regular Musalmáns. They shoe horses and bullocks and earn enough to live on and to save, but most of them are given to the use of country liquor and are in debt.

**Rangrezs**, or Dyers, said to represent Hindu converts of the same caste, are found in towns. Their home tongue is Hindustáni and they speak Maráthi abroad. In look, dress, food, and customs they are the same as Nálbands. They dye clothes and are well-to-do. They are Sunnis of the Hanafi school, but seldom say their prayers or send their boys to school.

**Sa'rba'ns**, or Camel Drivers, believed to represent converts of several Hindu castes, are found in towns. Except that they eschew beef and worship Hindu gods, in dress food and customs they are the same as Maháwats. Their calling has ceased to be well paid since the opening of roads, and they are constables, messengers, and husbandmen. They do not send their boys to school and are a decaying class.

Of the twenty-six communities who are separate from the regular Musalmáns in marriage and other customs six are of non-local origin:

### Chapter III.

#### People.

#### MUSALMÁNS.

##### *Kágzis.*

##### *Manya'rs.*

##### *Maháwats.*

##### *Nálbands.*

##### *Rangrezs.*

##### *Sárbáns.*

**Chapter III.**  
**People.**

**MUSALMÁNS.**

*Bohorás.*

**Bohora's**, or Ismáili Shiás, mostly immigrants from Gujarát and Bombay are found in Kolhápur town. In look, food, dress, speech, and customs they are the same as the Bohorás of Poona and Sátára.<sup>1</sup> They are tinsmiths and piecegoods dealers. As they are a small body they marry with Sunnis and obey the regular *kázi*. They do not follow the Mulla Sáheb of Surat or pay his dues. They teach their children to read Gujaráti and Maráthi and are a steady class.

*Labbays.*

**Labbays**, mostly immigrants from Maisur and the Malabár coast, said to represent the descendants of Arab and Persian immigrants between the seventh and the fourteenth century, are found only in towns. They speak Arvi or Tamil among themselves and Hindustáni with others, and in other points do not differ from the regular Musalmáns. They dress in a skullcap, a long coat falling to the knees, and a waistcloth, and are leather dealers. They are hardworking and thrifty and as a class are well-to-do. They are Sunnis of the Shafái school, say their prayers regularly, and are said to be a pushing class.

*Mehmans.*

**Mehmans** or Memans, properly Momins or Believers, are found in Kolhápur cantonment. In look, speech, food, dress, and customs they are the same as the Mehmans of Sátára and Sholápur. They are hardworking, quiet, honest, and thrifty, and deal in piecegoods and English furniture. They teach their sons to read the Kurán, say their prayers, and are well-to-do.

*Mukris.*

**Mukris**, or Deniers, are found in Kolhápur cantonment. They are the same in speech, dress, food, and customs as the Sátára Mukris and have a bad name for cheating. They were formerly money-lenders and now deal in grain, groceries, and piecegoods. They are Hanafi Sunnis and seldom say their prayers. They send their boys to school and are fairly off.

*Gái Kasábs.*

**Gái Kasa'bs**, or Beef Butchers, are believed to represent the Abyssinian slaves in the service of Haidar Ali (1763-1782) and his son Tipu (1782-1799). Their home tongue is Hindustáni, and in look, food, dress, and customs they are the same as the Gái Kasábs of Sátára. They are beef butchers, and spend most of their earnings on liquor. They do not give their boys any schooling, and on the whole are a falling class.

*Wahábis.*

**Waha'bis**, or Followers of Abdul Waháb an Arab reformer of the eighteenth century, number about a hundred, most of whom are Panjábi wrestlers in the service of the State. They do not yet form a separate class. About five years ago a Wahábi missionary from the Panjáb visited Kolhápur and gathered about him, besides the Panjábis who were Wahábis, a few Bágbáns, Támbolis, and Atárs. As soon as the spread of Wahábi tenets became known among the regular local Musalmáns, pressure was brought to bear on the converts and all, except the North Indian wrestlers, returned to the regular faith. Except that the men wear a headscarf or skullcap, their dress is the same as that of the regular Musalmáns. They

<sup>1</sup> Details of Bohorás are given in the Sátára Statistical Account.

35  
in  
speak Hindustáni with themselves and Maráthi with others. They are neat and clean in their habits, and their staple food is mutton, wheateakes, milk, and eggs, and they drink tea in the morning and coffee at night. They are a lazy and unthrifty class, never taking to any calling, and living on the allowance which they get from the State as gymnasts. They are strict in saying their prayers, and teach their sons to read the Kurán. They send their boys to school, and as a class are well-to-do.

The twenty separate communities<sup>1</sup> of local origin differ from the regular Musalmáns chiefly in eschewing beef, worshipping Hindu gods, and keeping Hindu feasts. Besides their hereditary callings they are husbandmen, constables, messengers, and servants. In all other respects they are nearly the same as the regular Musalmáns. They speak Hindustáni with themselves and Maráthi with others. They are Sunnis of the Hanafi school, but seldom say their prayers or teach their sons to read the Kurán. They keep the Musalmán fasts and feasts, circumcise their sons, and fast during the month of *Ramzán*. They obey the *kázi* and ask him to conduct their marriage and death ceremonies. They form distinct communities and marry among themselves, have a well managed organization under a headman usually called either *pátíl*, *mehtar* or *chaudhari*, and each settle their caste disputes at meetings of their own castemen. These separate communities are : Bágbáns or fruiterers ; Bándarválás or monkey-showmen ; Bhois or palanquin-bearers ; Bojgars or millet beer or *boj* makers ; Dhavads or iron smelters ; Dhobis or washermen ; Dhondphodás or quarrymen and stone masons ; Gárudis or magicians ; Gavandis or masons and house builders ; Halálkhors or nightsoil-men ; Jhárás or dust-sifters ; Kasábs Sultáni or mutton butchers ; Momins or weavers ; Nagárjis or kettledrum-beaters ; Pakhális or water-carriers ; Patvegars or silk tassel twisters ; Pinjáis or cotton teasers ; Sikalgars or armourers ; Tásjis or drummers ; and Támbois or betel sellers. Except the Bágbáns or fruiterers and Bakar Kasábs or mutton butchers who are somewhat better off and the Dhavads or iron smelters who are poorer the condition of these castes is much the same as the condition of corresponding castes in Sátára.

Christians are returned as numbering 1253 and as found generally in the town and cantonment of Kolhápúr. Of these fifty-two are Europeans and 1201 Native converts.<sup>2</sup> Kolhápúr has three mission societies, one belonging to the English church, another to the Roman Catholic, and a third to the American Presbyterian church. The Church of England Mission, supported by the Society for the Propagation of the Gospel, was established in 1870 when the Revd. J. Taylor was sent to Kolhápúr. He at first took up his residence at Bávda three miles north-east of Kolhápúr, and in 1873 removed to a well built bungalow on the Brahmápurí hill on

## Chapter III.

## People.

## MUSALMÁNS.

Local  
Communities.

## CHRISTIANS.

<sup>1</sup> Details of the customs of each of these communities given in the Sátára Statistical Account apply equally to the Kolhápúr classes.

<sup>2</sup> Details of the customs of native converts are given in the Ahmadnagar Statistical Account.

## Chapter III.

## People.

## CHRISTIANS.

the Panch Ganga near the centre of Kolhápúr town, which the State granted to him on *rayat* tenure. Walls of the old native houses in the neighbourhood were utilised for a small Christian hamlet with a chapel and a school. About 1877-78 the Mission obtained twenty-one famine orphans. In December 1881 two ladies arrived from England, one of whom works among the native women of the town, and the other has charge of the Christian girls' school. On the 25th of December 1882 a new church was opened at a cost of about £3000 (Rs. 30,000), of which Government contributed about £650 (Rs. 6500). In 1882 the Reverend J. Taylor was transferred to Ahmadvnagar and at present (1883) his assistants are in charge of the Kolhápúr station. This mission has preached over a large area, and especially near Pandharpur they have been fairly successful. But the number of Christians belonging to this mission is not large. A Roman Catholic missionary was appointed at Kolhápúr in 1846. The Roman Catholic community then numbered 130 including women and children. Divine service was first held in a temporary shed erected by private subscriptions, but in 1848 Government sanctioned a sum of £15 (Rs. 150) to erect a small building in the cantonment. During the 1857-58 mutiny when European troops were temporarily located at Kolhápúr the chaplain's salary was increased in consideration of the additional work devolving upon him and the cost of the establishment was charged to the Kolhápúr State. But with the withdrawal of the troops from Kolhápúr the Roman Catholic chaplain was also transferred and the station has been periodically visited by a chaplain either from Belgaum or Sátára. The present chapel, which lies within cantonment limits, was built in 1864-65 by private subscriptions, the Kolhápúr State having contributed £70 (Rs. 700) for the purpose. The American Mission was established at Kolhápúr about 1845 and was transferred to the American Presbyterian Society in 1870. The work is generally carried on in the vernacular and special attention is given to the education of the lower classes. This mission has three principal stations in the State, Kolhápúr town, Panhála, and Vádi-Ratnágiri. At the Kolhápúr station they have ten schools, nine for non-Christians and one for Christians, with an average attendance of 350 boys and seventy-five girls. The number of Native Christians attending the American Mission schools at Kolhápúr is eighty-two, at Panhála fifty, and at Vádi-Ratnágiri thirty.

## BUDDHISTS.

**Buddhists** returned at only twelve are Chinese who have come to Kolhápúr for trade. They are hardworking thrifty and prosperous.

## JEWS.

**Jews** are returned as numbering only five and as found in Kolhápúr town. They are not permanent residents of the State but visit it for trade and leave it as soon as they have made enough money.

## PÁRSIS.

There was only one male Pársi belonging to the Sháhansháí sect. There are no Pársi settlers in Kolhápúr, and those who come here on business remain for a short period.

## CHAPTER IV.

## AGRICULTURE.

AGRICULTURE supports 435,633 or 54.44 per cent of the total population.

Chapter IV.  
Agriculture.  
HUSBANDMEN.

Kunbis form the bulk of Kolhápúr husbandmen. Besides Kunbis Jains, Lingáyats, Maráthás, Bráhmans, Musalmáns, Berads, Bhandáris, Hanbars, Dhangars, Kolis, Mhárs, and the artisan classes are cultivators. Of these Kunbis are found all over the State; Jains and Lingáyats mostly in the east, in Alta, Ichalkaranji, Katkol, Ráybág, and Shirol; Berads and Hanbars mostly in Gadinglaj; and Bhandáris in a few villages below and along the Sahyádris. The other castes are found distributed throughout the State. Kunbis are sober and industrious but are too conservative. Though not thriftless, they are lavish in their expenditure on marriages and other social rites. They understand the benefit of keeping their fields free from weeds and use manure; but Jains and Lingáyats are better farmers in many respects. These are good gardeners, and raise most of the garden crops of the State especially the sugarcane crop which requires both skill and capital. There is more spirit of self-reliance in the Jain community. This particular trait in their character was well shown in the famine of 1876-77 when scarcely a Jain sought State relief. Finding cultivation impossible they sought a livelihood by importing grain and thus succeeded in supporting themselves and their plough cattle. They are somewhat obstinate and quarrelsome. Though ordinarily thrifty, they spend lavishly on marriage and other great rites. The Lingáyats are as good farmers as the Jains. They are enduring and thrifty. Bráhmans and well-to-do Maráthás are not pure cultivators. They hold land both as proprietors and tenants, but either employ labourers or sublet their land for a fixed share of the produce. They are not good farmers. Musalmáns are less hardworking and more reckless than Kunbis and are often given to drink. Berads, Bhandáris, Hanbars, Dhangars, Kolis, and Mhárs form the poorest class of cultivators. Though on the whole sober, they are slovenly slothful and negligent farmers. The artisan classes having other pursuits keep no stock and reap a poor return from cultivation.

Bráhman, Jain, Lingáyat, and well-to-do Marátha husbandmen live in well built houses raised on stone plinths. The houses, which are roomy and well-furnished, are built of bricks or uncoursed rubble with tiled or flat roofs and cost £50 to £500 (Rs. 500 - 5000). The houses of middle-class husbandmen, chiefly of Kunbis, are generally

Chapter IV.  
Agriculture.  
HUSBANDMEN.

near the Sahyádris, built with mud and gravel walls covered with thatched roofs. The rafters are generally bamboos and the roof is supported on posts and beams of rough untrimmed timber. The houses in the plain country are somewhat better and ordinarily cover a space of thirty-five feet by sixty. The value of a middle-class house varies from £7 (Rs. 70) in the hilly west to £10 (Rs. 100) in the open east. A few brass and copper cooking vessels and most of the minor field tools and some household gear are all that are seen in these classes of houses. Poor husbandmen Dhangars, Berads, Kolis, Bhandáris, Mhárs, and Musalmáns live in small shapeless thatched huts, in which little else than a handmill, a brass, and a few earthen pots can be seen.

The husbandmen as a class are superstitious. No important act of husbandry such as sowing, reaping, harvesting, and pressing sugar-cane is undertaken except at the lucky hour fixed by the village astrologer. Ploughing on Monday is scrupulously avoided. The day is sacred to Mahádev whose favourite riding animal is the bull or Nandi. The women do not help in the field except at harvest, but manage all household affairs. They also spin cotton and visit the neighbouring market to dispose of the yarn and the surplus produce of the dairy, and to buy condiments and articles of domestic use with their earnings. The poorest gather headloads of grass and cotton stalks for sale in the markets or halting places. The bulk of the farmers are small peasant proprietors. Since the opening of the Sahyádris and the construction of other main roads the number of carts has greatly increased much to the benefit of husbandmen in the plain country, who cart their produce as far as the coast to secure a better price. The Dhangars always add to their earning by weaving coarse blankets and selling wool and the surplus stock of their folds. Musalmáns and Mhárs keep fowls. Both fowls and eggs find a ready sale in towns. The poorer husbandmen work also as field labourers chiefly in weeding and harvesting. Kunbis freely move with their families at harvest time in search of work. It is estimated that perhaps ten per cent of the husbandmen are free from debt. The causes of debt are chiefly a series of indifferent seasons since 1866 and undue expenditure on marriages. Jains who are somewhat litigious often incur debt through law suits. Maráthás owe their indebtedness to extravagant living and thriftlessness. Especially in the west the husbandmen are generally compelled to borrow grain from the bankers for their support in the rainy season. Such advances are repaid in the harvest season with an addition of twenty-five per cent or *savái* as interest. The yearly rate of interest which a husbandman pays varies from twelve to thirty-six per cent. During the 1876-77 famine the country near the Sahyádris and the eastern sub-divisions of Shirol, Ráybág, and Katkol suffered most. Every form of property, even the family gods and door frames were sold. It will require a series of good years with moderately high prices to enable them to regain their former condition. But on the whole a marked change for the better is noticeable in the condition of the husbandmen as compared with that of thirty years ago. The population has increased more than thirty per cent and the land under tillage has almost reached its maximum. The



Chapter IV.  
Agriculture.

## SEASONS.

farm stock has increased immensely, and except in the hilly sub-divisions grass huts have everywhere given way to buildings with tiled or flat terraced roofs.

In dry-crop or *jirdyat* land the seasons are the *kharif* or early or rain harvest and the *rabi* or late or cold weather harvest.<sup>1</sup> The early harvest is the more important. The time of sowing depends on the breaking of the south-west monsoon which generally takes place between the fifth and the twentieth June. The chief early crops are of the cereals *bájrí*, *barag*, *harik*, *jondhla*, *káng*, *náchni*, *rála*, rice, *sáva*, and *vari*; of the pulses *chavli*, *kulith*, *math*, *mug*, *tur*, and *udid*; of the oilseeds *ambádi*, *bhuimug*, *erandi*, *korte*, and *tíl*; and of fibres hemp. Of these *udid*, *chavli*, *vari*, and *rála* ripen by the end of August, rice and *náchni* by the end of September, and the rest by the end of November. The chief late crops are wheat, late Indian millet, cotton, maize, gram, peas, coriander seed, safflower, mustard seed, linseed, and tobacco.

## SOIL.

The soil may be classed *káli* or black, *támbad* or red, *máli* or *malva* the orchard and rice land, and *khári* or *pándhar* or white, or again as good, middling, and poor. About one-third of the arable area is good soil yielding garden crops or two crops in the year; about a fourth is middling soil including patches near villages; and about five-twelfths especially in the hilly west are poor soils bearing coarse grains and requiring long fallows. The black and red soils are the most valuable. Their productiveness depends much on situation. The best black soil is found near the rivers and stretches to an average depth of five feet throughout the bottom of the valleys. Frequent wide seams of lime, however, pervade the black mass and *kankar* or lime nodules are spread for miles over the surface especially in the sub-divisions of Karvir Panhála and Shirol. A superior kind of red soil is met with on the sides or slopes of the hills near the Sahyádris which are of a ferruginous character for the most part. A stiff light coloured soil which is composed of decayed clay-slate is found on the hill sides and in the smaller valleys particularly in the sub-divisions of Panhála and Bhudargad and the dependencies of Vishálgad and Bávda. It is very retentive of moisture and chiefly valued for rice tillage. From the very best black and red soils two or three crops can be yearly raised. In the hilly west the land is bare fallowed from one to ten years; in other parts of the State all the better soils are under tillage.

<sup>1</sup> Besides these two main divisions Kolhápúr husbandmen divide their year into twenty-seven parts each corresponding with one of the lunar asterisms or *nakshatras*. The rainfall in one of these periods is called after its corresponding *nakshatra*; thus the early rain about the middle of June is called the *mrig* rain or *mrigdcha páus*. The average length of each of these periods is about 13½ days. In 1882-83, *Ashvini*, the first *nakshatra* began on 11th April 1882 and *Revati*, the last on the 29th March 1883. The following is the order of the twenty-seven *nakshatras* or lunar asterisms: *Ashvini*, *Bharni*, *Krittika*, *Rohini*, *Mrig*, *A'dra*, *Punarvasu*, *Pushya*, *A'shlesha*, *Magha*, *Purva*, *Uttara*, *Hast*, *Chitra*, *Svati*, *Vishakha*, *Anurádh*, *Jyeshtha*, *Mul*, *Purvashádh*, *Uttarashádh*, *Shravan*, *Dhanishtha*, *Shatádraka*, *Purvábhádrapada*, *Uttarabhádrapada*, and *Revati*. According to these divisions of the year, all their field operations, ploughing, sowing, weeding, and harvesting for different crops are regulated.

Chapter IV.  
Agriculture.

## ARABLE LAND.

Extensive tracts of waste land are only to be found in the western hills where the climate is unhealthy and the soil shallow and poor.

Of an area of 2493 square miles 1584 square miles or 1,013,760 acres or 63·5 per cent have been surveyed in detail. Of the total area 681 square miles belong to 356 alienated villages. Of the remainder 973,937 acres or eighty-three per cent are arable land; 30,925 acres or 2·6 per cent unarable; 53,466 acres or 4·6 per cent grass or *kuran* and forest<sup>1</sup>; and 101,585 or 8·7 per cent village sites, roads, river-beds, and hills. In 1881 of the 973,937 acres of arable land in State villages, of which 236,057 acres or 24·23 per cent are alienated, 559,736 acres or 75·85 per cent were occupied. Of these 490,638 acres or 87·7 per cent were under dry-crop, 53,808 acres or 9·6 per cent were under rice, and 15,290 acres or 2·7 per cent were under irrigated garden land.

## HOLDINGS.

In 1881-82, including alienated lands the total number of holdings was 75,345. Of these 35,362 were holdings of not more than five acres; 16,787 were of six to ten acres; 12,778 of eleven to twenty acres; 7800 of twenty-one to fifty acres; 2145 of fifty-one to a hundred acres; 370 of 101 to 200 acres; eighty-three of 201 to 500 acres; thirteen of 501 to 1000 acres; five of 1001 to 2000 acres; and two of more than 2000 acres. The largest holdings are in the Shirol sub-division.

## STOCK.

According to the returns of 1881 the farm stock included 37,921 ploughs, 8592 carts, 149,762 bullocks, 112,735 cows, 61,130 he-buffaloes and 74,043 she-buffaloes, 5583 horses including mares and foals, 876 asses, and 144,477 sheep and goats.

## A PLOUGH OF LAND.

One pair of oxen can till about twenty acres of blacksoil land, ten acres of *māli* or orchard land, or one acre of garden land. From ten to twenty acres of dry-crop land and either three acres of garden land or five acres of rice land would enable a husbandman to live like an ordinary retail dealer. Ten to twenty acres of dry-crop land will in ordinary seasons support a family consisting of a man, his wife, two children, and a farm servant.

## CROPS.

In 1881-82 the area under tillage was distributed as follows:

1. CEREALS, seventy per cent, namely,				2. PULSES, seven per cent, namely,			
			Acres.				Acres.
<i>Jvāri</i> ...	...	...	260,197	<i>Tur</i> ...	...	...	22,078
Rice ...	...	...	89,038	Gram ...	...	...	17,738
<i>Nāchni</i> ...	...	...	82,980	Peas ...	...	...	4470
<i>Bājri</i> ...	...	...	32,570	<i>Udid</i> ...	...	...	3308
<i>Sāva</i> ...	...	...	19,952	<i>Kulith</i> ...	...	...	2539
<i>Rāla</i> ...	...	...	19,125	<i>Mug</i> ...	...	...	2294
Wheat...	...	...	10,014	<i>Masur</i> ...	...	...	1513
<i>Vari</i> ...	...	...	7148	<i>Pāvta</i> ...	...	...	1049
Maize ...	...	...	3295	<i>Math</i> ...	...	...	696
Barley...	...	...	146	<i>Chavli</i> ...	...	...	232
<i>Barag</i> and <i>Harik</i>	...	...	1314				
Total... 525,779				Total... 55,917			

<sup>1</sup> Forest reserves are being formed and it is likely that the area under forest will be increased.

## 3. OILSEED, six per cent, namely,

	Acres.
Earthnut ... ..	27,543
<i>Korte</i> ... ..	9442
Safflower ... ..	5223
Castor plant ... ..	1986
Sesame ... ..	927
Linseed ... ..	505
<i>Ambáḱi</i> ... ..	482
Total...	46,108

## 4. FIBRES, four per cent, namely,

	Acres.
Cotton... ..	29,192
<i>San</i> ... ..	3160
Total...	32,352

## 5. GARDEN CROPS, three per cent, namely,

	Acres.
Sugarcane ... ..	9900
Chillies ... ..	8469
Turmeric ... ..	1267
Sweet Potatoes ... ..	401
Others ... ..	319
Total...	20,356

## 6. MISCELLANEOUS, nine per cent, namely,

	Acres.
Tobacco ... ..	10,193
Coriander ... ..	2570
Others ... ..	52,657
Vegetables, fruits, and flowers ... ..	1161
Total...	66,581

To the above must be added 1504 acres or only 2 per cent under grass and fallows.

In the plain country of Kolhápur the field tools are the plough or *náṅgar*, the large and small harrows or *kulav*, the bullock hoe or *kolpa*, the four seed-drills, the seed-drill for sowing rice and other early hill crops, the *chanpan* for sowing early *javári* and other early crops, the *hadgi* for late *javári* and other late crops and the *tipan* for cotton, the crowbar or *sabbal*, the sickle or *vila*, the hand-weeder or *khurpe*, the hatchet or *dhákti kurhád*, the axe or *thorli kurhád*, the pickaxe or *kudal*, the rake or *khore*, the leather-bag with its gear or *mot*, the sugar-mill or *ghána*, the sieve or *chálán*, the winnowing basket or *topli*, the cart, and the wooden mallets for crushing clods. Of these the chief are the plough, the harrow, the bullock hoe, the seed-drill, the sugarcane-mill, the leather-bag with its gear, and the cart.

The plough or *náṅgar* is a thick *bábhul* or *Acacia arabica* log with its lower end called *isád* sharp and curving at an obtuse angle from the main block. The share or *phál*, which weighs about fourteen pounds and goes seven to nine inches deep, is a flat iron bar about two feet long and somewhat pointed at the end which cuts the soil. It is let into a socket called *mutirna* and fixed to the wooden point by a movable iron ring or *vidi*. The plough costs about 10s. (Rs. 5) and is drawn by eight bullocks and managed by two men. One man holds the plough, and the other, sitting in the middle of the yoke of the third pair, drives the leaders. The share lasts about ten to twelve years and the ropes six months.

The harrow or *kulav*, which costs about 5s. (Rs. 2½), loosens the soil before sowing, covers the sown seed, breaks clods, and uproots shrubs and weeds. In the east where lands are ploughed only after long intervals, every year to prepare the soil for sowing, the harrow, which turns up the soil about two inches, is worked three to four times. The harrow consists of two coulter joined by a level cross iron blade or *phás* set obliquely in a wooden beam called *dinda* about

Chapter IV.  
Agriculture.  
CROPS.

## FIELD TOOLS.

## Plough.

## Harrow.

Chapter IV.  
Agriculture.  
FIELD TOOLS.

four feet long. A pole unites it to the yoke and it is guided by an upright handle. To add weight to it generally two boys sit on the beam on either side of the handle and are ready to pick away any stone or stubble that may impede the harrow. Except in size the small harrow is exactly like the large and is used for clearing the land between the rows of a sugarcane crop. When the soil is very stiff a heavy harrow drawn by eight bullocks is used. This implement is also required to dig up earthnuts.

*Bullock Hoe.*

The bullock hoe or *kolpa* costing from 2s. to 3s. (Rs. 1-1½) has three blocks each with two hoes and is drawn by two to four bullocks. As the bullock hoe is worked, each hoe of the block passes on either side of the row taking the young crop between the hoes in the opening.

*Seed Drill.*

The seed-drill consists of three to six iron-shod coulters set in a block of wood and fed with seed through bamboo tubes from a wooden bowl into which the seed is dropped by hand. When mixed grains are to be sown in one of the drills, the driver plugs the cup hole for that drill and the seed is sown by a man who walks behind, through a hollow bamboo called *mogna*, which is attached by a rope to the drill. The seed-drill is used in sowing rice and early hill crops and has generally six iron-shod coulters. The *chanpan* has three coulters and is used for sowing early *javari* and other early crops. The *hadgi* is much heavier than the *chanpan* and has four coulters, and is used in sowing late *javari*, peas, gram, and other late crops. It is drawn by eight bullocks. The cotton seed-drill or *tipan* is made on the same plan as the grain-sowing *kurgi*. It has only three coulters and no cup with tubes. It is worked by a pair of bullocks. At the back of the beam of the seed-drill are tied by ropes three hollow bamboos or *mognás*, which are kept in furrows drilled by the iron coulters, by two sowers, who, from a clothful of seed at their waist, drop the seed through them.

*Sugarcane  
Mill.*

The sugarcane-mill or *ghóna* is only possessed by well-to-do husbandmen and Gujarát Vánis or traders who let it on hire at 1s. (8 as.) the day. The mill costs about £2 10s. (Rs. 25) and lasts five to six years. It consists of two solid *bábhul* cylinders called *navra* and *navri* or husband and wife set close together vertically between two thick wooden boards, the lower of which is cut out into a shallow trough. The *navra* is a little longer than the *navri* and passes through the upper board. The upper parts of both the cylinders are turned into double spiral screws which work in each other. To the upper end of the larger screw is fixed a lever. To work the mill the lever is united to the yoke of bullocks which are driven round the mill. As it is pressed out, the juice drops into the trough-shaped lower wooden board. From the board it passes through an under-ground tube into an earthen vessel called *mándan*. From the *mándan* it is taken to the boiling cauldron. Before the wooden mill was brought into use, a stone mill was used which has of late nearly disappeared.

*Leather Bag.*

The leather-bag or *mot* with its gear consists of a leather bag, two hemp ropes, the large called *náda* and the small *sonddor*, two

uprights supporting six feet above the well a fixed pulley about eighteen inches in diameter and its one foot long axle, and close to the ground a wooden cylinder about  $2\frac{1}{2}$  feet long and six inches in diameter. The cylinder is so fixed in the uprights as to move freely round itself. The leather-bag, which holds about sixty gallons, has two mouths, the upper one wide and laced to an iron or wooden ring, and the lower one tapering into a pipe. To the ring is tied the large rope or *náda* which passes over the pulley and joins the leather-bag to the bullock yoke. The *sonddor*, which passes over the cylinder on the edge of the well, is long enough to keep both the mouths of the bag in one level, as it is drawn up the well. As the bag reaches the edge of the well the *sonddor* ends, and the bag becoming straight empties itself in a cistern in front of the well. Though the bag is generally large enough to hold about sixty gallons nearly ten gallons are spilt into the well as the bag is being drawn up.

In Kolhápúr husbandmen use three kinds of carts, the *gáda*, the *bagi*, and the *chhakda*. The *gáda* or harvest-cart, which is going fastly out of use, is very heavy and can only be drawn by eight bullocks. It is nearly twelve feet long and about three and a half feet broad. The body of the cart consists of two long beams joined together by cross pieces fixed all along their lengths. Each wheel is made of a single solid block or two or three blocks joined together by a massive iron tire. Though clumsy and very heavy, with outriggers on both sides, it is very useful in carrying large quantities of grass and manure. The *gáda* costs £5 to £6 (Rs. 50-60). Of late the *gáda* has given place to the lighter *bagi*. It has spoked wheels about four feet in diameter with a massive tire. The framework is generally of *bábhul* and the axle is of iron. This cart carries twelve to fourteen hundredweights, is drawn by four bullocks, and costs £4 to £5 (Rs. 40-50). Except that it is lighter than the *bagi*, the *chhakda* does not differ in any way from the *bagi*. It is used in making trips to the coast or carrying field produce to distant markets, and costs £3 to £4 (Rs. 30-40).

The field tools used by the Konkan husbandmen are the plough or *nángar*, the four harrows, the *dátka*, the *dind* or *gutha*, the *páte*, and the log of wood for turning up the soil before the sowing of rice; picks for digging hill land, the billhook or *koyta*, the weeding sickle or *khurpe*, the crowbar or *sabbal*, the bullock hoe or *kolpa*, the harrow or *kulav*, and the seed-drill or *kurgi*. The plough is light, well suited to small patches of rice land, and is drawn by two bullocks. The *dátka* has wooden teeth and is drawn by a pair of bullocks. The *dind* or *gutha* is a log of wood used for breaking clods, and the *páte* is a flat board used for levelling and smoothing the soil.

In the plain or eastern country in good black soil it is usual to plough only once in several years. Ordinarily the land is considered fit for sowing after it has been stirred up a few inches with a *kulav* or harrow. When the land is overgrown with *haryáli* *Cynodon dactylon* and *kunda* grasses, it is dug up with the pickaxe to bring up their long strong and tortuous roots to the surface. These are

## Chapter IV.

## Agriculture.

## FIELD TOOLS.

## Leather Bag.

## Carts.

## PLOWING.

Chapter IV.  
Agriculture.  
PLOWING.

collected and removed from the field. When there is no ploughing the field is harrowed several times after a heavy April or May shower, and it is cleared of shrubs and weeds if there be any. The field is then fit for sowing. Ploughing is generally begun soon after the early crops are harvested in December or January, when the soil is moist and easily worked. As the soil dries, the clods become hard and stiff and after months of exposure to the weather, the lumps of earth become brittle and are easily broken down by the harrow or *kulav*. The plough is large and is drawn by eight bullocks. In the west the land is ploughed lengthwise with the light plough or *nāngri* in April; the clods are then broken by pickaxes and clubs, and a large beam called *dind* is dragged over to level the surface. The field is cross-ploughed and ploughed along the original furrow. Manure, according to the husbandman's means, is spread over the soil generally broadcast out of a basket and the field is ready for the seed. Hilly and hard soils are first broken with pickaxes and crowbars, and afterwards ploughed with a large plough, the bushes having been cut down during the previous hot season and burnt on the ground.

SOWING.

The seed is sown either by the hand or by seed-drill. The seed is covered with the *kulav* or harrow. A sort of brush harrow follows the *kulav*. This is generally made of *bābhul* branches. The brush harrow is used three or four times till the seedlings appear within a fortnight. Sheep are sometimes folded on the land for a night at this stage. The rows of young seedlings are styled *kākryas*.

MANURE.

The value of cowdung and sweepings as manure is generally understood, but artificial manures are not known. Rice and garden lands are invariably manured, but dry-crop lands only as often as the husbandmen have the means. Alluvial or *māli* lands on river banks are not manured at all. Black and good brown soils are manured only once in three years, but in red and poorer brown manure has to be applied every second year at least and in some cases, if the husbandman can afford it, every year. Holders of garden lands generally use all the available manure of their farm yards for their *mala* or garden especially for sugarcane; and thus their dry-crop lands suffer more than those of second class husbandmen, who have no garden lands and who use all their manure in their dry-crop lands. There are five kinds of manure. The first is mixed manure, which consists of crop stubble, ashes, droppings of cattle, urine, and every kind of rubbish stored in a pit near the husbandman's house. Here the heap rots. It is occasionally damped by the drainings from the cook room. As at night no grass is spread on the ground for cattle to lie down, there is no litter. Urine is either gathered by ducts and thrown into the pit, or is carefully mixed with the dung when cleaning the cattle shed every morning before it is thrown into the pit. During the dry months cowdung is made into fuel-cakes about a foot in diameter, dried and stacked, and so it goes to the manure-pit for only seven months April to December. In large towns besides the home supply the husbandman can buy of Gavlis or cowherds at the rupee rate of two cart-loads or thirty hundredweights of ordinary pit manure and three cart-

1. Farmyard  
Manure.



loads or forty-five hundredweights if poor in quality. It is estimated that after setting aside what is wanted for other purposes an ordinary third class holding of about ten acres of dry-crop land with two pairs of plough bullocks, a milch buffalo, and perhaps a steer, would yearly yield five cartloads of manure or just enough for half an acre. Nightsoil manure or *sonkhat* was formerly never used, but now the nightsoil manure prepared by the Kolhápúr municipality according to the dry-earth system is freely used by husbandmen of the surrounding villages and is highly valued especially for sugarcane, tobacco, and other rich crops. The third kind of manure consists of sheep and goat droppings. The husbandman engages a shepherd to fold his flocks on his field for a certain number of days and pays him in grain at the rate of 80 to 120 pounds grain worth about 3s. (Rs. 1½) a thousand sheep penned in his field a night. In the west stubble, weeds, and scrub-forest wood or *ráb* are gathered, heaped on the field and burnt, and the ashes are mixed with soil by ploughing. Green manure is the fifth kind of manure. Bombay hemp or *tág* and sometimes sesame is sown and is allowed to grow for three months when it begins to flower. It is then ploughed in with the *kulav*. This manure is considered good for the sugarcane crop. The supply of manure is limited. An acre of sugarcane land receives from thirty-five to fifty cartloads of mixed manure and the droppings and urine of a thousand sheep for six to eight days. Where it can be had half the quantity of nightsoil manure is sufficient for the same area. An acre of rice land requires about twenty cartloads, and an acre of dry-crop land which is manured every second third or fourth year as circumstances allow, receives generally ten carts. Sheep are folded on the land whenever available. It is considered essential to adopt this method of manuring for tobacco and chillies. The late *jvári*, cotton, gram, and wheat are generally sown without manure.

There are no irrigation works, old or new, though Kolhápúr, with ranges of hills here and there, is apparently favourably situated. There are no canals except a few *páts* or water-courses which dry by January or February, and, except at Kolhápúr, where the Rankála and one or two other ponds water a few acres of garden land, there are no ponds or reservoirs large enough to water any considerable area. But a great scope exists for improving reservoirs by throwing embankments across the rivers in the hilly sub-divisions. What little irrigation exists is carried on chiefly from wells or *budkis* dug in stream beds. Water is taken out from these wells by the *mot* or water-bag.<sup>1</sup> The number of wells has greatly increased within the last twenty years and many old wells have been substantially rebuilt. In 1881 the number of working wells was reported to be 7547. Everywhere the cultivators show a desire to avail themselves of the means of irrigation for garden crops which are more profitable than dry-crops. The chief irrigated crops are sugarcane, *náchni*, spelt wheat, chillies, turmeric, onions, garlic, and

## Chapter IV. Agriculture.

### MANURE.

#### 2. Nightsoil or Poudrette.

#### 3. Sheepdung.

#### 4. Ráb or Wood- ash Manure.

#### 5. Green Manure.

### IRRIGATION.

<sup>1</sup> Details of the working of the *mot* are given in the Belgaum Statistical Account, p. 241.

# Chapter IV. Agriculture.

## WEEDING.

sweet potatoes. In 1881, of 559,736 acres, the total area under actual tillage, 15,290 acres or 2.73 per cent were watered.

When the young plants have appeared above ground, weeding begins. Till the end of the second month it is generally carried by a light hoe or *kolpa* drawn by bullocks. After the second month when the crops grow too high to permit of bullock hoeing without damage, hand weeding is resorted to.

## WATCHING.

From the time the grain forms, to drive off birds the crop is watched from a wooden platform generally raised in every field. The husbandman, who watches the crop, shouts and slings stones.

## REAPING.

When it is ripe, the crop is either reaped with the sickle or pulled by the roots, and kept where it is cut for a few days to dry. It is then bound in sheaves and stacked with the ears of grain outward. The stack or *buchad* is kept a fortnight to a month, by the end of which the ears are thoroughly dried and the crop is carried to the threshing floor or *khale*.

## THRESHING.

The threshing floor or *khale* is prepared in the hardest part of the field by wetting and beating the ground with wooden mallets till it is hard and smooth and then by smearing it with cowdung. An upright post about six feet high is set in the centre, and round this post are thrown the heads of grain or the whole plant, as the case may be, to be thrashed. A team of ten muzzled oxen is tied to the pole side by side and driven round and round to tread out the grain. It is estimated that a pair of bullocks can thrash out about 320 pounds (2 *mans*) of grain in a day; but however large the team may be, not more than two *khandis* (2½ tons) can be trodden out at a time. Usually one *khandi* is the maximum on the floor at one time. Some crops such as hemp, castorseed, some pulses, *kardai*, and *khapli* or spelt are threshed by hand with sticks on the floor. Dry sesame plants are only shaken with the hand to set free the seed.

## WINNOWING.

The grain is winnowed from the chaff by the help of the wind. Winnowing baskets or *sups* are filled with the grain and chaff as it comes from the threshing floor and are handed by one man to a second man who stands on a high stool called *vāvdi* and empties the basket slowly with a shaking motion. The heavy grain falls on the ground prepared for it and the light chaff with dust is blown aside.

## STORING.

In the east grain is often stored in under-ground chambers. Grain is also often in the east and always in the west stored in cylindrical baskets kept in the husbandman's house.

## MIXED SOWINGS.

The sowing of mixed crops is a common practice with Kolhápúr husbandmen. As many as nine crops may be seen in the same row at the same time, alternating with a certain number of rows of the principal crop. *Bājri* as a principal crop is sown with *tur*, *ambádi*, *matki*, *kulthi*, and *korte*, in different proportions and in different combinations; *shálu* or late Indian millet, with castor seed, gram, barley, *pávta*, peas, and linseed; cotton with sesame, *kulith*, coriander, *ova*, fennel, carrot, *kápusválke*, chillies, *rála*, and linseed; *jondhla* or early Indian millet, with *udid*, *tur*, *ambádi*, *mug*, and *matki*; *bhuimug* or earthnut, with maize, *rājgira*, *chavli*, and

coriander; rice with *tur* and *ambádi*; *náchni* with *tur*, *ambádi*, and maize; *sáva* with *gidgyáp* a variety of *jondhla*, *tur*, and *korte*; *khapli* or spelt with mustard seed and maize; maize with *pávta*, castor seed, watermelons, *bhopla* or gourd, cucumber, *bhendi*, *govári*, and fennel; gram with *kardai*, mustard seed, and *shálu* or late Indian millet; and chillies with coriander and cotton. Besides the above, *vari* is sown with maize, wheat with *kardai* and linseed, *rála* with maize, *mug* with *rála*, and *charli* with *náchni*.

*Kumri* or woodash tillage is much practised on the slopes of the Sahyádris. Under this tillage a patch of brushwood covered ground is chosen by the husbandman. In April or May he burns the bushes in the ground with branches of some other trees. If it is flat, the ground is ploughed, and, if sloping, only scratched by a pickaxe or *kudal*; and just after the first shower of rain, *náchni* is sown either by the seed-drill or broadcast. Before the crop ripens by the end of September or October, the field is weeded by hand twice or thrice. The average acre outturn in the first year is about 800 pounds of grain. In the second year *sáva*, *vari*, or some other coarser grain is sown in the same ground without fresh burning of the soil. The average acre outturn in the second year is about 480 pounds. In superior soils generally sesame is raised in the third year, and then the land is allowed to lie fallow till it is again covered with scrub. Of late strict orders have been issued prohibiting this mode of tillage within five miles of the ridge of the Sahyádris, and it is probable the area under *kumri* tillage will greatly be curtailed as forest conservancy comes into force.

The value of a change of cropping is well known, and rotation of crops, according to certain fixed rules, is observed. In ordinary rice land, rice is taken year by year, so in watered and other superior rice lands which are retentive of moisture, but with this difference that a second crop of peas, gram, beans, or *khapli* or watered wheat is raised; sugarcane, as a rule, is grown on the same land only once in three years. Sugarcane is followed either by *javári* mixed with *tur* or rice and *khapli* or *náchni* and *khapli* or sweet potatoes in succession. Sometimes instead of *khapli*, brinjals, carrots, garlic or onions also follow rice or *náchni*. In the third year the soil is exhausted to a certain extent and is not in a state to yield a bumper crop. The husbandman then puts in such crops as tend to the healthy growth of sugarcane in the succeeding year. These crops are called *bevads* or preparatory crops. The usual sugarcane *bevads* are Bombay hemp, chillies, tobacco, *udid*, *rála*, and *turmeric*, among which hemp and chillies are considered the best. When it follows *rála*, hemp is generally ploughed in as a green manure. In dry-crop lands near the Sahyádris or in *kumri* lands *náchni* in the first year is followed by *sáva* in the second year and sesame or *korte* in the third year; or *javári* in the first, *náchni* in the second, and hemp in the third; or *harik* in the first, *barag* in the second, and sesame in the third. In inferior lands under *kumri* tillage, no rotation will permit cropping for more than two years without fallow. In such lands *náchni* or *harik* in the first year is followed by *vari* or *barag* in the second year, and then by a long fallow of eight or nine

#### Chapter IV. Agriculture.

##### WOODASH TILLAGE.

##### ROTATION OF CROPS.

# Chapter IV. Agriculture.

## ROTATION OF CROPS.

years. In black soil where the holdings are small, husbandmen sow *javári* and cotton alternately. But where holdings are large, a better rotation is adopted, namely cotton in the first year, tobacco in the second year, gram and wheat in the third year, and *javári* in the fourth year. Gram is considered the best *bevad* or preparatory crop for *javári*. It is also as a late crop raised successively in the same field for several years.

## FALLOWS.

As shown above fallows are very rare in the flat country of the eastern parts of the State. The fertility of the soil is maintained by the alternation of cereals with oilseeds pulses and fibre plants, by the mixtures of crops, and by manuring. In the western uplands crops are secured for three or four years, but fallows varying from three to twelve years are then necessary. Lastly in lands under *kumri* after two or at most three years of cropping absolute rest for seven to twelve years is needed to allow the scrub to grow again.

## CROP DETAILS. Cereals.

The following are the chief details of the leading field and garden crops. Of cereals there are fifteen :

### Kolhápúr Cereals.

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Bájri</i> ...	Spiked Millet...	<i>Penicillaria spicata</i> .
2	<i>Barag</i> ...	Millet ...	<i>Panicum miliaceum</i> .
3	<i>Bhát</i> ...	Rice ...	<i>Oryza sativa</i> .
4	<i>Gahu</i> ...	Wheat ...	<i>Triticum aestivum</i> .
5	<i>Khapli</i> ...	Spelt ...	<i>Triticum speltum</i> .
6	<i>Harik</i> ...	.....	<i>Paspalum frumentaceum</i> .
7	<i>Jedri</i> ...	Indian Millet ...	<i>Sorghum vulgare</i> .
8	<i>Káng</i> ...	.....	<i>Panicum italicum</i> .
9	<i>Maka</i> ...	Maize ...	<i>Zea mays</i> .
10	<i>Náchni</i> ...	.....	<i>Eleusine corocana</i> .
11	<i>Rájjira</i> ...	.....	<i>Amaranthus polygamus</i> .
12	<i>Bála</i> ...	.....	<i>Panicum italicum</i> .
13	<i>Sáru</i> ...	Barley ...	<i>Hordeum hexastichon</i> .
14	<i>Sáva</i> ...	.....	<i>Panicum frumentaceum</i> .
15	<i>Vari</i> ...	.....	<i>Panicum miliare</i> .

### *Bájri*.

*Bájri*, of only one kind with an area of 32,570 acres,<sup>1</sup> holds the fourth place among the crops of the State. It is a finer grain than *javári*, and requires much more careful tillage. Though it is sometimes grown in garden lands and river-side alluvial deposits, the best lands suited to it are the red, brown, and alluvial soils. It is generally sown in August-September and reaped after four months. It holds a secondary place among the staples of the State. The stalks called *savam* are used as fodder for cattle. The average acre outturn is about 850 pounds.

### *Rice*.

Rice, with an area of 89,038 acres, is an early crop, sown towards the end of May and in the beginning of June. Rice holds the second place among the cereals of the State, and the rice-crop forms twelve per cent of the entire produce of the country. It is the staple food of all the richer classes and the inhabitants of the tract near the Sahyádris. Rice is grown throughout the State, especially in the western hilly sub-divisions where the rainfall is heavy. The crop is raised in the rich valleys and on the slopes of the hill-

<sup>1</sup> The tillage area given here is throughout for 1881-82.

sides, where the tillage is carried far up the ascent in a series of well defined terraces prepared with embankments to retain the soil and regulate the water-supply. In Kolhápura twenty-three varieties of rice are grown, of which about fifteen ripen in September and are called *halve bhát* or early rice; seven ripen by the end of October or the beginning of November and are called *mahan bhát* or late rice; and one, *váyangan* the only irrigated rice-crop, ripens by the end of March.<sup>1</sup> It is grown only in a few places in the alluvial river-beds and in hill-side terraces well supplied with water. In Kolhápura rice grown in Ajra is considered the best. Two varieties *jirge* and *kálebhát* are also highly esteemed for their delicious odour when cooked.

There are four distinct modes of cultivating rice: 1. It is raised from rábed seedlings near the Sahyádris. In April a plot is chosen for the seedbed, and on it are spread layers of cowdung brushwood and straw. These layers are called *ráb*.<sup>2</sup> When it is quite dry the *ráb* is fired at noon. The next morning the plot is ploughed with a light plough to mix the ashes with the soil. After the first rain in June the seed is sown broadcast and ploughed in. The seedbed is then carefully levelled. By the end of a fortnight when six or eight inches high, the seedlings are taken from the seedbed and planted out by hand in bundles of four to six at a distance of a span from one another in wet narrow fields which have been ploughed four times, well manured, and levelled. If rain fails the plants are watered. In September the crop is weeded twice, and by the latter end of October it is reaped and left on the ground for a day or two to dry. It is carried to the thrashing floor where it remains spread on straw for two days, when it is trodden out by bullocks and winnowed by hand. 2. It is raised from artificially germinated seed. To induce germination the seed is mixed with cowdung and hot water, placed in bundles of grass, and subjected to pressure for three to four days. It is then sown broadcast on a carefully prepared level seedbed and left as it falls. The seedbed requires to be watched for two days to protect the uncovered seed from birds. Sometimes the seedlings are not transplanted but transplantation as in the first mode of cultivation is the custom. 3. In the plain country the seed is sown broadcast, but there is no transplanting. 4. Further east where the land is more level, rice is sown by the ordinary seed-drill. Rice is usually pounded and then called *tándul* and boiled for food. But it is also customary to grind the cleaned rice into flour. Of this a coarse bread is made. The straw is used as cattle fodder. An average acre outturn of rice in husk varies from 900 to 1280 pounds. A large quantity of rice is exported from the State to the principal markets of the Eastern Deccan and other parts of the Bombay Karnátaḱ.

## Chapter IV.

## Agriculture.

## CROP DETAILS.

## Rice.

<sup>1</sup> The twenty-three varieties of rice are: *ambemohor*, *antarsál*, *aviste*, *bhongál*, *gajvel*, *jirge*, *joge*, *jondhle*, *kálebhát*, *karámat*, *khavrisál*, *khársál*, *kokansál*, *kothimbirsál*, *lavhesál*, *patni*, *ráybhog*, *somsál*, *támsál*, *váksál*, *vándarsál*, *varanjál*, and *váyangan*.

<sup>2</sup> The chief difference between *ráb* and *kumri*, the two forms of woodash tillage, is that in *ráb* the burning is confined to the seedbed.

Chapter IV.  
Agriculture.

CROP DETAILS.

Wheat and Spelt.

*Gahu* together with *khapli* showed an area of 10,014 acres, thus holding the twelfth place in the order of crop returns. Wheat is a late or cold weather crop. As a dry-crop it is grown in black soil where a shower of rain, as the crop comes above ground, is considered beneficial; but in cool seasonable weather with heavy dews it thrives best. As a wet crop it is grown in garden lands. The chief varieties of Kolhápur wheat are *shetgahu* a dry-crop, and *khapli* usually but incorrectly considered as a variety of wheat and *pángahu*, two watered crops. *Shetgahu* a hard red variety is grown in black and alluvial soils as cold weather crop. Both these soils are highly retentive of moisture and in them it thrives best. *Khapli* is largely grown in watered lands as a crop alternating with sugarcane. The grain is coated with an adhering husk which cannot be separated without pounding. *Pángahu*, which is said to have travelled from Gujarát during the 1876 famine, is yellowish, large, full, and soft. It is only sown to a small extent with *khapli* in garden lands. But as it is one of the varieties now so largely exported to Europe, it is likely that it will spread as people understand its value better. To sow an acre with wheat, forty to eighty pounds of seed are required. In black soil the land is prepared by running the harrow three to four times over the land so as to clear it of weeds. In rice or garden lands where wheat is grown as a second crop, the soil is first broken up by the plough and then harrowed. Wheat is sown with the heavy seed-drill, followed by the harrow to cover up the seed. The dry-crop variety ripens in about four months. The irrigated varieties take a month longer. The average acre outturn is about 480 pounds. The ripe grain is principally made into bread. It is used by rich classes and seldom by the poor except on feast days. The flour is also used largely in pastry and sweetmeats. A small quantity of wheat is exported to the Konkan.

*Harik.*

*Harik* is grown in Sahyádrí villages both on flat lands and on steep hill slopes, where, according to a general practice, it follows *vari* and is followed by sesame. As it is the cheapest grain in the State *harik* is largely used by the poorer classes. It is generally sown about the end of June and takes about four months to ripen. The average acre outturn of *harik* is estimated to be 500 pounds.

*Jvári.*

*Jvári*, the most largely grown cereal in Kolhápur, covered 260,197 acres. There are numerous varieties of Indian millet, some of which belong to the early and others to the late harvest. The early crop is called *kár* and the late *shálu*. The *kár* or early Indian millet *Holcus sorghum* with 220,697 acres, is the staple food of the eastern sub-divisions and with *náchni* is largely used by the lower classes of the western sub-divisions. It is sown from the beginning of June to about the middle of July and takes four to five months to ripen. It has eleven varieties, *dagdíkoli*, *dukri*, *gidgyáp*, *gulbhendi*, *khirságar*, *kuchkuchi*, *madangitti*, *motichur*, *sadgar*, *turáti*, and *vángi*. Of these the *gidgyáp*, *dukri*, and *sadgar* are common and are grown as substantive crops. The others mixed with these are sown to a small extent. The unripe ears of the *khirságar*, *kuchkuchi*, and *gulbhendi* varieties are plucked and roasted. The stalks or *kadba* provide the



best fodder for cattle, those of *gidgyáp* being specially preferred to those of other varieties on account of their being leafy and soft. In *mál* or uplands the early varieties are sown with occasional rows of *ambádi*, *kulith*, *matki*, *mug*, *náchni*, *rála*, *tur*, and *udid*. In good black soil free from weeds, the land for the early varieties does not require ploughing every year, but it is only stirred up with the *kulav* before sowing. Inferior black soil, red soil, and land overgrown with weeds always require ploughing. Whenever practicable five to ten cart-loads of manure are laid on an acre of millet field. The average acre outturn of the early varieties is 1170 pounds. A small quantity of it is sent to the Konkan districts below the Sahyádris, and a large portion is consumed locally. *Shálu* or late Indian millet *Holcus saccharatum*, with 39,500 acres, is not so important as the early or *kár* millet. It is sown chiefly near river-banks and in the Shirol and Gadinglaj sub-divisions where, on account of the lateness of the rains, early millet cannot be sown. Its grain is much prized for its white and sweet flour; and as it is hard and without much pulp, its stalk is not considered good food for cattle. The four varieties of the late Indian millet are *kálgundi*, *machchundi*, *mangundi*, and *mháldandi*. It is generally sown in September and October and takes about five months to mature. The average acre outturn is about 960 pounds. *Shálu* is grown in garden lands as a fodder crop only for cattle in the hot season.

*Maka*, with an area of 3295 acres, is one of the important crops in the State. This crop is largely grown to provide unripe ears for roasting. When specially so intended it is grown in garden lands and in small gardens attached to houses. It is sown in June, and by the end of two months and a half the heads or *buthás* become ripe enough for roasting. The regular crop is sown in September all along the river-banks and as a row crop in turmeric, earthnut, *rála*, *náchni*, and *vari* fields. It takes about four months to ripen. The average acre outturn is about 1300 pounds. The middle and poorer classes use maize as a substitute of *javári*.

*Náchni* or *nágli*, with 82,980 acres, is the staple food of the people in the west and holds the third place among the crops of the State. It is also largely sown in garden and alluvial lands in the plain country. Its tillage differs considerably in black and red soils. In red soil the same process of burning and preparing the soil as used for rice is pursued. As an early crop it is sown in June either by hand or with the drill. After it is reaped, it is dried for a few days before it is thrashed. The husk and straw are used as cattle-fodder. On hill land where *ráb* is practised it is always the first crop after the fallow. In the plain country the land is ploughed and harrowed and the seed drilled as for *javári*. In the Konkan Ghátmátha it is also grown as a cold weather crop by the help of water. In garden and alluvial lands *náchni* is always followed by a second crop of watered wheat, peas, gram, castor seed, or other crop. Some pulses and *javári* are sown with *náchni* as row crops. On hill-side slopes *náchni* is grown as a mixed crop with *káng*. *Náchni* takes about three to four months to harvest. The average acre outturn is about 300 pounds in hilly lands and about 1600 pounds in alluvial and garden lands.

Chapter IV.  
Agriculture.  
CROP DETAILS.  
*Jvári*.

*Maize*.

*Náchni*.

# Chapter IV. Agriculture.

## CROP DETAILS.

### *Rála.*

*Rála*, with an area of 19,125 acres, holds the ninth place among the crops of the State. Poor people use it as a substitute for rice. In Kolhápúr five varieties of *rála* are grown. *Lácka* and *dhoka* as substantive crops and *panada* as a row crop are grown in garden lands. *Lunga* or *mohana* is grown as an early crop on the *mál* lands. *Tuljápuri* is sown as a row crop in cotton fields. When *rála* is sown as a principal crop, *udid*, *mug*, and sometimes *tur* are sown with it. The average acre outturn is about 850 pounds.

### *Sáva.*

*Sáva*, with an area of 19,952 acres, holds the eighth place among the crops of the State. It is much used by middle-class and poor husbandmen in the sub-divisions of Ajra, Bhudargad, Gadinglaj, and Panhála. It is sown broadcast in June and harvested after three or four months. The average acre outturn of *sáva* is about 480 pounds.

### *Barley.*

*Sátu*, with an area of 146 acres, is grown only to a limited extent. In rice fields it is grown as a second crop and as subordinate crop with other cereals. It is sown in the end of September and in the beginning of October and harvested in January. The average acre outturn is about 320 pounds.

### *Vari.*

*Vari*, with an area of 7148 acres, stands next to *náchni* as a staple food in the State. Kolhápúr *vari* is of three kinds, *vari* proper, *gholvari*, and *vara*. The first two kinds are grown in poor uplands and *kumri* lands. They are sown in June and are harvested after two months and a half. *Vara* is grown as a garden crop in black soil in the plain country. Its grain is larger than the *vari* proper. The average acre outturn of the latter and *gholvari* is about 500 pounds and that of *vara* about 700 pounds.

Besides these chief cereals some coarse grains such as *barag*, *káng*, and *rájgira* are sparingly grown. They are sown in June and harvested after three to four months.

### *Pulses.*

Ten pulses are grown in Kolhápúr. The details are :

#### *Kolhápúr Pulses.*

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Chavli</i> ...	.....	<i>Vigna catjang.</i>
2	<i>Harbhara</i> ...	Gram ...	<i>Cicer arietinum.</i>
3	<i>Kulth</i> ...	Horse-gram ...	<i>Dolichos biflorus.</i>
4	<i>Masur</i> ...	Lentil ...	<i>Ervum lens.</i>
5	<i>Math</i> ...	Kidney Bean ...	<i>Phaseolus aconitifolius.</i>
6	<i>Mug</i> ...	Green Gram ...	<i>Phaseolus mungo.</i>
7	<i>Pavta</i> ...	.....	<i>Dolichos lablab.</i>
8	<i>Tur</i> ...	Pigeon Pea ...	<i>Cajanus indicus.</i>
9	<i>Udid</i> ...	Black Gram ...	<i>Phaseolus radiatus.</i>
10	<i>Vatana</i> ...	Peas ...	<i>Pisum sativum.</i>

### *Gram.*

*Harbhara*, with an area of 17,738 acres, holds the tenth place among the crops of the State. Gram is a cold-weather crop. It is generally sown in the end of September and in the beginning of October, and takes about five months to harvest. In black soil it is sown as a first crop, and in rice and garden lands it is raised as a second crop following rice or *náchni*. It is also grown as a subordinate crop with *shálu* or late Indian millet, and sometimes barley and *kardai* are sown mixed with it. Gram is considered

the best *bevad* or preparatory crop for *javári* and cotton. It certainly checks weeds. But it as certainly benefits the land in other ways also, which are not yet satisfactorily known. The average acre outturn is about 650 pounds. It is eaten raw, but is also made into *dál* and eaten boiled in a variety of ways, and its flour is used in many sweetmeats. It is given whole to horses, and thus a large quantity is consumed by the State cavalry and in the palace stables. Husbandmen use the young leaves and shoots as a vegetable.

*Mug*, with an area of 3308 acres, is grown to a limited extent. It is sown as a subordinate crop in June or July and reaped in about four months. The average acre outturn is about 300 pounds.

*Tur*, with an area of 22,078 acres, holds the seventh place among the crops of the State. It is generally grown as a subordinate crop with *báji* or *javári* in black and alluvial soils, and with *náchni* or *sáva* in red soil. *Tur* does not yield a certain crop every year. It succeeds best when the main crop with which it is sown fails. *Tur* is said to flower seven times a season. Its outturn is precarious because especially in cloudy weather it is much eaten by worms. *Tur* is generally sown as an early mixed crop. It ripens slowly and always remains standing after the other crops of the field have been cut. It is generally harvested in January-February, and its acre outturn varies from 150 pounds to 600 pounds. The green pods are eaten as a vegetable and the ripe pulse is split and eaten boiled in a variety of ways. The yellow split pulse is in common use, being made into *ánti* and *varan* which resemble porridge. The leaves and husk are used as cattle fodder. The stalks make the best charcoal for gunpowder.

*Udid*, with 3308 acres, is grown to a small extent chiefly in the Alta, Gadinglaj, and Panhála sub-divisions. It is sometimes grown alone in black and red soils, but it is generally grown as a mixed crop with *javári*, *náchni*, *rála*, and *sáva*. It is considered the most fattening grain for horned cattle and is also used as a pulse. It is generally sown in June and harvested by the end of August. The average acre outturn is about 300 pounds.

*Vátána*, with an area of 4470 acres, is sown in rice or *náchni* fields after those crops have been reaped, between lines of *tur* which remain standing. In alluvial land it is sown as a subordinate crop with *shálu* or late Indian millet. In the western sub-divisions peas are largely used in the place of gram and *tur*. Peas are sown in September-October and are harvested in January-February. The average acre outturn of peas is about 300 pounds.

*Chavli*, *kulith*, *math*, *masur*, and *pávta* are grown only to a small extent.

Eight oilseeds are grown in Kolhápúr. The oils of some are solely used in cooking, of some both in cooking and burning, of some in burning and medicine, and of some in medicine only. The spread of kerosine as a lamp-oil is said to have slackened the demand for country oils and the area under oilseeds has fallen. The details are :

## Chapter IV. Agriculture.

### CROP DETAILS.

*Gram.*

*Mug.*

*Tur.*

*Udid.*

*Peas.*

*Oilseeds.*

Chapter IV.  
Agriculture.  
CROP DETAILS.

## Kollāpur Oilseeds.

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Ambādi</i> ...	Brown Hemp ...	<i>Hibiscus cannabinus</i> .
2	<i>Bhuimug</i> ...	Earthnut ...	<i>Arachis hypogaea</i> .
3	<i>Erandi</i> ...	Castor-seed ...	<i>Ricinus communis</i> .
4	<i>Javas</i> ...	Linseed ...	<i>Linum usitatissimum</i> .
5	<i>Kardai</i> ...	Safflower ...	<i>Carthamus tinctorius</i> .
6	<i>Korte</i> ...	.....	<i>Vernonia anthelmintica</i> .
7	<i>Mohari</i> ...	Mustard ...	<i>Sinapis racemosa</i> .
8	<i>Tū</i> ...	Sesame ...	<i>Sesamum indicum</i> .

*Brown Hemp.*

*Ambādi*, with an area of 482 acres, is grown as an early crop. It is generally sown with *bājri*, *javāri*, *nāchni*, *rāla*, and rice. It is grown both for its seed and fibre. According to his yearly want, every husbandman grows more or less *ambādi*. It is sown in June and ripens late in December. Oil is extracted from the ripe seed generally mixed with the seeds of safflower. The bark yields a valuable fibre which is separated from the stalk by soaking. The stalks are tied in small bundles and kept for five to six days in water. When thoroughly soaked, the bundles are taken out, and every stalk is separately washed. The bark is then stripped off beginning at the root end and dried in the sun. The dry bark is tied in bundles and either sent to market or kept for home use. It is made into ropes for various purposes. As *ambādi* grown in the State is not enough to meet the wants of the people, aloe fibre is extensively used by husbandmen for rope-making. When *ambādi* is grown in earthnut and sugarcane fields, its tender leaves, which have an acid flavour, are used as a vegetable.

*Earthnut.*

*Bhuimug*, with an area of 27,543 acres, holds the sixth place among the crops of the State. It is grown to a considerable extent as a garden crop. *Bhuimug* thrives best in alluvial black soils, and though it will grow in other soils such as *chunghad*, it then requires liberal manuring. It is sown in June and harvested in January. After the south-west monsoon has ceased in November and December, it requires four to five waterings. Poorer classes use it at the evening meal and on fast days. Almost all classes eat it parched. An edible oil is pressed from the nuts which are first mixed with *kardai*. When not mixed with *kardai*, five pounds of *bhuimug* yield about one pound of oil. Though edible the oil is chiefly used for burning. The oil-cake or *pend*, the residue left after the oil has been expressed, is an excellent food for cattle. The average acre outturn of *bhuimug* is thirteen hundredweights without shells and seventeen hundredweights with shells.

*Castor Seed.*

*Erandi*, with an area of 1986 acres, is either grown by itself or with late *javāri* and maize in red, black, and alluvial soils, and harvested in January. There are three varieties, *chitkya* or small seeded, *dholkya* or large seeded, and *ghaderandi*. The first two varieties are grown as ordinary field crops, and the third, as it requires much water, is planted either near the leading channel of a sugarcane field or around the field. The oil, which is used more for burning than as a medicine, is drawn by boiling the bruised beans and skimming from the surface. To raise the oil to the surface, cold

water is poured on. The refuse is an excellent manure for plantain trees and the stems are used as fuel or thatch. The average acre outturn is 530 pounds.

*Javas*, with an area of 505 acres, is grown to very small extent. It is grown with cotton, late *jvári*, and wheat. It is harvested in about 3½ months. Pure linseed oil is expressed for painting purposes only. Most of the linseed grown in the State is sent to Bombay. Its average acre outturn is 375 pounds.

*Kardai*, with an area of 5223 acres, is grown in considerable quantities as a late crop. It is sown in September and harvested in January. In rich black soil it is grown with gram and wheat and in poor soil as a regular rotation crop. Though much esteemed in cooking pure *kardai* oil is seldom offered for sale. As it does alone not yield a large quantity of oil, *kardai* seed is generally mixed with *ambádi*, *bluimug*, *korte*, and *javas*. The average acre outturn of *kardai* is 600 pounds.

*Korte*, with an area of 9442 acres, is grown in considerable quantities as an oilseed, and holds the fourteenth place among the crops of the State. It is grown both in red hilly lands and in black soil. Though sometimes sown with *bájri* and *rála*, *korte* is often raised as a second crop in land first cropped with *rála sáva* and *vara*. As an early crop in red hilly soil it is sown in June, and in black soil always in August. It is always pressed mixed with *kardai*. The average acre outturn is about 300 pounds.

*Mohari* is grown in small quantities as a row crop with wheat, peas, onions, maize, and earthnut. The seed is used in spices, the seed-oil in medicine, and the young leaves as a vegetable.

*Til*, with an area of 927 acres, is grown only in small quantities. It is of two kinds, black or brown and white. It is sown in June and harvested in September. As the produce is small, sesame is not much used as an oilseed. It is sometimes eaten raw and forms an ingredient in many sweetmeats. Sugar-coated sesame seed is distributed among friends and kinsfolk on *Sankránt* the 12th of January. The average acre outturn is 320 pounds.

Besides these, oil is expressed from *kángoni* and *karanj*. These seeds are gathered in the western forests and the oil obtained from them is mostly used in medicine.

Four fibre plants are grown in Kolhápúr. The details are:

*Kolhápúr Fibre Plants.*

No.	MARÁTHI.	ENGLISH.	BOTANICAL.
1	<i>Ambádi</i> ...	Brown Hemp ...	<i>Hibiscus cannabinus</i> .
2	<i>Gháyamári</i> ...	Aloe ...	<i>Aloe indica</i> .
3	<i>Kápus</i> ...	Cotton ...	<i>Gossypium herbaceum</i> .
4	<i>Tág</i> ...	Bombay Hemp ...	<i>Crotalaria juncea</i> .

*Ambádi*. See under Oilseeds.

*Gháyamári* is planted along hedges. As aloe fibre is much used in rope-making, its cultivation is likely to increase and will probably soon compete with brown hemp. The broad aloe leaves are cut into

Chapter IV.  
Agriculture.

CROP DETAILS.  
*Linseed.*

*Safflower.*

*Korte.*

*Mustard.*

*Sesame.*

*Fibre Plants.*

*Ambádi.*  
*Aloe.*

Chapter IV.  
Agriculture.  
CROP DETAILS.

Cotton.

strips and soaked for ten to twelve days and then dried in the sun and beaten with a wooden mallet to separate the fibre. The ropes, which are used for various field purposes, are generally made by Māngs and sometimes by husbandmen.

*Kāpus*, with an area of 29,192 acres, is the most important fibre crop and holds the fifth place among the crops of the State. As attempts in growing the American and other exotic varieties have not proved successful only the indigenous variety is sown. It is grown in black soil in the eastern parts and thrives best in the Ichalkaranji and Shirol sub-divisions. It is sown in August and harvested in February. The seed is mixed with fine manure and sown with the seed-drill. Cotton is picked by women, who generally receive the tenth part of the picked cotton as their wages. The seed is given to cattle as food, the leaves to sheep and goats, and the dry stalks are used as fuel. In 1881 the cotton crop was estimated at about 9790 hundredweights of cleaned cotton or thirty-seven pounds per acre. The yield per acre varies from 250 to 300 pounds seed cotton in rich soils and from 125 to 250 pounds in ordinary soils. The proportion, by weight, of seed to clean cotton is three to one. The husbandman for one acre of cotton spends about 7*s.* (Rs. 3½) in labour, 4*s.* (Rs. 2) in manure, and 1½*d.* (1 *a.*) in seed, and pays 9*s.* 3*d.* (Rs. 4½) in rich soils and 6*s.* (Rs. 3) in ordinary soils as rental, and according to the season his profit varies from 11*s.* 6*d.* (Rs. 5¾) to 4*s.* 6*d.* (Rs. 2½) in rich soils, and from 7*s.* 6*d.* (Rs. 3¾) to 3*s.* (Rs. 1½) in ordinary soils.

Bombay Hemp.

*Tāg*, with an area of 3160 acres, is grown as a fibre crop. As it is supposed to refresh the exhausted soil, it is considered a good *bevad* or preparatory crop, and is grown as such every second or third year in some of the fields required for sugarcane, tobacco, and other rich crops. Sometimes it is grown as a second crop and ploughed in when young as a green manure. It is sown in August and harvested in December. When full-sized the plants are cut and the heads are separated. The plants are then tied in bundles and soaked for about a week, when they are dried in the sun, and the bark is separated in the same way as in *ambādi*. The bark is tied in bundles, soaked in water, and beaten to loosen the fibre. Of the fibre a long smooth thread is spun by means of a *chāti* or reel, from which are made well-ropes, twine, and sacking. The average acre outturn of Bombay hemp is 150 pounds.

Dyes.

Only one dye is grown in Kolhāpur. *Halad*, Turmeric, *Curcuma longa*, with 1267 acres, holds an important place in the garden crops of the State. In Kolhāpur two varieties of turmeric, *gadvi* and *lokhandi*, are grown. *Gadvi* is short and spare and is not much grown. *Lokhandi* produces a long hard and well-filled tuber, and is widely grown. When there is a good supply of well-water turmeric is sown in May, otherwise it is generally sown in June after the first rain. Except that it is not so well manured, the land is ploughed and prepared in the same way as for sugarcane. Turmeric seed is planted on the sides of furrows nine inches apart and alternating with rows of maize. After the maize crop is



removed, the turmeric crop is manured with cowdung. It requires watering once a week. It is harvested in January. The tubers are dug out by women with the *kudal* or pickaxe. The central and round tuber is kept for seed and the offshoots are boiled and dried. The unripe tuber which is called *chora* is sold to Atárs or perfumers for making *kunku* or redpowder with which Hindu women mark their brows. The root is in universal use as a condiment, being the chief constituent of curry powder. Only a small part of Kolhápur *halad* is used locally. The greater part is exported to Bombay. The average acre outturn is 720 pounds of dry turmeric besides the seed.

Three narcotics are grown in Kolhápur. The details are :

*Kolhápur Narcotics.*

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Pán</i> ...	Betel-leaf ...	Piper betel.
2	<i>Supári</i> ...	Betelnut ...	Areca catechu.
3	<i>Tambákhu.</i>	Tobacco ...	Nicotiana tabacum.

*Pán* is grown to a small extent in Alta and a few other villages, most of the leaves used in the State being imported from the neighbouring districts. It has two kinds *deti* and *gángerí*. The latter has a red stem and fibre and is softer than *deti*. Of the two kinds *deti* is chiefly grown. It thrives only in rich soils such as alluvial or black, and requires great skill and attention and a plentiful supply of good sweet water. The betel-vine garden is well fenced and is divided into convenient blocks crossed by water channels. One acre of betel-leaf garden is divided into forty blocks, each having seventeen beds, fifteen small and two large. The two large beds are called *baudtáng*. Of the small beds, two on the left side are called *khandtáng*, the four front beds *chiretáng*, and the remaining nine *kurgache váfe*. Plantain leaves are used to shelter the vines from the sun and wind and for this purpose plantains are grown along the hedgerows and at certain points in the beds. The vines are trained up slender *hadga*, *nimb*, *pángra*, *shevga*, and *shevri* trees. For this purpose in June *shevri* seeds are sown along the ridges of beds, and *hadga*, *nimb*, *pángra*, and *shevga* seeds are sown here and there all over the garden. When the standards have grown two feet high, cuttings about fifteen inches long from the best ripened shoots of the old vines are planted three inches deep and nine inches apart. In each large bed eighteen and in each small bed twelve cuttings are planted. In about a fortnight the cuttings begin to throw out new leaves. As it grows, the vine is trained to nurse-trees at short intervals and tied with *lavhála* grass. It wants water twice a week and in the hot season every alternate day. Fifteen months after planting the leaf-picking begins. The leaf-picker cuts the leaf with his thumb sheathed in a sharp nail-like claw. Every year in January the vine is loosened from the nurse-tree, stripped of its leaves, coiled away, and buried above the root under fresh earth and manure. The old vine throws new shoots which are trained up the nurse-tree.

## Chapter IV. Agriculture.

### CROP DETAILS. *Turmeric.*

### *Narcotics.*

### *Betel Leaves.*

**Chapter IV.****Agriculture.****CROP DETAILS.***Betel Leaves.*

Some of them which are unhealthy die off. In five or six years when they are at their best, each vine has thrown out generally eight to ten shoots. In good soils the vines go on yielding ten to twelve years. Tirgul Bráhmans, who generally cultivate the vine, sell it to leaf-dealers. The betel-leaf is chewed by all classes with betelnut, quicklime, catechu, and sometimes with tobacco and several spices. The average yield of a well covered block is estimated at about five *kudtans*.<sup>1</sup> The leaves are sold retail at the rate of a penny a hundred.

*Betelnut.*

*Supári* is planted in pleasure gardens above the Sahyádris and as a crop in a few villages below the Sahyádris in the Báyda State.

*Tobacco.*

*Tambákhu*, with an area of 10,193 acres, holds the eleventh place in the crops of the State. It is grown in the customary rotation in black and alluvial soils and garden lands. It is sown in the middle of August and reaped after six months. The soil is prepared as for other late crops, but is always richly manured by folding sheep. The average acre outturn varies from 300 pounds in ordinary soil to 450 pounds in alluvial soils. Most of the tobacco grown in the State is locally used.

*Spices.*

Thirteen spices are grown in Kolhápúr. The details are :

*Kolhápúr Spices and Condiments.*

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Ále</i> ...	Ginger ...	<i>Zinziber officinal.</i>
2	<i>Badishep</i> ...	Sweet-fennel ...	<i>Anethum feniculum.</i>
3	<i>Halad</i> ...	Turmeric ...	<i>Curcuma longa.</i>
4	<i>Kadhilimb</i> ...	Curry-leaf ...	<i>Bergera kenigii.</i>
5	<i>Kalimiri</i> ...	Pepper ...	<i>Piper nigrum.</i>
6	<i>Kothimbir</i> ...	Coriander ...	<i>Coriandrum sativum.</i>
7	<i>Methi</i> ...	Fenugreek ...	<i>Trigonella fenugracum.</i>
8	<i>Mirchi</i> ...	Chillies ...	<i>Capsicum frutescens.</i>
9	<i>Mohari</i> ...	Mustard ...	<i>Sinapis racemosa.</i>
10	<i>Ooa</i> ...	Country barage...	<i>Coleus aromaticus.</i>
11	<i>Shepu</i> ...	Dill-seed ...	<i>Anethum sowa.</i>
12	<i>Us</i> ...	Sugarcane ...	<i>Saccharum officinarum.</i>
13	<i>Veldoda</i> ...	Cardamom ...	<i>Elletteria cardamomum.</i>

*Ginger.*

*Ále* is grown to a small extent in Alta and Panhála. It is raised from layers at any time. Dry ginger is not prepared in the State but is brought from Rájápúr and Vengurla. As it keeps longer than Kolhápúr ginger, Sátára green ginger is also brought into the State.

*Fennel.*

*Badishep* is grown to a small extent. The seed is eaten in curry, and is largely used as medicine for women and for children especially in diarrhoea.

*Turmeric.*

*Halad* is in universal use as a condiment and forms the chief ingredient of curry powder. Details have been given above under dyes.

*Curry Leaf.*

*Kadhilimb* is generally grown in house compounds. The tree is large and the leaves are used in curry.

<sup>1</sup> Four hundred leaves make one *kavli* and forty-five *kavlis* make one *kudtan*.

*Kálimiri* is grown in small quantities in gardens and house compounds in villages of the Konkan Ghátmátha. The produce is small and is barely enough for local consumption.

*Kothimbir* covered 2570 acres, 2472 of which were in the Gadinglaj sub-division where it is mostly grown for its seed. It is raised both as a green vegetable and as a crop for its seed called *dhane*. The green leaves are much used in curries and relishes and the powdered seed in spices. When grown as a vegetable it is raised at any time of the year; but when raised for its seed, it is sown in good black soil in September and harvested after three months. The soil is ploughed and prepared in the same way as for *javari*, and the seed is sown with the seed-drill with *kardai* in occasional rows. To sow an acre with coriander, about sixty pounds of seed are required. The average acre outturn is 1300 pounds. The rupee rate of coriander varies from eighty to a hundred pounds. The yearly export from the State to Athni, Bágalkot, Belgaum, Poona, Rájápur, and Vengurla is estimated to be worth £2500 (Rs. 25,000).

*Methi*, like coriander, is grown at any time of the year and is largely used by all classes. The leaves are eaten boiled as a vegetable and the seed is used in medicine and condiments.

*Mirchi*, with an area of 8469 acres, is sown both in garden and dry lands. It is generally grown in red and black soils. It is of two kinds, the long with thin pods and the short with thick pods. The long pods are more pungent than the short pods and are much used locally; the short pods are mostly exported. The seed is sown in May in a seedbed, and when after six weeks or two months they are six inches high, the seedlings are planted out two at a time in rows three feet apart. The plants are earthed up and in garden lands are watered once or twice. Sometimes a row of cotton plants or coriander plants is grown between two rows of chillies, when they have grown about a foot high. When the plants are sown the soil is harrowed with the *kulav*, and the soil around the plants is weeded and loosened with a *khurpe* or trowel. In about three months the plants begin to bear and the first green crop is gathered about the middle of August. As they become fully coloured, the pods are picked and spread in the sun to dry thoroughly. The average acre outturn of chillies is about 200 pounds. Nearly one-fourth of the produce finds its way to Chiplun in Ratnágiri, and the rest is locally used.

*Mohari*. See under Oil-seeds.

*Ova*, a blind nettle with fleshy aromatic leaf, grows freely as a weed in gardens.

*Shepu* is grown sparingly just enough for local use. The green leaves are used as vegetable and the ripe seed both in condiments and medicine.

Sugarcane, one of the most important crops in the State, occupied in 1881-82, an unusually dry year, a tillage area of 9900 acres. In ordinary years the tillage area under sugarcane varies from 12,000 to 15,000 acres. As it requires a larger capital and a longer

## Chapter IV. Agriculture.

### CROP DETAILS. Coriander.

*Fenugreek.*

*Chillies.*

*Mustard.*

*Ova.*

*Dill Seed.*

*Sugarcane.*

## Chapter IV.

## Agriculture.

## CROP DETAILS.

## Sugarcane.

time to ripen than most other garden crops, it may be fairly presumed that the farmer who grows it is fairly prosperous. Five kinds of sugarcane are grown in Kolhápur *bhonga*, *chinnápunda*, *khadkya*, *rámrasál*, and *támbdi* or red. Of these five kinds *bhonga* is streaked white and red and is grown in garden lands to a less extent than *rámrasál*. *Chinnápunda* seems to be a species of *rámrasál*. Its skin is thin and its joints are close. As it is considered inferior to other kinds very little sugar is made from it. *Khadkya* is white, grows about the thickness of a good Indian millet-stalk, and has very little saccharine matter. It is grown in the Panhála, Karvir, and Bhudargad sub-divisions. It is hard and requires to be watered thoroughly only once during the dry months. *Rámrasál*, a white variety, about five to eight feet high and an inch thick, is largely grown in the garden lands of the Alta, Karvir, and Shirol sub-divisions. Its joints are far apart, and it is the most juicy of all varieties. *Támbdi* or red was once very common, but it has now given way everywhere to *bhonga* and *rámrasál*. Though less juicy it is sweeter than *rámrasál* and is much eaten. Of these five kinds the white and the striped kinds seem to have been introduced about thirty-five years ago, and they, if not the acclimatised varieties of Mauritius, very much resemble it. Sugarcane is grown in three kinds of soil black, red, and brown-red which is alluvial deposit on river-sides. The brown-red is considered the richest and best suited to sugarcane. Sugarcane requires much watering and heavy manuring. Sugarcane takes much out of the soil. Unless he is satisfied with a poor return, the Kolhápur landholder does not grow sugarcane oftener than once in three years. Still when the area of garden land is small, sugarcane is grown alternately with either hemp chillies or spiked millet; but this soon impoverishes the soil and makes long rest necessary after a few years' cropping. In the plain country sugarcane is followed in the second year after a heavy manuring by Indian millet, and in the third year either by hemp, chillies, groundnuts, or spiked millet. In the western parts of Kolhápur sugarcane alternates with rice or *náchni*. In garden lands and river-side lands which are flooded as many as a thousand sheep are folded on one acre for five days and besides this about thirty-five to fifty cartloads of ordinary manure are laid on the ground. Nightsoil where procurable is preferred. It is considered superior and the quantity required is about half that of ordinary manure. In river-side alluvial deposits sheep urine and droppings are the only manure. When he cannot afford to manure the whole field, a husbandman only covers the furrows in which the cuttings have been planted with ordinary manure.

In parts near the Sahyádris sugarcane cuttings are planted in December, and in the eastern sub-divisions of Alta and Shirol between January and March. In the western parts the land is ploughed three to four times, the clods are broken down with the *kulav*, and furrows about eighteen inches apart are made by a heavy plough. The cuttings are then laid and are covered with manure. A small plough runs by the sides of the furrows and covers the cuttings. The field is then watered. After the cuttings have

Chapter IV.  
Agriculture.  
CROP DETAILS.  
*Sugarcane.*

sprouted the field is weeded. Before the crop is ready the field is occasionally weeded and the plants are earthed up. The plantation is generally well hedged to protect it from jackals and wild pig. In garden lands and river-watered plots the field is ploughed crosswise in December and the clods are broken and the surface levelled with wooden mallets. Between January and February the field is manured with sheep urine and droppings and then with ordinary manure. The field is then thoroughly ploughed to work in the manure. Parallel ridges or *sárs* about eighteen inches apart are made and water is let into channels between the ridges. The field is ready for planting. Much care is taken in selecting cuttings. Cuttings are taken from the healthiest and biggest canes in the field. It is also seen that the canes have no *turás* or flowery spikes at the top. Seed canes are cut into *kándis* or pieces fifteen to eighteen inches long with three or four shoots. They are then dropped lengthwise into the furrows and pressed by the foot well into the ground. About 10,000 cuttings cover an acre. On the fourth day after planting comes the first watering or *ambavni* and on the eighth day the second watering or *chimbavni*. After these waterings comes the regular irrigation after five to eight days according to the soil and sufficiency of water. A week after planting the cuttings begin to sprout; after three weeks when the plants have come a few inches above the ground the field is weeded by hand. During the first four months the field is weeded every month by hand. In four months the cane grows about four feet high and the *kulav* is run between the rows of plants to earth up their roots. In the fifth month the field is again weeded by hand. After this month till the crop is ripe no weeding takes place but the field is watered at regular intervals. In the western parts where rainfall is heavier sugarcane does not want watering after the fifth of June; and in the eastern plains where rain is less heavy and falls at long intervals it requires occasional watering even in the monsoon months. In the western parts sugarcane is watered either by *páts* or by *budkis* that is wells built on the bank of a river or stream. In drawing water from *budkis* husbandmen club together. The water is raised from the *budki* to an intermediate receptacle and thence to another and so on to the level from which it can be distributed by gravitation. To draw up water from one place to another *mots* or leather-bags are used. There are generally three to four lifts, but sometimes as many as six. Considering the expense and labour thus required to raise the water, the land watered is taxed in proportion to the number of lifts. When more than four lifts are used the land is assessed at the rate of full dry-crop assessment. In the eastern parts, like other garden crops sugarcane is watered by well-water raised by *mots* or leather-bags. Sometimes during a few months in the year, when the well-water supply is low, the field is watered by channels drawn from streams dammed at higher levels. While the crop is young pot-herbs are grown along the furrows. If the crop is stunted the ground is loosened with the hoe or *kudal*; and to give it a fresh start two to three inches of the roots of the plants are cut. Sugarcane takes about eleven months to mature. When ripe it is heavy, its skin is smooth and brittle and its juice sweet and sticky. If not cut in the eleventh

Chapter IV.  
Agriculture.

CROP DETAILS.  
Sugar cane.

month, it is kept till the thirteenth, as the husbandman believes that it yields much less juice when cut in the twelfth month. As it is believed that the root part contains particularly rich juice, sugar-cane is cut several inches below the ground. The dry and loose leaves are taken off and the canes are taken to the mill. Near large towns and market-places it often pays to take canes to markets to sell by retail for eating. But most of the cane goes to the mill.

The mill is set up in a corner of the field and employs about seventeen hands and sixteen bullocks. Five men called *phadkaris* are employed in cutting, topping, and stripping the cane. Fresh cut canes give a larger percentage of juice and so the cane is cut as required by the mill. One man called *molkyā* or the bundle-man carries the cut canes to the mill. The *khāndkya* chops the canes into pieces about a yard long. The tops with one joint are kept for seed-cuttings, and the lower pieces are tied in bundles. Seven men work at the mill. The *bharkavlyā* feeds the mill with the cut cane received from the *kāndyāghālnār*. The *lendkavlyā* sits on the side of the mill opposite the feeder and thrusts back between the rollers the pieces of cane as they come through. Each piece passes three times between the rollers. The crushed cane or *chipād* is burnt with other fuel for boiling the juice. Two men called *pātkyās* drive the bullocks yoked to the mill. Two called *ādemodes* take the juice that falls into the *māndan*, an earthen pot large enough to hold about sixty gallons, to the boiling pan; and they also remove the boiled juice from the boiling pan or *kāil*. The boiling pan, which is large enough to hold about 120 gallons, is placed on a stone and is heated by a long flue. When the scum rises in bubbles and breaks into white froth the juice is sufficiently boiled. This takes about three to four hours. The impurities in the juice rise with the scum and are taken out with a bamboo sieve or *vārdi*. To cause impurities to rise the juice is constantly stirred, and sometimes a handful of ashes of the myrobalan and milkbush or *aghāda* *Achyranthus aspera* are added to it. An expert styled the *gulrāndhya*, from time to time takes a little juice between his forefinger and thumb to see whether the boiling has been carried on sufficiently. When he is satisfied, the juice is poured into a wooden trough to cool and from the trough into regular holes made in the ground and lined with cloths to keep out dirt. At this stage the juice is called *kākvi* or molasses, which in the holes crystallizes into raw-sugar or *gul* in about three to four hours. These lumps of raw-sugar are dark-brown in colour and weigh thirty-six to forty pounds. The kindling of the fire and feeding it are entrusted to two men called *chuljālyā* or hearth-burners. These are generally village *Mhārs*. The burning cinders to light the fire must be brought from a *Mhār's* house. The labourers who work at the mill are paid in kind at the rate of three canes and 2½ pounds of raw-sugar. The village servants or *balutedārs* are paid in proportion to the work they do. The carpenter or *sutār* has the largest share of work. He repairs the water-lifts and keeps the mill in good order. He receives six pounds of raw-sugar and eight canes a day while the pressing is going on. The leather-worker or *chāmbhār* repairs the leather-bags and buckets and leather ropes and fastenings and receives half as much as the carpenter. The



blacksmith who mends the field tools, the Máng who supplies ropes and whips, the potter who supplies earthen pots, the barber who shaves the husbandman, and the washerman who washes his clothes, are entitled to three-fourths of a pound of raw-sugar and three canes a day so long as the mill is at work. The *tarál* sweeps the place where the mill works and gets three pounds of raw-sugar and five canes. The Bráhmaṇ astrologer, the Jain Upádhyā, and the Lingáyāt Jangam fix the day for working the mill and are granted two pounds of raw-sugar on the first day. The village Gurav prays to Ganpati to remove all difficulties that may come, and the Mulláni or Muhammadan priest extends the protection of his patron saint by distributing ashes of frankincense burnt before the saint. These get one-fourth of a pound of raw-sugar, two canes, and a potful of juice once only during the course of the pressing. When the pressing and boiling is over and the *gul* is being removed to the village, the village *balutedárs* receive half as much as they have already earned. Believing that retail sale of sugarcanes in the field will bring him ill-luck and freehanded gifts will be rewarded by a plentiful outturn, the husbandman freely gives canes, juice, and bits of new raw-sugar to any one who asks for them, and crowds of beggars throng the field. It is estimated that about twenty to twenty-five per cent of the produce thus goes in wages and charity. As the juice easily ferments under the heat of the day, pressing and boiling take place at night. For home consumption the husbandman keeps a little molasses. The outturn of molasses per acre is estimated at about 1170 gallons worth about £22 10s. (Rs. 225).

Except in some of the villages of the Alta, Kágál, Karvir, and Shirol sub-divisions, no sugar is made in the State. The craft of sugar-making in Kolhápúr is of late growth and is wholly in the hands of Jains, Lingáyats, and Musalmáns. Because it was first made at Yelgund in Alta by a Gujarát Musalmán sugar-maker about thirty years ago, Kolhápúr sugar is called Yelgundi. Of late it has improved both in quality and quantity. Most of the sugarcane juice in Yelgund and in the surrounding villages is made into sugar, and sugar of the present day is far superior in colour and taste to what it was about twenty years ago. The sugar-refiner buys the juice off husbandmen at 14s. (Rs. 7) a can of 120 gallons. Except that more care is taken to skim off the impurities, the juice is boiled in the same way as in raw-sugar making. To aid the rising of impurities to the surface a handful of ashes of the *bhendi* *Hibiscus esculentus* is dropped into the boiling juice. The boiled juice is then poured into a wooden trough, and from it into earthen jars where it consolidates. After a week or ten days the lumps are put in a boiling pan rubbed inside with salt water and heated. The syrup is then poured into a bamboo basket six feet in circumference and two and a half to three feet in height and placed on a stool nine inches high. Under the stool is dug a hole in which the treacle drains from the basket. For a week the basket is kept thus. Then the surface of the sugar in the basket is stirred to the depth of nine inches, two to three pounds of milk are poured into it, and the surface is smoothed with a *pitali* or platter rubbed with clarified butter. The surface is then covered with a thick

Chapter IV.  
Agriculture.  
CROP DETAILS.  
*Sugarcane.*

*Sugar.*

# Chapter IV. Agriculture.

## CROP DETAILS.

### Sugar.

ayer of a moss called *kāju* in Hindustáni, a piece of coarse cloth and a layer of sugarcane leaves one over the other. The drainage into the hole below the stool goes on. Every third day the covering of the basket is taken off, the layer of refined sugar which has been formed is removed, and a fresh layer of the moss is laid. In this way all the refined sugar is gradually removed. The treacle which is collected in the hole is sold for making liquor. The average acre outturn of sugarcane is 3960 gallons of juice worth about £25 (Rs. 250). The same quantity of juice when made into sugar yields about 2250 pounds of sugar worth £28 (Rs. 280) at the average rate of 6s. (Rs. 3) the *man* of twenty-four pounds.

### Cardamom.

*Veldoda* has of late been introduced into the State gardens at Panhála. The 1881 yield was  $2\frac{1}{2}$  pounds, worth about £1 3s. 6d. (Rs. 11 $\frac{3}{4}$ ). As it has thriven well it is likely that cardamom will be grown as a crop.

### Bulb Vegetables.

Eight bulb vegetables are grown in Kolhápúr.<sup>1</sup> The details are :

#### Kolhápúr Root Crops.

No.	MARÁTHI.	ENGLISH.	BOTANICAL.
1	<i>Batáta</i> ...	Potato ...	<i>Solanum tuberosum</i> .
2	<i>Chín</i> ...	Common Yam ...	<i>Dioscorea alata</i> .
3	<i>Gájar</i> ...	Carrot ...	<i>Daucus carota</i> .
4	<i>Kánda</i> ...	Onion ...	<i>Allium cepa</i> .
5	<i>Lasun</i> ...	Garlic ...	<i>Allium sativum</i> .
6	<i>Mula</i> ...	Radish ...	<i>Raphanus sativus</i> .
7	<i>Ratáde</i> ...	Sweet Potato ...	<i>Convolvulus batata</i> .
8	<i>Suran</i> ...	Elephant-foot ...	<i>Amorphophalus campanulatus</i> .

### Potato.

*Batáta* has of late been introduced in the State and is only grown to a limited extent. But as it has apparently succeeded well in Panhála and other western parts, potato is likely to spread over the State. The variety now grown is the Mahábaleshvar potato. As it has more nutritious qualities than many native root crops, potato will be a good substitute for *harik*, *sáva*, and *vari* now so largely used by poor people. It is planted in August and harvested after three months.

### Common Yam.

*Chín* is not so much relished as sweet potatoes. It is grown in vegetable gardens near houses in the western villages. It is planted in June and is ready after six months.

### Carrot.

*Gájar* is grown in almost all gardens in the State. As a vegetable it is much relished by husbandmen. It is sown broadcast between September and November, and becomes ready for use within three months. During the first two months the crop is watered every ten days. In the third month the root begins to ripen and watering is stopped. A full sized carrot is four to five inches long and weighs about two ounces. Carrot is eaten either raw or boiled and is given to milch-buffaloes.

### Onion.

*Kánda* is one of the most important crops in the State. As a second crop it follows rice, *sáva*, *rála*, and *náchni*. Onions are sown in seedbeds, and when one month old the seedlings are planted out in December. It is fit for use in two months after planting and takes two months more to come to maturity. It requires

watering once a fortnight. *Chákvat*, *pokla*, *rágira*, and other pot-herbs are grown with onions. The average acre outturn of onion is 1500 pounds.

*Lasun* is grown under irrigation and requires water every week and constant weeding. The segments of the bulb are planted at the rate of 120 pounds per acre. The average acre outturn is 240 pounds. Garlic is an important condiment and husbandmen largely use it in their *chatnis* or relishes.

*Mula* is largely grown in garden lands. It is raised twice in a year. To sow the seed small holes eighteen inches apart are dug by a pointed peg. The hole is first filled with manure, the seed is then put in and covered with earth. In two months and a half the root becomes fit for use and is eaten raw or boiled; the leaves are used as a pot-herb.

*Ratále* is grown under irrigation and with manure. It is raised from layers put down at any time in the rains or cold weather, but chiefly in the middle of September, and comes to maturity within four months. The ground is levelled and richly manured, and cuttings from the old crop are planted nine inches apart. It requires water every week. If watering is neglected the crop is attacked by a minute grub. Except weeding and earthing up the crop requires no attention. When ready for use the rut is dug out, the haulms are separated from the root and given as fodder to cattle. The sweet potato is much esteemed as a vegetable. It is also eaten either raw or roasted chiefly on fast days.

*Suran* is grown in plantain and betelnut gardens in the west. It takes three years to mature. The root grows to a large size, weighing about ten pounds, is much esteemed as a vegetable and chiefly eaten by richer classes.

Besides the above, the *máinmul* is grown by the sides of water channels in garden lands. The root makes a good pickle.

Thirteen fruit vegetables are grown in Kolhápur. The details are :

*Kolhápur Fruit Vegetables.*

No.	MARÁTHI.	ENGLISH.	BOTANICAL.
1	<i>Bhopla</i> ...	Pumpkin (red) ...	<i>Cucurbita hispida</i> .
2	<i>Dodka</i> ...	Cornered Cucumber	<i>Cucumis acutangulus</i> .
3	<i>Dudhyábhopla</i> ...	Bottle Gourd ...	<i>Cucurbita lagenaria</i> .
4	<i>Ghosdla</i> ...	.....	<i>Luffa pentandra</i> .
5	<i>Kákdí</i> ...	Common Cucumber.	<i>Cucumis sativus</i> .
6	<i>Kárlé</i> ...	.....	<i>Momordica charantia</i> .
7	<i>Káshibhopla</i> ...	Squash ...	<i>Cucurbita melopepo</i> .
8	<i>Kohala</i> ...	.....	<i>Cucurbita alba</i> .
9	<i>Padval</i> ...	Snake Gourd ...	<i>Trichosanthes anquina</i> .
10	<i>Shetátluk</i> ...	Field Cucumber ...	<i>Cucumis utilitatissimus</i> .
11	<i>Tondle</i> ...	.....	<i>Bryonia grandis</i> .
12	<i>Vánga</i> ...	Brinjal or Egg-plant	<i>Solanum melongena</i> .
13	<i>Vel Vánga</i> ...	Tomato or Love-apple.	<i>Lycopersicum esculentum</i> .

*Bhopla* is mostly grown near homesteads, along the headlands of sugarcane plantations, and on river banks in alluvial lands. As a vegetable it is eaten boiled, and when grown in abundance is chopped into pieces and given to buffaloes.

#### Chapter IV. Agriculture.

##### CROP DETAILS.

*Garlic.*

*Radish.*

*Sweet Potato.*

*Suran.*

*Fruit Vegetables.*

*Pumpkin.*

# Chapter IV. Agriculture.

## CROP DETAILS. *Dudhyábhopla.*

*Dodka* is largely grown on sides of sugar-cane plantations and in *javári* and cotton fields. It is eaten boiled and is much esteemed as a vegetable.

*Dudhyábhopla* like red pumpkin is grown near homesteads, along sugarcane plantations, and on river sides in alluvial soil. As a vegetable it is much esteemed, and when grown in abundance is chopped and given to buffaloes.

### *Ghosále.*

*Ghosále* is grown near cottages on which it is allowed to climb. The fruit the only part eaten is smooth, of the same size as the *dodka*, and marked lengthwise with light lines. It is used in the same way as the *dodka*.

### *Cucumber.*

*Kákdi* is grown in gardens, by sides of sugarcane plantations, and in house-yards. In the western parts it grows to a large size and is called *tosa*. Cucumber is generally eaten raw. The *tosa* is chiefly used in making a dry preserve called *sándge*.

### *Kárlé.*

*Kárlé* is generally grown in sugarcane and turmeric fields and sometimes by itself on a separate patch of garden land. The fruit, the only part eaten, though bitter is much used as a vegetable.

### *Squash.*

*Káshibhopla*, that is Benares pumpkin, is grown and used in the same way as the *dudhyá-bhopla*.

### *Kohala.*

*Kohala* is grown and used in the same way as the *káshibhopla*. The fruit is never eaten raw, but is much esteemed as a vegetable.

### *Snake Gourd.*

*Padval* is largely grown near homesteads and is much esteemed as a vegetable.

### *Shetváluk.*

*Shetváluk* is largely grown as a vegetable. It is of two kinds the *shetváluk* proper and the *phut* or *shendád*. The seed of *shetváluk* is either sown in February June or August and the plant begins to bear within two months. *Phut* or *shendád* is largely grown in black soil, chiefly cotton fields. The fruit is eaten only when ripe.

### *Tondle.*

*Tondle* is grown near cottages and fences where cuttings are planted. The creeper is allowed to climb over the cottages and fences. The fruit is the only part eaten.

### *Brinjal.*

*Vangi* is grown as a garden crop in alluvial lands near river sides. It is of two kinds, the *bangáli* or large long brinjal and the *dorli* or small round brinjal. The *bangáli* brinjal takes much from the soil and the next year's crop is almost always poor. In August seedlings are made in richly manured seedbeds, and in September they are planted two feet apart on land manured with ordinary manure or sheep droppings. To protect the plants from canker, the ends of the roots are cut and the roots dipped in a solution of cowdung and assafetida. The field is hoed and weeded as often as it is needed, and the plants are watered once a fortnight. In about two months the plants begin to bear and continue to bear about six months. Brinjal is much liked by natives and is largely sold in all markets. When in season brinjal is sold at four pounds a penny.

### *Tomato.*

*Velvángi* is grown only in gardens in Kolhápúr city. The seed is either imported or kept from the last year's crop.

Six pod vegetables are grown in Kolhápúr. The details are :

## Kolhápura Pod Vegetables.

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Bhendi</i> ...	.....	<i>Hibiscus esculentus</i> .
2	<i>Ghevda</i> ...	.....	<i>Dolichos lablab</i> .
3	<i>Govári</i> ...	.....	<i>Dolichos fabaformis</i> .
4	<i>Hatga</i> ...	.....	.....
5	<i>Kharsámbli</i> ...	.....	.....
6	<i>Shevga</i> ...	Horse Radish ...	<i>Hyperanthera moringa</i> .

*Bhendi* is of two varieties, large and small. The large variety is largely grown in sugarcane and turmeric fields. The small variety is generally grown in *jvári* and cotton fields. *Bhendi* is either eaten green or dried. Dried *bhendi* is stored for the hot season when fresh vegetables are scarce.

*Ghevda* has many varieties, the chief being the *ghevda* proper, the French bean which is grown in Kolhápura alone, *viláyati ghevda* or double bean, and *shrávan ghevda*, which is cheap and largely eaten during the rainy months. The pods are eaten boiled as a vegetable and the grain is used as a pulse.

*Govári* is grown in gardens at any time and during the rains on the edges of early grain crops. It begins to bear within three months, and if watered occasionally goes on bearing for some months. The pod is eaten green and is much prized as a vegetable.

*Hatga* is grown in house compounds and betel-vine gardens. The pods are largely used.

*Kharsámbli*, a creeping plant, is grown without water or manure near houses on the edges of garden lands. It begins to bear in three months and in good soil goes on bearing three or four years. The pod when young and tender is used as a vegetable.

*Shevga* is grown near houses and in betel-vine gardens. The tree is large and bears many long pods. The pods are largely used as a vegetable.

Gram, peas, and many other pulses when green are used as vegetables. Radish pods are also largely used as a vegetable.

Eleven leaf vegetables are grown in Kolhápura. The details are:

## Kolhápura Leaf Vegetables.

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>Alu</i> ...	.....	<i>Caladium esculentum</i> .
2	<i>Chakvat</i> ...	Goose-foot ...	<i>Chenopodium viride</i> .
3	<i>Chandanbatva</i> ...	.....	<i>Chenopodium (?)</i> .
4	<i>Chavli</i> ...	Hermaprodite ...	<i>Amaranthus polygamus</i> .
5	<i>Chuka</i> ...	Amaranth.	.....
6	<i>Ghol</i> ...	Blister Sorrel ...	<i>Rumex vesicarius</i> .
7	<i>Máth</i> ...	Purslane ...	<i>Portulaca oleracea</i> .
8	<i>Pokla</i> ...	.....	<i>Amaranthus tristis</i> .
9	<i>Rajjira</i> ...	.....	<i>Amaranthus (?)</i> .
10	<i>Tándli</i> ...	Eatable Amaranth.	<i>Amaranthus candidus</i> .
			<i>Amaranthus oleraceus</i> .

*Alu* is largely grown in marshy places, in house compounds, and in refuse-pits in which bath and cook-room water is drained. The leaves and stems are eaten boiled and are much esteemed as a vegetable.

## Chapter IV.

## Agriculture.

## CROP DETAILS.

## Pod Vegetables.

*Bhendi.**Ghevda.**Govári.**Hatga.**Kharsámbli.**Horse Radish.**Leaf Vegetables.**Alu.*

**Chapter IV.**  
**Agriculture.**  
**CROP DETAILS.**

The remaining nine plants are grown in garden lands at any time of the year. They are only raised for their leaves which are eaten boiled as vegetables.

Besides the above given leaf vegetables tender shoots of brow hemp and gram and young leaves of *methi*, dill-seed, mustard, radish, and safflower are largely eaten boiled as vegetables.

European vegetables are grown in gardens attached to the Palace and the Infantry Lines and have succeeded well, but the people have not taken to growing them freely.

*Fruit Trees.*

Twenty-three fruit trees are grown in Kolhápur. The details are :

*Kolhápur Fruit Trees.*

No.	MARATHI.	ENGLISH.	BOTANICAL.
1	<i>A'mba</i> ...	Mango ...	<i>Mangifera indica.</i>
2	<i>Ananas</i> ...	Pineapple ...	<i>Bromelia annanus.</i>
3	<i>Anjir</i> ...	Fig ...	<i>Ficus carica.</i>
4	<i>Bel</i> ...	.....	<i>Egle marmelos.</i>
5	<i>Bor</i> ...	Jujube ...	<i>Zizyphus jujuba.</i>
6	<i>Bund</i> ...	Coffee ...	<i>Coffea arabica.</i>
7	<i>Chinch</i> ...	Tamarind ...	<i>Tamarindus indica.</i>
8	<i>Dalimb</i> ...	Pomegranate ...	<i>Punica granatum.</i>
9	<i>Draksha</i> ...	Grape ...	<i>Vitis vinifera.</i>
10	<i>Id</i> ...	.....	<i>Citrus limonum.</i>
11	<i>Jambhul</i> ...	.....	<i>Eugenia jambolana.</i>
12	<i>Kavath</i> ...	Woodapple ...	<i>Feronia elephantum.</i>
13	<i>Kel</i> ...	Plantain ...	<i>Musa paradisiaca.</i>
14	<i>Lambu</i> ...	Lime ...	<i>Citrus limetta.</i>
15	<i>Mahatung</i> ...	Citron ...	<i>Citrus medica.</i>
16	<i>Naral</i> ...	Cocoanut ...	<i>Cocos nucifera.</i>
17	<i>Naring</i> ...	Orange ...	<i>Citrus aurantium.</i>
18	<i>Popal</i> ...	Popal ...	<i>Carica papaya.</i>
19	<i>Papnas</i> ...	Pomello or Shad- dock. ...	<i>Citrus decumana.</i>
20	<i>Peru</i> ...	Guava ...	<i>Psidium guava.</i>
21	<i>Phanas</i> ...	Jackfruit ...	<i>Artocarpus integrifolia.</i>
22	<i>Ramphal</i> ...	Bullockheart ...	<i>Annona reticulata.</i>
23	<i>Stidphal</i> ...	Custard-apple ...	<i>Annona squamosa.</i>

*Mango.*

*Ámba* is common in gardens and fields. In some places mangoes are planted in groves. The largest groves in the State are near Chokak, Kágál, and Top. Although mango flourishes everywhere in the State, the fruit is considered inferior to Goa and Ratnágiri mangoes, and every year large quantities of mangoes are brought from those places. Of late within the last twenty years some attempts have been made to introduce Alphonso or *áphus* and Pariera or *páyri* mango grafts into the State gardens. As it requires care and skill, the growing of grafted mango trees is not much taken by the people.

*Pineapple.*

*Ananas* is grown in Bávda and Anaskura, where it thrives well. It is also brought from below the Sahyádris.

*Fig.*

*Anjir* is grown sparingly. It thrives well at Panhála and a few other places.

*Bel.*

*Bel* is commonly found in flower gardens and near Shiv temples. It is largely planted in Lingáyat burying grounds. The triple leaves are offered to Shiv, and the young fruit is made into a preserve. As a medicine the pulped fruit is given to check diarrhoea.

*Jujube.*

*Bor* is grown in here and there gardens, but also as a substantive crop. The fruit is largely eaten by children.

*Coffee.*

*Bund* has been only partially introduced in Kolhápur. Experiments hitherto made show that the climate of Kolhápur is not moist



enough for the healthy growth of the plant. At higher levels such as at Bhudargad, Malkápur, and Panhála, with irrigation the plant grows luxuriantly; and it is supposed that the plant would thrive well in the western Gháts. The berries are sown in seedbeds, and when they grow about a foot high the seedlings are planted out in holes five to six feet apart. Coffee requires to be manured every year. To encourage branching the top-shoot is nipped when the tree is five feet high and the side branches are pruned periodically. The tree begins to bear in four years. It flowers in June and the berry is ready for picking in November-December. In 1881 in different State gardens at Bávda, Panhála, and Vishálgad the coffee trees numbered 5000, and the whole outturn for the year was 960 pounds worth £32 (Rs. 320) at three pounds the rupee.

*Chinch* grows in forests, by roadsides, and in waste ground near village sites. The fruit is largely used by all classes in cookery. It ripens in February-March. The thin hard and loose shell of the ripe fruit is removed, the black stony seed is taken out and the pulp is dried with or without salt and stored for use throughout the year. The young leaves and the stony seed are largely used by the poorer classes. The leaves which have a sour taste are eaten boiled as a vegetable, and the seed is used as a *chatni* or relish. The wood is tough and is much used for field tools. The Kolhápur market is supplied with tamarind from Pohále, Top, and other neighbouring villages. It sells at two pounds the penny.

*Dálimb* is not much grown in the State. Most of the fruit used is imported from Miraj, Pandharpur, and Sátára.

*Dráksha*, though once largely grown in Torgal, has of late declined chiefly owing to a kind of blight which attacks the vine. But from the experiments made at Kolhápur with indigenous and foreign varieties, it appears that the vine can be protected from the blight by care and scientific treatment. Kolhápur grapes are of three kinds *bhokri*, *káli*, and *vildáyati*. The *bhokri* is green and round; the *káli*, so called from its colour, is oval black and larger and sweeter than the *bhokri*; and the *vildáyati* which was introduced by Colonel Anderson, is black, and though smaller is sweeter than the *káli*. The supply is not enough to meet the local demand and large quantities of *bhokri* grapes are imported from Sátára.

*Id*, which has a bitter taste, is much used for pickles. It is little and the markets are supplied from Bijápur, Miraj, and Pandharpur.

*Jámbhul* is cultivated but it also grows wild in forests. The fruit is largely eaten by the children of husbandmen.

*Kavath* is grown in gardens and in house yards. The fruit is much esteemed for its sour flavour and is said to possess antibilious properties.

*Kel* is grown in gardens and near homesteads. It is also grown in betel-vine and coffee gardens to shade the young plants. It thrives well in Panhála and Ráybág. There are six kinds, *bangáli*, *kanheri*, *lokhandi*, *rasbál* or *ráikel*, *sonkel*, and *támbdi* or red. Of these the *rasbál* and *lokhandi* are most common. The small and sweet *sonkel* and the *kanheri* which is smaller than the *sonkel* are

#### Chapter IV. Agriculture. CROP DETAILS. *Coffee.*

*Tamarind.*

*Pomegranate.*

*Grape.*

*Id.*

*Jámbhul.*

*Wood Apple.*

*Plantain.*

Chapter IV.  
Agriculture.  
CROP DETAILS.  
Plantain.

light croppers and want much water. At Panhála they are grown for home consumption in the gardens of the rich. The thick-skinned *bangáli* and the *támbdi* or red have been of late introduced from Ratnágiri and other British districts. The red variety thrives best in Malkápur. As it is inferior in flavour, the *bangáli* though the largest, is not much liked. Light black or red soil suits the plantain best. In the beginning of the south-west monsoon the ground is ploughed and levelled; and pits two feet square and two feet and a half deep are dug from six to seven feet apart. Each of the pits receives about twenty pounds of mixed manure, and the young plant is buried in the pit a foot below the surface. In the dry months plantain requires water twice a week. It bears after eight or nine months and lasts three months. A healthy tree is said to yield as many as 250 plantains, but the average varies from eighty to a hundred. When nearly ripe the bunches of fruit are cut and laid in a room in a heap on straw covered with plantain or other leaves. After three days it is ready for eating. When cut half ripe, the fruit is laid in a heap on straw and is covered with a thick layer of plantain leaves coated with cowdung or mud. To make the fruit soft and to turn the skin yellow a small opening is made, through which cowdung smoke is admitted. The smoke is kept in for three to four days. On fast days plantains are largely used by Hindus. They sell at eight to twelve the penny. The flower spike which is called *kelpul* or plantain flower is used as a vegetable, and the juice of the inner part of the stem which is felled as soon as the fruit is cut, is used in preparing wafer biscuits or *pápáđ*. The green leaves are used as plates; and the leaves and ashes which are also used as a mordant in dyeing make an excellent manure.

*Lime.* *Limbu* is grown only to a small extent. The markets are mostly supplied from Bijápur, Miraj, and Pandharpur.

*Citron.* *Máhábung* is grown in Bávda and Panhála. It is used for pickles and preserves. In good soils it grows to a large size and weighs as much as four pounds.

*Cocoanut.* *Náral*, above the Sahyádris, is only grown in pleasure gardens and near homesteads. Below the Sahyádris there are a few rich cocoanut gardens in Bávda and on the State *sheri* estates in Málván in Ratnágiri. The soil above the Sahyádris does not suit the palm; but as water greatly helps its growth, it is likely that cocoanut cultivation may increase with the development of irrigation. The tree begins to bear after fifteen years.

*Orange.* *Náring* is grown only in the State gardens at Kolhápur.

*Papai.* *Popai* is grown only in pleasure gardens. The fruit is eaten both ripe and unripe.

*Pomello.* *Papnas* is grown in gardens at Kolhápur. As the fruit is inferior both in taste and size to imported fruit and as the plant does not bear regularly, the pomello is not much grown in Kolhápur.

*Guava.* *Peru* is grown in gardens in the Alta and Shirol sub-divisions. The Kolhápur market is chiefly supplied from Miraj.

*Phanas* is grown near village sites and in private estates in the west. The fruit, which grows to a large size, is largely eaten as food by poor people. At Kolhápúr, according to size, the ripe fruit sells at two-pence to a shilling. The wood is largely used in carpentry and the leaves when stitched together are used as plates.

*Rámphal* is grown in pleasure gardens. For the Kolhápúr market it is grown at the village of Top. The fruit matures about December and is sold at a penny each.

*Sitáphal* is grown in gardens and house yards. The tree bears in June-July and matures in October. The fruit when ripe has an excellent flavour and is much eaten. It sells at half a farthing.

The chief Kolhápúr berries are *chiklyā*, *karvand*, and *toran*. They grow wild and are much eaten by children.

Besides the fruits and vegetables above described, many wild fruits and herbs are eaten by the poor as vegetables in ordinary years and form their chief support in famine years. The fruit of *kusari* which is as big as a coffee berry, is boiled and eaten with salt and pepper. The *nerli* fruit is red and is eaten by children. The *shevri* is boiled and eaten with salt and pepper. *Tetu* pods, which are as big as horse-radish pods, are eaten boiled and mixed with pepper and salt. The ripe *umbar* fruit is eaten by the poor. The *pendhri* is eaten cooked with salt and pepper. The *nibar* is a small berry and is eaten by children. The *rátambi* and *niv* are eaten cooked. The roots of the *lohakir shendval* and *shede*, the roots and beans of the *phursi*, the heart of the *dinda*, and the sprouts of the *murud* and *ránchiva* are boiled and eaten with salt and pepper. The leaves of the *tákla*, *dhámela*, *nál*, *kurli*, *surpin*, *yálvot*, and *ken*, and the flowers of the *bhárang* are boiled and eaten with salt and pepper. The bulbs of the *kadu-kárandá* and *ránálu* are also eaten boiled as vegetables. The pods of the *mugni* and *birbola* are also eaten cooked.

A general taste for flowers prevails throughout the State. The neat little public garden at Kolhápúr serves as a model and nursery for flower gardens in the State. Roses are found in every village and a flower *pách*, from which the essence called *pácholi* is extracted is abundant. *Sonchápha* grows wild on the Panhála hills. The tuberose is most common in native gardens and affords always a plentiful supply of flowers for idol-worship. *Shevti* grows to a large size in Kolhápúr. The chief plants that are seen in native gardens are *bakul*, *davna*, *davanshevti*, *gulchhabu*, *jái*, *jásvand*, *jui*, *madan-bán*, *moghri*, *motia*, *marva*, *nágchápha*, *neváli*, *pách*, *pándhráchápha*, *párijátaḱ*, *guláb*, *sádháguláb*, *sonchápha*, and *shevti*. The foreign plants introduced into the State gardens at Kolhápúr have spread to all parts of the State.

Though frequent, blights are seldom so widespread as to affect the general harvest. *Jvári* or Indian millet suffers from both strong north-easterly and westerly winds. With strong north-easterly winds the stalk turns red and grain does not form. The disease is called *jangamyádrog*. If a strong westerly wind blows when the crop is in ear, the ears remain unfilled or the green grain or *isad* is converted into a sticky mass called *chikta*. If a timely

# Chapter IV. Agriculture. CROP DETAILS.

*Bullockheart.*

*Custard Apple.*

FLOWERS.

BLIGHTS.

# Chapter IV. Agriculture.

## BLIGHTS.

shower of rain falls the crop improves. Indian millet also suffers from diseases known as *gosávi*, *kánde-kuri*, and *káni* which are said to be brought by cloudy weather. In *gosávi* the grain sprouts in the ear. In *kánde-kuri* the plant becomes barren. And in the *káni* (Anglicè smut) the ears become elongated and black, and the seed contains only a black powder which is easily freed. Indian millet affected by *gosávi* and *kánde-kuri* is cut for green fodder. Wheat sometimes suffers from a disease called *tamberi* (Anglicè rust). The grain is shrivelled and the stalk and leaves are covered with reddish spots. Spiked millet or *bá-jri* is sometimes though rarely affected by a blight called *shenda*. The leaves of the crop become yellow and the stalk is stunted. Gram, peas, pigeon pea, and other pulses suffer more from worms than from diseases induced by unseasonable weather. To destroy these worms which in cloudy weather gather on leaves, much vigilance and labour are required. Among vegetables brinjals suffer most from worms. To guard the plant against worms its roots are dipped before transplantation in a solution of cowdung and assafoetida. If they appear when the plant is growing the grubs are got rid of by cutting the main stalk of the plant a few inches above the ground. When watered the stem sprouts again and grows into a healthy plant. Sunday is considered the luckiest day for planting out brinjals and sprinkling them with cow's urine to keep off leaf-insects. Cotton suffers from a disease called *chimta* which is said to be brought by close and cloudy weather. With a timely late shower the crop improves. Sugarcane suffers from white ants and an insect called *humni*. It is also much damaged by rats and jackals. Sometimes if not watered in time the sugarcane becomes hollow in the centre.

## LOCUSTS.

In Kolhápúr locusts were till lately almost unknown. Their first visit, when the numbers were not large enough to do any harm, is recorded to have taken place about ten years ago. Their visits however seem to have become more frequent. In 1882 both before and after the rains myriads appeared along the Sahyádrí range and a good distance inland. The husbandmen lighted fires and beat drums in their fields to drive them off; but their efforts were in vain and so they look upon locusts as a visitation from God.

## FAMINES.

Kolhápúr, with its good rainfall and rich land especially in the valleys of the Dudhganga, Krishna, Várna, and Panchganga, is more free from famine than most of the Deccan districts. Owing to failure of crops in some outlying parts of the State, on account of scarcity of rain, prices have been occasionally high; but except in 1876-77 no famine has been recorded. Even the 1876-77 distress was caused more by the condition of the surrounding British districts than by a total failure of crops in the State.

In 1804-5 in Kolhápúr though the season was tolerably good the people suffered from scarcity of food which is said to have been caused by the devastations of the Marátha army in the interior of the Marátha country. All the starving persons from the neighbouring Marátha country flocked to Kolhápúr for relief. There was a great pressure on local supplies and the rupee price of grain rose to seven pounds and a half. The number of deaths from starvation

Chapter IV.  
Agriculture.  
FAMINES.

1876-77.

appears to have been large. Shiváji, the then ruling prince of Kolhápúr, as well as Himmat Bahádar, Bhim Bahádar, and other *sardárs* and well-to-do persons, distributed food to the starving people who had flocked to Kolhápúr from other places. The following year was a year of plenty and the people soon recovered from the effects of this distress.

In 1876-77 the scanty rainfall of twenty-six inches led to a failure of crops, which following the bad crops of the previous years, by reason of which there was no grain in store, spread distress amounting to famine. The east suffered most. The Shirol sub-division between the Várna and the Krishna with its outlying part Ráybág suffered most; next to it Kátkol an outlying portion of Gadinglaj just south of the Belgaum-Kaládgi road; and then the tracts on the Sahyádri hills. While scarcity prevailed in the rest of the State, famine had full sway in these parts. For weeks together people lived on herbs mixed with chaff and sometimes committed petty thefts to satisfy hunger. When the 1876-77 monsoon set in very sparingly husbandmen became alarmed and grain-dealers who had only small grain stores gradually raised the rates. Things looked gloomy, but it was not till the first week in October that the full extent of the calamity was felt. It was a week of panic. Prices suddenly rose to famine rates; village traders, moneylenders, and well-to-do persons, whose grain stocks had been already reduced by successive bad seasons, did not like to lessen their stock further and refused to make advances to husbandmen on the usual security of their field produce; there was no field work; and the people clamoured for relief works. At first small works were opened by the State to give immediate relief to Mángs, Mhárs, and other classes more or less given to theft, who would otherwise have taken to wholesale plundering. At the outset, the wages on relief works which were somewhat less than the ordinary rates in the State, were 3*d.* (2*as.*) for a man, 2½*d.* (1½*as.*) for a woman, and 1½*d.* (1*a.*) for a boy or girl capable of doing work. But subsequently the sliding scale, based on the price of staple food grain, fixed by the British Government, was strictly adhered to. Under this scale the wages on works under Public Works agency were, for a man the price of one pound of grain and 1½*d.* (1*a.*), for a woman the price of one pound of grain and ¾*d.* (½*a.*), and for a boy or girl above seven years the price of half a pound of grain and ¾*d.* (½*a.*); and on the civil works, for a man the price of one pound of grain and ¾*d.* (½*a.*), for a woman the price of one pound of grain and ¾*d.* (½*a.*), and for a boy or girl above seven years the price of half a pound of grain and ¾*d.* (½*a.*). Children under seven years were given ¾*d.* (½*a.*).

In November 1876, the first relief-works were opened in Shirol and Ichalkaranji in the east where distress began to be felt early and in the hilly parts of Vishálgad in the west, where owing to failure of crops in 1875, distress already prevailed. As the number of relief-seekers increased in December and January earthworks were started all over the State. The numbers of labourers became large. The number was doubled, and went on steadily increasing till September when it began to fall off gradually to the end of November when all relief works were finally closed.

Chapter IV.  
Agriculture.

FAMINES.  
1876-77.

From July 1877, the Imperial Public Works Department took charge of some of the relief-works carried on a large scale. To these works large numbers of able-bodied labourers were transferred with their children under seven years. The total cost on relief-works amounted to £26,030 (Rs. 2,60,300).

Besides these works gratuitous relief was given to those who were unable to work. In Kolhápur and in the feudatory States under it there were already several permanent charitable houses. The scope of these was enlarged soon after the scarcity began to be generally felt. As the distress increased new relief-houses were opened at convenient places. In all there were about eighteen relief-houses. The inmates of Kolhápur alms-houses were on two occasions supplied with clothing. The clothing funds were contributed by a lady in England who sent out £40 (Rs. 400) and by Mr. Bháu Mansáram of Poona who gave £100 (Rs. 1000). The gratuitous relief cost the State £5680 (Rs. 56,800). The following statement shows for each of the famine months in 1876 and 1877, the number of persons employed on relief-works, both under the Civil and Public Works Agency, with the average rupee prices of *javári* and *náchni*:

*Kolhápur Famine, 1876-77.*

MONTHS.	AVERAGE DAILY NUMBERS.				AVERAGE PRICES IN POUNDS.	
	On Relief Works.			On Gratuitous Relief.	<i>Javári.</i>	<i>Náchni.</i>
	Civil Agency.	Public Works.	Total.			
1876.						
November ...	269	...	269	1537	17	20
December ...	1438	...	1438	3342	22	...
1877.						
January ...	4305	...	4305	6295	21	23
February ...	4901	...	4901	8764	18	25
March ...	3976	...	3976	7417	19	24
April ...	4144	...	4144	35,135	16	21
May ...	9657	...	9657	73,645	10	18
June ...	7010	...	7010	86,720	15	18
July ...	2760	945	3705	80,107	8	13
August ...	5049	2942	7991	137,189	10	15
September ...	3857	5206	9063	155,281	15	23
October ...	1795	3493	5288	103,831	16	28
November ...	721	2320	3041	46,212	18	35
December ...	...	...	...	8233	37	43
Total ...	50,182	14,906	65,088	756,708	...	...
Average ...	3860	2981	5007	54,050	...	...
Total Cost ...	...	Rs. 2,60,300	56,800	...	...	...
-			817,100			

As the agricultural season of 1877 approached advances were made to a large number of cultivators who would otherwise have been left without any means of cultivating their fields, as they had neither credit nor the means of buying either food or seed grain. The sum advanced, which amounted to £21,600 (Rs. 2,16,000) was subsequently recovered.

The average yearly number of deaths for the three preceding years ending 1875-76 was 13,792; and in the famine year of 1876-77 it rose to 28,573 or more than double. The increased death-rate was more due to cholera, diarrhoea, small-pox,



and other epidemics which broke up in the hot season of 1877, than to actual starvation. The harvest of 1877 was fair, but the affected people who had been weakened by their previous suffering died in large numbers especially along the hills. The poorer classes suffered most. In some of the villages of Ráybág whole families of husbandmen deserted their villages and were not heard of afterwards. The loss of cattle was great. Many Dhangars or Shepherds living in the hilly parts lost all their cattle, owing partly to want of fodder and partly to cattle-disease which accompanied the other epidemics. Well-to-do people did not actually seek State relief, but lost all they had. Ornaments, metal pots, spare clothing, and even family idols were freely sold. Though all visible signs of distress have disappeared, it will require a succession of good years to enable the husbandmen to recover what they have lost<sup>1</sup>.

**Chapter IV.**  
**Agriculture.**

FAMINES.  
1876-77.

---

<sup>1</sup> This chapter owes much to additions and corrections by Mr. E. C. Ozanne, C.S., Director of Agriculture, Bombay.

## CHAPTER V.

## CAPITAL.

Chapter V.  
Capital.

OF 800,189 the total population of the State according to the 1881 census, 12,252 were in a position which implied the possession of capital. Of these 11,858 had a capital of £20 to £1000 (Rs.200-10,000), 296 of £1000 to £2500 (Rs.10,000-25,000), seventy-seven of £2500 to £5000 (Rs. 25,000-50,000), and twenty-one of £5000 to £10,000 (Rs. 50,000-1 *lakh*). The bulk of the capitalists are moneylenders and traders.

## CURRENCY.

Of old rupees four were current in Kolhápúr, old *Hukeri*, *Nilkanthi*, *Panháli*, and *Shambhu Pirkhání*. Of these for every hundred coins the old *Hukeri* was cashed for eighty-six Imperial rupees, the *Nilkanthi* for 56½, the *Panháli* for 96½, and the *Shambhu Pirkhání* for 87½. The old *Hukeri* weighed 171·075 grains of which 142·174 were pure metal, the *Nilkanthi* 169·627 grains of which 91·598 were pure metal, the *Panháli* 169·092 grains of which 114·492 were pure metal, and the *Shambhu Pirkhání* 175·039 grains of which 141·767 were pure metal. Of these the *Panháli*, the chief rupee, was coined at Pánhála which lies about twelve miles north-west of Kolhápúr and was the former capital of the Kolhápúr State. After 1788 when the capital was removed from Pánhála to Kolhápúr, the *Panháli* rupee was occasionally coined at the Kolhápúr mint. In 1839 the Kolhápúr mint was abolished, and at present (1883) the Imperial rupee is the only current coin.

## INSURANCE.

There is no insurance in the State.

## BILLS.

The most usual forms of bills of exchange or *hundis* are two *darshani* that is payable at sight, and *mudati* that is payable at some particular time after presentation. Bills are of three classes, *dhani-jog* that is where payment is to be made to the payee or his order; *sháhájog*, that is where payment is to be made to a nominee of the payee known to the payer; and *nishájog*, that is descriptive or where some marks on the body of the payee are inserted in the bill for identification. The *nishájog* bill becomes necessary in a place where the payee is unknown to the payer, and, being a stranger, is not able to find out a man known to the payer who can speak to his identity. Bills are not drawn in sets; but the drawer sends a letter of advice or *jabáb* to the drawee stating the number of the bill, the name of the payee, and the amount to be paid. No drawee will cash the bill unless he receives the *peth* or letter of advice. Payment is generally made in cash but sometimes another bill called *badli hundi* is given. When payment is received in either of these ways the payee passes a receipt on the bill and it is

## Chapter V.

## Capital.

## BILLS.

returned to the drawer. The receipted bill returned is called a *khoka* and is retained by the drawer as a voucher. Sometimes a bill is not for any determined sum but the drawee is asked to pay the payee sums of money as he may require them. This is called a *bhalávan patra* or *binájábtí*. It does not require a letter of advice, and the drawee sends to the drawer a letter as each payment is made. The bill must be cashed on the day specified if demanded, no days of grace being allowed. If the payment is delayed the payer is obliged to pay interest at a certain rate varying according to the position of the drawer. If he is a banker one-half per cent a month is paid, in other cases three quarters per cent. If payment is sought before the bill falls due, a discount at the above rates is deducted. If the bill is dishonoured and sent back uncashed, the drawee has to pay interest at double the rate of current interest from the date when the bill was drawn. He must also pay a non-acceptance penalty called *nakrái*, varying in different places. Formerly he was also liable to pay all the expenses of the payee. The practice is not now in vogue. If the bill is lost or stolen a duplicate or *peth* letter stating the amount of the bill and requiring payment is granted; if the duplicate is lost a triplicate or *parpeth* mentioning both the *hundi* and the *peth* is issued, and if the *parpeth* is also not forthcoming, an advice or *jáb* mentioning the *hundi peth* and *parpeth* is sent. The drawee is responsible for the payment he makes, for if he makes a payment to a wrong person he is obliged to make the payment over again to the holder of the *peth*. It is therefore customary for the drawee to take security from the payee when the drawee is not quite certain of the payee. The payee in the case of an advice letter or *jáb* passes a separate receipt, while the *hundi*, *peth*, and *parpeth* are simply endorsed. After payment the drawee debits the drawer with the amount paid. If a drawer overdraws his account and the bill is lost or dishonoured he alone is responsible. It is usual after endorsing the bills to sell them to bill brokers or *daláls* who are paid a certain percentage. When a bill thus travels to several places it is necessary in case of its loss that the *peth*, *parpeth*, and *jáb* should travel through the same places before it reaches its final destination. As treasure is seldom sent bills are adjusted by debits and credits and *badli hundi*s whose rates vary according to the conditions of the transaction. The interchange of bills has been greatly simplified by the introduction of a uniform coinage. Formerly the different rupees and the different rates of exchange made the system much more complicated and was a source of no small profit to local bankers. The drawer of the bill generally charges a certain percentage on the transaction and the person who wants the bill pays it. The rate however is variable according to the condition of the market. There are only three firms in the town of Kolhápúr which can cash at once a bill up to £4000 (Rs. 40,000). It is generally the practice of the bankers, however, not to draw bills payable at sight for larger amounts. The introduction of postal money orders has not affected the bankers to any perceptible extent.

Chapter V.  
Capital.  
BANKING.

There are nine banking houses, of which eight are at Kolhápur and one at Malkápur. Where there is an agent or *munim*, the clerk or *gumásta* acts under him. Generally there are no *munims* and the clerk is subordinate to his master alone. He is usually a Bráhmaṇ and is paid £20 (Rs. 200) a year.

SAVING CLASSES.

Of townspeople, moneylenders, traders, shopkeepers, brokers, pleaders, and a few highly paid State servants, and of country people landlords, village headmen or *pátils*, moneylenders, and a few rich cultivators save money. Savings are mostly invested in ornaments, lands, houses, and moneylending. The Government Savings Bank at Kolhápur is used almost solely by State servants, pleaders, and well-to-do men. In 1881-82 about 150 persons had £7500 (Rs. 75,000) invested in the Savings Bank.

MONEYLENDING.

Moneylending is the chief form of investment. Everybody who saves something, except perhaps State officials, takes to moneylending. Of 947 professional moneylenders the chief are Bráhmaṇs, Jains, Lingáyats, and Gujarát and Márwár Vánis. Besides regular moneylenders there are low usurers who for short periods lend small sums at heavy rates to the poorest borrowers. Among the professional moneylenders the Gujar and Márwári foreign moneylenders are hardhearted and show no sympathy to their debtors. Among other moneylenders those who have lately taken the profession are harsher than those who are hereditary lenders. Under the present administration after 1845 moneylending has greatly suffered. The old practice of forcing payment by personal torture and *dharna* or fasting has been discontinued. This has made the lenders cautious in lending, and they generally ask for security before they lend. Under the old farming system of collecting the revenue the farmers had often to borrow money on hard terms to meet sudden demands of the *darbár* or court. The husbandmen had dearly to pay for such demands. Under the new administration the farming system has been stopped. The settlement of many of the *sardárs*' or estate-holders' debts and the introduction of paying debts by instalments have much crippled the profits of moneylenders.

INTEREST.

Interest is charged monthly. In large transactions the usual rate varies from six to nine per cent a year, and in small transactions from nine to twelve per cent; but according to the credit of the individual borrowers this rate rises to as much as twenty-four to thirty per cent a year. When articles are pawned, the yearly rate is twelve per cent for pearls,  $7\frac{1}{2}$  for gold, and  $7\frac{1}{2}$  to nine for silver. In land and house mortgages the yearly rate varies from six to nine per cent. In grain advances during the rains which are generally paid after harvest, a quarter of the quantity lent is generally charged as interest.

BORROWERS.

Among borrowers except labourers, husbandmen are perhaps the worst off. Of the husbandmen those of the Konkan or hilly parts are worse off than those of the Desh or plain. In the Konkan the land generally yields no more than what is enough to maintain a farmer's family during half the year; during the other half of the

year most husbandmen live on wild herbs and fruits and labour where possible. The bulk of the husbandmen are Kunbis. The Kunbi is sober, hardworking, and peaceful. He is also shrewd and thrifty in his daily life, but spends much on marriage and other caste feasts. The Jain husbandmen are superior to Kunbis in intelligence and self-dependence. In the Konkan about ten per cent and in the plain about thirty per cent of the husbandmen live without borrowing. During the American war (1862-1865) when cotton and grain prices were unusually high, husbandmen made large savings; but these savings were lavishly spent on marriage and other great ceremonies. In Kolhápúr debtors are protected by the State law by which a limit of twelve years is fixed for the recovery of pawns and cash debts, and of husbandmen the land and the dwelling except when it is specially mortgaged, are exempted from sale in the execution of court decrees.

During the American war (1862-1865), when prices were unusually high, land was in much demand and fetched high prices. At the close of the American war the fall in prices lessened the value of land. Of late the opening of new made-roads and markets has again increased the demand for land. In the execution of court decrees land is not sold except when it is specially mortgaged. Land is mortgaged either with or without possession. In mortgages with possession the mortgagee receives the produce either as interest, the land being redeemable on payment of the principal; or sometimes the mortgagee receives the produce partly as interest and the surplus as part-payment of the principal. In mortgages without possession the land stands as security for the satisfaction of the mortgaged debt. The debtor pays the interest yearly, and if the debt is not paid back in time, the land is handed to the creditor usually through the intervention of the civil courts. When the land is handed to the mortgagee, the mortgagor is generally kept as tenant by the mortgagee to till the land.

To raise loans for marriage and other great occasions labourers often pledge their service to moneylenders and husbandmen for a period of three to ten years. During this period they receive free food and clothing from the mortgagees.

About thirty years ago (1853) unskilled labourers were paid about 3*d.* (2 *as.*) a day and skilled labourers 6*d.* to 1*s.* (4-8 *as.*) a day. At present (1883) unskilled labourers earn 3½*d.* (2½ *as.*) a day in villages and 4½*d.* (3 *as.*) in towns; and of skilled labourers carpenters, blacksmiths, masons, and stonecutters each earn 6*d.* to 1*s.* 6*d.* (4-12 *as.*) a day, and tailors and clothweavers 6*d.* to 1*s.* (4-8 *as.*). When employed in the field day-labourers are paid either in cash or grain. Women and children are largely employed as labourers, a woman earning about three-quarters and a child about one-half of a man's wages.

Till 1847 no uniform weights and measures were used. Every village and every shopkeeper had their own weights and measures made of any material at hand. Since 1847 new standard weights and measures have been introduced. According to these new weights the *tola* is equal to the Imperial rupee.

## Chapter V.

## Capital

## Borrowers.

## LAND MORTGAGE.

SERVICE  
MORTGAGE.

## WAGES.

WEIGHTS AND  
MEASURES.

## Chapter V.

## Capital.

WEIGHTS AND  
MEASURES.

Gold and silver are sold by the following table, eight *gunjás* one *mása*, twelve *másás* one *tola*, twenty-four *tolás* one *sher*, forty *shers* one *man*, and twenty *mans* one *khandi*. Inferior metals and other articles are sold by the following table: five *tolás* one *chhaták*, two *chhatáks* one *navták*, two *navtáks* one *pávsher*, two *pávshers* one *achher*, two *achhers* one *sher*,  $1\frac{1}{2}$  *pakka* or five *kachcha shers* one *pásri*, two *pásris* one *dhada*, four *dhadás* or twelve *pakka shers* one *man*, and twenty *mans* one *khandi*. A *pakka sher* is equal to eighty rupees in weight and a *kachcha sher* varies in weight from fifteen to twenty-six rupees. In selling metals a *man* is equal to sixteen *shers* or thirty-two pounds. Grain is sold by measures. A *sher* measure when filled with any of the nine grains, barley, *sáva* *Panicum miliaceum*, *nágli* *Eleusine corocana*, gram, wheat, spiked millet, Indian millet, rice, and *tur* *Cajanus indicus*, is in weight equal to 100 Imperial rupees. The table of grain measures is  $6\frac{1}{4}$  *tolás* one *nilva*, two *nilvás* one *kolva*, two *kolvás* one *chipta*, two *chiptás* one *mápta*, two *máptás* one *sher*, two *shers* one *adishri*, two *adishris* one *páyli*, sixteen *páylis* one *man*, and twenty *mans* one *khandi*. Of liquids oil is sold by the measure, four *kachcha shers* one *támbiya* or *pakka sher*, thirteen *pakka shers* one *man*, and twenty *mans* one *khandi*. A *kachcha sher* of this measure is equal to twenty *tolás*. Clarified butter is sold by the measure, twenty *tolás* one *pávsher*, four *pávshers* one *sher*, and twelve *shers* one *man*. For milk forty instead of twelve *shers* make one *man* and twenty *mans* one *khandi*. Till 1868, when the survey was introduced, the current land table was eight *javs* one *angul*, four *anguls* one *mushti*, three *mushtis* one *vit* or span, two *vits* one *hát*,  $5\frac{1}{2}$  *hát*s one *káthi*, twenty *káthis* one *pánd*, twenty *pánds* one *bigha*, and 120 *bighás* one *cháhur*. Since 1869 the land measure is sixteen *ánás* one *guntha* and forty *gunthás* one acre. Of cloth waistcloths, women's robes, and *khádi* or coarse cloth are measured by cubits or *hát*s; silk cloth is generally sold by the table two *angulis* one *tasu*, twelve *tasus* one *hát*, and two *hát*s one *gaj*; and other cloth by twelve inches one foot and three feet one yard. Timber is sold by a table of eighty *tolás* one *sher*, forty *shers* one *man*, and twenty *mans* one *khandi*. Grass is sold by so many hundred bundles the rupee. Bamboo matting is measured by the surface and sold by the cubit. Cut stones are sold singly or by the hundred and uncut stones by the cartload.

## PRICES.

Yearly price details, which are little more than estimates, are available for the forty-one years ending 1883. During these forty-one years the rupee price of Indian millet, which is the staple grain of the State varied from eighty-eight pounds in 1851 to twelve pounds in the famine year of 1877 and averaged fifty pounds. The forty-one years may be divided into eight periods. Except in 1844 when it was seventy-four pounds, in the first period of five years ending 1847 the price varied from fifty-seven pounds in 1846 to forty-six pounds in 1843 and averaged fifty-seven pounds. In the second period, the six years ending 1853, the price varied from eighty-eight pounds in 1851 to seventy-five pounds in 1853 and averaged eighty-one pounds. In the third period, the seven years



Chapter V.  
Capital.  
PRICES.

ending 1860, the price varied from sixty-five pounds in 1857 and 1858 to sixty pounds in 1854 and averaged sixty-three pounds. In the fourth period, the five years ending 1865, the price varied from fifty-two pounds in 1861 to thirty-two pounds in 1864 and averaged forty pounds. Except in 1869 when it was forty-three pounds, in the fifth period, the seven years ending 1872, the price varied from twenty-nine pounds in 1867 1868 and 1870 to twenty-one pounds in 1866 and averaged twenty-nine pounds. In the sixth period, the four years ending 1876, the price varied from forty-five pounds in 1874 and 1875 to thirty-six pounds in 1876 and averaged forty-two pounds. In the seventh period, the four years ending 1880, the price varied from thirty-one pounds in 1880 to twelve pounds in 1877 and averaged twenty-one pounds. And in the eighth period, the three years ending 1883, the price varied from sixty pounds in 1881 to fifty-five pounds in 1882 and averaged fifty-seven pounds. The details are :

*Kolhápur Grain Prices in Pounds, 1843-1881.*

PRODUCE.	FIRST PERIOD.					SECOND PERIOD.							THIRD PERIOD.		
	1843	1844	1845	1846	1847	1848	1849	1850	1851	1852	1853	1854	1855	1856	
Indian Millet...	46	74	54	57	56	84	81	81	88	77	75	60	61	64	
Wheat ... ..	67	54	45	47	54	49	60	60	63	64	54	42	39	48	
Rice ... ..	31	30	27	32	30	30	32	31	31	34	34	26	27	20	

PRODUCE.	THIRD PERIOD —continued.				FOURTH PERIOD.					FIFTH PERIOD.				
	1857	1858	1859	1860	1861	1862	1863	1864	1865	1866	1867	1868	1869	1870
Indian Millet ...	65	65	64	61	52	46	38	32	33	21	29	29	43	29
Wheat ... ..	46	49	48	46	43	25	18	17	14	14	20	14	19	19
Rice ... ..	23	25	22	22	20	22	19	32	12	14	12	16	13	14

PRODUCE.	FIFTH PERIOD <i>—contd.</i>		SIXTH PERIOD.				SEVENTH PERIOD.				EIGHTH PERIOD.		
	1871	1872	1873	1874	1875	1876	1877	1878	1879	1880	1881	1882	1883
Indian Millet...	25	25	41	45	45	36	12	21	22	31	60	55	56
Wheat ... ..	14	16	19	27	30	17	15	21	19	20	27	36	35
Rice ... ..	13	14	24	14	17	11	7	14	14	14	16	22	23

## CHAPTER VI.

## TRADE.

## Chapter VI.

## Trade.

## ROADS.

TILL 1845 when British superintendence was introduced Kolhápúr had no made roads. Of the pathways those that led west down the Sahyádris to the coast were hardly fit for lightly laden cattle, and those that went inland were mere beaten cattle tracks. During the rains from June to November when the rivers and streams were full, the passage across the inland tracks was entirely closed and foot passengers crossed the rivers in the broad but shallow and unsafe sugar-pans which yearly caused a great loss of life. Between 1845 and 1854 about 300 miles of road were made at a cost of £10,300 (Rs. 1,03,000). Since 1854 old roads have been much improved and new roads made, the chief being the Poona-Belgaum mail road. At present (1883), besides several small roads, Kolhápúr has four main lines of communication, one the Poona-Belgaum road running north and south, and three the Kolhápúr-Ámba pass, the Kolhapur-Phonda pass, and the Sankeshvar-Párpoli pass roads, running west towards the coast. The Poona-Belgaum mail road, the chief inland road in the State, enters the Kolhápúr State at the Várna river in the north and runs about fifteen miles south-west to Kolhápúr, and from Kolhápúr runs south-east fifteen miles further by Kágál to the Dudhganga on the southern frontier. The road is metalled and bridged throughout, the chief bridges being across the Várna, Panchganga, and Dudhganga. It is repaired from Provincial funds by the British Government. Beginning from the north, by the Ámba Phonda and Párpoli passes which are now fit for carts, three roads from Kolhápúr run west down the Sahyádris to the coast. Of these the Ámba pass road leads to Ratnágiri, the Phonda pass road to Vijaydurg Devgad and Málvan, and the Párpoli pass road to Málvan and Vengurla. The Kolhápúr-Ámba pass road runs from Kolhápúr forty-two miles north-west to the village of Ámba on the Sahyádris on the borders of Kolhápúr and Ratnágiri. At Brahmapuri, about two miles north-west of Kolhápúr, the road crosses the Panchganga, and then through the Panhála gorge passes the villages of Navli, Ávli, and Bambavda, and the large town of Malkápúr. From the village of Ámba on the Sahyádris the road descends west by the Ámba pass to Ratnágiri. Within Kolhápúr limits the road was completed in 1883 with drains and bridges at a cost of £48,234 (Rs. 4,82,340). Of the three coast roads, the Kolhápúr-Ámba pass road is the shortest for Kolhápúr and Sàngli, Miraj, Shirol, Kurundvád, Ichalkaranji, and Athni lying east of Kolhápúr. The Kolhápúr-Phonda pass road runs forty-two miles south-west to the village of Dájipur near the Sahyádris on the borders of Kolhápúr and Ratnágiri. From Kolhápúr the road passes by the villages of Haladi, Ananj, and Valivda. Of the

## Chapter VI.

## Trade.

## ROADS.

forty-two miles, the total length of this road in Kolhápúr, twenty-six miles, from Kolhápúr to Gibikhind were in 1874 built by the Kolhápúr State at a cost of £7307 (Rs. 73,070) and the remaining sixteen miles from Gibikhind to Dájipur are now being drained and bridged and when completed will afford direct communication with the coast during the rains. From Dájipur near the Sahyádris the road descends by the Phonda pass into Ratnágiri, one branch going north-west to Vijaydurg, another going west to Devgad, and a third south-west to Málvan. At present (1883) for Kolhápúr this road is the most direct to the coast. About twenty-six miles south of Kolhápúr, by the towns of Saravda and Murgod, this road branches east to Nipáni in Belgaum. This portion to Nipáni is now being cross-drained under British supervision. From Sankhesvar on the Poona-Belgaum mail road, about thirty-six miles south of Kolhápúr, the Sankeshvar-Párpoli pass road runs thirty-six miles west to the village of Dhangarmola near the Sahyádris on the borders of Kolhápúr and Sávantvádi. In South Kolhápúr the road passes by the towns of Gadinglaj and Ajra. From Dhangarmola near the Sahyádris the road descends by the Párpoli pass into Sávantvádi. After leaving Vádi the road branches in two, one passing north-west to Málvan and the other south-west to Vengurla. Of the thirty-six miles the total length of this road within Kolhápúr limits, about ten miles between Sankeshvar and Gadingláj were in 1881 completed at a cost of £9273 (Rs. 92,730), of which half was paid by the British Government and the other half by the Kolhápúr State. For these ten miles as well as for twelve miles further from Gadinglaj to Ajra which were made solely by the Kolhápúr State at a cost of £9347 (Rs. 93,470), the road is *murumed* that is laid with crumbly trap, and for the remaining fourteen miles from Ajra to the Párpoli pass which were also made by the Kolhápúr State, the surface is laid with laterite. Except the Hiranyakeshi and a few small streams the road is cross-drained throughout. It is the most direct coast road for Athni, Gokák, Hukeri, and Nipáni in Belgaum, and for Tásgaon in Sátára. The traffic on this road is heavy, averaging about 150 carts a day. Most of the cross roads are unfit for carts and many are difficult for pack bullocks. Of the small inland roads, besides the through Poona-Belgaum road, the Kolhápúr-Miraj road runs twenty-six miles east from Kolhápúr to Udgaon by the towns of Hirla, Attigre, Alta, and Hátkalangda. At Udgaon the road crosses the Krishna and runs further east to Miraj. It is a first class bridged and drained road built in 1877 at a cost of £21,168 (Rs. 2,11,680). From Attigre on the Kolhápúr-Miraj road a drained and bridged road, built at a cost of £5003 (Rs. 50,030), runs nine miles south-east to Ichalkaranji; and from Ichalkaranji a fair weather cart track runs seven miles east to Kurundvád. From Udgaon on the Kolhápúr-Miraj road a cross-drained road built at a cost of £1747 (Rs. 17,470) runs four and half miles south to Shirol, two and half miles from Shirol to Kurundvád, and five miles from Kurundvád to Hervad. On the east side of the Krishna near Udgaon a four-mile road from Sángli joins the Kolhápúr-Miraj road in the south. At the eighth mile north-west of Kolhápúr, on the Kolhápúr-

## Chapter VI.

## Trade.

## ROADS.

Ámba pass road, a *murumed* and bridged road about four miles long runs west to the old fort of Panhála. The portion immediately below the entrance to the fort is very steep, the gradient being about one in five. It is now proposed to make this portion more easy. From Malkápur on the Kolhápur-Ámba pass road a second class fair weather *murumed* road runs twenty miles east to Kápsi by Sarud. From Sarud a fair weather road without bridges or drains joins the Kolhápur-Ámba pass road at Bambavda and from Bambavda it continues to run as far as the village of Pishvi.

Of the roads that are being built, a drained and bridged road estimated to cost about £3200 (Rs. 32,000), will run three miles south from Shirol to Narsobáchivádi. From Kolhápur a new road is being made thirty-two miles south to Gárgoti, the headquarters of the Bhudargad sub-division. Of these thirty-two miles twenty have been cross-drained and *murumed* that is laid with crumbly trap till 1882. In 1883 the remaining twelve miles were surveyed.

## TOLLS.

Of the thirteen tolls nine are on *gháts* or hill passes and four on plain roads. Beginning from the north, the nine tolls on the hill passes are at Chándel, Ámba, Prabhánvalli, Anaskura, Kájirda, Bávda, Phonda, Ghotga, and Hanmant; and the four road tolls are at Unchgaon on the Poona-Belgaum road, at Vádi-Ujlai on the Kolhápur-Kágal road, at Herla on the new Miraj road, and at Ajra on the Sankeshvar-Vengurla road. The tolls charged are for every four-wheeled carriage 1s. (8 *as.*), for every two-wheeled cart or carriage 6*d.* (4 *as.*) if drawn by two animals and laden and 3*d.* (2 *as.*) if unladen, 9*d.* (6 *as.*) if drawn by four animals and laden and 4½*d.* (3 *as.*) if unladen, 1s. (8 *as.*) if drawn by six animals and laden and 6*d.* (4 *as.*) if unladen, 2s. (Re.1) if drawn by eight animals and more and laden and 1s. (8 *as.*) if unladen, 2s. (Re.1) for every elephant, ¾*d.* (½ *a.*) for every camel, horse, pony, mule, buffalo, or bullock whether laden or unladen; ¾*d.* (¼ *a.*) for every ass laden or unladen, ½*d.* (¼ *a.*) for every sheep, goat, or pig, 6*d.* (4 *as.*) for every palanquin or other litter carried by four or more bearers and 3*d.* (2 *as.*) for every small litter carried by less than four bearers. Every year in May the tolls are farmed to the highest bidder for one year. The tolls are managed by the farmers who pay the amount to the State by monthly or quarterly instalments. In 1881 the tolls were farmed for £1847 8s. (Rs. 18,474), of which £1126 16s. (Rs. 11,268) were for the nine hill-pass tolls and £720 12s. (Rs. 7206) for the four plain road tolls. Besides these tolls the municipality of Kolhápur levies tolls on all imports into and exports from Kolhápur city. In 1883 the city toll yielded a revenue of £1202 12s. (Rs. 12,026).

## RAILWAYS.

At present (1883) Kolhápur has no railways. Of the three systems of railways, the East Deccan or Hotgi-Gadag, the South Deccan or Belári-Mármagaon, and the West Deccan or Poona-Londa which are being now introduced into the Southern Marátha and Kánarese districts of Bombay, the Poona-Londa line will pass by Miraj, about seven miles from the eastern boundary of the Kolhápur State and thirty-two miles east of Kolhápur city.

Of the twelve hill passes or *gháts* in the Sahyádris, beginning from the north, one the Devda is in the Vishálgad sub-division, three the Ámba Chándel and Prabhánvalli are both in the Vishálgad and Panhála sub-divisions, one the Anaskura is in the Panhála sub-division, one the Kájirda is in the Panhála and Bávda sub-divisions, one the Bávda is in the Bávda sub-division, two the Phonda and Shivgad are in the Bávda and Bhudargad sub-divisions, and three, the Bharasvádi Ghotga and Umarja are in the Bhudargad sub-division. Of these hill passes the Ámba and Phonda are fit for carts.<sup>1</sup> Besides these there are about seventy-five gorges or *khinds*. Most of the gorges are fit for foot passengers and a few are used with difficulty by pack bullocks. Of the seventy-five gorges twenty-four are in Vishálgad, four in Panhála, seven in Bávda, and forty in Bhudargad. Besides these, the hill forts of Bhudargad, Gad-inglaj, Gagan-Bávda, Kágál, Panhála, Pávangad, Shivgad, and Vishálgad, are approached by difficult hill passes, 500 to 2500 feet long. Of these gorges a few are fit for pack bullocks and the rest are used by foot passengers only.

The twelve rivers on which ferries ply during the rains (June-October) are the Bhogávati, Chitri, Dudhganga, Ghatprabha, Hiranyakeshi, Kadvi, Kásári, Krishna, Kumbhi, Panchganga, Várna, and Vedganga. During the fair season from November to June these rivers have water in deep reaches separated by sandy plots and have fords at a distance of two to four miles. Before 1845 iron sugar-pans instead of boats were used as ferries, which yearly caused a large loss of life. In 1854 twenty boats and twenty baskets plied during the rains. At present (1883) the ferry-boats have increased to sixty-four of which twenty-two belong to the State and forty-two to private persons. Of the twenty-two State ferry boats four ply on the Dudhganga at Sulkud, Shidurli, Bachni, and Ghosarvad; three ply on the Kásári at Vaghne, Bajárbhogaon, and Padal; three ply on the Kumbhi at Malhárpeth, Sangrul, and Sálvan; five ply on the Panchganga at Rui, Ichalkaranji, Vadinga, Rukdi, and Shiye; two ply on the Várna at Kodoli and Shitur; and five ply on the Vedganga at Nidhori, Mudga-budruk, Anur, Chikhli, and Bange. The ferry boats vary in size from thirty-six by 12½ feet to 7½ by two feet. In twelve towns at Kágál, Khárepátan, Malkápur, Mhamdápur, Mesoli, Nesari, Rájápur, Rashivda, Salgaon, Sulkud, Thergaon, and Vengurla, the ferry boats are built of teak, *bábhul*, mango, and *sávri* or silk-cotton tree wood. Generally the whole boat is made of one kind of wood, but sometimes it is built of planks of two or three different kinds. The boatmen are Bágdis, Bhandáris, Chámbhárs, Kolis, Kunbis, Lingáyats, and Musalmáns. At the twenty-two State ferries, the boatmen are not paid in kind or grain, but have service lands given in return for their labour. The ferry boats carry 200 to 400 passengers. Except eight private ferries which work free of charge, they charge a fee of ¾d. (¼ a.) for each passenger. Besides passengers, the larger ferry boats carry cattle and carts, generally bullocks for ¾d. (¼ a.), horses for 1½d. (1 a.), and camels for 3d. (2 as.).

## Chapter VI.

## Trade.

## PASSES.

## FERRIES.

<sup>1</sup> Fuller details of Hill-passes are given in Chap. I. under Hills.

Chapter VI.  
Trade.  
BRIDGES.

Of the five chief bridges within Kolhápúr limits the Krishna bridge is the largest and lies twenty-six miles east of Kolhápúr near Udgaoon on the Kolhápúr-Miraj road. It is a stone bridge with eleven spans of seventy feet and with foundations resting on hard rock. The roadway is seventy-five feet above the river-bed. The bridge was completed between 1875 and 1879 at a cost of £45,000 (Rs. 4,50,000), of which £25,000 (Rs. 2,50,000) were paid by the British Government, £10,000 (Rs. 1,00,000) by the Kolhápúr State, £5000 (Rs. 50,000) by the Súngli State, and £2500 (Rs. 25,000) each by Miraj Senior and Junior. Besides the Várna bridge on the northern border and the Dudhganga bridge on the southern border which were built by the British Government, the Panchganga bridge on the Poona-Belgaum mail road at Unchgaon, about three miles north of Kolhápúr, has seven openings of sixty feet with masonry piers and wrought-iron superstructure. It was originally intended for masonry arches, but as the foundation of the north abutment was faulty, lattice girders were substituted to diminish the pressure. This bridge was completed in 1874 at a cost of £25,000 (Rs. 2,50,000). The remaining three bridges are on the Kolhápúr-Ámba pass road over the Panchganga, Shalli, and Kadvi rivers. About a mile north of Kolhápúr on the Kolhápúr-Ámba pass road the Panchganga is crossed by a masonry bridge with five spans of seventy feet. This bridge was completed between 1874 and 1878 at a cost of £18,913 (Rs. 1,89,130). At Malkápúr on the Kolhápúr-Ámba pass road the Shalli is crossed by a masonry bridge with five thirty feet spans. This bridge was completed between 1880 and 1881 at a cost of £3805 (Rs. 38,050). About six miles west of Malkápúr on the Kolhápúr-Ámba pass road the Kadvi is crossed near Gade-Gaund by a masonry bridge with five thirty feet spans. This bridge was completed between 1881 and 1882 at a cost of £3540 (Rs. 35,400). Besides these five bridges a masonry bridge with five sixty feet spans is being built over the Bhogávati three miles west of Kolhápúr on the Kolhápúr-Bávda road. This bridge is estimated to cost about £16,082 (Rs. 1,60,820).

REST-HOUSES.

Of the five travellers' bungalows for European travellers three are on the Poona-Belgaum mail road at Kinni Kolhápúr and Kágál, a fourth is at Dájipúr on the Kolhápúr-Phonda pass road, and a fifth is at Panhála. Of the three bungalows on the Poona-Belgaum mail road the Kinni bungalow lies fourteen miles north of Kolhápúr. It accommodates four persons and has furniture and cooking vessels but no messman. Except mutton and beef ordinary supplies are obtainable. Water is scanty and is brought from a well about 250 yards from the bungalow. Each traveller is charged a daily fee of 2s. (Re.1). The Kolhápúr bungalow lying close to the Sadar Bazár has room for six persons. Supplies are abundant, and besides furniture and cooking vessels the bungalow has a messman. Each traveller is charged a daily fee of 2s. (Re.1). The Kágál bungalow lies ten miles south of Kolhápúr. It has room for four persons and has furniture and cooking vessels but no messman. Water and food are abundant. The bungalow belongs to the chief of Kágál, the present Regent of Kolhápúr, who lets travellers use it free of charge. The Dájipúr bungalow lies thirty-nine



miles south-west of Kolhápura on the Kolhápura-Phonda pass road. It has been now (1884) rebuilt and has room for two persons. As there are no large towns in the neighbourhood, food and carriage are difficult. Water is obtained from the Bhogávati which runs close to the bungalow. A daily fee of 2s. (Re. 1) is charged for each traveller. The Panhála bungalow lies within the fort of Panhála, about twelve miles north-west of Kolhápura. As Panhála is the present health-resort of Kolhápura, the bungalow is always occupied during the hot season. Food is easily obtained. As some of the springs pass through the laterite foundation which is highly charged with iron, the drinking water is said to possess medicinal properties. A daily fee of 3s. (Rs. 1½) is levied from each traveller. Besides these five, a sixth bungalow is to be built at Ámba, forty-two miles north-west of Kolhápura on the Kolhápura-Ámba pass road.

For Native travellers the State has built twenty-five standard and 105 ordinary rest-houses. Of the twenty-five standard rest-houses seven are in Karvir, four in Bhudargad, three each in Panhála Kágala and Ichalkaranji, two in Alta, and one each in Gadinglaj Shirol and Vishálgad. Of the 105 ordinary rest-houses thirty-one are in Karvir, seventeen in Gadinglaj, sixteen in Kágala, twelve in Shirol, ten in Ichalkaranji, six each in Bhudargad and Bávda, five in Alta, and two in Panhála. Besides these 1308 temples and mosques serve as rest-houses. Of these 292 are in Alta, 209 in Gadinglaj, 187 in Ichalkaranji, 180 in Kágala, 131 in Vishálgad, ninety each in Bhudargad and Panhála, fifty-eight in Shirol, fifty-five in Karvir, and sixteen in Bávda.

Of the seventeen post offices two, the chief disbursing office and a town sub-office, are in the city of Kolhápura; fourteen are sub-offices at Ajra, Gadinglaj, Gagan-Bávda, Gárgoti, Hátkalangda, Ichalkaranji, Kágala, Katkol, Malkápura, Panhála, Ráybág, Shirol, Torgal, and Vadgaon; and one is a village office at Narsobáchi Vádi. The disbursing office is in charge of a postmaster drawing a yearly salary of £84 (Rs. 840). The sub-offices are in charge of sub-postmasters who draw yearly salaries of £36 (Rs. 360) for the town sub-office of Kolhápura and of £18 (Rs. 180) for other sub-offices. The village office is in charge of a schoolmaster who draws a yearly allowance of £3 12s. (Rs. 36) for this additional work. Besides in some places by runners who draw a yearly allowance of £2 8s. (Rs. 24) for this additional work, letters are delivered by seventeen postmen who draw yearly salaries of £9 12s. to £12 (Rs. 96-120). The post offices are supervised by the Superintendent and his assistant the inspector of post offices Deccan division, who both have their head-quarters in Sátára. The salaries of the superintendent and inspector are personal, the present superintendent drawing a yearly salary of £240 (Rs. 2400) and the inspector of £120 (Rs. 1200). Mails to and from Bombay are carried by the Great Indian Peninsula Railway between Bombay and Poona; the mails between Poona and Kolhápura are carried in pony carts or *tongás* which run from Poona to Hubli through Sátára, Kolhápura, Belgaum, and Dhárwár. Besides the British post offices, eight postal lines, maintained by the State at a yearly cost of about £400 (Rs. 4000),

## Chapter VI.

## Trade.

## REST-HOUSES.

## POST OFFICES.

## Chapter VI.

## Trade.

## POST OFFICES.

carry only official letters in the various sub-divisions. Of the eight lines seven run from Kolhápúr, one to Bhudargad; a second to Panhála; a third to Hátkalangda, Shirol, Ráybág, and Katkol; a fourth to Kágál and Gadinglaj; a fifth to Malkápur; a sixth to Ichalkaranji; and a seventh to Bávdá; the eighth line runs from Ichalkaranji to Ajra. Every morning at about nine o'clock official letters are sent from Kolhápúr with runners who travel at two and a half to three miles an hour. Every month about 12,000 official packets are despatched from Kolhápúr and nearly the same number is received.

## TELEGRAPH.

Since 1854 Kolhápúr city has a Government Telegraph Office wire directly connected with Poona and Belgaum. During the fourteen years ending 1882 the yearly messages rose from 599 in 1869 to 1360 in 1882. Since 1880 a telegraph has also been opened between Kolhápúr and Ratnágiri, Rájápur and Chiplun.

## TRADE CENTRES.

Of the twelve chief trade centres and market towns two are in Karvir, at Kolhápúr and Sangrul; four in Panhála at Kadoli, Mále, Panhála, and Sarud; one in Alta at Vadgaon; one in Gadinglaj at Gadinglaj; two in Vishálgad at Kápsi and Malkápur; one in Kágál at Murgud; and one in Ichalkaranji at Ichalkaranji. Except at Ichalkaranji where a market is held twice a week, at all these places markets are held once a week. These markets are spreading as well as gathering centres. Of the imports and exports, at Kolhápúr grain, cloth, earthenware, baskets, and cattle largely come from neighbouring places; most of these articles find their way to Nipáni in Belgaum and Chiplun and Rájápur in Ratnágiri. From Sangrul rice is largely sent to Nipáni and other places. At Kadoli grain is largely sold; from Kadoli cotton, molasses, and chillies, and from Panhála rice are largely sent. At Sarud grain is brought in large quantities and cloth exported. At Vadgaon, which is a large trade centre, dates, cocoa-kernel, sugar, and English yarn are brought from the sea ports, and a number of cattle from neighbouring places for sale; and besides chillies, tobacco, and wheat and other grains, molasses is largely exported. At Gadinglaj the chief trade is in grain, coarse cloth, and cattle. At Kápsi the local dealers take grain, chillies, and other articles for sale to Islámpur, Miraj, Sángli, and Tásgaon. At Malkápur grain and cattle come from neighbouring villages, and cocoanuts, dates and other articles from Ratnágiri ports. The chief exports are rice, *javari*, wheat, grain, and chillies. At Murgud grain comes in large quantities from neighbouring villages and rice is exported. At Ichalkaranji grain and cattle are brought for sale. Besides at the large trade centres, forty-seven small weekly markets are held. Of these seven are in Karvir at Bida, Dhamoda, Hassarbudruk, Kandgaon, Khebavda, Shiroti, and Thikpurli; five are in Panhála at Bajár-Bhogaon, Kalhen, Kotholi, Padal, and Pishvi; six are in Shirol at Chinchli, Ghosarvad, Nándni, Parmánand-Vádi, Ráybág, and Shirol; eight are in Alta at Alta, Hátkalangda, Herla, Hupri, Kumbhoj, Rendal, Rukdi, and Savgav; six are in Gadinglaj at Halkarni, Harli, Kadgaon, Kápsi, Katkol, and Nesari; seven are in Bhudargad at Madilge, Saravde, Shengaon, Shevpur,

Chapter VI.  
Trade.

## FAIRS.

Tárla, Valivda, and Válva; one is in Vishálgad at Mahágaon; three are in Bávda at Bávda, Rashivda, and Tisangi; three are in Kágál, at Chikhli Kágál and Mángaon; and one is in Ichalkaranji at Ajra.

Five large fairs are held in the State, at Chinchli, Jotiba's Hill, Kágál, Godchi, and Narsinh's Vádi. The fair at Chinchli is held on the bright fifteenth of *Mágh* in January-February and lasts for five days. At this fair a large number of cattle are brought for sale. It is attended by about 35,000 people and the sales average £6000 (Rs. 60,000). The fair at Jotiba's Hill or Vádi-Ratnágiri is held on the bright fifteenth of *Chaitra* in March-April and lasts for one day. It is attended by about 40,000 people, and the sales average £4,500 (Rs. 45,000). The fair at Kágál is held on the bright second of *Kártik* in October-November and lasts for one day. It is attended by about 10,000 people and the sales average £800 (Rs. 8000). The fair at Godchi in Torgal is held in *Márgashirsh* in November-December and lasts for four days. It is attended by about 12,000 people and the sales average £700 (Rs. 7000). The fair at Narsinh's Vádi is held on the dark fifth of *Mágh* in February-March and lasts for one month. It is daily attended by about 5000 people and the total sales average £30,000 (Rs. 3 lákhs). Besides these, small fairs are held at nineteen other places. The details are :

## Kolhápúr Fairs, 1882.

PLACE.	NAME.	MONTH.	DAYS.	AVERAGE SALE.	ATTENDANCE.
<i>Karvir.</i>					
Shingnápúr ...	Visháli ...	December-January.	1	£ 280	7500
Bávda ...	Triyambuli ...	September-October.	1	230	7000
Pádali ...	Prayág ...	January-February..	30	100	200
Nandvái ...	Vithoba ...	June-July ...	1	40	2000
Vashi ...	Biroba ...	January-February..	1	50	1500
<i>Panhála.</i>					
Vádi-Ratnágiri ...	Jotiba ...	March-April ...	1	4500	40,000
<i>Alta.</i>					
Pátan Kodoli ...	Biroba ...	September-October.	1	1700	5000
Alta ...	Dhuldev ...	March-April ...	1	60	5000
Narande ...	Nágnáth ...	January-February.	1	60	1000
Khodashi ...	Bhairav ...	March-April ...	1	190	3000
Hupri ...	Ambábái ...	January-February..	3	170	1000
<i>Shirol.</i>					
Narsinhvádi ...	Narsinhvádi ...	February-March ...	30	30,000	5000
Chinchli ...	Máyáka ...	January-February..	5	6000	(daily). 35,000
<i>Gadínglaj.</i>					
Chinchevádi ...	Bhim Sheshgiri...	January-February..	1	180	2000
Godchi ...	Virabhadra ...	Novr.-Decr. ...	4	700	12,000
<i>Bhudargad.</i>					
Bhudargad ...	Bhairi ...	January-February.	1	130	800
<i>Vishálgad.</i>					
Mahágaon ...	Mahákáli ...	December-January. (Alternate year).	1	280	2000
Malkápúr ...	Dhopeshtar ...	January-February.	1	50	2000
Achirne ...	Rasál ...	December-January.	15	1300	5000
<i>Kágál.</i>					
Kágál ...	Gaibi ...	October-November.	1	800	10,000
<i>Ichalkaranji.</i>					
Lát ...	Kaleshtar ...	October-November.	1	110	4000
Shivápúr ...	Rámling ...	July-August ...	1	80	2000
Ajra ...	Rámling ...	January-February.	1	400	5000
Útur ...	Jomkál ...	February-March ...	1	200	00

## Chapter VI. Trade.

Except that they are much larger gatherings, these fairs differ little from the weekly markets. The chief articles sold are grain, cloth, silk, blankets, copper, brass and earthen vessels, glass bangles, pearls, perfumes, and sweetmeats.

### SHOPKEEPERS.

Every village large or small has its shopkeeper generally a Váni or Gujar, who deals in groceries, spices, grain, salt, oil, sugar, molasses, and other supplies. The whole stock is worth £1 to £30 (Rs. 10-300). He buys some of the more lasting wares at one of the chief trade centres or at some large fair. But most of his stock is bought from time to time at the nearest market or sub-divisional town. As the rich lay in the chief part of their grain and groceries for a whole year, buying them in the larger markets, they take from the village shopkeepers such perishable articles only as oil, groceries and sugar. The middle and poorer classes, except what they themselves produce, draw almost all their supplies from the village shopkeeper, and according to their credit pay ready money or, what is commoner, have a weekly or monthly account. Even in the wilder parts the village shopkeeper seldom barter. He is often a moneylender, and in the accounts of many of his customers oil and spice entries are often mixed with money advances.

### PEDDLERS.

Below the village shopkeeper is the peddler. Some of the peddlers are craftsmen, generally weavers and coppersmiths. During the rains the weavers weave cloth and the coppersmiths make copper and brass vessels which during the fair season they sell from village to village. Other peddlers sell groceries, perfumes, glass bangles, and hardware. Peddlers move from house to house carrying their stock on a packbullock or pony and sometimes by headload. The peddlers sell most of their stock by barter, specially exchanging brass and copper vessels for old clothes and laces.

### CARRIERS.

The chief wandering carriers are the Bágváns, Lamáns, and Lonáris. Of late, since the making of good through roads and the introduction of carts, carriers have much decreased. At present (1883) 7347 pack bullocks are employed in carrying grain and firewood. Of these 1500 are in Panhála, 1236 in Karvir, 931 in Gadinglaj, 800 in Bhudargad, 798 in Bávda, 604 in Shirol, 434 in Alta, 382 in Kágál, 376 in Vishálgad, and 286 in Ichalkaranji. Besides bullocks, donkeys are used by Lonáris in carrying firewood and lime.

### IMPORTS.

The chief imports are salt, metal, cocoanuts, dates, groceries, oil, hardware, twist, and piece goods. Salt was formerly brought entirely by pack bullocks from the Konkan. Under metal come gold, silver, copper, brass, and iron. During the American war (1862-1865) gold and silver were largely imported; during the scarcity of 1876-77 a large amount of gold and silver in ornaments left the State; and since the return of prosperity in 1881 and 1882 gold and silver have again been imported. Sheets of copper and brass are brought in small quantities, and ready-made vessels and drinking mugs in large quantities chiefly from Poona. Formerly iron was locally smelted and it is now largely brought from Bombay by Vánis and Bohorás. It is much used for cart tiers and axles and in making iron pots. Dates, groceries, kerosine and coconut oil, iron buckets, and water

pots are brought from Bombay. Steam-spun twist, both English and Bombay-made, is brought and sold to hand-loom weavers. Piece goods are hand-made and steam-made. Of hand-made goods the chief are turbans and women's robes from Poona, Sháhápúr, Sholápúr, and Yeola; waistcloths or *dhotars* from Nágpur and Sháhápúr; and silk waistcloths or *pitámbars* and robes or *paithanis* and turbans from Burhánpur and Poona. Of the steam-made cloth the coarse strong cloth is Bombay-made and the finer cloth is from England.

The chief exports are of grains, rice, *javári*, *bájri*, *náchni*, wheat, and gram; of groceries and spices coriander turmeric and chillies; of oilseeds sesame linseed and earthenut; and of other exports cotton, cotton tape, hemp, tobacco, molasses, and sugar.

Kolhápúr crafts are only of local importance. The chief crafts are, working in gold and silver, copper and brass, iron, stone, lime, earth, glass, wood, and leather; the weaving of coarse cotton cloth and woollen blankets; oil-pressing; the making of paper and perfumes.

Goldsmiths are found in almost all market towns, and every large village has an hereditary goldsmith or *potdár* to test the coins paid as land revenue. Of the total 1200 families about one-third, besides working as goldsmiths, till land. Of the eight divisions, Ahir, Deshasth Deváng, Konkanasth, Lád, Márwári, Rajput, and Vidur goldsmiths, the Deshasths and the Konkanasths are the most skilled. Except a set of tools a goldsmith requires no capital; the raw gold and silver are supplied by customers. On every rupee weight of the ornaments made, for silver work goldsmiths are paid 1*d.* to 6*d.* ( $\frac{3}{4}$  - 4 *as.*) and for the best gold work and jewelry as much as 8*s.* (Rs. 4). In the city of Kolhápúr some rich bankers employ goldsmiths on daily wages to make ornaments for sale. In this way ornaments worth about £10,000 (Rs. 1 *lák*h) are yearly made and sold at a profit of five to ten per cent. Goldsmiths have fairly steady work all the year round. They work about eight hours a day, from six to ten in the morning and four to eight in the evening. The women do not help the men, but boys when about twelve years old begin to learn the work. Goldsmiths are a well-to-do class. A first rate worker earns about 2*s.* (Re. 1) a day or £36 (Rs. 360) a year, a middling worker 1*s.* to 1*s.* 6*d.* (8 - 12 *as.*) a day or £18 to £27 (Rs. 180 - 270) a year, and a poor worker 6*d.* (4 *as.*) a day or £9 (Rs. 90) a year.

Coppersmiths or *Támbats* and *Kásárs*, of whom there are about seventy families, are found in a few large towns. They require a dead stock worth £2 to £5 (Rs. 20 - 50). At Kolhápúr the metal dealers bring copper and brass sheets from Poona and Sátára and occasionally from Sàngli and sell them to the local smiths at 10½*d.* to 1*s.* (7-8 *as.*) a pound. Of these raw sheets coppersmiths make water-jars, mugs, and cooking vessels and sell copper vessels at 1*s.* 3½*d.* (10½ *as.*) and brass vessels at 1*s.* 2½*d.* (9½ *as.*) the pound. During the fair season coppersmiths work ten hours a day; during the rains, owing to the cost of coals, their work is dull. To sell their stock they move from village to village and attend fairs during the dry season. On the chief Hindu festivals and on the *Amávásya*

## Chapter VI.

## Trade.

## IMPORTS.

## EXPORTS.

## Crafts.

## GOLD AND SILVER.

## COPPER.

Chapter VI.  
Crafts.

or the 30th of every month coppersmiths stop work. Owing to large imports of ready-made vessels from Násik, Poona, Rájápur, Sátára, Sháhápur, Shirála, and Terdál, the craft is not prosperous. Coppersmiths earn  $10\frac{1}{2}d.$  to  $1s.$  ( $7-8 as.$ ) a day. Copper and brass vessels are also brought for sale by Bogárs or Jain workers.

## IRON.

Blacksmiths or Lohárs and Ghisádis or tinkers of whom there are 940 families, are found in almost all villages. Besides these Dhavads and a few carpenters also work in iron. At Kolhápur Jain, Bohora, and other Musalmán dealers bring bars and sheets of iron from Bombay by Chiplun and sell them to local Lohárs and Ghisádis. The chief iron articles made are spoons, hatchets, sickles, and sugar-pans or *káhils*, which fetch  $1\frac{1}{4}d.$  to  $2\frac{3}{4}d.$  ( $\frac{2}{3}-1\frac{3}{4} as.$ ) the pound. Steel is sold at  $4\frac{1}{2}d.$  ( $3 as.$ ) the pound. Their services are in constant demand throughout the year. During the fair season their chief work is mending field tools. Except on big holidays and on every *Amávásya* or no-moon day when they do not work, blacksmiths work nine to ten hours a day. The women and children help in working the bellows. Blacksmiths earn a daily wage of  $1s. 3d.$  to  $2s.$  (Re.  $\frac{2}{3}-1$ ). In villages where they chiefly mend field tools, blacksmiths are paid in grain, about sixty pounds ( $6 páyis$ ) a year. During the fair season Ghisádis move from village to village and mend field tools. For this they are paid generally in grain at a lower rate than Lohárs.

## STONE.

The chief stone workers are Pátharvats, Beldárs, and Khandárs. Beldárs and Khandárs are quarrymen and earn  $6d.$  to  $9d.$  ( $4-6 as.$ ) a day. Rubble fetches  $6s.$  to  $10s.$  (Rs.  $3-5$ ) the hundred feet and other stone  $1\frac{1}{2}d.$  to  $4\frac{1}{2}d.$  ( $1-3 as.$ ) the foot. The Pátharvats dress the stone and earn  $1s. 6d.$  to  $2s.$  (Re.  $\frac{2}{3}-1$ ) a day. The best dressers are the Musalmán Pátharvats of Kolhápur who make excellent ornamental carving. Besides these, Marátha and Musalmán Gayandis or masons build with stone and mortar or mud and earn  $1s.$  to  $1s. 9d.$  ( $8-14 as.$ ) a day. Stonecutters work eight to ten hours a day. The women do not help the men, but boys when about twelve years old begin to learn.

## LIME.

Lonáris make lime in a kiln which is a circular hole built about ten feet above the surface of the ground. The surrounding walls are of stone and mud. At the bottom which has a hole, they place a layer of firewood, then a layer of *kankar* or lime nodules mixed with charcoal, and again a layer of firewood. The wood is kindled, and after eight or ten days when the whole is thoroughly burnt, the contents are taken out, separated from the charcoal, and sprinkled with water. The lime is ready for sale, and fetches £2 to £2 8s. (Rs. 20-24) the *khandi* of a hundred cubic feet.

## EARTH.

Kumbhárs or potters of whom there are about 200 families, make earthen pots, tiles, and bricks. They are Maráthás, Kánada Lingáyats, and Pardeshis of whom the Pardeshis chiefly make bricks. The chief raw materials are clay, horsedung, ashes, stable refuse, and of fuel firewood and cowdung cakes. The clay is generally dug out of the fields for which the Kumbhárs pay rent, but they are allowed to take river-bank silts free of charge. Till about ten years ago (1872) Kumbhárs used to get clay horsedung and stable-refuse



## Chapter VI.

## Crafts.

## EARTH.

from the State tables on giving about 4000 earthen pots a week. Since 1872 this practice has been stopped, and the horsedung and stable-refuse of the State stables are sold by public auction when the Kumbhárs buy them. The potter takes about thirty-six pounds ( $1\frac{1}{2}$  *mans*) of clay and mixes it in water with half the quantity of horsedung and as much of ashes. The mixture is kneaded with the hand and then trodden with the feet. This is done twice and the process takes two hours. Of the potters' tools the chief are a wooden wheel worth about 2s. (Re. 1); three pieces of *bábhul* or *khair* wood, each worth  $1\frac{1}{2}$  d. ( $\frac{3}{4}$  a.) one four inches long, another three inches, and a third two inches; a stone four inches long and two inches broad having a handle let in; and a stick to turn the wheel. To make the wheel a flat piece of wood is cut into a circular form of about eight inches in diameter and a small flat circular stone having a hollow in the middle is fixed in the centre; six thin sticks are inserted as spokes in the piece of wood which serves as the nave. Afterwards three hoops are tied to the ends of the spokes with a thin rope and the circumference of the wheel is loaded with a mixture of clay and goat hair to make it heavy. A stout wooden peg is buried in the ground all but about nine inches. A pit is filled with water and the wheel is placed on the peg, which rests in the hollow of the stone fixed in the nave. The potter then places about five pounds ( $2\frac{1}{2}$  *shers*) of prepared mud on the wooden nave, and turning the wheel by a stick fixed in a hole made for the purpose in the rim, makes the wheel whirl at a great pace. The potter then takes a piece of wet cloth in his fingers and the required form is given to the mud, which is moistened with water during the operation. By continual handling turning and applying fresh mud, the pot is enlarged and strengthened and the requisite finish of shape is given. The pots are then dried and their outsides rubbed with red earth found at Bid, Adur, and Koparde and polished by rubbing with strings of smooth *kunjka* and sometimes with *káte bhovra* seeds besmeared with oil. The pots are then baked in a kiln with rubbish. At the bottom of the kiln some rice husk and cowdung cakes are spread, and the pots are then imbedded in regular rows among the husk and cakes which are also plentifully heaped over the pottery. The kiln is set on fire in the evening. By about four next morning the whole kiln is on fire, and after the husk and rubbish fuel is consumed the pots are taken out. The chief earthen vessels are pots to fill water called *budukutis*, *derás*, *ghágars*, and *moghás*, round pots or *kundales*, saucers or *parals*, cups or *jáms*, coverings for pots or *jháknis*, *chilims* or smoking pipes, and *mandans*. Of these *mandans* cost 1s. to 1s. 6d. (8-12 *as.*) each, *derás*  $4\frac{1}{2}$  d. to 6d. (3-4 *as.*), *kundales* and *ghágars*  $\frac{3}{4}$  d. to  $1\frac{1}{2}$  d. ( $\frac{1}{4}$  -  $\frac{3}{4}$  a.), and others  $\frac{3}{4}$  d. ( $\frac{1}{4}$  a.) and less. Tiles are of two kinds cylindrical and triangular. To make cylindrical tiles twelve bullockloads of clay, two headloads of horsedung, and two headloads of kiln ashes are mixed together in water and reduced to thick mud. One man prepares the mud, another gives the requisite quantity to be placed on the wheel, and the third turns the wheel and prepares the tiles in the shape of a hollow cylinder tapering towards one end. These cylinders are about seven or eight inches long and about three inches in diameter.

## Chapter VI.

## Crafts.

## EARTH.

While wet, two cuts are made with a piece of stone or wood on each side of the cylinder, leaving it joined together on the upper or lower end. When dry the cylinders are baked in a kiln. As the tiles are made of red earth no red solution is applied. Baked cylinders fetch 3s. to 3s. 6d. (Rs.  $1\frac{1}{2}$  -  $1\frac{1}{4}$ ) for every five hundred. When used, the cylinders are longitudinally divided into two parts. Three men make 300 cylinders or 600 tiles a day. To make triangular tiles sixteen bullockloads of clay, three headloads of horsedung, and three headloads of kiln ashes are mixed together in water and kneaded in the same way as in making cylindrical tiles. The mixture is turned into flat triangular pieces of the required size and allowed to dry a little. Each piece is placed over an oblong wooden mould having its upper side convex and tapering towards the end. The mould is then drawn through the mixture leaving the tiles on the ground which are afterwards baked. Triangular tiles fetch 2s. 6d. to 4s. (Rs.  $1\frac{1}{4}$  - 2) the thousand. To burn a thousand large or small tiles fuel worth 1s. (8 as.) is required.

Potters' work is brisk during the fair season and dull during the rains. Generally on Mondays and specially on the Mondays of *Shrāvan* (July-August) and on *Shivratra* or the dark 13th of *Māgh* (January-February) potters do no work. The women help the men bringing clay and mixing it with horsedung and ashes. About ten families of Kumbhārs work in iron, making large sugarpans or *kāhils* and buckets. These earn a daily wage of about 1s. (8 as.). Some potters make earthen pictures and sell them at the fairs.

## GLASS.

The only glass bangles locally made are at Padli about three miles from Kolhāpur. The workers are ten or fifteen Maráthás, who either bring raw glass from Bombay or locally collect broken bangles. In making bangles the large blocks of glass are first exposed to heat, and water is poured over them to reduce them to small pieces, which are then placed on five small earthen dishes over the mouth of a circular furnace divided into compartments, and heat is applied from the inside of the furnace. A large cover is placed over the dishes, leaving an opening at each dish. After the heat has been continued for about six hours, the glass begins to melt, and the glassmaker sits with his face towards the furnace on a blanket or any other non-conductor of heat. He dips the point of a stick in the melted glass in the *paral* or saucer before him, and with both hands turns the stick till the glass forms into a small ball. The stick is then placed on a cross stone, and the worker keeps patting it with a flat piece of wood until it is perfectly round. A gentle blow is then given to the stick, which shivers the ball into a ring and the ring is enlarged by inserting a flat piece of wood. The ring is then passed to an earthen mould and is turned round to the requisite size by means of an iron spindle which is fixed in it. The process must be performed with great speed. When the whole mould is covered with bracelets they are removed. The bangles made are of inferior quality. The banglemakers sell their bangles to Musulmán dealers called Manyárs and to Hindu dealers called Kásárs. As better bangles are brought from Bombay Miraj and Poona, the craft does not thrive.

Wood-work is carried on in most large villages. Most of the workmen are Sutárs who chiefly work to order. Of the raw wood teak is brought from Bombay or the Haliyál timber store in Kánara, and jack, mango, *jámbhul* *Syzigium jambolanum*, *khair* *Acacia catechu*, *kinjal* *Terminalia paniculata*, and *nána* *Lagerstræmia parviflora* timber is brought from the local forests. During the fair season carpenter's work is brisk, and for ten months they earn 9*d.* to 2*s.* (Re.  $\frac{3}{4}$  - 1) a day. The women do not help the men. Some of the carpenters are clever wood-carvers, and at Potgaon they make good cradles. Village carpenters mend ploughs and other field tools and are yearly paid in grain.

Tanning is carried on in almost all villages by Dhors. Village Mhárs generally flay the hides which the Dhors buy. Hides dried in the sun are useless. In tanning the hide is macerated in limewater to separate the hair, the fat, and the fleshy parts. After the hide is well soaked, the hair is scraped with a scraper or *sip* and the fat and fleshy parts are removed with a knife or *rápe*. The hide is then washed in a running stream and soaked for nearly three days in a solution of three parts of *bábhul* bark and one part of myrobalan water. To tan the hide thoroughly the soaking must be thrice repeated. The hide is then tied into a bag and hung up filled with a stronger solution of the *bábhul* bark and myrobalan water. In this state it is left in the sun for seven days to dry and on the eighth day it is washed in a stream and dried. The hide is then *pakka* or well-tanned. According to length, breadth, and thickness hides fetch 1*s.* to 17*s.* (Rs.  $\frac{1}{2}$  - 8 $\frac{1}{2}$ ). Tanners require a capital of about £2 10*s.* (Rs. 25). Tanned hides are sold locally. Except on Mondays tanners work from morning to evening. The women help in fetching water and in pounding the *bábhul* bark and myrobalan berries. Each hide yields the tanner a profit of about 6*d.* (4 *as.*). The competition of Chámbhárs has lately reduced the profit of Dhor tanners.

Weaving goes on in towns and most large villages. The chief industries connected with weaving are the weaving by Deváng and Lingade Koshtis of coarse cloth or *khádi*, large and small waist-cloths or *dhotars* and *panchás*, women's robes or *lugdes* with or without silk borders, and loincloths or *rumáls*; the weaving by Musalmán Momins of turbans and *káchás* or thigh-cloths; and the weaving by Sangars of blankets. Of 3102, the total number of weaving looms, 2444 belong to cloth weavers, 2238 to Hindu Koshtis, and 206 to Musalmán Momins; and the remaining 658 belong to Sangars or blanket-weavers. Of these looms 688 are in Alta, 654 in Gadinglaj, 422 in Karvir, 397 in Shirol, 350 in Ichalkaranji, 236 in Panhála, 179 in Kágál, 86 in Bhudargad, 58 in Bávda, and 32 in Vishálgad. Besides these, seventeen looms in the Kolhápúr jail factory weave all sorts of cloth including towels and table cloths. Of cloth weavers the Koshtis chiefly use the coarse and strong hand-spun thread which is bought locally and the Momins use the better and cheaper steam-spun thread which is brought from Bombay. Of 2238 looms owned by Koshtis, 1008 use coloured thread and 1230 use white thread. Coloured thread is chiefly used in weaving women's robes. Black thread is obtained locally; it is

## Chapter VI.

## Crafts.

## Wood.

## LEATHER.

## WEAVING.

## Chapter VI.

## Crafts.

## WEAVING.

generally brought from Nilári dyers and sometimes white thread is given to them to be dyed black. Red thread is bought from Lingáyat Bangars who bring it from Chikodi, Gokák, and Sirgaon, and sometimes from Bombay. Of the cloth woven by the Koshtis a pair of *dhotars* or waistcloths for men, each about eighteen feet long and three feet broad fetches 3s. (Rs. 1½); a pair of *panchás* or waistcloths for boys, each about nine feet long and 2½ feet broad fetches 1s. 3d. (12 as.); a silken bordered *lugde* or woman's robe about twenty-one feet long and three feet broad fetches 6s. 6d. (Rs. 3¼); an ordinary robe about 19½ feet long and three feet broad fetches 4s. 6d. (Rs. 2¼); and a loincloth or *rumál* about 3¼ feet long and the same broad fetches 4½d. (3 as.). Of the clothes woven by the Momins turbans are twenty to ninety feet long and fetch 6d. to 5s. (Rs. ¼-2½), and thighcloths or *káchás* are seven to thirty-six feet long and fetch 6d. to 1s. 9d. (4-14 as.). Weavers earn £1 10s. to £3 10s. (Rs. 15-35) a month. The hand-made cloth woven in the State is all used locally, and some comes from Nipáni, Rámdurg, and Vadgaon. Of late, imports of machine-made Bombay and Manchester cloth have greatly reduced the number of hand looms.

BLANKET  
WEAVING.

Of 658 looms used by Blanket-weavers or Sangars 155 are in Shirol, 151 in Gadinglaj, 100 in Alta, ninety-nine in Karvir, thirty-eight in Kágál, thirty-three each in Bhudargad and Panhála, twenty-three in Vishálgad, and thirteen each in Bávda and Ichalkaranji. At 1½ pounds (2 *mures*) the rupee the Sangars buy the worsted thread from Dhangars or shepherds who both tend the flocks and spin the thread. Before it is woven, the thread is cut and sorted to the required length and stretched. A paste made by boiling dried tamarind seeds in water is then applied in the open air with a brush to the worsted thread to make it smooth and straight. Blankets about ten feet long and three feet broad fetch 2s. to 4s. (Rs. 1-2); they are in great local demand, especially among husbandmen, shepherds, and labourers.

## OIL-PRESSING.

Oil-pressing is an important industry employing about 500 families. Oilmen or Telis are of four divisions, Lingáyat or Pancham, Káre or Kála, Marátha, and Pardeshi. Of these Lingáyat Telis are the most numerous. The chief oilseeds locally grown are safflower or *kardai*, niger-seed or *korte* or *kárla*, earthnut or *bhuimug*, and brown hemp or *ambádi*. In extracting oil from these seeds safflower, which yields most oil, is generally mixed with other seeds. As most niger-seed goes to Bombay, it is not largely pressed. Brown hemp does not yield much oil, but is pressed chiefly for its oilcakes which it yields largely. Besides from these four seeds, oil is pressed to order from sesame, mustard, and linseed. Oil is also sometimes pressed from dry cocoa-kernels, but most cocoanut oil comes from outside the State. Of these eight kinds of oil, the oil pressed from safflower, niger-seed, earthnut, and brown hemp is used both for burning and cooking. The sesame oil is used sparingly for burning and cooking but it is chiefly pressed for perfumers who mix it with scented oils. The mustard oil is used in preserving pickles and as medicine. When required for medicine garlic is usually mixed with the mustard seed in extracting the oil.

The linseed oil is locally used by painters, but most linseed now goes to Bombay. The cocoanutoil is chiefly used in burning and in anointing the hair. To yield twenty-six pounds (1 *man*) of oil 180 pounds of safflower are required, 110 pounds of niger-seed and of earthnuts, 320 pounds of brown hemp, 100 pounds of sesame, 140 pounds of linseed, and forty-eight pounds of dried cocoanut kernel. From the various quantities of oilseed, besides yielding twenty-six pounds of oil, safflower, niger-seed, earthnut, and linseed each yields sixty pounds of oilcake, brown hemp 192 pounds, sesame thirty-six pounds, and cocoa-kernel eighteen pounds. Mustard-seed which is rarely pressed, requires thirty pounds of the seed to yield two pounds of oil. When mixed with other seeds, to extract twenty-six pounds (1 *man*) of oil, ninety pounds of safflower require 160 pounds of brown hemp and sixty pounds of niger-seed, and forty-five pounds of safflower require eighty-four pounds of earthnut. In these mixtures, when mixed with brown hemp, safflower yields 144 pounds of oilcake, and when mixed with niger seed or earthnut it yields sixty pounds of oil cake. Besides from these seeds, in the west of the State oil is pressed from the seeds of the *karanj* *Pongamia glabra* and in Alta from tobacco. In some villages the wives of husbandmen press small quantities of oil from castor seed or *erandi*, hart-pea or *karad kungoni*, Mexican thistle or *pivla dhotra*, and from the angular leaved physic-nut or *mongli erandi*. Of these the castor oil is used both in burning and as a purgative, the *pivla dhotra* oil as ointment for skin diseases, and other oils chiefly as medicines.

The oilmill in general use in Kolhápúr is simple. It consists of a wooden trough, which holds the seeds, and a wooden cylinder about four feet high fitted right in the centre of the trough with a heavy cross beam on the top in a standing position, one end of which rests about a foot from the ground. A semicircular block of wood is attached to the lower part of the trough with a piece of wood projecting and forming a right angle with the upper beam at the end nearest the ground. On this piece of wood a large stone is placed and communication with the upper beam is effected by means of ropes playing on a pulley, and as the ropes are tightened and the block rises the pressure of the cylinder is increased. A bullock blindfolded is yoked to the upper beam. The bullock goes round the trough, and by the revolving of the cylinder the seeds are crushed and formed into a mass, and by the pressure of the cylinder the oil is squeezed out and falls to the bottom of the trough, while the residuum forms into a solid mass round the sides of the trough as oilcake. An oilmill costs £2 (Rs. 20) and holds thirty to forty pounds of oilseed.

In some villages a hand oilmill is used which consists of a flat stone about five or six feet square with a hole in the centre, in which a stone pestle is made to fit upright. The seeds are put into the hole and the pestle is turned with the hand. In the handmill the oil rises to the top and runs out over the sides into a pot.

As on Mondays and on important holidays the mill is not worked at all and on market days it is worked only for half the day, the Teli or oilman works the mill on an average for twenty-four days in a month. Most mills work for eight months in the year. During

## Chapter VI.

## Crafts.

## OIL-PRESSING.

## Chapter VI.

## Crafts.

## OIL-PRESSING.

the rains only those oilmen who have capital enough to lay in a stock of oilseeds press oil. The oilman works the mill for eight hours a day. Except brown hemp which takes three or four days, the oilman generally extracts in one day twenty-six pounds (1 *man*) of oil from most oilseeds. It may be roughly estimated that twenty-six pounds (1 *man*) of oil which generally fetch 5s. to 6s. (Rs. 2½-3) pay the cost of the oilseed, and the oilcakes worth 1s. to 1s. 6d. (8-12 *as*.) remain as the oilman's profit for one day. At this rate the earnings of an oilman during his eight working months average £15 to £20 (Rs. 150-200). Out of this about £4 (Rs. 40) go as food of the bullock and £1 (Rs. 10) as reserve to meet the occasional cost of a new mill or bullock, leaving £10 to £15 (Rs. 100-150) as the net profit of working one mill for eight months. The outturn of all the local mills is roughly estimated at about 9200 tons worth £12,000 (Rs. 1,20,000). The late imports of kerosine oil which is now largely used by the people have not materially affected the oilman's profit, as a considerable quantity of the oil locally pressed is sent to Bombay by Chiplun, Rájápur, and Vengurla for the oiling of machinery. This oil is chiefly exported by local dealers who buy it from oilmen. To the people oil is generally sold by the oilman's wife from house to house.

## PAPER.

Kolhápúr has four paper mills owned by Mális, Musalmáns, and Rajputs. Each mill employs on daily wages about six Musalmán workers called Kágdis or Kágzis. Two mills work on the owners' capital and the other two on borrowed money. The paper made in Kolhápúr is coarse, but strong and glazed. Sacking which is the chief raw material, is brought from Belgaum, Kagnoli, and other places. About ninety-six pounds (4 *mans*) of sacking are cut into small pieces and plunged in limewater for a night. It is then reduced to a pulp in a machine called *dang* which consists of a heavy wooden lever with a heavy wooden pestle. The lever is fixed by axles on two upright posts driven into the ground. At the end of the pestle nearest the ground two heavy iron-teeth are fixed, each weighing about ten pounds, the whole weight of the pestle being about fifty pounds. The object of this apparatus is to pound the fibrous material into a pulp to effect which two men are employed in alternately raising the pestle and allowing it to fall with a heavy blow on a stone slab 2½ feet square firmly fixed in the ground with a terraced floor round it. Three men are employed to work the *dang*, two at the lever and one to keep the sacking between the stone and the pestle. From the tedious motion of the pestle fourteen days are required to reduce ninety-six pounds (4 *mans*) of sacking into a coarse pulp. The pulp is then washed in a river or pond, by placing about twelve pounds (½ *man*) in a piece of *dangri* or coarse cloth gathered at the corners and tied to the waists of two men. These men stand in the water up to the waist, and by continually stirring the pulp bring all dirt and impurities to the surface, and carefully remove them. To wash ninety-six pounds (4 *mans*) of pulp takes three hours. The pulp is then brought to the land, and the water is allowed to drain off, after which about ½ pound (¼ *sher*) of carbonate of soda or *pápad-khár* and two pounds (1 *sher*)



of lime are added. It is again pounded in the *dang* for three days for about ten hours each time. After which it is again washed and two pounds (1 *sher*) of country soap and two pounds (1 *sher*) of lime are added. Four men are now employed to tread the pulp on a terraced floor for several hours. It is then made into large lumps and left for four days to bleach and putrify, and on the fifth day it is again for the third time put into the *dang* which it leaves this time in the shape of a thin pulp. The bleached and putrid mass is now put into a lime cistern filled with water, four feet square and four feet deep. The mass is stirred with a bamboo, and the process of paper-making begins. The gelatinous mass is received on a mould called *khasi* which consists of a wooden frame three feet long  $2\frac{1}{2}$  feet broad and  $1\frac{1}{2}$  inches deep, with cross wooden bars at intervals of three inches. Over this frame is placed a matting called a *chhapri* made from the blades of *karas* grass woven with horse hair. Over this matting another thin frame of wood is fitted close to the mould this second frame being used to keep the stuff on the mould, and to limit the size of the sheet. A man now sits with the mould in both hands on the edge of the cistern, and inclining the mould a little towards the cistern, dips it into the cistern, and lifts it again horizontally giving it a shake to distribute the stuff equally over the mould. This is repeated three or four times until a sufficient quantity of the pulp settles on the mould. The matting is then taken off the mould, and placed on a terraced floor called *baksar* or *paksar*. On depositing it on the *baksar* the side on which the paper is formed is turned towards the floor and pressed with the hand to squeeze out the water, after which the matting is carefully taken up and the sheet of paper remains deposited on the floor. Sheet after sheet is then taken off and laid one over the other in a pile, until the pulp in the cistern is exhausted. The pile is then introduced between two stout boards, over which a couple of heavy stones are placed and a man keeps stamping on the board with his foot to squeeze out the superfluous water. The sheets are then carefully separated one by one and plastered to dry on the house walls which are in the first instance washed with white earth and water. As the water is absorbed the paper dries and falls to the ground. The paper at this stage is called *rúst*. It is then again hung in the sun for a short time to dry, after which it is made into a large pile, and pressed with great force to render the sheets flat and smooth. The paper now requires finishing by being sized and polished. The size used in Kolhápúr is made of rice gruel mixed with powdered *turti* or alum which is laid on both sides of the paper with a brush and allowed to dry in the sun on a rope. It is then polished by placing it sheet by sheet on an even board and drawing over it smartly a smooth flint stone or shell until it is glazed. It is then cut and the edges are made even. After the paper is cut it is counted into quires or *dastás* of twelve sheets each, folded and packed into *gaddis* or folds of ten *dastás*. At Kolhápúr three kinds of paper called *vahicha* or for books, *kharchi* or for ordinary use, and *rúst* or inferior, are made of different sizes strength and finish. The *vahicha* paper is eighteen inches long and

## Chapter VI.

Crafts.

PAPER.

## Chapter VI.

## Crafts.

## PAPER.

twelve inches broad and a *gaddi* or fold of ten *dastás*, each having twenty-four sheets or *páns*, fetches 5s. to 6s. (Rs. 2½ - 3). The *kharchi* paper is fourteen inches long and twelve inches broad and a *gaddi* or fold of ten *dastás*, each having twelve sheets or *páns*, fetches 1s. 6d. to 1s. 9d. (12-14 as.). The *rústh* paper, used as wrappers, is neither sized nor polished and a fold or *gaddi* of ten *dastás*, each having twelve sheets or *páns*, fetches 1s. to 1s. 3d. (8-10 as.). Paper is made in separate buildings as workhouses. The workmen work ten hours a day and are allowed twelve holidays in the year. The women and children help the men in sizing and drying the paper. Each mill yields a yearly outturn worth £75 (Rs. 750) of which £42 (Rs. 420) go in wages and £33 (Rs. 330) remain as profit. Of the total yearly outturn of paper worth £300 (Rs. 3000) in the four mills, about £270 (Rs. 2700) worth of paper is locally used, £200 (Rs. 2000) in the State offices and £70 (Rs. 700) by the people; and the rest worth £30 (Rs. 300) goes to Miraj and Sāngli. Since 1854 when there were eighteen paper mills employing 666 workers in all or thirty-seven for each mill, paper-making has much declined, chiefly owing to imports of better and cheaper European paper.

## PERFUME.

Four kinds of perfumery, scented powder called *abir* or *buka*, scented sticks called *agarbattis* or *udbattis*, frankincense oil or *udel*, and dentrifrice or *dútran*, are made by Musalmán and Lád Atárs. To make scented powder about three pounds (120 *tolás*) of the dried flowers of *ghonesari*, *nakla* a fragrant substance apparently some species of dried shell-fish, and *pách* *Pogostemon heyneanum*, all costing about 2s. 6d. (Rs. 1¼), are reduced to a fine powder by being beaten in a stone mortar with an iron bar. This powder is then sifted through a cloth of loose texture, the coarser grains being again ground, beaten in the mortar, and sifted. In this process about one-fourth of the raw materials goes as waste. To two pounds of this fine powder is added a paste made by mixing in equal parts three ounces (7½ *tolás*) of spirit of frankincense, the essence of sandalwood, and *rosel* or spice grass oil, and  $\frac{1}{16}$ th ounce ( $\frac{1}{4}$ th *tola*) of musk, which are all reduced to paste by being beaten in a mortar. The whole is again crushed in the mortar with a crowbar. The result is *abir* or *buka* which fetches 3s. (Rs. 1½) the pound. To make scented sticks or *agarbattis* 1¼ pounds of *bábhul* charcoal and one pound of *gavla* powder a fragrant drug, *kachora* or dried root of the *Curcuma zedoaria*, *tagar* or the flowers of the *Tabernæ montanacoronaria*, frankincense, *nágarmotha* or a sweet-smelling grass *Cyperus pertenuis*, and sandalwood are reduced to a fine powder in the same way as in making scented powder, about one-fourth the quantity being wasted in the process. The mixture is then reduced to a paste by being beaten in a mortar. Small pieces of thin sticks are then coated with this paste. To give superior quality to the sticks musk is mixed in the paste. Scented sticks fetch 4s. to 6s. (Rs. 2-3) the pound. To make *udel*, oil is drawn from frankincense and mixed with sesame oil. To make tooth powder eight substances, catechu, myrobalans, sulphate of copper or *morchut*, wild myrobalans or *bibha*, *ávalkátí* or dried berries of *ávla* *Phyllanthus emblica*, Cassia buds or *nág-keshar*, sulphate of iron, and powdered

clove or *lavangchur* are separately ground into coarse powder, mixed together, and pounded. Perfume-makers require a capital of about £4 (Rs. 40). For four months from September to January the work is brisk and they earn 1s. (8 *as.*) a day ; during the rest of the year the work is dull and they earn 3*d.* to 9*d.* (2-6 *as.*) a day. On every sale of 2s. (Re. 1) they make a profit of about 6*d.* (4 *as.*). Of late, owing to perfumery being imported by local dealers from Bombay and some Musalmáns coming to sell these perfumes from Bombay and Miraj, perfume-making is not at present a thriving industry.

## Chapter VI.

## Crafts.

## PERFUME.

## CHAPTER VII.

## HISTORY.

Chapter VII.  
History.EARLY HISTORY.  
A.D. 100.

KOLHÁPUR history may be divided into three periods, an early Hindu period, partly mythic and partly historic, reaching to about A.D. 1347; a Musalmán period lasting from A.D. 1347 to about 1700; and a Marátha period since 1700. The oldest historic place in the State would seem to be Kolhápur where in making some excavations in 1877 the foundations of a large Buddhist relic mound were turned up and in the centre of the mound was found a square stone box with, on the inner face of its square lid, an inscription in letters of about the third century before Christ recording 'The gift of Bamha made by Dhamaguta.'<sup>1</sup> Copper and lead coins and brass models have also been found at Kolhápur which show that about the first century after Christ it was under rulers who were members or Viceroys of the great Shátakarni or Ándhrabhṛitya kings of the North Deccan, one of whom bore the name Viliváyakura.<sup>2</sup> About A. D. 150 the Egyptian geographer Ptolemy mentions Hippokura as the capital of Baleocuros who governed the southern division of the Deccan peninsula. Hippokura is probably Kolhápur and Professor Bhándárkar identifies Baleocuros with the Viliváyakura of the coins.<sup>3</sup> To about this time or a little earlier belong the Buddhist caves called Pándav Dara about six miles west of Panhála, and the Pavála caves near Jotiba's hill about nine miles north-west of Kolhápur. From the Ándhrabhṛityas the district would seem to have passed to the early Kadambas (A.D. 500) whose chief capital was at Palásika or Halsi in Belgaum about a hundred miles south-east of Kolhápur. From the early Kadambas it would seem to have passed to the early and Western Chalukyas from about 550 to 760; to the Ráshtrakutas to 973; from the Ráshtrakutas to the Western Chálukyas, who held the district, to about 1180 and under them to the Kolhápur Siláháras (1050-1120); and to the Devgiri Yádavs to the Musalmán conquest of the Deccan about 1347. Of the early and Western Chalukyas no copperplates or stone inscriptions have yet been

<sup>1</sup> Journal Bombay Branch Royal Asiatic Society, XIV. 147-154; Bombay Archaeological Survey, Separate Number 10, p. 39.

<sup>2</sup> Journal Bom. Br. Roy. As. Soc. XIV. 152, 153; Professor Bhándárkar's Deccan Early History, 17, 20.

<sup>3</sup> Bertius' Ptolemy, 205; Deccan Early History, 20.

found in the district. Of the Ráshtrakutas two copperplate grants have been found, one at Sámángad fort four miles south of Gadinglaj and another at Sángli town. The Sámángad grant, which belongs to the seventh Ráshtrakuta king Dantidurga or Dantivarma II. bears date *Shak* 675 (A.D. 753-54) and mentions that Dantidurga's victorious elephants ploughed up the bank of the river Reva or Narmada, that he acquired supreme dominion by conquering Vallabha, and that he early defeated the army of the Karnátak which was expert in dispersing the kings of Kánci or Conjeveram and Kerala, the Cholas, the Pándyas, Shriharsha, and Vajrata.<sup>1</sup> The Sángli copperplate grant belongs to the fourteenth king Govind V. and is dated *Shak* 855 (A.D. 933-34).<sup>2</sup> Of the Western Chálukyas who succeeded the Ráshtrakutas in 973, except a copperplate grant from Miraj, no inscriptions have been found within Kolhápur limits. The Miraj grant belongs to the king Jayasimha III. and was made by him in *Shak* 946 (A.D. 1024-25) at his victorious camp, which, after warring against the mighty Chola the lord of the city of the Chandramila, and after seizing the possessions of the lords of the Seven Konkanas, was located near the city of Kollápura or Kolhápur, for conquering the northern country.

The<sup>3</sup> Kolhápur Siláháras possessed the territory lying round Kolhápur and in the north-west part of the Belgaum district from about the end of the tenth to early in the thirteenth century A. D. Their inscriptions are found at Kolhápur and places in its neighbourhood, at Miraj and at Sedbál in the Athni sub-division of the Belgaum district. Like their relatives of the northern branch in the Konkan, the Siláháras of Kolhápur claim to be of the lineage of the Vidyádharma Jimutaváhana, who saved the Nága king Shankhachuda from Garuda by offering his own body to be torn instead of his; and also like them they carried the banner of a golden Garud *suvarnagarudadhvaja*. The Siláháras of Kolhápur were Jains by religion. Their family goddess was Mahálakshmi of Kollápura or Kolhápur; and though this town is not expressly mentioned as their capital till *Shak* 1109 (A.D. 1187-88), it must always have been one of the chief seats of their power, and it furnishes the most

## Chapter VII.

## History.

## EARLY HISTORY.

A.D. 750.

<sup>1</sup> Fleet's Kánarese Dynasties, 32-33. This is the earliest known inscription in which the date is expressed by figures arranged according to the decimal system of notation.

<sup>2</sup> Jour. Bom. Br. Roy. As. Soc. IV. 97; Fleet's Kánarese Dynasties, 37.

<sup>3</sup> Fleet's Kánarese Dynasties, 98-106.

## Chapter VII.

## History.

## EARLY HISTORY.


Siláhāras,  
1050-1120.

Márasimha.

convenient appellation of this branch of the family for distinguishing it from the other branches.<sup>1</sup>

All that is at present known about the earlier members of the family is derived from a copper-plate grant of Márasimha, also called Gonkana-Ankákára and Guheyana-Singa, which was found somewhere in the neighbourhood of Miraj and is dated *Shak* 980 (A.D. 1058-59), the Vilambi *Samvatsara*. In it Jatiga I. is called 'the lion of the hill-fort of Panhála,' which is about ten miles to the north-west of Kolhápúr; Jatiga II. is called 'the king of the city of Tagara;' and Gonka is described as possessing the countries of Karaháta, Kundi, Mirinja, and the Konkana. Karaháta is the modern Karád or Karhád in the Sátára district, at the junction of the Krishna and the Koyna; and Mirinja is the modern Miraj about thirty miles north-east of Kolhápúr. Kundi is the Three-thousand district which in *Shak* 902 (A.D. 980-81) constituted the government of Kártavirya I. of the Ratta *Mahámandaleshvaras* of Saundatti, and which, so far as the Ratta inscriptions go, was still entirely in the possession of that family in *Shak* 970 (A.D. 1048-49), in the time of Anka, and again in *Shak* 1004 (A.D. 1082-83), in the time of Kannakaira II.; but unless this statement of Gonka holding the country of Kundi is an invention or an exaggeration, the Rattas must shortly before or after *Shak* 970 (A.D. 1048-49) have suffered some temporary loss of territory to which no allusion is made in their own inscriptions. And the

<sup>1</sup> The Siláhāra family tree is :





possession by Gonka of part of the Konkana, probably in the time of Nágárajuna of the North Konkana branch of the Siláháras, who was intermediate between Chhittarája (*Shak* 946, A.D. 1024-25), and Mummuni or Mumváni (*Shak* 982, A.D. 1060-61), and as to the events of whose reign the inscriptions of his family are silent, is corroborated by a passage concerning Anantapála or Anantadeva, the son of Nágárajuna, which has been quoted by Mr. Fleet<sup>1</sup> to show that the king of Kápardikadvipa who was killed by Jayakesi I. of the Kádambas of Goa, must have been Nágárajuna, and in which the expression 'a time of misfortune from relatives that had become hostile' plainly shows that Jayakesi I. who then overran and devastated the whole of that part of the Konkana, had taken advantage of dissensions and contests between the Siláháras of the Konkana and their relatives of Kolhápura. In the same inscription of Márasimha, Guvala I. or Gubala is called 'the lord of the hill-fort of Kiligila or Khiligila.' This place, which was also Márasimha's capital, has not yet been identified. Like his successors Márasimha styles himself only a *Mahámandaleshvara*, but gives no indication of any paramount sovereign of whom he was the feudatory. It is not likely, however, that the Siláháras were independent throughout the whole of the period for which records are available. The Siláhára princess Chandaladevi or Chandralekha, who was one of the wives of the Western Chálukya king Vikramáditya VI. was probably a daughter of Márasimha.

The next name in respect of which there has been any historical information is that of Bhoja I. He seems to be undoubtedly the Bhoja who invaded the territories of Achugi I. of the family of the Sindha *Mahámandaleshvaras* of Erambarage, and who was successfully repulsed by Achugi. This must have been in about *Shak* 1020 (A.D. 1098-99).

There is an inscription of Ballála at Honnur near Kágala, which intimates that he ruled in conjunction with his younger brother Gandaráditya.<sup>2</sup> But it is not dated, and it gives no historical information.

The succession was continued by Gandaráditya, also called Ayyana-Singa I., the youngest son of Márasimha. His inscriptions range from *Shak* 1032 for 1031 (A.D. 1109-10) the *Virodhi samvatsara*, to *Shak* 1058 for 1057 (A.D. 1135-36) the *Rákshasa samvatsara*, and are found at Kolhápura itself and at Tálalem in the neighbourhoood.<sup>3</sup> In *Shak* 1031 he was governing the Mirinja country, together with Saptakholla and a part of the Konkana, and his capital was Tiraváda in the Edenád district.<sup>4</sup> In *Shak* 1057

## Chapter VII. History.

### EARLY HISTORY.

Siláháras,  
1050-1120.

Márasimha.

Bhoja I.

Ballála.

Gandaráditya.

<sup>1</sup> Fleet's Kánárese Dynasties, 91.

<sup>2</sup> Graham's Kolhápura, 466.

<sup>3</sup> Jour. Bom. Br. Roy. As. Soc. XIII. 1; and unpublished inscriptions, of which imperfect versions are given in Graham's Kolhápura, 326-480.

<sup>4</sup> This must be a totally different district to the Edenád Seventy which is mentioned in inscriptions at Balagámve (P. S. and O. C. Inscriptions No. 158), Sorab (Mysore Inscriptions, p. 239), Merkara (Ind. Ant. I. 365), and Bengalur (Mysore Inscriptions, 294), and which is placed by Mr. Rice near Ságar in Maisur.

## Chapter VII.

## History.

## EARLY HISTORY.

Siláháras,  
1050-1120.

Vijayáditya.

his capital was Valaváda, which, as suggested by Sir Walter Elliot, is probably the modern Válva,<sup>1</sup> about sixteen miles to the south of Kolhápur.

Gandaráditya was succeeded by his son Vijayáditya or Vijayárka, also called Ayyana-Singa II., whose inscriptions range from *Shak* 1065 for 1064 (A.D. 1142-43) the Dundubhi *samvatsara*, to *Shak* 1078 for 1075 (A.D. 1153-54) the Shrimukh *samvatsara*, and are found at Kolhápur, Miraj, Bámni near Kágál, and Sedbál in the Belgaum district.<sup>2</sup> His capital continued to be at Valaváda. In the copper-plate grant of his son and successor Bhoja II., Vijayáditya is said to have reinstated the rulers of the province of Sthánaka or Thána and the kings of Gova or Goa. The first statement must refer to some assistance rendered by him to his relatives of the Konkana branch, after the reign of Anantapála or Anantadeva and before the reign of Aparáditya; and it was probably through this assistance that Aparáditya came to reign at all. The date that is usually allotted to Aparáditya is *Shak* 1109 (A.D. 1187-88):<sup>3</sup> but, that this must have been towards the end of his reign, and that he was reigning between *Shak* 1058 and 1068 (A.D. 1135-1145), has been shown by Dr. Bühler;<sup>4</sup> and this proves almost conclusively that it was Aparáditya whom Vijayáditya reinstated at Sthánaka. The statement regarding the kings of Gova, if it refers to any events affecting Goa itself, and unless it simply means that the Konkana Siláháras continued to bear the title of kings of Gova, though the place itself was lost to them, must allude to some occurrences between the time of Jayakesi II. and Permádi or Shivachitta, of the Kádambas of Goa, to which no reference is made in the Kádamba inscriptions or in any others that have as yet come to notice.

## Bhoja II.

Vijayáditya was succeeded by his son Bhoja II. also called Vijayádityadevana-Singa, whose inscriptions range from *Shak* 1101 for 1100 (A. D. 1178-79) the Vilambi *samvatsara*, to *Shak* 1115 (A. D. 1193-94) the Pramádi or Pramádicha *samvatsara*. His stone-tablets are found at Kolhápur;<sup>5</sup> and a copper-plate grant of his reign has been produced from somewhere in the Sátára district.<sup>6</sup> In *Shak* 1100 Valaváda was his capital, but in *Shak* 1109 his capital was Kollápura, the modern Kolhápur itself, and in *Shak* 1112 it was Pannáladurga, or, as the Sanskrit version of the name is, Padmanáladurga, the hill-fort about ten miles to the north-west of Kolhápur. That he was still reigning in *Shak* 1127 (A.D. 1205-6), the Krodhana *samvatsara*, is shown by a note at the end of the

<sup>1</sup> Latitude 16° 29' north and longitude 74° 14' east. Possibly, however, it may be the 'Wulewur' of the maps, about five miles to the east by north of Kolhápur, or the 'Wulewra' and 'Wulewday' of the maps, about six miles to the south-west of Válva.

<sup>2</sup> Unpublished inscriptions.

<sup>3</sup> Ind. Ant. X. 39.

<sup>4</sup> Jour. Bom. Br. Roy. As. Soc. XII. Extra Number p. 52.

<sup>5</sup> Graham's Kolhápur, 382-414.

<sup>6</sup> Transactions of the Literary Society of Bombay, reprint of 1877, III. 411.

*Shabdárnavachandrika* of Somadeva, according to which the work was composed in that year in the reign of Bhoja II. at a Jain temple founded by Gandarāditya at Ājurika, the modern Ājra, in the country of Kolhápur.<sup>1</sup>

Bhoja seems to have been the greatest of the dynasty and is said by tradition to have reigned over the tract extending from the Mahádev hill north of Sátára to the Hiranyakeshi river south of Kolhápur and including all the southern tract of the Konkan as far as Sadáshivgad or Kárwár in North Kánara. He is the reputed builder of fifteen hill forts, six of which Bávda, Bhudargad, Khelna or Vishálgad, Panhála, Pávangad, and Sámángad are in Kolhápur limits. Bhoja II. is said to have especially devoted his attention to the subjugation of the hill tribes on the West Kolhápur frontier and is therefore styled in one of his inscriptions as a thunderbolt levelling the mountain-like race of the turbulent chiefs who had subjugated the hill forts.<sup>2</sup>

With the exception of what has been noted above in connection with Vijayāditya, the inscriptions of Gandarāditya and his successors give no historical details. But, as regards the termination of their power, there has been no trace of any member of the family after Bhoja II.; and, as in *Shak* 1135 (A.D. 1213-14), the Shrimukha *samvatsara*, the Devgiri-Yádav king Singhana II. was in possession of the country round Miraj, as is proved by his Khedrápur inscription,<sup>3</sup> which records the grant by him of the village of Kudaladámaváda, the modern Kurundvád, in the Mirinji country; and as inscriptions of Singhana II. shortly after that date are found at Kolhápur itself,<sup>4</sup> it would seem that Bhoja II. was the last of his family, and that he was overthrown and dispossessed by Singhana II. in or soon after *Shak* 1131 (A.D. 1209-10), the Shukla *samvatsara*, which was the commencement of Singhana's reign. This is borne out by one of Singhana's inscriptions dated *Shak* 1160,<sup>5</sup> which speaks of him as having been 'a very Garuda in putting to flight the serpent which was the mighty king Bhoja, whose habitation was Pannála.'<sup>6</sup> There are some inscriptions extant which show that the descendants of Singhana exercised authority in Kolhápur. It may be assumed that the territory remained part of the dominions of the Yádavs of Devgiri, though probably the connection was merely nominal, as the hilly part of the country was occupied by Marátha *pálegárs*.

<sup>7</sup>After the overthrow of the Yádav dynasty by the Musalmáns the eastern subdivisions of Kolhápur came under the Bahmani kings

## Chapter VII.

### History.

#### EARLY HISTORY.

Siláháras,  
1050-1120.

*Bhoja II.*

<sup>1</sup> Dr. Kielhorn, Ind. Ant. X. 75.

<sup>2</sup> Lieutenant-Colonel E. W. West.

<sup>3</sup> Jour. Bom. Br. Roy. As. Soc. XII. 7.

<sup>4</sup> Graham's Kolhápur, 425-436.

<sup>5</sup> P. S. and O. C. Inscriptions, No. 112, I. 10-11.

<sup>6</sup> Pannála-nilaya-prabala-Bhojabhupála-vyála-vidrávana-Vihamgarāja.

<sup>7</sup> The history of the Musalmán and Marátha periods is contributed by Lieutenant-Colonel E. W. West.

## Chapter VII.

## History.

MUSALMÁN  
PERIOD,  
1347-1700.

of the Deccan (1347-1489),<sup>1</sup> but it was not till the reign of Allá-ud-din II. (1435-1457) the tenth king of the dynasty, that an attempt was made to bring the western part of the district into subjection. In 1453 the Bahmani general Malik-ul-Tujár was persuaded by a Rája in the Konkan belonging to the Shirke family, whom he had captured and wished to convert to the faith of Islám, to make an attack on Shankar Rái the Rája of Khelna or Vishálgad, whom the cunning Hindu declared to be his rival and enemy. When the Musalmán general hesitated on account of the difficult nature of the country, his objections were obviated by the proposed convert promising to act as guide and the army accordingly set forth. For two days the march was beset by no difficulties, but on the third day the invaders were led by intricate paths through a wild savage country, to describe the horrors of which exhausts the Muhammadan historian's stock of hyperbole. They were finally led into a dense forest surrounded on three sides by mountains, and their condition having been betrayed by their treacherous guide to the enemy, they were attacked at midnight, and nearly 7000, among whom was the general, are said to have been massacred.

Several years then elapsed before the Musalmáns made a further effort against Vishálgad. At last, in 1469, Muhammad Sháh Bahmani II. (1463-1482) sent his minister Máhmud Gáwán at the head of a powerful army against Shankar Rái. More careful than his unfortunate predecessor, the new Bahmani general took every precaution that prudence could suggest. Having cut his way through the forest by fire and the axe he besieged the fort of Vishálgad, and when obliged after a five months' siege to discontinue operations, in consequence of the setting in of the rains he left the passes in charge of 10,000 seasoned troops, and with the rest of his army proceeded to Kolhápúr, where he cantoned during the rainy season. As soon as the weather admitted of military operations being carried on he resumed his former position, and, as the historian above alluded to says, 'by stratagem and gifts of money obtained possession of the fortress of Khelna, which had never till then been in the hands of the Musalmáns.' Even after this success he did not leave the country till he had thoroughly subjugated it and taken ample revenge for the loss of the first army. After this he took Goa; and one of his officers, Khush Kaddam, who received on the occasion the title of Kishwar Khán, was on the return of the army to Bedar, placed in charge of the newly-conquered districts.

Kishwar Khán, for some unknown reason, transferred the charge of Goa to one Najm-ud-din Giláni, on whose death one of his officers,

<sup>1</sup> There have been no means of knowing exactly when this took place. An inscription at Miraj records the building of a mosque there in A.D. 1413, that is during the reign of Firoz Sháh Bahmani (1397-1422), so the Muhammadans must have been established there for some time before that date, and the masters of Miraj would naturally hold the neighbouring districts which now belong to Kolhápúr. There are said to be inscriptions recording the existence of a Musalmán settlement called Nabipur on the hill of Panhála in 1376.

named Bahádur Giláni, in 1486 seized Goa and occupied Kolhápur as well as other places, being instigated to this course by Yusuf Adil Khán, then one of the nobles of the Bahmani king, but who afterwards (1489-1510) became himself king of Bijápur. Bahádur Giláni, thus established in a position of semi-independence, availed himself of his command of the sea coast to send expeditions against Bombay and to seize vessels belonging to Gujarát. This conduct naturally excited the anger of Máhmud Begada (1459-1511) the king of the latter country, who in 1493 sent an embassy calling on the Bahmani king to punish his rebellious vassal, failing which, the Gujarát prince stated, he would have to employ his own troops. This message aroused Máhmud Sháh Bahmani II. (1482-1518), who prevailed on his feudatories (so soon to become independent princes) to assist him and marched against Bahádur Giláni. The latter first took up his residence at Sankeshvar from whence he fled on the approach of the royal forces. His troops were then defeated near Miraj, and that fort was surrendered to the king, on which Bahádur made offers of submission. He was promised more favourable terms than he could have expected, so much so that, conceiving that such generosity could only proceed from weakness, he rejected them and renewed hostilities. In these, however, he was so unsuccessful that he had to take refuge in Panhála. Unfortunately for himself he quitted the fort, and after again negotiating, and again rejecting the terms offered to him, he was killed in an action with the royal troops, and his estate or *jágir*, including Kolhápur, was bestowed upon Ain-ul-Mulk Giláni.

In 1498, on the dissolution of the Bahmani kingdom and the elevation of its chief feudatories into the position of sovereign princes, Kolhápur and the adjoining country fell to the share of Bijápur. The latter kings of this dynasty, especially the two Ibráhims, paid much attention to the fortification of Panhála, which they strengthened considerably, as is attested by the numerous Persian inscriptions still extant there.

When the great Shiváji entered upon his work of creating a nation and founding an empire, the hill-forts in the Kolhápur territory were too favourably situated for his purpose not to attract his notice. The districts of Miraj and Kolhápur were held at the time by Rustum Zamán in *jágir* from Bijápur, and there are good reasons for believing that he allowed himself to be bribed. Either by bribery or stratagem Shiváji in 1659 obtained possession of Panhála and its neighbour Pávangad and from this *point d'appui* he reduced Ránga and Khelna or Vishálgad, together with the other forts in the district above and below the Sahyádris. He soon made use of his new acquisitions. After defeating Rustum Zamán near Panhála he assembled his forces at Vishálgad and thence carried on operations in the Konkan, where he acquired both territory and booty. Subsequently (1661) when the Bijápur army, under Sidi Johár, marched against him to avenge the slaughter of Afzul Khán and his army, Shiváji shut himself up in Panhála, whence, after enduring a four months' siege, he escaped by a

## Chapter VII.

## History.

MUSALMÁN  
PERIOD,  
1347-1700.

## Chapter VII.

## History.

MUSALMÁN  
PERIOD,  
1347-1700.

characteristic stratagem and fled to Rángna.<sup>1</sup> His flight left Panhála at the mercy of the Bijápur king; but Shiváji still retained Vishálgad and from that eyrie, undismayed by the hostile forces gathering from all quarters, he swooped down on Mudhol the *jágir* of Báji Ghorpade, against whom he had long vowed vengeance for seizing his father Sháháji and delivering him to the Bijápur authorities. His position at Vishálgad also enabled him to recover possession of Panhála in 1673, and under its walls he, in the following year, defeated the Bijápur troops. Panhála was subsequently used as a place of confinement for Shiváji's eldest son Sambháji, who was there when his father died in 1680, and who nine years afterwards sallied forth from it to be surprised and captured by the Musalmáns. It would appear that the place was actually being besieged by Takarrib Khán at the time when Sambháji left the place and went to Sangameshvar in the Konkan, where he gave himself up to riotous living with his unworthy favourite the Bráhmañ Kalusha. So entirely was he given up to his pleasures that the Moghal general, who had received information as to where he was, followed him with a detachment, and seized him before Sambháji had any idea that there was an enemy in the neighbourhood. The death of Sambháji and the capture of the infant son of the latter by the Moghals made Rájárám, the second son of Shiváji, the *de facto* Rája of the Maráthás. While he carried on operations in the south he left his family at Vishálgad in comparative security, as, though Panhála had been speedily taken by Aurangzeb's forces, yet Vishálgad and Rángna with the adjacent country held out still under Rámchandra Pant, the ancestor of the present Pant Amátya of Bávda in Kolhápur.<sup>2</sup> The tenure of Panhála, too, by the conquerors was but temporary, as the place was ere long retaken by Parashurám Trimbak. After his escape from Ginji, Rájárám again visited Vishálgad; but during the latter part of his reign the most important operations he was engaged in were all carried on in the country situated to the north of Kolhápur, and his death took place in 1700 at the fort of Sinhgad near Poona, a month before Sátára, then besieged by the Moghals, fell into the hands of Aurangzeb.

MARÁTHÁS.  
Shiváji II.,  
1700-1712.

On the death of Rájárám his elder widow Tárábái, who was the mother of his eldest son Shiváji, placed the latter then ten years of age, on the throne, and assumed charge of the administration, aided therein by the Pant Amátya, the Senápati,<sup>3</sup> and Parashurám Trimbak whom she made Pratinidhi. Her first act was to place in confinement her husband's second widow Rájasbái, with the

<sup>1</sup> Grant Duff's History of the Maráthás (Indian reprint, I. 132).

<sup>2</sup> In imitation of their progenitor Shiváji, the Kolhápur princes appointed eight chief ministers known as the *Ashtapradhāns*. The Pant Amátya of Bávda and the Senápati of Kápsi are the only representatives of the *Ashtapradhāns* now in Kolhápur.

<sup>3</sup> Sidoji Ghorpade, a member of one of the oldest and most distinguished Maráthá families, had been made Senápati by Sambháji, and received the *jágir* of Kápsi, which his descendants still hold. See note above.



latter's son Sambháji, a child of three years of age. Her position was a most difficult one, as, shortly after Rájárám's decease, Aurangzeb in person moved against Kolhápur and besieged Panhála and Vishálgad, both of which places he took. His siege of the former place possesses a special interest as, while he was engaged on it in 1701, he received Sir William Norris, an ambassador sent to him on behalf of the new East India Company with letters from the King of England. The annalist of the East India Company gives a very elaborate account of the ambassador's procession on the occasion of his reception on the 28th of April by the Emperor, but refrains from giving historical information of any importance. We only learn that Sir William Norris presented 200 gold *mohars* to Aurangzeb, that his negotiations on behalf of the new Company were unsuccessful, and that he finally took his leave of the Great Moghal on the 5th of November. Aurangzeb, however, was ere long called away by the state of his affairs towards Ahmadnagar, and the effects of his absence were soon perceived. The Pant Amátya shortly after the Emperor's departure took Panhála by escalade, whereupon Tárábái took up her abode in it, and the place was for many years the virtual capital of Kolhápur. The Maráthás met with equal success elsewhere, and the Moghal power in that part of the country was annihilated; but after the death of Aurangzeb in 1707 a stroke of policy was effected by his successor which checked their onward progress by the divisions it excited among them. This was the release of Sháhu, the son of Sambháji, who was encouraged to assume his place as head of the nation. He accordingly sent letters and messengers to the leaders of the Maráthás, calling on them for assistance and announcing his approach. Tárábái, however, was not disposed readily to give up the authority she had so long held, or to see her son's claim to the sovereignty set aside. She therefore affected to treat Sháhu as an impostor, and was supported in her resistance by the leading men of the Maráthás who led an army against the grandson of Shiváji.

Sháhu, however, managed to win over to his cause one of the ablest of the generals opposed to him, after which he defeated Tárábái's forces, and in 1708 obtained possession of Sátára, where he formally seated himself on the throne. He pressed on operations in the following year against Kolhápur, and at first met with considerable success, Panhála and Vishálgad falling into his hands and Tárábái being obliged to fly into the Konkan. After this success he withdrew his forces in order to attack the Pant Sachiv, but no sooner were they withdrawn than the energetic Tárábái returned and recovered Panhála. All her hopes, however, were frustrated and her prospects blasted by the death, in 1712, of her son Shiváji. She was on this event immediately placed in confinement together with her son's widow Bhavánibái, and Sambháji, the second son of Rájárám, was placed on the *gádi*, the administration being conducted by Rámchandra the Pant Amátya of Bávda. The eldest son of the Pratinidhi joined the cause of Sambháji, which was

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji II.,  
1700-1712.

## Chapter VII.

## History.

MARÁTHÁS.

Sambhaji II.,  
1712-1760.

further strengthened by the support of Sarjeráv Ghátge of Kágál. The dissensions between the descendants of Shiváji were actively fomented by Chin Kuli Khán, the first Nizám, whose policy it was to weaken the Maráthás, and who threw his influence into the scale on the side of Sambhaji. On the other hand Sháhu was assisted by the genius of the first Peshwa Baláji Vishvanáth, and the Pratinidhi,<sup>1</sup> and was favoured by the Moghal Emperor, whose feudatory he professed to be. It is not necessary to follow here in detail the fluctuations of the struggle that continued for years between the Kolhápúr and Sátára parties. The latter, while holding their own against Kolhápúr, directed their attention chiefly to affairs in the north; but in 1727 a crisis was brought about by the ill-judged action of the Nizám, who claimed to be arbiter in the dispute between Sháhu and Sambhaji, and sequestered some territory belonging to the former pending its settlement. Sháhu and the Peshwa on this directed their whole power against the Nizám and his ally Sambhaji. The Nizám was soon obliged to give up the cause of Sambhaji, and the latter brought down the vengeance of Sháhu on his head by rejecting the overtures made to him; after which, when moving with an army towards Sátára, he was utterly defeated by the Pratinidhi and driven to Panhála with the loss of all his baggage. Tárábái and her daughter-in-law Bhavánibái, the widow of Shiváji II., were taken prisoners on this occasion and confined in the fort of Sátára. Sambhaji by this defeat was so reduced that he was obliged to come to terms, and in 1730 a treaty was concluded by which he gave up all claims to territory north of the Várna river, his sovereignty being acknowledged over the tract of country lying between the rivers Várna and Krishna on the north and north-east and the Tungbhadra on the south, and over the part of the Konkan between Salsi and Ankola. It does not appear that the whole of the tract of country thus defined was at any time in the possession of the Rájás of Kolhápúr; and reading between the lines of the treaty the real purport of the instrument seems to have been that the Kolhápúr Rájás might make what conquest they liked to the south of the Várna, provided they kept that river as their northern boundary and did not cross the Krishna on the east. Sambhaji and his successors indeed seem to have made hardly any attempt to assume the sovereignty of the whole of the districts thus made over to them, and some thirty-four years after the date of the treaty the Peshwa granted to the Patvardhan family a large *saranjám*, a very considerable portion of which was situated in these very districts. The effect of the treaty was to isolate Kolhápúr from all that lay to the north of the territory, and consequently from participation in the stirring events that took place there. Such of the

<sup>1</sup> Both of these officials died before matters were finally settled, and were succeeded, the first by his son Bájiráv and the other by his second son Shripatráv, the eldest son having adhered to the cause of Sambhaji and become the founder of the family of the Pratinidhi, the chief of Vishalgad in Kolhápúr.

Kolhápur princes as had any special energy contented themselves with feuds with the neighbouring chiefs, and with piracy, in which last pursuit they acquired considerable proficiency and an evil reputation.

Before twenty years had elapsed from the date of the treaty, events seemed to be tending to the union of both branches of Shiváji's family under one head. Sháhu, the Rája of Sátára, had lost his only son, and being now advanced in years it became incumbent on him to adopt. Notwithstanding his prolonged wars with his cousin Sambháji he in this emergency thought of adopting the latter, and the Kolhápur prince, being supported by Sháhu's wife, seemed likely to succeed. Such an arrangement, however, would have been fatal to the prospects of the Peshwa's party, whose interest it was to divide the family of Shiváji and to keep the Rája of Sátára a puppet in their hands. At this juncture a discovery was made, or pretended to be made, which materially altered the aspect of the question. It will be recollected that on the death of Shiváji II. of Kolhápur his mother Tárábái and his widow Bhaváníbái were placed in confinement, and that they afterwards fell into the hands of the Sátára Rája. It was now asserted that Bhaváníbái at the time of her husband's death was pregnant, and that she had afterwards borne a son Rájárám whose life Tárábái managed to save, at the same time that she kept his existence a secret, by getting him conveyed out of the fort of Panhála and sent to a sister of Bhaváníbái's who brought him up. Such an assertion of course made at such a crisis did not meet with universal credence. It was loudly asserted by the partisans of Sambháji that the so-called posthumous son of Shiváji was spurious, and arrangements were made to oppose his pretensions. While this discussion and these preparations were going on, Sháhu (1749) lay on his death-bed constantly attended by his wife, who was opposed to the Peshwa. The latter however, it is said, managed to obtain a secret interview with the Rája, whom he persuaded to sign a deed empowering the Peshwa to govern the whole Marátha empire on condition of his keeping up the dignity of the house of Shiváji in the person of Rájárám, Tárábái's grandson, and his descendants. The document further acknowledged the independence of the Kolhápur State, and gave the Peshwa power over the Marátha *jágirdárs*.

The question whether Rájárám was or was not the son of Shiváji and whether the deed of cession to the Peshwa was or was not really executed by Sháhu, is one that has been much discussed; and the historians Mountstuart Elphinstone and Grant Duff<sup>1</sup> take opposite sides, the former doubting and the latter maintaining the genuineness of both heir and deed. It is sufficient for the purpose of this sketch to state that Rájárám was eventually acknowledged by the Maráthás as the adopted son and successor of Sháhu.

In 1760 Sambháji of Kolhápur died without issue and his widow

## Chapter VII.

### History.

MARÁTHÁS.

Sambháji II.,  
1712-1760.

<sup>1</sup> Elphinstone's History of India, 4th Edition, 642; Grant Duff, II. 22-25.

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji III.,  
1760-1812.

Jijibái, according to his wishes, selected for adoption the son of Sháháji Bhonsla of Khánvat a collateral descendant of the house of Shiváji. This step, however, was strongly opposed by the Peshwa, whose interest it was now to unite, as it had formerly been to divide, the Sátára and Kolhápúr families. Jijibái, however, managed to obtain possession of the boy; and the Peshwa, unwilling to offer open opposition to an arrangement so much in accordance with Hindu feeling, religion, and custom, acknowledged the adoption which he could not prevent, and did so with as good a grace as possible, presenting the usual honorary dresses and gifts. The boy thus adopted received the name of Shiváji, and during his long minority the Kolhápúr State was administered by his adoptive mother Jijibái.

This period was a disastrous one for Kolhápúr. The Peshwa, in order to keep it in check, established the powerful family of Patvardhans on the eastern frontier with a large *saranjám* sufficient for the maintenance of 8000 horse. Afterwards, irritated at the communication kept up by the Kolhápúr court with the Nizám, he deprived the State of the two districts of Chikodi and Manoli, which he bestowed on the Patvardhans. He restored them, it is true, afterwards, but the example he set was followed and the districts in question constantly changed hands during the succeeding fifty years. Then piracy increased to such an extent that in 1765 an expedition was sent from Bombay against the maritime possessions of Kolhápúr, and Fort Augustus or Málvan was taken by the English.<sup>1</sup> In the following year a treaty was entered into, the first one between the British and Kolhápúr, in which it was stipulated that the fort should be restored on payment of £38,289 12s. (Rs. 3,82,896). It was further agreed that the English should be allowed to establish a factory in the neighbourhood of Málvan and should have full freedom of trade. Other commercial privileges were conceded, provision was made against piracy and wrecking, and the treaty concludes with the following fourteenth article, which shows a somewhat astute diplomacy on the part of the English: 'Maharája Jijibái, the Ráni, agrees, should the Honourable Company be attacked and they should require her assistance, to provide them with what troops they may want, they supplying them with provisions only. The Honourable Company in like manner agrees to assist the Ráni should it be convenient for them.'

The name of the Regent Jijibái has terrible associations connected with it in Kolhápúr. It is related that one night the goddess Káli, under her manifestation as Sita, appeared to her with the intimation that to secure prosperity the shrine of the goddess at Panhála, where Jijibái always resided, should be kept constantly wet with human blood. The intimation was obeyed but too implicitly, and

<sup>1</sup> The Kolhápúr pirates were known in Bombay as the Málvanis from the name of the port. Those from Sávantvádi were termed *Kempsaunts*, a corruption of the name of the Sar Desái Khem Sávant.

parties sent out by the Regent at night constantly scoured the neighbourhood of Panhála to procure fresh victims, who were sacrificed at a spot in the inner fort which is still pointed out with horror.

In 1772 Jijibái died, leaving her adoptive son still a minor and surrounded by enemies. The Peshwa's troops were encamped on the Krishna and committed great devastation in the eastern districts of the Kolhápúr territory: Konherráv Trimbak, one of the Patvardhan Saranjámdárs, was making raids from the same quarter, while the Pant Pratinidhi of Aundh was threatening hostilities from the north. Eshvantráv Shinda, the minister in whose hands the administration then was, showed considerable energy. He entered into negotiations with Haidar Ali of Maisur, with the object of getting assistance from that prince and punishing the Peshwa Mádhavráv by getting his uncle and rival Raghunáthráv installed in his place, at the same time that he induced the Peshwa to withdraw his troops from the Krishna, and routed the Patvardhan. He suffered, however, a signal defeat at the hands of the Pratinidhi, and was so weakened that Konherráv again overran the country and laid siege to Kolhápúr. The tide then turned again for a time. Instigated by the Court at Poona the chiefs of Kágál, Bávdá, and Vishálgad in 1777 rose in revolt against the minister, but Eshvantráv Shinda, aided by Haidar Ali with money, defeated them without difficulty, and then turned his arms against the officer deputed by the Peshwa to recover Chikodi and Manoli, whom he drove out of those districts. This success, however, proved in the end disastrous to Kolhápúr as it brought the Poona Court to see the necessity of strenuous efforts, and Mahádji Sindia was accordingly despatched with a large force against Kolhápúr. The Darbár of that State applied hastily to Haidar Ali, who promised to send a force of 25,000 men, but these reinforcements did not arrive in time, so that the Kolhápúr authorities were obliged to come to terms with Sindia and to agree to make a payment of £150,000 (Rs. 15 *lákhs*) for which Chikodi and Manoli were given as security. The Kolhápúr Rája was further bound to abstain from plundering the adjacent districts, and from receiving and harbouring rebels against the Peshwa.

The troubles of Kolhápúr were however by no means over, for the Patvardhans continued hostilities on the eastern frontier, while on the south-west the Sar Desái of Sávantvádi fomented and stirred up rebellion and then assumed an openly hostile attitude.<sup>1</sup> He was defeated at Ránga by the contingents of the Vishálgad and Bávdá chiefs, but the mutiny he had excited among the garrison of the strong hill-fort of Bhudargad in the south of Kolhápúr was

## Chapter VII.

### History.

MARÁTHÁS.

Shiváji III.,  
1760-1812.

<sup>1</sup> The feud with Sávantvádi arose partly from disputes about villages in the Málván sub-division which were claimed both by that State and Kolhápúr. It was exacerbated at this time by jealousy on the part of the Kolhápúr court at the honors obtained for the Sar Desái by Shinda, whose niece he had married, and who was all-powerful at Delhi. The distinctions that gave rise to so much jealousy were the title of Rája Bahádúr, and the privilege of using the *morchals* or peacock's feather fans.

## Chapter VII.

## History.

MARÁTHAS.

Shivaji III.,

1760-1812.

not so easily suppressed, and that fort was given up by the mutineers to Parashurám Bháu, the greatest of the Patvardhans, who had previously taken Akevat and Shirol towns on the north-east frontier of Kolhápúr.

At this juncture Eshvantráv Shinda died in 1782, and was succeeded by Ratnákar Pant, who persuaded the young Rájá to leave his seclusion at Panhála, which thenceforth ceased to be the seat of the court, and put himself at the head of the army which was to march against the Sávantvádi chief. The expedition was successful, the Sar Desái being compelled to sue for peace and pay the arrears due to Kolhápúr. The title of Himmat Bahádúr, bestowed for his services on this occasion on a member of the Chaván family or clan, is still held by his descendants.

After his return to Kolhápúr the Rájá had to face a new trouble. The Gadkaris<sup>1</sup> of the fort of Báyda followed the example of their brethren at Bhudargad, and revolted in consequence of some real or supposed interference with their rights. The Rájá proceeded in person to suppress the revolt; but the fort, which is situated on a precipitous hill rising directly from the Konkan and only joined to the main line of the Sahyádris by a narrow passage, was found to be impregnable. He was obliged to withdraw his forces and grant the terms demanded by the mutineers; but shortly afterwards, when the Gadkaris of Pávangad were stirred up by the Sávantvádi chief to follow the example of revolt, he was more successful. He marched at once against the fort, which was surrendered immediately, and finding there ample proof of the part played by the Sar Desái he resolved to punish the latter by invading his territories. This expedition also was successful, and districts were added for a time to Kolhápúr yielding a revenue of £15,000 (Rs. 1½ *lákhs*) per annum.<sup>2</sup> While the Rájá was engaged on this foray the minister Ratnákar Pant was equally successful in suppressing a revolt raised by some disaffected chiefs.

The State then enjoyed comparative peace for some years. During this period piracy, which though checked had never been totally extinguished, revived and became more rife than ever. So much annoyance was caused to the English by this that in 1789 they meditated an attack on the piratical states of Sávantvádi and Kolhápúr, but hesitated about attacking the latter, because they fancied it was subject to the Peshwa with whom they were anxious not to embroil themselves. Nána Fadnavis (1774-1800), the famous minister of the Peshwa, eagerly caught at the means that thus seemed to be offered of subverting the independence of Kolhápúr, and informed the Rájá of the designs of the English, persuading him at the same

<sup>1</sup> In each fort in the Marátha country a permanent garrison was kept up composed of men called Gadkaris, for whose maintenance lands were assigned which they held on condition of service. These men were always very tenacious of their real or fancied rights, and ready to resent any infringement of them by taking advantage of their secure position.

<sup>2</sup> They were restored in 1792 through the intervention of the Peshwa and Sindia.



time to throw himself on the protection of the Peshwa, and save himself by the intervention of the latter. The scheme was nearly successful, for the Rájá at first listened to the voice of the tempter, and seemed inclined to accept the mediation of the Poona Court. Finding, however, that there was little immediate danger, as the English were about to engage in a war with Tipu Sultán (1782-1799) and suspecting the designs of Nána Fadnavis, he broke off the negotiations, and piracy flourished more than ever while the English were occupied with the Maisur war. As soon as it was over, however, they made vigorous preparations for the suppression of piracy, and the Rájá to avoid hostilities was obliged to sue for peace and agree to the terms offered. The second treaty between Kolhápúr and the English was then, in 1792, concluded. The former State was bound by it to pay an outstanding balance due to the English, and accepted as a favour the remission of the interest due on the same. Immediate payments were made as compensation for the losses suffered by the British merchants at the hands of the Kolhápúr pirates, and further payments on the same account were arranged for, as a security for which the establishment of an English factory at Málvan was stipulated for, to be temporary or permanent at the option of the British. The latter were further authorised to establish a factory at Kolhápúr itself, and the Rájá agreed to furnish the provisions required for the sepoys of both factories till the articles of the treaty were fully executed. Satisfactory as these arrangements were on paper, the practical results were less so, as in the year immediately following the treaty there were the same complaints as of old against the Kolhápúr Rájá, and piracy was not suppressed till the latter was deprived of his maritime possessions.

The close of the Maisur campaign brought another difficulty to Kolhápúr. Parashurám Bháu Patvardhan, who had taken part in the campaign as an ally of the English, on his return to his *sarajám* commenced a series of attacks on the eastern districts of the State and committed great devastation. In one of these excursions the Patvardhan's troops under Parashurám's son Rámchandra were met at Alta, a town about fifteen miles to the east of Kolhápúr, by the Kolhápúr forces under the Rájá in person and totally defeated, Rámchandra with his principal officers being captured and taken to Kolhápúr. They were not only kindly treated there, but were almost immediately set at liberty and dismissed to their homes with presents and dresses of honour. If this policy was intended to bring about peace with Parashurám Bháu it entirely failed. Stung at the humiliating defeat his troops had undergone, that leader renewed hostilities, and carried them on with such vigour and skill that he succeeded in penetrating to the capital, which he closely invested. At last he was induced to raise the siege on the Rájá agreeing to pay £30,000 (Rs. 3 *lákhs*), and making over hostages for the payment of the sum. However successful Parashurám Bháu was at the time, he soon found reason to repent of having made the Kolhápúr Rájá a deadly enemy, as the current of events in a very short time brought to the latter an opportunity of revenge which was not neglected. A quarrel took place between Nána Fadnavis

## Chapter VII. History.

MARÁTHÁS.  
Shiváji III.,  
1760-1812.

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji III.,  
1760-1812.

and Parashurám Bháu; and while the latter was engaged at Poona, in the thick of the intrigues that followed the suicide of Mádhavrát Peshwa and ended finally in the accession of Bájirát, the Rájá was incited by the minister to attack the districts of his enemy, which were thus left undefended. Shiváji was not slow to take the hint, and further perceived clearly what an opening was offered to him by the dissensions that paralysed the Peshwa's power. Calling out the entire force of his State he recovered the fort of Bhudargad which was still in the hands of Parashurám Bháu, and then carrying the war into the latter's country burnt the town of Tásgaon and his palace there. He further repossessed himself of the districts of Chikodi and Manoli which during the late disturbances had fallen into the hands of the Nipánikar, the chief of Nipáni some thirty miles to the south of Kolhápúr, who had recently raised himself from the position of a humble Desái to that of a powerful leader. Encouraged by these successes the Rájá carried his arms to the south, took the fort of Jamkhandi for Nána Fadnavis, and sent his forces to plunder and levy tribute in the Karnátak.

While these events were going on, the Rájá of Sátára made an attempt to throw off the yoke of the Peshwa, but was defeated by Parashurám Bháu. His brother Chitur Sing, however, escaped and collected some troops, with which he joined the Kolhápúr Rájá. Parashurám Bháu and Nána Fadnavis having now become reconciled, the Court at Poona was able to turn its attention to affairs in the south, and the Patvardhan chief was despatched to hold the Kolhápúr Rájá in check. He met the latter at a village called Pathankudi in Chikodi and an engagement ensued in which Parashurám Bháu was killed in 1799. This event led to fresh exertions on the part of the Peshwa, and Rámchandra, the son of the fallen chieftain, was sent against Kolhápúr with a large force, his own troops being reinforced by those of the Poona feudatories and five of Sindia's disciplined battalions under the command of a European officer, a Major Brownrigg. The invaders met with a check at first, but soon rallied and regularly invested the town of Kolhápúr. The siege lasted for two months; but though the besiegers were reinforced by the Peshwa's general Dhondo Pant Gokhale, and a wide breach was made in the fortifications, all attempts to carry the place by storm failed. The siege was at last raised in consequence of an intrigue at Poona. Nána Fadnavis had died, and Sindia at the instigation of his favorite Sarjeráv Ghátge<sup>1</sup> who was a Kolhápúr subject and with the connivance

<sup>1</sup> Sakhárám Sarjeráv Ghátge was rewarded for the service done to Kolhápúr on this occasion by the grant of the Kágál estate, though he was the representative of the younger branch of the family in whose possession it had been more or less continuously for many years. Sarjeráv Ghátge's career is a matter of history. Sindia married his daughter the well known Bájábái; and his son, who received the title of Hinduráv, resided entirely at Gwalior, and seldom, if ever, visited Kágál. The estate is now held by Hinduráv's adoptive grandson. When Sakhárám Ghátge received the grant of the Kágál estate a smaller appanage was conferred on the representative of the senior branch of the Ghátge family, which is still held by his descendant. The chief distinction of this branch is their frequent intermarriages with the royal family of Kolhápúr.

of the Peshwa Bájráv, who was a deadly enemy of the Patvardhans, resolved to take possession of the *saranjám* belonging to that family, and ordered his troops at Kolhápur to act accordingly.

Rámchandraráv thus deserted and betrayed had no option but to fly, and his districts were taken by his quondam allies. The siege was thus raised, and the Rája, who had been at Panhála while it was going on, entered the city in triumph. The besiegers are said to have suffered a loss of 3000 killed and wounded on the day they attempted to storm the town.<sup>1</sup>

One of the first steps taken by the Rája, after the siege was raised, was to retaliate on the Patvardhans. The Nipáni chief, who was in alliance with Sindia, had unsuccessfully besieged the fort of Nerli in the Miraj *saranjám*, but on troops being sent to his assistance from Kolhápur the place fell. Kolhápur indeed seemed just then to be exceptionally fortunate. Sarjeráv Ghátge, who came from Poona with the draft of the treaty that was to be entered into with Sindia, brought with it two standards that had been taken by the Pratinidhi of Karád from Kolhápur, and also the formal consent of the Peshwa to the resumption by the Rája of the districts of Chikodi and Manoli. The happiness of the prince was completed by the birth of a son and heir, who received the name of Shambhu, but was generally known as Ába Sáheb.

Kolhápur for some time after this enjoyed unusual quiet, General Wellesley when engaged in the campaign against Sindia and the Rája of Berár having given the Kolhápur prince plainly to understand that aggressions against the allies of the English would not be permitted. The feud with the Sar Desáis of Sávantvádi however was kept up, and mutual incursions were made which resulted, in 1806, in the defeat of the Sávants in a pitched battle and the siege of their capital. The place would probably have been taken had not Lakshmbái, the Regent of Sávantvádi, applied for aid to the Peshwa. The latter assisted her by secretly instigating the Nipáni chief to take possession of the districts of Chikodi and Manoli, on which the Kolhápur Rája hastily raised the siege of Vádi and returned to his own territory. Active hostilities then took place between him and the Nipánikar which resulted in the total defeat of the former in a battle at Sávgaoon in 1808. The Nipánikar, however, did not press his advantage, and in the following year a peace was negotiated which was to be consolidated by the marriage of the Nipánikar with one of the Kolhápur princesses. The marriage took place, but had not the desired effect. In the midst of the wedding festivities the Nipáni chief suddenly decamped with his bride, and a hostile incursion made not long after into

## Chapter VII. History.

MARÁTHÁS.  
Shiváji III.,  
1760-1812.

<sup>1</sup> Among the killed were some of the European officers of Sindia's forces. The tombstones over the graves of a French and a Spanish officer are still extant. The former bears the inscription 'Jules Romeu, né 1768 à Cette en Languedoc, Comman un Battalion de l'armée de Sindia. Tué aux tranches de Colapour, 23 Mars 1800.'

## Chapter VII.

## History.

MARÁTHÁS.  
Shiváji III.,  
1760-1812.

Kolhápur territory showed that the new tie was not of much political importance. This attack, which was made at the instigation of the Peshwa, was so successful that the town of Kolhápur would probably have been taken were it not for a new treaty made with the English in 1812 under the following circumstances.

The attitude assumed by the great feudatories of the Peshwa towards their master rendered it necessary for Mr. Elphinstone, the British Resident at Poona, to interfere and bring them to terms. With this view he assembled a force at Pandharpur in 1811. It was resolved to take advantage of this opportunity to put a stop once for all to the piracy which prevailed in the States of Sávant-vádi and Kolhápur, and which the provisions of former treaties had utterly failed to suppress. Accordingly negotiations were entered upon with the Kolhápur Rájá. Some delay was occasioned by the Peshwa, who made an assertion as bold as it was false that the Rájá was his feudatory while at the same time he kept urging on the Nipánikar to continue hostilities against Kolhápur. Fortunately however for the Rájá, Mr. Elphinstone was not easily deceived. On the 1st of October 1812, a treaty was concluded by which the Rájá ceded to the British the harbour of Málvan and its dependencies, engaged to abstain from piracy and wrecking, renounced his claim to the districts of Chikodi and Manoli, and further agreed not to attack any foreign State without the consent of the British Government, to whom all disputes were to be referred. In return for these concessions the British renounced all their claims against the Rájá, who received the British guarantee for all the territories remaining in his possession 'against the aggression of all foreign powers and States.' Kolhápur, in short, became a protected State in alliance with the British Government.

After a reign of fifty-three years the Rájá Shiváji died on the 24th of April 1812, leaving two sons Shambhu *alias* Ába Sáheb and Shaháji *alias* Báva Sáheb. The condition of Kolhápur during this period is thus summarised by Major Graham in his statistical account of that Principality on which a considerable part of this sketch has been based:

'The long reign of Shiváji had been from the commencement one of almost incessant hostility and continued suspense between the prospects of ruin and of conquest; and to support the fierce struggle for independence every effort to provide means had been resorted to, piracy at sea, plunder at the court, and oppression in the collection of the revenue, and all frequently without avail.

'Grants of land were unsparingly made to the impoverishment of the Crown estates; two-thirds of the entire country were thus transferred to partisans for military services, and a swarm of reckless characters were left behind who rejoiced in anarchy, and whose livelihood was to be gathered only among the troubled waters. All the evils also of the feudal system prevailed in full force; continued warfare was allowed between the petty authorities; the rayats were oppressed and the entire rent forcibly seized during the hardest

season; fines increased as commutation for all other punishment; justice was one-sided and only meted out to favoured followers; merchants and wayfarers were despoiled during the journey; the labour of the cultivator was exacted without remuneration; and a multiplicity of monopolies existed to the destruction of all trade.'

Shambhu or Ába Sáheb,<sup>1</sup> who succeeded to the *gádi* at this juncture, was a prince of a mild disposition, too mild indeed for the people whom he had to govern. He devoted his attention to the restoration of order in his State and to the cultivation of the arts of peace in preference to those of war. Some five years after his accession the war broke out between the British and the Peshwa, and he espoused the cause of the former. He was rewarded for his conduct at the close of the war by the grant of the districts of Chikodi and Manoli, which had changed hands so often during the previous sixty years. At the same time arrangements were made for the management of his possessions in the Konkan, which had for their object the consolidation of the British power in that quarter and the effectual prevention of piracy.

In 1821 Ába Sáheb met with a violent death. A refugee Sardár from Karád, of the Mohite family, who had been hospitably received in the Kolhápur territory and had received villages for his maintenance, felt aggrieved at a grant of land in one of these villages being made to a servant of the Rájá, and expressed his sense of this grievance in unbecoming terms, at the same time that he pressed with vehemence for the payment of some £2000 (Rs. 20,000) which he said were due to him. After his repeated petitions on the subject had been disregarded, he presented himself at the palace on the 2nd of July, accompanied by six of his relations fully armed. On being admitted to the presence of the Rájá, Sayáji the leader behaved with such insolence that Ába Sáheb ordered him to be expelled from the palace and turned himself to leave the room. As he did so one of the party discharged a pistol at him, which inflicted a desperate wound. Four of the Rájá's confidential servants were then slain, and, strange to say, such a panic was created that the murderers were able to hold their position in the palace and to keep the wounded Rájá in their hands throughout the whole day. In the evening they surrendered on their lives being guaranteed by two Sardárs of high rank and the chief *guru* or priest. Shortly afterwards, however, the Rájá died, and the securities, feeling unable to act up to the guarantee they had given, provided the Mohites with horses and allowed them to escape. The murderers however were soon overtaken and cut to pieces by a party sent in pursuit by the Rájá's widow, and vengeance was taken on their families, who were either trampled to death by elephants or imprisoned in Panhála.

## Chapter VII.

## History.

MARÁTHÁS.

Shambhu,  
1812-1821.

<sup>1</sup> Every Marátha of standing has, besides his proper name, another designation such as Bába Sáheb or Nána Sáheb which is used by those about him. The later Rájás of Kolhápur are almost invariably referred to by these familiar names.

## Chapter VII.

## History.

MARÁTHÁS.

Sháháji,  
1821-1837.

Ába Sáheb having left an infant son, arrangements were made to secure the regency for the child's mother to the exclusion of his uncle. The death of the boy shortly afterwards, however, changed the state of affairs, and Sháháji, generally known as Báva Sáheb, the second son of Rája Shiváji, succeeded without dispute, his title being recognized in open Darbár by the Governor of Bombay, who visited Kolhápur at this juncture.

The new Rája was of a character very different from that of his brother and predecessor, wild, reckless, debauched, utterly regardless of truth and honesty, his conduct at times seemed to pass the bounds of sanity. Most of the leading men of the State having taken part in the attempt to exclude him from the regency during his nephew's lifetime, he deliberately set them aside and chose for his officers and associates men of low rank and lower character. With such companions and such counsellors he soon threw off all restraint and embarked on a mad and self-willed career. Justice was unheard of, the rights of property ceased to be respected, and life was utterly insecure. The revenues of the State were alienated to support the profligate extravagance of the Rája and his seraglio, and the friends relations and dependants of the women of the harem. The Rája himself accompanied a favourite servant of his, Sabbhána Nikam by name, who was at the head of a gang of highway robbers, on his marauding excursions, and on one occasion he is said to have used the services of this band to plunder his own treasury. The object of this last feat was to get possession of the State jewels, and thus supply himself with funds without the notoriety that would attach to pawning these jewels.

The Rája's conduct soon attracted the attention of the British Government, but in accordance with the policy of the day no notice was taken of it officially so long as the general peace of the country was left undisturbed. This, however, was not long the case. Báva Sáheb, shortly after his accession, increased his forces considerably and during the disturbance that took place in 1824 at Kittur, when Mr. Thackeray, the Political Agent, and some other British officers were killed, his movements excited considerable apprehension. The suppression of the Kittur insurrection checked whatever intention he may have had of acting against the British Government, but he proceeded to use his forces in a way that soon called for the intervention of that power. His own feudatories the chiefs of Kágal and Ichalkaranji<sup>1</sup> were attacked and their *jágirs* overrun, and the Rája marched about with his forces,

---

<sup>1</sup> The founder of the Ichalkaranji family was a Bráhman clerk named Náro Mahádev, in the service of an ancestor of the Senápati of Kápsi, who bestowed on him the village of Ichalkaranji in *indm*. In compliment to his benefactor the grantee assumed the latter's family name of Ghorpade. Náro Mahádev soon increased in wealth and power, and his fortunes reached their zenith in 1722, when his son was married to the daughter of Báláji Vishvanáth the first Peshwa. This alliance was of immense importance to the chiefs of Ichalkaranji, who were always in consequence supported by the Peshwás, and, though feudatories of the Kolhápur Rájás, were often thereby enabled to assume temporary independence.



sacking towns and plundering and devastating. His own subjects were not the only sufferers from his acts of violence, which extended even to allies and subjects of the British Government. As it was absolutely necessary to put a stop to such proceedings, a force was marched against Kolhápúr. The Rájá at first meditated resistance, but thought better of it, and in January 1826 concluded a treaty with the British Government. In this engagement the Rájá bound himself to reduce his army and refrain from disturbing the public peace, as well as from molesting the Kágál and Ichalkaranji chiefs and others. He also promised to respect the rights of the Sávantvádi State, as well as the rights and privileges of the *inámdárs* and others in the districts of Chikodi and Manoli, the cession of which to the Kolhápúr State was formally confirmed by this treaty, which also fully acknowledged 'the independence of the Rájá as a Sovereign Prince.'

As soon, however, as the immediate pressure was removed the Rájá returned to his former ways, kept the country in a constant state of alarm, and violated the treaty that had just been concluded, so that a force had again to be marched against Kolhápúr, and a new preliminary treaty was concluded in October 1827. In this the instances of breach of the former treaty were set forth side by side with the steps the British Government was compelled to take. Thus the Rájá, though bound by the former treaty to reduce his army to the peace establishment, had not only raised large forces, but had employed them in disturbing the public tranquillity and committing all sorts of excesses. He was therefore now bound down to keep no more than 400 horse and 800 foot exclusive of garrisons for his forts. The districts of Chikodi and Manoli were resumed by the British Government, and Akivát, a notorious haunt of robbers, was ceded to the latter. The Rájá bound himself to pay compensation to the amount of about £15,000 (Rs. 1½ *lákhs*) to those who had suffered from his lawless violence, and agreed to transfer temporarily territory yielding £5000 (Rs. 50,000) for the liquidation of this debt. To secure observance of the present treaty it was stipulated that British garrisons should be received into the forts of Kolhápúr and Panhála the expenses of the same being defrayed by the Rájá.

With a view to getting this treaty modified, Báva Sáheb proceeded to Poona to see the Governor, accompanied by a force considerably in excess of the number to which he had bound himself to limit his army. After the intentions of Government had been fully explained to him, he still remained on regardless of all hints and intimations that he had better return to his own territory, apparently in the hope of wearying out the Government by his pertinacity. During this period the lawless conduct of himself and his followers made them most unwelcome visitors, until at last an act of violence was perpetrated on a trooper in the British service, and the Rájá in fear of the possible consequences left Poona hastily. Untaught by experience, Báva Sáheb renewed on his return to Kolhápúr the excesses which had already brought him

## Chapter VII.

## History.

MARÁTHÁS.

Sháháji,  
1821-1837.

## Chapter VII.

## History.

MARÁTHÁS,

Sháháji,  
1821-1837.

into such trouble, wantonly violated his engagements with the British Government, and disturbed the public tranquillity to such a degree that a force had to be sent against him for the third time. A definitive treaty was concluded on the 24th of October 1827 in which were embodied the provisions of the preliminary treaty made in the previous year, with an additional article empowering the British Government to appoint a chief minister, removable at their pleasure, by whose advice the Rájá agreed to be bound in all matters relating to the administration of his State. On this occasion a brigade of British troops was left at Kolhápúr to secure the observance of the treaty. After some time, however, this was withdrawn.

During the last ten years of Báva Sáheb's reign he abstained on the whole from such conduct as would necessitate the intervention of the paramount power to preserve the peace, but his rule was what might be expected from a prince of his character. Overwhelmed with debt he never thought of reducing expenditure by legitimate means, but maintained a large standing army and the same expensive style of grandeur as before. As the pay of his troops and officials was issued most irregularly, they helped themselves to whatever they could get. Most of the *sardárs* had to mortgage their estates to the moneylenders and thus became beggared. Money being scarce and land of little value, the Rájá alienated an enormous proportion of his territory by grants and *ináms* with which the most trifling services were rewarded. Of course with such a ruler and under such circumstances bribery, favouritism, and pandering to his evil passions were the only means of advancement, and altogether the State was reduced to as miserable a condition as can well be conceived.

The very last act of Báva Sáheb was most characteristic. Under pretence of a pilgrimage to Tuljápúr he prepared for a plundering expedition by raising an army of 20,000 men. As he was bound by treaty not to take guns about with him, he concealed his ordnance in carts under leaves and started off. Fortunately for his descendants, however, he was attacked with cholera before he could execute his wild project, and died at a village near Pandharpur on the 28th of November 1837, leaving two sons, Shiv or Shiváji and Shambhu, generally known as Bába Sáheb and Chima Sáheb and two daughters.

Shiváji IV.,  
1837-1866.

Bába Sáheb was at once placed on the *gádi*, but being a minor, a council of regency was formed, consisting of his mother, his aunt the Diván Sáheb as she was styled, and four *kárbháris*. The ladies quarrelled, and in the course of six months the Diván Sáheb, being the most energetic and having the strongest followers, managed to get the whole power into her hands. As she blindly followed, in most respects, the system adopted by the late Rájá, her rule was not by any means calculated to improve the condition of the State. Indeed, with a population composed of such turbulent elements as that of Kolhápúr, and so inured to anarchy and violence, it would have been impossible for a woman to stem,

even if she had the will to do so, the tide of corruption, oppression, and iniquity. The British authorities made a faint effort to improve matters by getting two of the *kárbhāris* dismissed and making use of an *akhbarnavis*<sup>1</sup> as Native agent, but no improvement was thus effected, and at last, in 1843, it was determined to act on the clause of the treaty which empowered the British Government to appoint a minister, and accordingly a respectable Bráhmaṇ official, Dáji Krishna Pandit, was selected for the post. Immediately after his arrival, two of his coadjutors were dismissed for peculation and the chief power was thus left uncontrolled in his hands. He at once set about the work of reform, reduced expenditure, and checked to a great extent the illicit gains of the chiefs and officials.

He also seems to have hurt the pride of the latter, and he became most unpopular throughout the State. The Diván Sáheb and her party did not relish the transference of power to a Bráhmaṇ interloper, as they considered the new minister to be, and every reform introduced and every abuse checked by the latter raised up for him a host of enemies. A year after his arrival the latent sparks of disaffection burst into a flame, and an insurrection arose which had to be suppressed by British troops. The actual insurgents were the Gadkaris, who have been previously mentioned in this sketch, the permanent garrisons of the hill-forts, but they enjoyed the sympathies, if not the more tangible support, of other classes as well. These men were dissatisfied with an arrangement by which their lands were placed under the supervision of the *mámlatdárs* of the adjoining sub-divisions. They had always been accustomed to seek redress by mutinying, and they were encouraged to do so on this occasion by the reports which had been carefully disseminated throughout the country of the paucity of British troops in those parts. Accordingly, in July 1844, the garrisons of Sámángad and Bhudargad, in the south of the Kolhápur territory, revolted and shut the gates of the forts.

A force was despatched from Belgaum in the middle of September against Sámángad, while Kolhápur troops were sent against Bhudargad. The British force, after taking the *peta* or sub-division found itself unable to take the former fort by storm, and was obliged to send to Belgaum for siege guns, while the Kolhápur force was worsted in a sally made from Bhudargad. This success of the insurgents brought numerous adherents to their cause and spread the disaffection widely. The *sibandis* or local militia at Kolhápur rose in revolt, confined the minister Dáji Pandit, and set up a government in supersession of that acknowledged by the British. Affairs having now assumed such a serious aspect, corresponding efforts were made for the suppression of the revolt. Reinforcements were sent to the disturbed district, and on the 8th of October General

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji IV.,  
1837-1866.

<sup>1</sup> Literally *akhbarnavis* means a newswriter, a class of official formerly much employed, whose duty it was to report what went on in Native States, and to act as the channel of ordinary communication between the chiefs and the British authorities.

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji IV.,  
1837-1866.

Delamotte assumed command of the whole force. Three days afterwards four siege guns arrived at Sámángad and were at once put in position. Mr. Reeves the Commissioner then gave the garrison an opportunity of stating their grievance and coming to terms, but as it was found that they only wished to gain time in the hope of getting aid from Kolhápúr fire was opened on the fort, a practicable breach was made in a day, and on the following day, the 13th of October, the place was stormed and taken. Colonel Outram at this time joined the camp as Joint Commissioner, and immediately after the fall of Sámángad marched towards Kolhápúr with a portion of the force. After much negotiation he, on the 24th of October, obtained the release of Dáji Pandit, and was joined by the young Rája, his aunt and mother, and several of the chiefs and *sardárs*. On this Bábáji Ahirekar, the ringleader of the *sibandi* rising, fled with five hundred of his men to Bhudargad. After considerable delay General Delamotte appeared with his force before this fort. He admitted the garrison to surrender on the 10th of November, and allowed himself to be detained at one gate while Bábáji and his party escaped by another and took refuge in Panhála. Shortly afterwards Colonel Ovans, who had been appointed Commissioner, was captured by the insurgents while proceeding to take up his appointment, and confined in the same place. General Delamotte therefore marched thither, and on the 25th of November appeared with his whole force before Panhála, accompanied by the Commissioner Mr. Reeves and Colonel Outram. The garrison were called on to release Colonel Ovans and surrender at discretion or take the consequences. With the first of these demands they complied in the hope of obtaining favourable terms, but as they refused to surrender the attack commenced. On the 27th of November the *peta* was taken. The batteries opened on the 1st of December, a breach was made in a few hours, and in the afternoon the place was stormed and taken. The garrison attempted to escape into the neighbouring fort of Pávangad, but were followed so closely by the British troops that this fort also was taken on the same day. During the storm Bábáji and some of the other leaders were killed and a large number of prisoners were taken.

Almost immediately after the fall of Panhála a force was despatched under Colonel Wallace against the fort of Rángna, which was evacuated by the garrison a day or two after his arrival. Vishálgad was about the same time surrendered, and this put an end to military operations, as far as Kolhápúr was concerned, the scene of hostilities being then transferred to Sávantvádi.

The captured forts were then dismantled and steps taken to secure the future tranquillity of the country.

Among the measures adopted for the administration of Kolhápúr was the appointment of a British officer as Political Superintendent. Previously to this the political supervision of the territory had been vested, first in the Principal Collector of Dhárwár, and afterwards in the Collector of Belgaum, who was also Political Agent in the Southern Maráthla Country. Experience however

showed that Kolhápur required the undivided attention of a British officer on the spot, and Captain D. C. Graham of the Bombay Army was appointed first Political Superintendent. He had a difficult task before him. The Principality was overwhelmed with debt, as, in addition to the debts incurred by its rulers, the cost of suppressing the insurrection was charged to Kolhápur, and had to be paid to the British Government by instalments. Education was almost unheard of, and the arrangements for the administration of justice were very imperfect. There were a large number of persons, too, in the State who despised any other occupation but that of carrying arms, and who, if left unemployed, would form a class dangerous to the community. Such persons were provided with occupation by being enlisted in a local corps which was raised and disciplined by British officers, and which has on more than one occasion done good service. Arrangements were made to liquidate by degrees the debts of the State, and the administration was carried on as economically as was consistent with due provision for the requirements of justice and education.

The work begun by Captain Graham was carried on by his successors, and the annals of Kolhápur during this period, if dull, as uneventful annals generally are, yet present a picture of continued progress. Under the steady firm government that was established, peace and order prevailed and the anarchy and disorder that had once characterised the place became a tradition of the past.

The stability of this improved state of affairs was severely tested in 1857, when the Twenty-seventh Regiment Native Infantry, which was then stationed at Kolhápur, followed the example of the Bengal Army, and mutinied. The Kolhápur local corps remained staunch on this occasion, and the mutineers receiving no support either from them or from the townspeople fled towards Ratnágiri, murdering, on the way, three of their European officers who had escaped when the mutiny broke out, but who unfortunately took a road that brought them in contact with the mutineers. Some time after this there was an abortive attempt at a rising in Kolhápur. A number of men marched into the town one day and took possession of the palace and the gates of the fort. Troops were immediately marched from the camp to the town, but found, on their arrival, that little remained for them to do, the ringleader of the insurgents having been shot by a guard of the local corps on duty at the palace, after which his followers only thought of making their escape.

During the mutiny of 1857-58 the Rája was considered to have remained staunch and loyal to the British Government, but his brother Chima Sáheb was charged with treason and deported to Karáchi, where he died a few years ago. The Government marked their sense of the Rája's loyalty by conferring on him the Order of the Star of India and granting a *sanad* of adoption. He was further, at the end of 1862, vested with the administration of his Principality, a new engagement being entered into defining his

## Chapter VII.

## History.

MARÁTHÁS.

Shiváji IV.,  
1837-1866.

## Chapter VII.

## History.

MARÁTHAS.

Rájárám II.,

1866-1870.

powers and providing for the liquidation of the debt still due to the British Government.

Bába Sáheb did not long enjoy his powers, as he died in August 1866. A son that he had by his wife, the daughter of the Gáikwár of Baroda, had died some time previously; so, being without issue, he adopted on his death-bed Nágojiráv, the son of his eldest sister, who had been married to a member of the Pátankar family, and had died not long afterwards. Nágojiráv, who received on his adoption the name of Rájárám, was about sixteen years of age at the time of the Rája's death and had received some education. When the adoption was sanctioned by the Paramount Power, and he was formally recognized as Rája, arrangements were at once made to finish his education and give him as complete a training as was possible under the circumstances. With this view a special Assistant to the Political Agent was appointed, who, in addition to his other duties, was entrusted with the supervision of the Rája's education and training, the actual work of tuition being carried on by a Pársi graduate of the Bombay University. Care was taken to isolate the young prince as much as possible from the noxious influences that ever lurk about a native palace, and he resided in a bungalow near the Residency, except on special occasions. Being of a very amiable disposition, and most anxious to improve himself his preceptors found their task comparatively easy, and on the few occasions when the Rája appeared in public he created a most favourable impression. As he expressed a strong wish to visit Europe, it was thought advisable that he should proceed there before attaining his majority, and accordingly, in May 1870, he left Bombay, accompanied by his guardian Captain, now Lieutenant Colonel, E. W. West, his tutor, and a few native servants. He was presented to the Queen not long after his arrival in London, and made the acquaintance of many of the leading men of the day. He spent altogether five months in seeing the wonders of London and other great cities and in making trips to Scotland and Ireland, enjoying himself thoroughly and winning golden opinions everywhere. On the 2nd of November he left England for the Continent en route to India. He unfortunately met with some very cold weather while proceeding from Munich to Innsbrück, and was laid up, in consequence, at the latter place. He was afterwards taken on to Florence, where the best medical advice was procured for him, but a sudden collapse took place on the 30th of November, and he breathed his last to the great grief of all who knew him. His remains were burnt, according to the rites of the Hindu religion, on the banks of the Arno, at a spot beyond the Cascini, now marked by a cupola and a bust of the deceased, and the ashes were collected afterwards and taken to the Ganges by his attendants.<sup>1</sup>

Shiváji V.,  
1870-1883.

As Rájárám left no issue, his widows were allowed to adopt and the choice of the family fell on Náráyanráv son of Dinkarráv

<sup>1</sup> A diary kept by the Rája during his residence in Europe was after his death edited by Captain, now Lieut.-Colonel, West and published by Smith and Elder of London.



Bhonsle, a member of the same branch of the family as that from which the adoption was made in 1760 as narrated above. The choice was approved by Government and in October 1871 the boy, then in his ninth year, was formally adopted, receiving on the occasion the name of Shiváji. Arrangements were made for the education of the minor prince under the guardianship of Mr. Hammick, a member of the Civil Service and everything progressed fairly up to 1879, when unfortunately His Highness' mind began to show signs of failing and he had to be withdrawn from the Ráj Kumár College at Rájkot, where he had been prosecuting his studies. In spite of the careful treatment of the several distinguished medical officers and the kindly offices of the guardians, his condition gradually became worse. In January 1882 a committee of medical officers appointed by Government examined His Highness. As the committee pronounced His Highness' malady to be incurable it became necessary for Government to appoint a form of administration during his disability. Accordingly in March 1882 under a Government Resolution the affairs of the Kolhápúr administration were transferred to a Regency Council. The Regent, the Chief of Kágál, is assisted by a Council of three, the Diván, the Chief Judge, and the Chief Revenue Officer.

On the 25th of December 1883 Shiváji Chhatrapati Mahárája died at Ahmadnagar where he was removed for the benefit of his health. As the Rájá died without issue, their Highnesses the Ránis of Kolhápúr, with the approbation of Government, selected Yashvantráv *alias* Bába Sáheb, the eldest son of the Regent, the chief of Kágál, to fill the vacant throne, and accordingly on the 17th of March 1884, under the style and title of Sháhu Chhatrapati Mahárája, he was adopted by Her Highness Anandibái Sáheb, the widow of the late Shiváji Chhatrapati. As the new Mahárája is only ten years old, the affairs of the State continue to be conducted by the Regency Council. The Rájá of Kolhápúr is entitled to a salute of nineteen guns and holds a patent or *sanád* of adoption. The military force of the State consists of 544 regular infantry, 156 irregular cavalry called red-coat *risála* and 486 police.

Of the eleven feudatories subordinate to Kolhápúr four are important, the chiefs of Vishálgad, Bávdá, Kágál, and Ichalkaranjí.<sup>1</sup> The chief of Vishálgad, styled Pant Pratinidhi, is a Deshasth Bráhmaṇ and his family name is Jaykar. His head-quarters are at Malkápúr twenty-eight miles north-west of Kolhápúr. He pays *nazar* or presents to the Kolhápúr State on the occasion of a succession and an annual contribution of £500 (Rs. 5000) on account of service. The chief of Bávdá, styled Pant Amátya, is a Deshasth Bráhmaṇ and his family name is Bhádanekar. He resides at


## Chapter VII.

### History.

MARÁTHÁS.  
Shiváji V.,  
1870-1883.

Sháhu  
(the present  
Rájá).

<sup>1</sup> The titles of the eleven feudatories are: Pant Pratinidhi or chief of Vishálgad, Pant Amátya or chief of Bávdá, Senápati or chief of Kápsi, Sarjeráv Vajarat Máb or chief of Kágál, Ghorpade or chief of Ichalkaranjí, Sena Kháskhel or chief of Torgal, Amir-ul-Úmráv or chief of Datvad, Himmat Bahádur, Sarjeráv Deshmukh of Kágál, Sar Lashkar Bahádur, and Pátankar.



## CHAPTER VIII.

## THE LAND.

UNDER the treaty of 1827 the British Government acquired the right of appointing a minister to the State. For nine years this right remained in abeyance. In November 1837, on the death of Sháhájí Chhatrapati also called Báva Sáheb Mahárája, the British Government found it necessary to make arrangements for the administration of the State during the minority of Rája Shivájí IV. also called Bába Sáheb Mahárája. It was at first deemed advisable to support the administration that was acceptable to the persons of greatest influence in the State. The *sardárs* or nobles had mostly attached themselves to one or other of two rival parties, one headed by the mother of the young prince and the other by the widow of his father's brother. As the attempts of both parties to form administrations equally failed, in 1844, on the recommendation of Mr. Townsend the Political Agent Southern Marátha Country, Dáji Krishna Pandit, the *daftardár* or native assistant to the Collector at Dhárwár, was placed at the head of the regency, and shortly after he was made sole minister of the State. Dáji Krishna's first step was to reduce the number of sub-divisions or *mámlás*. He divided the territory<sup>1</sup> into six sub-divisions or *petás* and two petty divisions or *thánás*, a distribution which has since remained almost unchanged.<sup>2</sup> Over each of the sub-divisions or *mámlás* an officer termed *mámlatdár* was appointed with revenue criminal and civil powers on a monthly salary of £10 (Rs. 100). Besides the sub-divisional and petty divisional officers, a *nyáyádhish* or judge on a monthly pay of £20 (Rs. 200) was placed in charge of the magisterial department, and a *kotvál* or police officer on £5 (Rs. 50) a month was appointed to conduct the police of the town of Kolhápúr. The discontent which these measures caused among the *gadkaris* or fortsmen, led, in 1845, to the appointment of Major D. C. Graham of the 28th Regiment N. I. as Political Superintendent to administer the affairs of the State during the minority of the prince, the minister Dáji Pandit continuing to work independently as the chief *kárbhári* or minister of the State.<sup>3</sup> In 1848 the civil functions of the *mámlatdárs* were transferred to a *sadar amín* on £15

## Chapter VIII.

## The Land.

STAFF,  
1844-1884.

<sup>1</sup> Exclusive of the four feudatory states Vishálgad, Bávda, Kágál, and Ichalkaranjí with its petty division of Ajra.

<sup>2</sup> The present (1884) sub-divisions are Karvir, Panhála, Shirol, Alta, Gadinglaj, and Bhudargad, and the petty divisions are Ráybág under Shirol and Katkol under Gadinglaj.

<sup>3</sup> There was besides a *jamínis* on a monthly pay of £6 10s. (Rs. 65), who examined the *mámlatdárs'* accounts and aided the minister in all financial matters; a *chitnis* or secretary on a monthly pay of £10 (Rs. 100) to conduct the correspondence; and a treasurer on £10 (Rs. 100) who had in addition to his duties the charge of the Rája's *khdsgí* or personal department.

## Chapter VIII.

## The Land.

STAFF,  
1844-1884.

(Rs. 150) a month, and two *munsifs* each on £7 10s. (Rs. 75), who were immediately under the Political Superintendent. In 1858 the State or *darbār* establishments were revised. The post of chief *kārbhāri* or minister was abolished, and the State or *darbār* work was conducted under the direct supervision of the Political Superintendent, aided by a *daftardār* on £25 (Rs. 250) a month. In addition a European Assistant and a Native Deputy Political Superintendent on £25 (Rs. 250) a month were appointed. One of the duties of these two officers was to superintend the work of the *mámlatdárs*. The treasurer's monthly pay was reduced from £10 (Rs. 100) to £9 (Rs. 90), but he was allowed an extra sum of £6 (Rs. 60) a month for the work of the *khāsgi* or personal department. In 1861 the title of the Political Superintendent was changed to Political Agent and that of the Deputy Political Superintendent to Native Agent; and the State correspondence began to be carried on in the name of Mahārāja Chhatrapati that is the Rāja. In 1862 the post of *daftardār* was abolished and a State *kārbhāri* or minister on £50 (Rs. 500) a month was appointed to aid the Rāja in managing the revenue department. In November 1863 the whole administration was entrusted to the Rāja Bāba Sāheb Mahārāja who ruled until his death in August 1866.

During the minority of Bāba Sāheb's successor, Rājārām Mahārāja,<sup>1</sup> the State again came (1866) under the direct management of the Political officer. In 1867 a European officer styled guardian to the Rāja and Assistant Political Agent, Kolhāpur, was appointed and entrusted with the direct control of the *khāsgi* or personal department. Appellate powers were given to the Political Agent and, on the death of the *kārbhāri*, an assistant *kārbhāri* or minister on £25 (Rs. 250) a month was temporarily appointed. In 1870 a new *kārbhāri* or minister on £70 (Rs. 700) was appointed.<sup>2</sup> In 1874 two district officers, on a monthly pay of £25 (Rs. 250) each, were appointed, one for the northern division and the other for the southern division, with powers and functions corresponding to those of district deputy and assistant collectors in British districts. In 1882 the malady under which the Rāja suffered, led to the transfer of State affairs to a council of regency appointed under Government Resolution of March 1882. The Council consists of the Regent, the *Diván* or Minister, the Chief Judge, and the Chief Revenue Officer. The pay of the Chief Revenue Officer is £60 (Rs. 600) a month, and his office corresponds with that of the Revenue Commissioner in British districts. He has an assistant on a yearly pay of £300 (Rs. 3000); a *daftardār* on £300 (Rs. 3000) who is in charge of the financial and revenue accounts and of the *huzur* or head-quarters treasury and is assisted by a *nāyab daftardār* on £90 (Rs. 900); two district officers, one for the northern and the other for the southern

<sup>1</sup> In May 1870 H. H. Rājārām Mahārāja proceeded to Europe and on his way back to India died at Florence on the 30th of November 1870. On the 23rd of October 1871 the dowager Rāni adopted with the sanction of the Government of India a boy from the Bhonsle family as heir and successor to the Kolhāpur *gadi*, who was called Shivāji V.

<sup>2</sup> The minister's monthly salary was raised from £70 (Rs. 700) in 1870 to £80 (Rs. 800) in 1874 and to £100 (Rs. 1000) in 1880.

division, who receive a yearly pay of £300 (Rs. 3000) each and correspond to assistant or district deputy collectors in British districts; a treasurer on £180 (Rs. 1800) in charge of the head-quarters treasury, and a record-keeper on £90 (Rs. 900) in charge of the head-quarters records. Each of the six fiscal sub-divisions is under an officer styled *mámlatdár* whose yearly pay varies from £120 to £210 (Rs. 1200-2100). Two of the sub-divisions have a subordinate petty division under an officer styled joint-officer. Their yearly pay is £54 (Rs. 540) and £48 (Rs. 480) and they correspond to the *mahálkaris* in British districts.

In revenue and police matters, the charge of the 1079 State and alienated villages is entrusted to 1377 headmen or *pátils*, of whom seven are stipendiary and 1370 hereditary. Of the stipendiary headmen, three perform police duties only and four police and revenue duties. Of the hereditary headmen, 347 perform revenue, 327 perform police, and 696 perform revenue and police duties. The headmen's yearly emoluments consist partly of cash payments and partly of land grants. The cash emoluments vary from £4 16s. to £9 12s. (Rs. 48-96) and average £6 14s. (Rs. 67). Of £9276 (Rs. 92,760) the total yearly charge on account of village headmen £1962 (Rs. 19,620) are paid in cash and £7314 (Rs. 73,140) are met by grants of land. To keep the village accounts, draw up statistics, and help the village headmen, there is a body of 693 village accountants, of whom twenty-four are stipendiary and 669 are hereditary. Each accountant has an average charge of about two villages, containing about 1155 people and yielding an average yearly revenue of about £374 (Rs. 3740). Their yearly pay averages about £9 12s. (Rs. 96). It amounts to a total cost of £6676 (Rs. 66,760).

Under the headmen and accountants are the village servants with a total strength of 5266. These men are liable both for revenue and for police duties. They are Musalmáns, or Hindus generally of the Koli, Mháṛ, and Máṅg castes. The total yearly grant for the support of this establishment amounts to £13,791 (Rs. 1,37,910), averaging £2 12s. (Rs. 26) to each man or an average cost to each village of £12 14s. (Rs. 127). Of this charge £13,484 (Rs. 1,34,840) are met by grants of land and £307 (Rs. 3070) are paid in cash.

The average yearly charge of village establishments may be thus summarised :

*Kolhápúr Village Establishments, 1884.*

		£.	Rs.
Headmen ... ..	...	9276	92,760
Accountants ... ..	...	6676	66,760
Servants ... ..	...	13,791	1,37,910
Total ... ..	...	20,743	2,07,430

Kolhápúr land tenures belong to three main classes, alienated or *ináṁ*, State or *sheri*, and personal or *rayatvár*. Alienations are of two kinds, *ináms* or assignments of land or land revenue and *nemnuks* or cash allowances. Each of these has four varieties, charitable or *dharmádáya* and other personal grants, temple grants

## Chapter VIII.

### The Land.

STAFF,  
1884.

#### Village Officers.

#### Village Servants.

#### TENURES.

## Chapter VIII.

## The Land.

## TENURES.

or *devasthán*, political grants, and grants for non-military service. Most alienations were made between 1618 and 1838. At present (1884) nearly half of the Kolhápúr territory is alienated to feudatories, *saranyámdárs*, *sardárs*, petty *inámdárs*, and servants.<sup>1</sup> The State or *sheri* lands are the Rájá's personal holdings. In 1881-82 they covered an area of 5811 acres assessed at £2346 (Rs. 23,460) and yielding a rental of £3723 (Rs. 37,230). These lands are managed by the district revenue officers who let them to the highest bidder for a term of years. Of the individual or *rayatvár* tenure the chief varieties were *mirási* or hereditary under which so long as the holder paid his fixed rental he could not be ousted; *upri* or casual under which at the end of one or two years the land might be given to a fresh holder; *chál khand* under which the holder paid something more or less than the fixed *bigha* rate; and *vatani* or *pálak rayatvár* that is hereditary proprietary under which hereditary officers such as the village headman or *pátíl*, the village accountant or *kulkarni*, the district superintendent or *deshmukh*, and the district accountant or *deshpánde*, held lands at something less than the usual rate of assessment.

Of other tenures were *makta khand* or contract sum, the holder under which paid a certain sum of money or a certain quantity of grain without reference to the usual rate of assessment; *kaul* or *istáva*, that is lease tenure, under which arable waste was given to be brought under tillage at a certain rent for a certain number of years, either unvarying under a simple *kaul* or gradually rising under an *istáva kaul* or increasing lease; *bhág jamin* or share-land under which the holder paid to the State half, one-third, or one-fourth of the produce of the land; *kardáva jamin* under which the holder was paid a fixed sum, while the land remained in the possession of the State which was responsible for its tillage; *sanadi jamin* or deed-land under which land was granted for service, but in the accounts was not shown in the grantee's possession but as a debit to service; *makta* or contract, under which villages were farmed for fixed amounts to be paid to the State without regard to the amount of revenue realised by the contractor who, however, had no authority to transfer or in any way dispose of the lands in the possession of permanent holders; *khoti* apparently originally lump sum under which the rents of a village were not collected from the individual holders, but in a lump from the contractor or *khot*, who, except lands in the possession of permanent holders, was allowed to transfer or in any other way dispose of village lands.

Besides the lands which came under these tenures, some were given for tillage by public auction to the highest bidder. In hilly tracts, under the system known as *kumri*, patches of land were tilled by landholders according to their convenience. After the crops were sown the patches were inspected by State servants with the aid of a jury

<sup>1</sup> As many of the alienations were held under doubtful titles, the necessity of inquiring into them was admitted at an early period of British management. The work of this inquiry was taken up by Major Graham the first Political Superintendent of Kolhápúr.



of respectable landholders and hereditary officers of the village to which the lands belonged, and part of the produce was fixed as the State share.

Besides the regular assessment, various taxes were imposed on the land. These cesses were generally called *pattis* and *bábtis*. When these extra taxes were first imposed, they were said to be for a time to meet some special State requirement; once introduced they were never abolished and continued permanent taxes blended with the ordinary land revenue.<sup>1</sup>

The revenue history of Kolhápúr falls under three periods. The first of 136 years between the establishment of the Kolhápúr State in 1708 and the direct interference of the British Government in 1844 when a State *kárbhári* or minister was appointed to administer the State; the second of twenty-three years between the appointment of a minister in 1844 and the introduction in 1867 of the regular revenue survey settlement; and the third is between 1867 and 1884.

Of the changes in the land management during the first period (1708 - 1844) little is known. Most of the old records have been either burnt or otherwise destroyed. From such sources of information as remain, it seems that in early times the arable lands of each village were divided into separate holdings and a rate fixed on each holding. In the beginning of the eighteenth century when Kolhápúr became the head-quarters of a separate Marátha State the system founded by Shiváji the Great was completely carried out. The affairs of the State were conducted by the prince with the aid of a council styled *ráymandal* of eight ministers or *ashtapradhán*. During this (1708 - 1844) period Kolhápúr was almost ceaselessly engaged in war with the neighbouring chiefs. No record of the condition of the people or of the country at that time has been traced. In theory the village constitution and the duties of the hereditary village officers were the same as they now are. In practice village officers had much more power than they have now. In the troubles and irregularities of those times there was no constant steady pressure of higher authority. The village officers were left to use their influence as they chose. They transferred lands without authority, changed village accounts to suit their purpose, and practised many forms of oppression and tyranny. The hereditary village officers were the sole managers of their villages, and the weal and woe of the landholding villagers rested in their hands. No uniform system for collecting the revenue was in force and the means employed in recovering arrears were generally oppressive and cruel. The lands

## Chapter VIII. The Land.

CESSSES.

REVENUE  
HISTORY,  
1708-1884.

1708-1844.

<sup>1</sup> The chief of these cesses, some of which were received in kind, were: *gavat veth*, a grass-cutting cess; *patil patti*, a tax on forage; *jone patti*, a tax on timber; *míráś patti*, a tax on hereditary land; *kot patti*, a fort tax; *urus* and *pir patti*, a fair cess; *sutlivár patti*, a contingent cess; *tupvargat*, a butter cess; *jhád patti*, a roadside tree cess; *taushi* and *bhopla patti*, a cucumber and gourd cess; a pondwater cess; a grain-carrying cess; *maslat patti*, a jury cess; *vargat patti*, a revenue cess; *tola patti*, a deficiency cess; *Rāngna patti*, a cess to keep up the Rāngna fort; *galla patti*, a grain cess; *jāgrī patti*, a sugar cess; a maize ear cess; and *mogham patti*, a vague cess. Some of these cesses are still (1884) levied in alienated and unsurveyed villages.

## Chapter VIII.

## The Land.

REVENUE  
HISTORY.  
1708-1844.

were divided into sixteen classes: *kálvat* or black; *khári* or brackish (soft); *máni* or blackish (hard); *támbola* or red (first sort); *támbad* or red (second sort); *mala* or land irrigated by a river; *mali* or alluvial land; *gerat* or black soil mixed with stones; *mál* or upland; *bhát* or rice; *malkat* or land situated at the village boundary; *barad* or rice ground left after yielding a crop of plantlets to rest for the next year; *regad* or black soil mixed with sand; *masár* or black; *bágáyat* or garden; and *chunkhad* or land mixed with mortar. The *bigha* rates of assessment varied from 7½d. to £3 1s. (5½ as. to Rs. 30½) for dry-crop lands, and from 8s. to £5 8s. (Rs. 4-54) for garden lands.<sup>1</sup>

Assured possession and enjoyment of land seems to have been unknown. The terms of *sanads* or land grants and other records seem to show that any land under whatever tenure it was held might be taken from its owner and granted to some one else. Instances are known in which hereditary holders of lands or *mirásdárs* were summarily ousted to make room for favourites of the prince or even of influential State servants. Lands were granted in *inám* or rent-free by a *mámlatdár* or even by hereditary village officers. Many land grants were made in return for presents or *nazars* of cash, horses, weapons, gardens, articles of curiosity, or other objects held in special

<sup>1</sup> The details are :

Kolhapur Dry-crop Bigha Rates.

Rs. a.	Rs. a.	Rs. a.	Rs. a.	Rs. a.	Rs. a.	Rs. a.	Rs. a.	Rs. a.
30 8	20 4½	15 10	13 0	10 12	8 7	6 6	4 14½	2 8
30 4	20 2	15 6½	12 12	10 10½	8 6	6 5½	4 14	2 4
28 12	20 0	15 4½	12 10	10 10	8 4	6 5½	4 11	2 0½
28 6	19 8	15 4	12 8	10 9	8 2	6 5	4 10	2 0
28 0	19 4	15 2	12 7	10 8½	8 0	6 4	4 8½	1 15½
27 0	19 0	15 1½	12 6	10 8	7 14	6 3½	4 8	1 13
25 0½	18 15	15 0	12 5½	10 6½	7 12½	6 2	4 6	1 12
25 0	18 14	14 12	12 4	10 6½	7 12	6 0	4 4	1 10
24 11	18 12	14 10½	12 3	10 4	7 11	5 14	4 2	1 8
24 8	18 10	14 8½	12 1½	10 0	7 8½	5 13½	4 1½	1 4
24 0	18 9	14 8	12 1	9 12	7 8	5 13	4 0	1 3
23 1	18 6½	14 6	12 0	9 9	7 7	5 12	3 14½	1 2
22 10	18 2	14 5	11 15½	9 8	7 4	5 11½	3 14½	1 0
22 9	18 0	14 0	11 15	9 6	7 2½	5 10½	3 12	0 15
22 8	17 10	13 12	11 12	9 5	7 2	5 10	3 10	0 12
21 12	17 8	13 10	11 8	9 4	7 1½	5 8½	3 8	0 10½
21 11	17 0	13 9½	11 7	9 1	7 0	5 8	3 6	0 8
21 10	16 15½	13 9½	11 5½	9 0½	6 15½	5 7½	3 5	0 6
21 9½	16 14	13 8	11 4½	9 0	6 13	5 7	3 2	0 6½
21 8	16 10	13 5	11 4	8 14½	6 12	5 6	3 0	0 5½
21 0	16 8	13 4	11 1½	8 12	6 11	5 4	2 14	...
20 10	16 2	13 2½	11 1	8 11	6 10½	5 2	2 13½	...
20 8	16 1½	13 2	11 0	8 10	6 10	5 1	2 13	...
20 7	16 0	13 1½	10 14	8 9½	6 9½	5 0½	2 12	...
20 4½	15 14	13 1	10 13	8 8	6 8	5 0	2 10	...

Kolhapur Garden Bigha Rates.

Rs.	Rs.	Rs.	Rs.	Rs.	Rs.
54	28	18	12½	10½	8½
50	25½	16½	12½	10½	8
48	25	15½	12	10½	7½
47	22½	15	11½	10	7
45	20½	14	11½	9	6
32½	20½	13½	11	8½	5
31½	20	13½	10½	8½	4
30	18½	12½	10½	8½	...

value by the prince. Several petty land grants were made by Sháháji or Báva Sáheb Maháráj between 1834 and 1837. The lands granted in *indám* were generally arable waste which the prince was anxious should be brought under tillage. As a rule no land was granted rent-free or on a quit-rent without a present or *nazar*. The land management was without system. The regular revenue constantly fell short of the State needs and special cesses had to be levied to make good the balance. Many departments were in charge of petty officers styled *mámlatdárs*, who had under their control a certain number of villages, the revenue of which they collected and applied to the expenditure of the departments with which they were entrusted.

The first change introduced by the State manager or *kárbhári* appointed by Government in 1844 was to reduce the number of the fiscal sub-divisions. The officers who, with the title of *mámlatdárs*, were placed in charge of these new groups, were ordered to work, as far as possible, in accordance with the system in force in British districts. Waste lands were gradually brought under tillage and material improvements were made in the system of settling and of collecting the State demands. Under Dáji Pandit (1844 - 1854) no change was made in the land tenures or in the rates of assessment. In 1862 it was found that in many cases landholders had larger areas of land than were shown in the accounts, that the lands were not properly classified, and that the rates of assessment were not fixed on any uniform system. These defects, combined with a great rise in grain prices, showed that a fresh survey and general revision of rates were necessary. In 1864 a rough measurement and classification of lands called *dágvári*, and revision of rates were begun by the State minister Rámráv. The work continued till 1866 when it was stopped by the death of the prince. The rates introduced under this survey varied from 6d. to £2 5s. (Rs.  $\frac{1}{4}$  - 22 $\frac{1}{2}$ ) a *bigha* in dry-crop lands and from 6s. to £4 7s. 6d. (Rs. 3 - 43 $\frac{3}{4}$ ) a *bigha* in garden lands.<sup>1</sup> The result of these revised rates was an increase in the revenue of about £17,500 (Rs. 1,75,000) or twenty-five per cent.<sup>2</sup>

## Chapter VIII.

## The Land.

REVENUE  
HISTORY.

1844-1867.

<sup>1</sup> The details are : Kolhápúr Dry-Crop Bigha Rates, 1864-1866.

Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	As.
22 $\frac{1}{2}$	15	11 $\frac{1}{2}$	10	8	6 $\frac{1}{2}$	5 $\frac{1}{2}$	3 $\frac{1}{2}$	2 $\frac{1}{2}$	1 $\frac{1}{2}$	10	
21 $\frac{1}{2}$	13 $\frac{1}{2}$	11	9 $\frac{1}{2}$	7 $\frac{1}{2}$	6 $\frac{1}{2}$	5	3 $\frac{1}{2}$	2 $\frac{1}{2}$	1 $\frac{1}{2}$	5	
18 $\frac{1}{2}$	12 $\frac{1}{2}$	10 $\frac{1}{2}$	8 $\frac{1}{2}$	7 $\frac{1}{2}$	6	4 $\frac{1}{2}$	2 $\frac{1}{2}$	2	1 $\frac{1}{2}$	4	
16 $\frac{1}{2}$	12 $\frac{1}{2}$	10 $\frac{1}{2}$	8 $\frac{1}{2}$	7	5 $\frac{1}{2}$	4	2 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	...	
15 $\frac{1}{2}$	11 $\frac{1}{2}$	10 $\frac{1}{2}$	8 $\frac{1}{2}$	6 $\frac{1}{2}$	5 $\frac{1}{2}$	3 $\frac{1}{2}$	2 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	...	

Kolhápúr Garden Bigha Rates, 1864-1866.

Rs.	Rs.	Rs.	Rs.
43 $\frac{3}{4}$	30	12	3
40	25	10	...
35	20	9	...
30 $\frac{1}{2}$	15	6	...

<sup>2</sup> Compared with 1862-63 the total land revenue collections in 1867-68 showed a rise from £70,077 (Rs. 7,00,770) to £89,878 (Rs. 8,98,780) or 28 $\frac{1}{2}$  per cent. Of this increase of nearly two *lákhs* of rupees, about 1 $\frac{1}{2}$  *lákhs* or £17,500 may be said to be due to the new rates.

## Chapter VIII.

## The Land.

REVENUE  
HISTORY.  
1867-1884.

Further experience of this *dágvári* survey showed that, though an improvement on the former state of affairs, it was not based on any scientific system or conducted by competent men. Colonel G. S. A. Anderson the Political Agent, himself an old survey officer, applied to Government to sanction the introduction of the regular revenue survey into the Kolhápúr territory; and his proposal was sanctioned in November 1867. Since then the survey has been carried on under the control and superintendence of the Survey Commissioner. Excepting Bhudargad all the sub-divisions have been surveyed and settled. Of the four feudatory States, Kágál and Ichalkaranji have been surveyed and settled, and the work is in progress in Vishálgad and Báyda. Most of the old forms of individual or *rayatvár* tenure have merged in the revenue survey tenure and extra petty taxes have ceased in those parts where this survey has been introduced and completed. The immediate results of the survey were the resumption of encroachments in alienated and other lands, and the occupation of arable waste, by which the revenue has been increased from year to year. Apart from the survey the revenue has also been increased by the resumption of alienations under the rules of the Alienation Inquiry. Compared with 1867-68, the collections in 1881-82 show an increase from £89,878 (Rs. 8,98,780) to £117,777 (Rs. 11,77,770) or a rise of thirty-one per cent.<sup>1</sup> The details of the survey settlement in each group are:

SURVEY.  
Ichalkaranji,  
1869-70.

In the Ichalkaranji feudatory state, survey measuring was begun in 1865 and finished in 1867 and classing was begun in 1868 and finished in 1869. The survey rates were introduced into eleven villages in 1869-70. They were arranged in six classes with highest dry-crop acre rates of 7s. 6d. (Rs. 3½) for Ichalkaranji; 6s. 6d. (Rs. 3¼) for four villages close to Ichalkaranji in the Panchganga valley; 5s. (Rs. 2½) for three villages, two of them beyond Nipáni and one near Ichalkaranji but not in the Panchganga valley; 4s. (Rs. 2) for one village to the west of Nipáni on the hills; 3s. 6d. (Rs. 1¾) for one village far away to the north-east and near the Tásgaon sub-division in Sátára; 2s. 6d. (Rs. 1¼) for one village far to the east and near the Athni sub-division in Belgaum. The collections in the first year of settlement £7062 (Rs. 70,620) showed an increase of 2·06 per cent over the collections £6919 (Rs. 69,190) of the year before the settlement. Under the survey rates the

<sup>1</sup> The details are :

Kolhápúr Land Revenue, 1846-1881.

YEAR.	Collections.	YEAR.	Collections.	YEAR.	Collections.	YEAR.	Collections.
	Rs.		Rs.		Rs.		Rs.
1846-47 ...	4,65,550	1855-56 ...	4,97,310	1864-65 ...	9,03,950	1873-74 ...	10,13,550
1847-48 ...	4,40,450	1856-57 ...	5,22,820	1865-66 ...	8,84,390	1874-75 ...	10,92,700
1848-49 ...	4,74,730	1857-58 ...	6,46,430	1866-67 ...	8,61,970	1875-76 ...	10,15,540
1849-50 ...	4,30,060	1858-59 ...	7,15,100	1867-68 ...	8,98,730	1876-77 ...	10,43,020
1850-51 ...	4,36,180	1859-60 ...	9,46,610	1868-69 ...	10,80,360	1877-78 ...	10,98,120
1851-52 ...	5,31,980	1860-61 ...	8,13,790	1869-70 ...	10,08,250	1878-79 ...	10,02,820
1852-53 ...	4,85,060	1861-62 ...	7,00,200	1870-71 ...	10,10,400	1879-80 ...	12,83,530
1853-54 ...	4,60,570	1862-63 ...	7,00,770	1871-72 ...	10,22,380	1880-81 ...	12,29,300
1854-55 ...	4,40,390	1863-64 ...	8,18,760	1872-73 ...	9,83,100	1881-82 ...	11,77,770

collections rose from £7062 (Rs. 70,620) in 1869-70 to £7421 (Rs. 74,210) in 1881-82. The details are :

*Ichalkaranji Revenue, 1868-1882.*

YEAR.	Collections.	YEAR.	Collections.
	Rs.		Rs.
1868-69 ...	69,193	1875-76 ...	71,329
1869-70 ...	70,616	1876-77 ...	70,550
1870-71 ...	71,205	1877-78 ...	71,977
1871-72 ...	71,085	1878-79 ...	72,418
1872-73 ...	70,838	1879-80 ...	73,392
1873-74 ...	71,267	1880-81 ...	75,049
1874-75 ...	71,394	1881-82 ...	74,212

## Chapter VIII.

### The Land.

#### SURVEY.

*Ichalkaranji,  
1869-70.*

In the Kágál feudatory State, survey measuring was begun in 1866 and finished in 1868 and classing was begun in 1868 and finished in 1869. Survey rates were introduced in 1870. Of forty-six villages thirty-four were State and twelve were alienated. They had an area of 82,390 acres or 129 square miles with 49,064 people or 380 to the square mile. The estate, chiefly the villages near Kágál and to the east of Belgaum-Kolhápúr road, was generally well placed for markets. The climate was generally good, but especially towards the west the rainfall was rather too heavy for good dry-crop tillage. The villages on the extreme west were rather rice than dry-crop villages, and the prevailing crop in them was *rági*. Under the survey settlement the villages were arranged in five classes. Three villages to the north-east of Kágál formed the first class with a highest dry-crop acre rate of 7s. (Rs. 3½); Kágál was placed in the second class with 6s. (Rs. 3); nineteen villages to the west and south-west of Kágál were placed in the third class with 5s. 6d. (Rs. 2½); eleven villages to the west and south-west of the third class formed the fourth class with a rate of 5s. (Rs. 2½); twelve villages in the extreme west and south-west of the estate formed the fifth class with a rate of 4s. 6d. (Rs. 2¼). For the rice land of all the villages a highest acre rate of 16s. (Rs. 8) was fixed, giving an average acre rate of 6s. 7½d. (Rs. 3¼). For garden lands highest acre rates of 12s. (Rs. 6) for well-water and 16s. (Rs. 8) for channel-water were fixed. Compared with the collections of 1868-69 the survey rental on the tillage area showed a fall from £5450 (Rs. 54,500) to £5328 (Rs. 53,280) or of 2.23 per cent. The details of the settlement are :

*Kágál,  
1870.*

*Kágál Survey Settlement, 1870.*

CLASS.	Villages.	Collections 1868-69.	Total Survey Rental.
		Rs.	Rs.
I ...	3	11,342	12,108
II ...	1	1300	2337
III ...	19	20,098	22,063
IV ...	11	7768	7794
V ...	12	13,993	11,386
Total ...	46	54,501	56,233

Under the survey rates the collections rose from £5144 (Rs. 51,440) in 1870-71 to £6191 (Rs. 61,910) in 1881-82 or 20.35 per cent. The details are :

## Chapter VIII.

## The Land.

## SURVEY.

*Kagal,  
1870.**Kagal Survey Results, 1870-1882.*

YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1870-71	51,440	1164	72,987	1876-77	54,335	1199	70,348
1871-72	52,243	896	72,474	1877-78	57,079	1218	67,523
1872-73	52,824	1141	71,987	1878-79	58,002	1232	66,580
1873-74	53,570	1167	71,144	1879-80	60,275	1268	64,304
1874-75	53,945	1159	70,760	1880-81	61,616	1233	63,001
1875-76	54,299	1087	70,509	1881-82	61,915	1233	62,703

*Alta,  
1870-71.*

In the Alta sub-division survey measuring was begun and finished in 1867-68 and classing was begun and finished in 1869-70. In 1870-71 survey rates were introduced in thirty-one State villages. Their area was 96,521 acres or 151 square miles and they had 67,664 people or 448 to the square mile. The villages had great natural advantages; they had a good climate, were fully peopled, and were within easy reach of trunk roads and good markets. The existing assessment was very unequal. Some villages paid rates double those of others though their soil was of the same quality. In many villages the pressure of the existing rates was severely felt and a good deal of arable land was waste. Under the survey settlement the thirty-one villages were arranged in two classes with highest dry-crop acre rates of 7s. 6d. (Rs. 3½) for nine villages and of 7s. (Rs. 3½) for twenty-two. For rice land of which there were only 362 acres, the highest acre rate was fixed at 18s. (Rs. 9). The rice land was of very indifferent quality and the average acre rate amounted to 5s. 7½d. (Rs. 2¼). The highest garden acre rate for well water was fixed at 13s. (Rs. 6½), and for lands watered partly by wells and partly by channel at 16s. (Rs. 8). Compared with the preceding year's collections the survey rental on the tillage area showed a decrease from £12,005 to £11,535 (Rs. 1,20,050 to Rs. 1,15,350) or 3·91 per cent. Under the survey rates the collections rose from £10,988 (Rs. 1,09,880) in 1870-71 to £13,128 (Rs. 1,31,280) in 1881-82. The details are:

*Alta Survey Results, 1870-1882.*

YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1870-71	1,09,876	1693	1,10,007	1876-77	1,17,790	5360	1,00,600
1871-72	1,11,446	1615	1,08,547	1877-78	1,22,746	5481	95,502
1872-73	1,12,363	4166	1,07,499	1878-79	1,26,101	3726	93,674
1873-74	1,13,444	4546	1,05,845	1879-80	1,27,975	4348	91,224
1874-75	1,15,248	4591	1,03,978	1880-81	1,30,780	4344	88,503
1875-76	1,16,613	4724	1,02,486	1881-82	1,31,277	4421	87,900

*Shirol,  
1870-72.*

In the Shirol sub-division survey measuring was begun in 1867-68 and finished in 1868-69 and classing was begun in 1869-70 and finished in 1870-71. Survey rates were introduced into a group of 20½ villages between 1870 and 1872. At the time of settlement these villages contained 59,495 acres or ninety-three square miles with 30,428 people or 327·18 to the square mile. Under the survey settlement they were arranged in two classes and charged highest dry-crop acre rates of 7s. 6d. (Rs. 3½) in 15½ villages and 7s. (Rs. 3½) in five villages. The highest garden acre rates were



17s. (Rs. 8½) for channel water and 15s. (Rs. 7½) for well water. Compared with the average collections of the ten previous years the survey rental on the tillage area showed an increase from £8174 (Rs. 81,740) to £9251 (Rs. 92,510) or a rise of 13·17 per cent. The following statement shows the collections between 1854 and 1882:

*Shirol Revenue, 1854-1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1854-55 ...	60,730	...	.....	1876-77 ...	1,00,531	5330	63,375
1868-69 ...	95,826	...	.....	1877-78 ...	1,05,321	4227	60,020
1871-72 ...	97,095	4153	67,580	1878-79 ...	1,05,951	4094	59,538
1872-73 ...	98,606	5102	66,099	1879-80 ...	1,07,429	4014	58,129
1873-74 ...	99,034	5135	65,648	1880-81 ...	1,08,437	3823	57,257
1874-75 ...	1,00,119	5133	64,540	1881-82 ...	1,10,417	3869	55,120
1875-76 ...	1,00,180	5345	64,209				

The Ráybág petty division of Shirol was settled in 1871-72. It contained sixteen State villages with an area of 75,039 acres or 117 square miles and 8296 people or 70·90 to the square mile. Under the survey settlement the villages were arranged in four classes with highest dry-crop acre rates varying from 5s. (Rs. 2½) to 2s. 6d. (Rs. 1¼). In the first class was placed one village which was detached from the rest of the tract and lay at the crossing of the Krishna on the Chikodi-Tásgaon road. For this village a highest dry-crop acre rate of 5s. (Rs. 2½) was fixed. Two villages to the east of the first class and in the west of the main tract formed the second class with a rate of 3s. 6d. (Rs. 1¾). Nine villages to the east of the second class and with a worse rainfall formed the third class with a rate of 3s. (Rs. 1½). Four villages in the extreme east and worst of all in point of rainfall formed the fourth class with a rate of 2s. 6d. (Rs. 1¼). Except Ráybág, none of these villages had much garden land. The highest garden acre rate was fixed at 13s. (Rs. 6½); and most of the watered fields were assessed at acre rates varying from 8s. to 10s. (Rs. 4 - 5). Compared with the average collections of the twenty years before, the survey rental on the tillage area showed an increase from £665 (Rs. 6650) to £1380 (Rs. 13,800) or a rise of 107·51 per cent, and compared with the preceding year's collections, an increase from £1246 (Rs. 12,460) to £1380 (Rs. 13,800) or a rise of 10·75 per cent. During the eleven years of the survey lease, the collections have risen from £1452 to £1815 (Rs. 14,520-18,150). The details are:

*Ráybág Survey Results, 1871-1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1871-72 ...	14,524	832	18,472	1877-78 ...	15,800	2342	15,197
1872-73 ...	14,766	881	18,199	1878-79 ...	12,439	6742	14,661
1873-74 ...	15,053	900	17,893	1879-80 ...	13,156	6980	14,016
1874-75 ...	15,619	784	17,436	1880-81 ...	14,993	5824	18,033
1875-76 ...	15,630	833	17,371	1881-82 ...	18,149	6063	9640
1876-77 ...	15,420	1414	17,005				

In Karvir survey measuring was begun in 1869 and finished in 1871 and classing was begun in 1872 and finished in 1879. Of 135 villages, one State village and twenty-six alienated villages have not

## Chapter VIII.

### The Land.

#### SURVEY.

*Shirol,  
1870-1872.*

*Ráybág,  
1871-72.*

*Karvir,  
1872-1883.*

## Chapter VIII.

## The Land.

## SURVEY.

Karvir,  
1872-1883.

been settled. The remaining 108 villages, ninety State and eighteen alienated, were settled between 1872 and 1883.<sup>1</sup> The State villages were settled in three groups: the first in 1872-73, the second in 1875-76, and the third in 1878-79. Of these the twenty-three State villages settled in 1872-73, lay immediately round Kolhápúr and included the lands of that city. This group contained 58,600 acres or ninety-two square miles and 65,022 people or 706·75 to the square mile.<sup>2</sup> The twenty-three villages were arranged in three classes and charged highest dry-crop acre rates varying from 8s. (Rs. 4) to 7s. (Rs. 3½). The town of Kolhápúr and the neighbouring villages were placed in the first class; villages a little further removed from Kolhápúr were put in the second class; and villages at a still greater distance from the town formed the third class. The details are:

*Karvir Survey Rates, 1872-73.*

CLASS.	HIGHEST ACRE RATE.			
	Dry Crop.	Rice.	Channel Water.	Well Water.
	Rs. a.	Rs. a.	Rs. a.	Rs. a.
I ...	4 0	9 0	10 0	6 8
II ...	3 12	8 0	10 0	6 8
III...	3 8	8 0	10 0	6 8

These rates were higher than those adopted for the Alta, Shirol, and Kágál sub-divisions. The increase was required as Kolhápúr and its immediate surroundings have an advantage over the villages of other sub-divisions in climate, communications, and market. Compared with 1870-71 the collections in 1881-82 showed a rise from £5795 (Rs. 57,950) to £7292 (Rs. 72,920) or an increase of 25·83 per cent. The details are:

*Karvir Revenue, 1850-1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1850-51 ...	26,780	...	...	1876-77 ...	58,385	9214	67,342
1870-71 ...	57,950	...	...	1877-78 ...	61,162	8965	65,076
1872-73 ...	58,000	7760	69,411	1878-79 ...	68,223	2789	64,104
1873-74 ...	58,710	7951	68,584	1879-80 ...	70,030	2850	62,318
1874-75 ...	58,659	8351	68,053	1880-81 ...	72,412	2535	60,206
1875-76 ...	58,601	8601	67,663	1881-82 ...	72,920	2400	59,635

These details show that during six years ending 1878 the rental of the arable waste increased from £776 (Rs. 7760) to £896 (Rs. 8960). This spread of arable waste was due to a series of bad seasons culminating in the 1876-77 famine. Since 1878 there has been steady improvement, and by 1882 the arable waste was reduced to one-third of what it was in 1872. The assessment of encroachments in alienated holdings has also materially contributed to the increase of collections in later years.

The second group of Karvir State villages, settled in 1875-76,

<sup>1</sup> State villages settled, twenty-three in 1872-73, seventeen in 1875-76, and fifty in 1878-79; alienated villages settled, one in 1880-81, three in 1881-82, and fourteen in 1882-83.

contained seventeen villages to the north and west of Kolhápúr and outside the circle of villages in the first group. The villages to the west of Kolhápúr were not so well placed as those in the first group either in climate or communications; the rainfall was heavier and the soil poorer, *rági* took the place of *juári* the staple dry grain of the plain. This second group contained 22,148 acres or thirty-five square miles, and 12,414 people or 354·68 to the square mile. The highest acre rates introduced by the survey in this group were: For six villages close to the city of Kolhápúr 8s. (Rs. 4) for dry-crop and 18s. (Rs. 9) for rice land, and for nine villages somewhat farther from Kolhápúr 7s. 6d. (Rs. 3½) for dry-crop and 18s. (Rs. 9) for rice land. An exceptional dry-crop rate of 4s. (Rs. 2) was fixed for the village of Jaital which lay on the high land south of Kolhápúr and was somewhat inaccessible for carts. The highest rice acre rate for this village was fixed at 14s. (Rs. 7). For Sandal, a part hill and part plain village, highest acre rates of 2s. 6d. (Rs. 1½) for dry-crop and 14s. (Rs. 7) for rice land were adopted. Compared with 1874-75 the collections at survey rates in 1881-82 showed a rise from £2788 (Rs. 27,880) to £3026 (Rs. 30,260) or an increase of 8·53 per cent. The details are:

*Karvir Revenue, 1854 - 1882.*

YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1854-55 ...	18,500	...	...	1876-79 ...	26,931	4644	23,901
1874-75 ...	27,876	...	...	1879-80 ...	28,099	4522	22,861
1875-76 ...	26,379	2787	26,059	1880-81 ...	29,700	3958	21,831
1876-77 ...	23,530	6111	23,794	1881-82 ...	30,262	3494	21,650
1877-78 ...	24,332	5909	24,702				

These details show that during the chief famine year (1876-77) the rental of arable waste rose from £279 (Rs. 2790) to £611 (Rs. 6110) and though since then the arable waste has steadily fallen the area is still (1882) in excess of what it was in 1875-76. The increase in collections is mainly caused by resumptions of encroachments in alienated holdings.

The third group of Karvir villages settled in 1878-79, contained fifty villages mostly to the south-west and west of Kolhápúr. These villages pass through every grade from excellent dry-crop villages in the Dudhganga and Bhogávati valleys to pure hill villages, where rice and *kumri* or wood-ash are the chief forms of tillage. These villages contained 55,380 acres or 86·5 square miles, and 24,190 people or 279·65 to the square mile. Under the survey settlement they were arranged in six classes with highest dry-crop acre rates varying from 8s (Rs. 4) to 4s. (Rs. 2). The details are:

*Karvir Survey Acre Rates, 1878-79.*

CLASS.	Villages	Highest Acre Rate.			CLASS.	Villages	Highest Acre Rate.		
		Dry Crop.	Rice.	<i>Kumri</i> or Wood- ash Tillage.			Dry Crop.	Rice.	<i>Kumri</i> or Wood- ash Tillage.
		Rs.	Rs.	Rs.			Rs.	Rs.	Rs.
I ...	1	4	9	1	IV ...	15	8	9	1
II ...	17	3½	9	1	V ...	11	2½	8	1
III ...	3	3½	9	1	VI ...	8	2	8	1

## Chapter VIII.

### The Land.

#### SURVEY.

*Karvir,  
1872-1882.*

## Chapter VIII.

## The Land.

## SURVEY.

*Karvir,*  
1872-1882.

Compared with 1875-76 the collections at survey rates in 1881-82 showed a fall from £5549 (Rs. 55,490) to £5441 (Rs. 54,410) or a decrease of 1.94 per cent. The details are :

*Karvir Revenue, 1856-1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1856-57 ...	31,278	...	...	1879-80 ...	51,496	2789	29,259
1875-76 ...	55,490	...	...	1880-81 ...	53,641	2194	27,545
1878-79 ...	49,921	3571	30,057	1881-82 ...	54,409	1782	27,270

*Panhála,*  
1872-1882.

In Panhála survey measuring was begun in 1868 and finished in 1871 and classing was begun in 1872 and finished in 1876. Of 204 villages, two deserted villages, eight suburbs of the Panhála fort, and twenty-six alienated villages were still unsettled in 1881-82. The remaining 168 villages, 160 State and eight alienated villages, were settled between 1875 and 1882.<sup>1</sup> The State villages were settled in four groups, one in 1875-76, a second in 1876-77, a third in 1877-78, and a fourth in 1878-79. The details are: The first or 1875 group contained thirty villages, some in the valleys of the Kasari and Várna rivers and some on the lofty Panhála range. The area of this group was 43,272 acres or 67.3 square miles with 24,878 people or 371.91 to the square mile. The highest acre rates introduced by the survey were: For the Kodoli village in the plain country of the Várna valley and for the two villages of Porla and Yavlujh on either bank of the Kasari river, a highest acre rate of 7s. 6d. (Rs. 3½) for dry-crop and 18s. (Rs. 9) for rice land; for eight villages in the Várna and Kasari valleys, but somewhat further removed from Kolhápúr and great lines of communication, a highest acre rate of 7s. (Rs. 3½) for dry-crop and 16s. (Rs. 8) for rice land; for six villages that lay more to the west and were on the Panhála range and had a heavier rainfall, 6s. (Rs. 3) for dry-crop and 16s. (Rs. 8) for rice land; for the hill villages of Ambávade and Bhadal on a spur of the Panhála range, 4s. (Rs. 2) for dry-crop and 14s. (Rs. 7) for rice; for eleven villages on the top of the Panhála range and at no great distance round Panhála itself, 2s. 6d. (Rs. 1¼) for dry-crop and 14s. (Rs. 7) for rice land. Though so far to the east these eleven villages were similar in their tillage to *ghát* or Mával villages, *náchni* being the staple dry-crop and rice tillage common. For hill villages their rates seem high. But, though very similar to hill villages, they had the advantage of a high road passing through the middle of them, an advantage very rarely enjoyed by villages in the hills near the Sahyádris. Except the hill villages and those on the flanks of the hills, the highest garden acre rate was fixed at £1 (Rs. 10) for channel-water and 13s. (Rs. 6½) for well-water. To meet the case of garden lands on rivers, watered by lifts from *budkis*, the Survey Commissioner allowed a

<sup>1</sup> State villages settled, thirty in 1875-76, sixty-five in 1876-77, seventeen in 1877-78, and forty-eight in 1878-79; alienated villages settled, three in 1877-78 and five in 1881-82.

proportionate reduction for each lift down to the fourth and at the fifth left the assessment at the full dry-crop rate. In the hill villages the highest garden acre rate was fixed at 9s. (Rs. 4½) for well water and 14s. (Rs. 7) for channel-water. In very little land does the actual rate exceed half of this amount. In a few villages in this group, while the village itself was well placed in the plain, it had a hamlet or *majra* whose lands were somewhat inaccessible. In such cases the lands of the hamlets were grouped with the hill villages. Compared with 1874-75 the collections at survey rates in 1881-82 showed a rise from £3674 (Rs. 36,740) to £5250 (Rs. 52,500) or an increase of 40·28 per cent. The increase was chiefly due to the reduction of alienations. The details are :

*Panhála Revenue, 1874-1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1874-75 ...	36,742			1878-79 ...	42,071	3572	33,758
1875-76 ...	40,920	2947	36,460	1879-80 ...	45,287	2434	32,568
1876-77 ...	40,003	3592	36,139	1880-81 ...	46,779	2195	31,906
1877-78 ...	42,598	3490	34,217	1881-82 ...	52,504	1996	25,754

The second or 1876 group contained sixty-five villages, some in the valleys of the Kasari and Kumbhi rivers and some in the valley of the Várna river north of the Panhála range. All the State villages of north-west Panhála were included in this group. They covered an area of 69,385 acres or 108 square miles and had 22,852 people or 211·59 to the square mile, all of them agricultural. Under the survey settlement the sixty-five State villages were arranged in seven classes with highest dry-crop acre rates varying from 7s. (Rs. 3½) to 2s. 6d. (Rs. 1¼). The highest rate was for good dry-crop villages on the open plain and in the valleys of the rivers, and the lowest for a hill village on a spur of the Panhála hills. A uniform highest acre rate of 16s. (Rs. 8) was adopted for rice tillage. The more westerly villages had some disadvantage in communication, but this disadvantage was modified by the higher value of rice in proportion to bulk compared with dry-crop produce. The acre rates adopted for the garden lands generally were £1 (Rs. 10) for channel-watered lands and 13s. (Rs. 6½) for well-watered lands. In a few cases 14s. (Rs. 7) the acre were levied on the better class of well-gardens. The details are :

*Panhála Survey Rates, 1876-77.*

CLASS.	VILLAGES.	HIGHEST ACRE RATE.		AVERAGE ACRE RATE ON OCCUPIED LAND.		
		Dry Crop.	Rice.	Dry-Crop.	Rice.	Garden.
		Rs.	Rs.	Rs. s. p.	Rs. s. p.	Rs. s. p.
I ...	15	3½	8	1 5 6	4 3 1	5 11 5
II ...	16	3	8	0 14 9	4 6 11	5 14 5
III ...	6	2½	8	0 9 7	4 10 1	5 7 7
IV ...	16	2	8	0 8 3	4 8 3	4 14 11
V ...	9	1½	8	0 4 5	4 11 2	4 8 5
VI ...	2	1½	8	0 2 11	4 5 1	...
VII ...	1	1½	8	0 8 3	5 2 7	...
Total ...	65	...	...	0 11 5	4 6 8	5 10 6

## Chapter VIII.

## The Land.

## SURVEY.

*Panhála,  
1875-1882.*

## Chapter VIII.

## The Land.

## SURVEY.

*Panhála,*  
1875-1882,

Compared with 1874-75 the collections at survey rates in 1881-82 showed a rise from £4971 (Rs. 49,710) to £5819 (Rs. 58,190) or an increase of 17·05 per cent. The increase is partly due to resumption of alienated lands. The details are :

*Panhála Revenue, 1855 - 1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1855-56 ...	26,733	...	...	1878-79 ...	48,732	9318	30,625
1874-75 ...	49,715	...	...	1879-80 ...	50,126	9031	29,464
1876-77 ...	50,850	4612	33,100	1880-81 ...	52,937	7621	28,066
1877-78 ...	48,662	8620	31,832	1881-82 ...	53,137	6890	23,496

The third or 1877 group contained seventeen villages mostly either on or to the north of the Kasari river. They covered an area of 37,487 acres or fifty-nine square miles and had 8987 people or 150·62 to the square mile. Under the survey settlement the seventeen villages were arranged in six classes with highest dry-crop acre rates varying from 7s. (Rs. 3½) to 3s. (Rs. 1½). The highest acre rate for rice land was fixed at 2s. (Rs. 1) and for *kumri* or wood-ash tillage at 1s. (8 as.). Compared with 1875-76 the collections at survey rates in 1881-82 showed a rise from £1600 (Rs. 16,000) to £1897 (Rs. 18,970) or an increase of 18·56 per cent. The details are :

*Panhála Revenue, 1856 - 1882.*

YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collections.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1856-57 ...	10,333	...	...	1879-80 ...	15,276	5013	5636
1875-76 ...	16,000	...	...	1880-81 ...	17,916	2670	5637
1877-78 ...	16,832	3051	6408	1881-82 ...	18,970	2502	4738
1878-79 ...	15,450	4684	6190				

The fourth or 1878 group contained forty-eight villages generally to the west of the Panhála sub-division. They covered an area of 106,814 acres or 167 square miles and had 17,125 people or 102·54 to the square mile. The population was distributed with very unequal density, being much thicker in the eastern villages than in those near and on the Sahyádris. Under the survey settlement these villages were arranged in six classes with highest dry-crop acre rates varying from 7s. (Rs. 3½) to 2s. 6d. (Rs. 1½). The details are :

*Panhála Survey Rates, 1878-79.*

CLASS.	Villages	Highest Acre Rate.			CLASS.	Villages	Highest Acre Rate.		
		Dry Crop.	<i>Kumri</i> or Woodash Tillage.	Rice.			Dry Crop.	<i>Kumri</i> or Woodash Tillage.	Rice.
		Rs.	Rs.	Rs.			Rs.	Rs.	Rs.
I ...	4	3½	1	9	IV ...	2	2	1	3
II ...	7	3	1	9	V ...	11	1½	1	7
III ...	4	2½	1	8	VI ...	20	1½	1	6

Compared with 1875-76 the collections at survey rates in 1881-82



showed a fall from £2158 (Rs. 21,580) to £2118 (Rs. 21,180) or a decrease of 1·85 per cent. The details are :

*Panhála Revenue, 1856 - 1882.*

YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.	YEAR.	Collec- tions.	Waste Rental.	Alienated Revenue Adjusted.
	Rs.	Rs.	Rs.		Rs.	Rs.	Rs.
1856-57 ...	11,929	...	...	1879-80 ...	15,129	15,439	7623
1875-76 ...	21,576	...	...	1880-81 ...	19,190	12,904	6993
1878-79 ...	15,644	14,715	7832	1881-82 ...	21,182	11,345	5627

In Gadinglaj survey measuring was begun in 1874-75 and finished in 1878-79 and classing was begun in 1878-79 and finished in 1879-80. In 1880-81 survey rates were introduced in fifty-four State villages with an area of 87,297 acres or 136 square miles with 40,428 people or 297 to the square mile. Under the survey settlement these villages were arranged in four classes with highest dry crop acre rates varying from 7s. (Rs. 3½) to 4s. 6d. (Rs. 2¼). The details are :

*Gadinglaj Survey Rates, 1880-81.*

CLASS.	VILLAGES.	HIGHEST ACRE RATE.	
		Dry Crop.	Rice.
		Rs. a.	Rs. a.
I. ...	23	3 8	10 0
II. ...	16	3 0	9 0
III. ...	11	2 10	9 0
IV. ...	4	2 4	9 0

Compared with the preceding year's collections the survey rental on the tillage area showed an increase of £5790 (Rs. 57,900) or two per cent.

The following is a summary of the chief available season details during the fourteen years ending 1862 and the nine years ending 1882 :

In 1849 the season on the whole was favourable. The early rainfall was rather scanty, but the late rain was excessive in some parts injuring the crops. The outturn both of the early and late crops, rice, *javári*, *bájri*, gram, peas, cotton, and tobacco, was good.

In 1850 the season on the whole was much below the average. The rainfall between June and September was unseasonable, and except those on black soil the crops were much injured. Copious rain in October did much good.

In 1851 the rainfall was sufficient and the harvest good. Heavy rain in October did some damage to the crops on low grounds and on the banks of rivers.

In 1852 the season was on the whole an average season. Except in the Gadinglaj sub-division, the rainfall was excessive. Up to the middle of September forty-one inches of rain fell. The early harvest was good, but owing to heavy falls in October the late crops were injured. Public health on the whole was good.

## Chapter VIII.

### The Land.

#### SURVEY.

*Panhála,  
1875-1882.*

*Gadinglaj,  
1880-81.*

#### SEASON REPORTS.

*1849.*

*1850.*

*1851.*

*1852.*

## Chapter VIII.

## The Land.

## SEASON REPORTS.

1854.

In 1853, except in the Bhudargad and Gadinglaj sub-divisions and the Bávda state, the rainfall was insufficient. The early harvest was half the average and the late crops were poor.

In 1854 the season was on the whole an average season. Except in Alta and Shirol the early rain was sufficient. Heavy falls in October injured the late crops, chiefly millets, gram, cotton, and tobacco. Grain prices rose in June but fell in the harvesting season. During the latter part of the rainy season small-pox and diarrhoea prevailed in Kolhápúr town and suburbs. Otherwise public health was good.

1855.

In 1855 in June July and August the rainfall was very scanty in Shirol, Alta, and Gadinglaj. Wells and streams dried and rice, *náchni*, *sáva*, sugarcane, *tur*, tobacco, and cotton entirely failed. Grain rose very high and the poorer classes were in great distress. Fears of scarcity were somewhat allayed by slight showers in September and October. In other parts of the Kolhápúr State the rainfall was sufficient and in some of the Bávda villages near the Sahyádris the rain was so heavy as to damage the rice and *vari*. Heavy showers in October did much good to all cold weather crops except tobacco and *bájri* which were beaten down. Public health was good.

1856.

In 1856 the rainfall was sufficient, the harvest full, and grain cheap. Cholera prevailed in July and August.

1857.

In 1857 the season on the whole was half the average. The early rains were sufficient, but owing to scanty late rainfall the late crops suffered. Cholera prevailed in June and July.

1858.

In 1858 the rainfall was scanty in some parts and heavy in others and the crops suffered. In Alta and Shirol the young rice plants and other crops were eaten by insects.

1859.

In 1859 the season was on the whole favourable. Some injury was done to sugarcane by a disease called *lakhia*.

1860.

In 1860, except for garden crops, the rainfall was sufficient. Cholera prevailed in August and September.

1861.

In 1861 the season on the whole was above the average. Between August and October cholera prevailed, and in one month out of 200 cases more than half the number proved fatal.

1862.

In 1862 the early rainfall was sufficient. The late rains were abundant and the late crops were above the average. Between July and October cholera of a mild type prevailed in Kolhápúr and Ajra.

1874.

In 1874 the rainfall was unfavourable for the early crops, but heavy enough for the late crops. Out of a demand of £89,650 (Rs. 8,96,500), £86,833 (Rs. 8,68,330) were collected, £20 (Rs. 200) remitted, and £2797 (Rs. 27,970) left outstanding.

1875.

In 1875 the early crops suffered from want of rain and the late crops from heavy rains in the middle of the cold season. Cholera and small-pox prevailed, and out of 127 persons attacked, fifty-eight died. Out of a demand of £91,052 (Rs. 9,10,520),

£86,977 (Rs. 8,69,770) were collected, £24 (Rs. 240) remitted, and £4051 (Rs. 40,510) left outstanding.

## Chapter VIII.

## The Land.

## SEASON REPORTS.

1876-77.

In 1876 the season was very unfavourable. Both the early and late crops in great measure failed. Shirol suffered most, in it scarcely a field yielded. Cholera twice broke out and public health was not good. Out of a demand of £93,055 (Rs. 9,30,550), £82,946 (Rs. 8,29,460) were collected, £32 (Rs. 320) remitted, and £10,077 (Rs. 1,00,770) left outstanding.

1877-78.

In 1877 the rainfall was abundant but unseasonable, considerably damaging the late crops. Cholera was severe. Out of a demand of £98,537 (Rs. 9,85,370), £91,555 (Rs. 9,15,550) were collected, £131 (Rs. 1310) remitted, and £6851 (Rs. 68,510) left outstanding.

1878-79.

In 1878 the rainfall was 50.65 inches. Cholera prevailed and public health was not good. In 1878 *javari* and *bajri* prices were double and wheat prices four times those of 1875. Compared with 1876 and 1877 rice was somewhat cheaper. The high prices were due to the small local stock. Out of a demand of £99,025 (Rs. 9,90,250), £93,880 (Rs. 9,38,800) were collected, £42 (Rs. 420) remitted, and £5103 (Rs. 51,030) left outstanding.

1879-80.

In 1879 the rainfall was seasonable and favourable and the harvest good. Rice suffered a little from want of rain and *javari* from blight. Public health was good. Out of a demand of £102,444 (Rs. 10,24,440), £97,795 (Rs. 9,77,950) were collected, £62 (Rs. 620) remitted, and £4587 (Rs. 45,870) left outstanding.

1880-81.

In 1880 the rainfall was below the average. It was not well distributed and the crops suffered. The harvest was poor, but grain prices fell. Public health was good. Out of a demand of £111,691 (Rs. 11,16,910), £104,508 (Rs. 10,45,080) were collected, £42 (Rs. 420) remitted, and £7141 (Rs. 71,410) left outstanding.

1881-82.

In 1881 the rainfall was very short. The wells did not fill and the rivers were unusually low. This affected the well and canal irrigation and materially reduced the area under sugarcane, the most important crop. The harvest on the whole was fair, rice yielding about a half and *javari* gram and wheat about a three-quarters crop. The markets were well supplied with grain and prices remained low throughout the year. Public health was not good. Cholera and cattle disease prevailed, and hundreds of cattle died. Out of a demand of £112,852 (Rs. 11,28,520), £109,287 (Rs. 10,92,870) were collected, £112 (Rs. 1120) remitted, and £3453 (Rs. 34,530) left outstanding.

1882-83.

In 1882 the early harvest was on the whole fair, but the late crops were far from favourable. In October, locusts partially destroyed the early crops in some places and the want of the usual October storms and rainfall greatly damaged the late crops. Public health was not good. Cholera, whooping cough, and measles prevailed.

## CHAPTER IX.

## JUSTICE.

## Chapter IX.

## Justice.

## CIVIL JUSTICE.

Before 1845.

BEFORE 1845 when it came under British superintendence, Kolhápúr had no regular courts for administering justice. In rural parts civil justice was administered by the *pátíl* or headman and in towns by other higher revenue officers. A complaint being made, the *pátíl* with the help of the *kulkarni* or accountant tried to settle the dispute amicably. If they failed, the dispute was referred to a *pancháyat* or jury. The higher revenue officers also followed the same system. The disputes usually referred to the *pancháyat* were about boundaries, lands, inheritance, and succession.

*Pancháyat.*

The jurisdiction of the *pancháyat* was solely based on the consent of the contending parties. The word literally signifies a 'jury of five' but as a fact there was no limit to the number of members. Sometimes a whole village constituted itself as a *pancháyat* and sometimes the proceedings were conducted under the supervision of a State officer. The first step was to take the *rājindmās* or agreements of the parties to submit the dispute to arbitration. Then followed their *karindās* or statements of their respective cases. The parties were also made to enter into security bonds or *jāmin-katbās* binding themselves to abide by the decision of the *pancháyat*. The court sometimes examined the parties. It received all the evidence both documentary and oral and accepted as evidence letters from absent witnesses. It then decided the matter according to the custom of the country on the evidence before it. Sometimes resort was had to ordeal. For instance the dispute was ended by one of the parties taking out a piece of iron from boiling oil, or by one of the disputants being taken out of the waters of a sacred river. Generally the *pancháyat* held its sittings in a sacred place such as the temple of the village god and in important cases it went to a place noted for its special sanctity. The proceedings of the *pancháyat* were often reduced to writing and contained a summary of the pleadings and evidence and ended with the verdict. This paper is known under the various names of *pancháyatndma*, *nivádáputra*, or *mahajar*; sometimes the party defeated passed a document to the winner which was called a *khutpatra*<sup>1</sup> in which he admitted his defeat and agreed not to molest the winner in future. The award of the *pancháyat* was generally willingly submitted to, but in cases where it was necessary to execute it by force the State officer obtained execution for the successful party by issuing the necessary orders and even royal mandates or *ājnápátras* were issued for the purpose.

<sup>1</sup> The word *khutpatra* literally means a letter of end and was so named because it

Refusal to submit a matter to a *pañcháyat* was looked upon as an indication of fraud and the party who refused to submit his dispute to the *pañcháyat*, or having agreed to do so did not put in his appearance before it, lost his case. Generally the decision was final but in exceptional cases a new trial was allowed. This system of administering justice though open to many objections was popular with the people and satisfied their wants so long as the disturbed state of the country and the weakness of the government tended to preserve a strong communal feeling among the village communities, and the potent voice of the village elders was universally respected.

In administering criminal justice the *pañcháyat* was rarely employed. In villages the *pátíl* took cognizance of small offences such as petty thefts, abusive language and simple hurt, and, having examined the parties and witnesses orally, either punished the offender with a small fine, or put him into the stocks, or sometimes imprisoned him in the village *chávdi*. Above the *pátíl* was the *kamávísḱár* or *mámlatḱár* who investigated into murders, dacoities, and robberies and submitted the proceedings for final disposal to the *huzur* or Rája's court. Sometimes these cases were handed over to the *nyáyáḱhish*.

The chief offences were treason, murder, dacoity, robbery, adultery, theft, and hurt. The usual forms of punishments were death, mutilation, imprisonment, and fine. Of these fine was most common. There was hardly any offence which could not be punished with simple fine. Sometimes murderers were compelled to make compensation to the family of the victim. Land thus given in compensation was called *khunkat*.<sup>1</sup> Mutilation was generally inflicted on women for adultery. There were no regular prisons, but offenders were confined in forts, and in Kolhápur itself there were cells in the centre of the city near Rankoba's temple. Prisoners were dieted on unwholesome food. Death was inflicted in various ways, by hanging, beheading, blowing from a gun, throwing off a precipice, trampling under an elephant's foot, or by *sul* or impalement. In 1821 the Mohite who attacked and murdered the Rája Ába Sáheb was trampled under an elephant's foot. Execution by *sul* consisted in impaling the offender on an iron stake fixed upright in the ground. Besides these there was a punishment called *dhind káḱhne* which was considered most ignominious. It consisted in making a man ride on an ass with his face which was besmeared with lampblack, towards the tail, and parading him in this condition through the town or village with the accompaniment of a drum. He was expelled from the town or village. In the absence of definite rules much was left to the discretion or rather the whim of the individual officer and sometimes punishments were accompanied with various cruelties.

The *jágirdárs* and inferior *sardárs* and *inámdárs* exercised both civil and criminal jurisdiction within their *jágirs*, *saranjáms*, and *ináms*. Their jurisdiction varied according to their position in the *Darbár*, the highest being empowered to inflict even death.

## Chapter IX.

## Justice.

## CIVIL JUSTICE.

Before 1845.

*Pañcháyat*.CRIMINAL  
JUSTICE.

Before 1845.

<sup>1</sup> *Khunkat* also applies to grants made by the State to destitute relations of the

## Chapter IX.

## Justice.

CRIMINAL  
JUSTICE.

Before 1845.

When the territories surrounding the Kolhápúr State came under British control the neighbourhood of a strong and just power began to have some influence on the judicial administration of the State. For in 1825 it appears that the reigning Rája was advised by Mr. Baber, the then Principal Collector of the Southern Marátha Country, to appoint a *shástri* and a *kázi* to whom all disputes were to be submitted for adjudication. He was instructed that though he might remove them for misconduct he should not otherwise interfere with them. After this event the *nyáyádhish* appears to have regained some of his lost influence as his decisions latterly appear to be more frequent. In 1842 *sati* or widow-immolation was abolished and in 1843 the sale of children prohibited. About 1844-45 when the State came under British superintendence, judicial administration was very badly conducted. In 1845 the late Mr. Reeves described it thus: 'The judicial system of Kolhápúr though founded on the ancient Hindu institute has been administered in such a manner as to leave room for injustice and oppression of every sort. The administration of justice has evidently depended entirely on the caprice of a few irresponsible agents at the *huzur*. In the districts the *mámlatdárs* have been all-powerful and below them again the *pátils*. The government has at the same time been so inefficient and weak that it may be safely asserted that the village townships, those indestructible atoms of which the Hindu policy is made up, have alone prevented it from falling to pieces.'

## CHANGES.

1848.

For about four years after Kolhápúr came under British superintendence, *mámlatdárs* as before were allowed to try civil and criminal cases. In 1848 three regular civil courts were established, two for *munsifs* and one for a *sadar amin*. The *munsifs* had power to try suits up to £500 (Rs. 5000) and the *sadar amin* up to £1000 (Rs. 10,000). Against their judgment appeal lay to the Political Superintendent and a final appeal to Government. As regards the criminal administration the *mámlatdárs* of the six sub-divisions or *petás* and the *kárbháris* or managers of Báyda Vishálgad and Kágál had power to award sentences of fine up to £5 (Rs. 50) and of imprisonment for not more than three months. In the city of Kolhápúr the court of the *nyáyádhish* or Judge had power to fine up to £20 (Rs. 200) and to imprison up to three years, and the *kotwál* or city magistrate tried petty criminal cases with power to fine up to £2 10s. (Rs. 25) and imprison up to thirty days. The highest criminal court was that of the Political Superintendent assisted by assessors who also heard appeals from the decisions of the inferior courts. The Political Superintendent had powers similar to the Sessions Judge in British districts. There were no definite laws on any subject but the courts were guided by the spirit of the Bombay regulations unless they were found to conflict with the established customs of the State. For instance in the execution of the decrees of civil courts no house required for the residence of a judgment-debtor was liable to sale unless it had been specifically assigned as security for payment of the decreed debt and declared by the court as liable to sale; no lands on any account were liable to sale and further no judgment-



the decreed debt. The jurisdiction of the *jágirdárs* was retained but they were not allowed to pass sentences of death or imprisonment for more than ten years; besides they were required to report the more heinous offences to the Political Superintendent.

This state of things continued up to 1862 when Shiváji or Bába Sáheb Mahárája was placed in charge of the administration of the State. This made certain changes necessary. The *nyáyádhish* or Native Judge was allowed to pass sentences up to seven years but sentences in excess of three years were subject to confirmation by the Mahárája. Appeals against the decisions of the inferior civil and criminal courts lay to His Highness the Mahárája who was also empowered to pass any sentence up to death; but sentences of death required Government confirmation. The Mahárája's decisions in civil suits were not open to appeal. By the agreement which was entered into between the Mahárája and the British Government the jurisdiction of the principal *jágirdárs* was limited to seven years' imprisonment and cases requiring capital punishment and imprisonment for more than seven years were to be sent up to the Political Agent<sup>1</sup> for submission to Government. In 1866 owing to the death of Shiváji the British Government resumed the administration of the State and the system of judicial administration was remodelled.

## Chapter IX.

## Justice.

## CHANGES.

1862.

In 1867 the *nyáyádhish* was invested with the following powers. In civil suits of the nature of small causes and not exceeding £50 (Rs. 500), one appeal was allowed from the subordinate courts to the *nyáyádhish*. In the other suits tried by the subordinate courts an ordinary appeal was allowed to the *nyáyádhish* and a special appeal to the Political Agent. Suits above £1000 (Rs. 10,000) were tried originally in the *nyáyádhish's* court with an appeal to the Political Agent. In criminal matters the *nyáyádhish* had the powers of a District Magistrate for the whole territory. He was also invested with the powers of an Assistant Sessions Judge and allowed to try cases which the Political Agent might refer to him. The Assistants to the Political Agent were also empowered to exercise powers of Assistant Sessions Judges and in civil matters to try appeals referred to them by the Political Agent. About this time the Indian Penal Code and the Criminal Procedure Code (Act XXV of 1861) were introduced. Under this Act the *mámlatdárs* were made second class sub-magistrates and their powers of punishment were reduced from three months to one month. Though the Penal Code was introduced adultery by a woman was punished with mutilation as formerly.

1867.

In 1873 the then new Criminal Procedure Code, Act X. of 1872, was introduced. Under this Act the *mámlatdárs* were invested with powers of a second class magistrate and could inflict imprisonment for six months and fine up to £20 (Rs. 200).

1873.

<sup>1</sup> On the transfer of the administration to the Rája the designation of the political officer attached to the Court was changed from Political Superintendent to Political Agent.

## Chapter IX.

## Justice.

## CHANGES.

1874.

In the beginning of 1874 two new officers called the District Officers were appointed and they were invested with the powers of a first class magistrate and placed each in charge of a division of the State. In 1879 the Code of Civil Procedure, Act VIII of 1859, was introduced but the old practice in the execution of decrees, as stated above, was retained. The State *kārbhāri* was invested with the powers of an assistant judge in civil and criminal matters.

1882.

Before 1882 when the Regency Council was formed, the Political Agent had the powers generally exercised by the British High Court. From 1882, the Regent in Council has been the final court of appeal and revision. At present (1883), as regards civil administration Kolhāpur has nineteen courts, one of the Regent in Council, one of the Chief Judge, one of the assistant judge, one of *sadar amin*, and fifteen of *munsifs*. The Chief Judge has the powers of a District Judge and his assistant those of an assistant judge. The *sadar amin* has powers to try suits up to £1000 (Rs. 10,000). Of the fifteen *munsifs* seven are stipendiary and the rest honorary; two belong to Kolhāpur proper and the rest to dependent *jāgirs* and *saranjāms*. Of the stipendiary *munsifs* two are at Gadinglaj and Shirol. The *munsifs* have powers to try suits of not more than £500 (Rs. 5000). The joint officer at Katkol has power to try suits of not more than £2 10s. (Rs. 25).

For the purposes of criminal administration Kolhāpur has forty courts, one of the Regent in Council, one of the Chief Judge, one of the assistant judge, four of first class, twenty-one of second class, and twelve of third class magistrates. Besides these the chiefs of Bāvda and Kāgal have powers to imprison up to seven years.

During the minority of *jāgirdārs* their *kārbhāris* have the powers of a *māmlatdār* and a *munsif*. On attaining majority the *jāgirdārs* are given judicial powers varying with individual ability and intelligence. At present (1883) except Bāvda and Kāgal, all *jāgirdārs* have the powers of a second class magistrate in criminal cases and those of a *munsif* in civil cases.

CIVIL COURTS,  
1877-1883.

Original Suits.

During the seven years ending 1883 the number of suits decided varied from 3614 in 1882 to 3153 in 1879 and averaged 3412. Of these the number of regular suits varied from 2699 in 1883 to 2198 in 1879 and averaged 2473; and the number of ex-parte decisions varied from 533 in 1879 to 426 in 1880 and averaged 481. During the same seven years the yearly value of suits decided varied from £36,290 in 1883 to £27,029 in 1879 and averaged £30,622; and the average value of each suit decided varied from £10 6s. (Rs. 103) in 1883 to £7 16s. (Rs. 78) in 1877.

Of 3521 suits disposed of during the year 1883, 160 were for the possession of land, 151 were otherwise connected with land, seventeen were for *haks* or perquisites, and 3193 for debts and movable property. Of these suits two were valued above £1000, one between £1000 and £500, twelve between £500 and £250, eleven between £250 and £100, forty-two between £100 and £50, seventy-nine between £50 and £30, 393 between £30 and £10, 686 between £10

During the seven years ending 1883 the number of appeals disposed of in the subordinate appellate courts varied from 243 in 1882 to ninety-two in 1881 and averaged 172. Of 172 appeals disposed of in 1883 thirty-four were decreed for appellants, ninety-five for respondents, twenty-five were remanded, eight dismissed on default, five adjusted or withdrawn, four amended, and one otherwise disposed of. During the same seven years the number of appeals and special appeals disposed of by the Regent in Council and the Political Agent varied from eighty-five in 1880 to six in 1877 and averaged forty-one; the balance of these appeals at the close of the year the 31st of March varied from 108 in 1878 to twenty-four in 1883 and averaged sixty. Since 1879, owing to the introduction of Act VIII of 1859 which prohibits special appeals on questions of fact, the number of special appeals has notably decreased, the fall in 1880 being thirty-three against ninety-six in 1879.

During the seven years ending 1883 the number of applications for execution of decrees disposed of varied from 2861 in 1881 to 2027 in 1878 and averaged 2401. Of 2629 applications disposed of in 1883, 614 were by private settlement, 1578 by execution of decrees, and 437 were dismissed owing to non-appearance of applicants. The following statements show in tabular form the working of the civil courts during the seven years ending 1883:

*Original Civil Suits, 1877-1883.*

YEAR.	Pending on 1st April.	Instituted during the year.	Received by transfer, &c.	Total.	Decided on merits.	Dismissed on default.	Adjusted or withdrawn.	Referred to other courts.	Otherwise disposed of.	Total.	Balance on 31st March.
1877 ...	531	3908	48	4487	2568	502	529	1	...	3600	887
1878 ...	887	2917	42	3846	2417	506	308	119	...	3410	436
1879 ...	436	3147	36	3619	2198	533	414	8	...	3153	466
1880 ...	510	3267	28	3805	2467	426	447	6	...	3346	459
1881 ...	459	3458	31	3948	2366	474	401	...	...	3241	707
1882 ...	707	3722	61	4490	2599	454	458	103	...	3614	876
1883 ...	876	3504	99	4479	2699	474	344	4	...	3521	938

*Value of Suits, 1877-1883.*

YEAR.	Suits.	Value of Suits.		YEAR.	Suits.	Value of Suits.	
		Total.	Average.			Total.	Average.
1877 ...	3600	£ 23,100	£ s. 7 16	1881 ...	3241	£ 27,331	£ s. 8 8
1878 ...	3410	31,837	9 6	1882 ...	3614	34,734	9 12
1879 ...	3153	27,029	8 11	1883 ...	3521	36,290	10 6
1880 ...	3346	29,033	8 13				

*Subordinate Appeals, 1877-1883.*

YEAR.	Pending on 1st April.	Instituted during the year.	Received by transfer.	Total.	Decreed for appellant.	Decreed for respondent.	Remanded.	Dismissed on default.	Adjusted or withdrawn.	Amended.	Otherwise disposed of.	Total.	Balance on 31st March.
1877 ...	31	226	...	257	48	90	24	13	...	3	...	178	70
1878 ...	79	194	...	273	60	135	20	13	...	6	...	236	37
1879 ...	37	153	...	190	30	91	20	12	...	1	1	155	35
1880 ...	40	146	...	186	28	71	14	7	...	2	1	126	60
1881 ...	60	190	...	250	22	40	13	7	...	7	...	92	158
1882 ...	158	175	...	333	47	138	23	6	...	24	...	243	90
1883 ...	90	165	1	256	24	95	25	8	...	4	1	172	84

**Chapter IX.**

**Justice.**

**CIVIL COURTS,  
1877-1883.**

*Appeals.*

*Applications  
for Execution  
of Decrees.*

## Chapter IX.

## Justice.

CIVIL COURTS,  
1877-1883.*Regent in Council: Appeals and Special Appeals, 1877-1883.*

YEAR.	Pending on 1st April.	Admitted during the year.	Total.	Disposed of during the year.	Balance on 31st March.
1877 ...	65	47	112	6	106
1878 ...	106	61	167	59	108
1879 ...	108	37	145	49	96
1880 ...	96	22	118	85	33
1881 ...	33	22	55	28	27
1882 ...	27	41	68	38	30
1883 ...	30	19	49	25	24

*Applications for Execution of Decrees, 1877-1883.*

	1877.	1878.	1879.	1880.	1881.	1882.	1883.
APPLICATIONS.							
Balance on 1st April ...	545	378	423	411	504	430	517
Filed during the year ...	2151	2072	2103	2281	2787	2761	2727
Total ...	2696	2450	2526	2692	3291	3181	3244
DISPOSED OF.							
By private settlement ...	743	582	551	571	702	571	614
By execution of decrees...	1253	1109	1265	1235	1607	1661	1578
Transfer to other Courts...	10	28	24	9	41	18	...
Dismissed owing to non-appearance of applicants.	312	308	278	373	511	414	437
Total ...	2318	2027	2118	2188	2861	2664	2629
Balance on 31st March ...	378	423	408	504	430	517	615

## REGISTRATION.

Registration of documents was unknown previous to 1859 in which year an office was opened for this purpose in the Political Superintendent's office. The rules of registration then introduced were based on Regulation IX. of 1827 and Acts I. and XIX. of 1843. This system continued in force till the beginning of 1875 when a body of new rules based on Act VIII. of 1871 was adopted and a separate registration department organised. The department is at present worked by a District Registrar<sup>1</sup> and eleven sub-registrars of whom seven are special and four other officers doing the duties of sub-registrars in addition to their own. There is a sub-registrar at the head-quarters of each sub-division. The working of the department is superintended by the Chief Revenue Officer as the Inspector General of Registration, the District Registrar, and the two District Officers. According to the registration report for 1883-84 the gross receipts for that year amounted to £1230 14s. (Rs. 12,307) and the charges to £476 6s. (Rs. 4763), thus leaving a credit balance of £754 8s. (Rs. 7544). Of 2398 the total number of registrations, 517 were deeds of sale, 1597 of mortgage, twenty-one of gifts of immovable property, 119 of leases, 106 of miscellaneous documents relating to movable property, nine of wills, four of bonds, and twenty-five of sundry documents. The total value of property affected by registration amounted to £77,858 6s. (Rs. 7,78,583).

## MAGISTRACY.

The administration of criminal justice was carried on in 1883 by the Political Agent assisted by his assistant and thirty-nine

<sup>1</sup> The *Daftardār* is ex-officio District Registrar.

magistrates. Of these latter one was the *nyáyádhish* or District Magistrate, four magistrates of the first class of whom two belonged to the Kolhápúr State proper and two to feudatory States; twenty-one magistrates of the second class of whom eleven belonged to the Kolhápúr State proper, four to feudatory States, and six to inferior *jágirdárs*; and thirteen magistrates of the third class seven belonging to the Kolhápúr State proper, three to feudatory States, and three to inferior *jágirdárs*.

During the year 1883 these magistrates disposed of 3498 cases. Of these 1614 or 46 per cent were discharged without trial, 417 or 12 per cent acquitted, 1351 or 39 per cent convicted, 114 or 3 per cent committed to the sessions, and two otherwise disposed of. During the same year the three sessions courts at Kolhápúr Bávda and Kágal disposed of 116 cases. Of these fifty or 43 per cent were acquitted, fifty-three or 45 per cent convicted, and thirteen or 11 per cent referred to the Regent in Council or Bombay Government. The following tables show the working of these courts during the seven years ending 1883:

Magistrates' Courts, 1877-1883.

YEAR.	Under trial on 1st April.	Apprehended during the year.	Total.	Discharged without trial.	Acquitted.	Convicted.	Committed to the Sessions.	Otherwise disposed of.	Total.	Balance on 31st March.
1877 ...	55	7917	7972	1999	510	4994	162	256	7921	51
1878 ...	55	5303	5358	1441	443	2910	87	428	5309	49
1879 ...	49	3856	3905	1149	314	1940	93	381	3877	23
1880 ...	28	3387	3415	935	246	1423	127	654	3385	30
1881 ...	30	3458	3488	896	311	1706	104	466	3473	15
1882 ...	15	3791	3806	1619	431	1699	95	3	3757	49
1883 ...	49	3506	3555	1614	417	1351	114	2	3498	57

Sessions Courts, 1877-1883.

YEAR.	Under trial on 1st April.	Committed during the year.	Total.	Acquitted.	Convicted.	Referred to Government or Regent in Council.	Otherwise disposed of.	Total.	Balance on 31st March.
1877 ...	33	162	195	71	78	17	...	166	29
1878 ...	29	87	116	48	45	6	...	99	17
1879 ...	17	93	110	55	59	12	...	106	4
1880 ...	4	127	131	29	93	6	...	128	3
1881 ...	3	104	107	31	67	8	1	102	5
1882 ...	5	95	100	32	48	11	...	91	9
1883 ...	9	114	123	50	53	13	...	110	7

There is no regular village police. The revenue headman or *pátíl* as a rule performs the duties of a police *pátíl*. The headman is assisted by the *shetsandis* or watchmen. The village police are empowered to act under the Village Police Act VIII of 1867. The police *pátíl* is subject to the control of the *nyáyádhish* or District Magistrate but his appointment and removal rest with the revenue authorities. The police *pátíl* of one village has power to try petty offences and several other *pátíls* will also be given the same powers.

## VILLAGE POLICE.

Chapter IX.  
Justice.

## MAGISTRACY.

CRIMINAL  
COURTS,  
1877-1883.

## Chapter IX.

## Justice.

## CRIMINAL TRIBES.

The chief criminal tribes are the Kaikádís, Mhárs, Mángs, Berads, Párdhis, Gárudis, Kolhátis, Bhámtás, and Vadárs, all of whom come from the South Deccan or Madras. They are basket-makers, cattle-dealers, day-labourers, and sometimes beggars. The Kaikádís and Kolhátis are well known gang robbers, the Bhámtás are noted pickpockets, and the Vadárs are generally given to house-breaking. The resident tribes such as Mhárs and Mángs are subjected to strict police supervision by their presence being required at a daily muster in each village and their not being allowed to leave it without a pass from the police *pátíl*. The other wandering tribes are watched in their movements while passing through the territory.

## Gang Robberies.

Formerly gang robberies were numerous, but of late years they have greatly decreased. A notable gang robbery was committed in 1879. Its object was to restore the Pretender Chima Sáheb to the Kolhápúr *gádi*. In this they were encouraged by the dacoities committed in neighbouring British districts by Hari Rámoshi and Váśudev Balvant Phadke.

## POLICE.

The police duties in former times were performed by the *pátíl* and the higher revenue officers assisted by the village watchmen and the *shetsandís*. After the State came under British superintendence in 1844-45, the *shetsandi* militia both horse and foot who held lands for military service were entrusted with police duties under the village police *pátíl* and their lands continued to them. The following arrangements were made with regard to the police of the State. A certain portion of the *shetsandís* slept at the *chávdi* during the night, and took the nightly guard; others lined the roads on *bazár* or market days, protected passes and forest wastes, and assembled when called out in mass; whilst detachments of trained horse and foot were stationed at the head-quarters of each *peta* or sub-division. Orders were issued by the police *pátíl* who had also the charge of mustering the predatory tribes, of granting them passes without which they could not leave their villages, and of keeping a general supervision over the villagers and over all strangers who might visit the village. Above the *pátíl* the *shaikh-dár* had the surveillance over a certain number of villages and the *mám-latdár* superintended the sub-division generally. Should a disturbance occur the village horsemen were despatched with the intelligence to the *mám-latdár*. The report was taken in turn by the horsemen in the nearest localities. The *shetsandís* assembled and when the *mám-latdár* approached, a respectable force assembled in readiness for tracking and pursuit. In each sub-division a police *kárkun*, attended by a party of ten horsemen, was continually moving about during the fair season from village to village, to superintend the general arrangement, to report on the efficiency of the police agents, to obtain intelligence, and to afford any assistance which might be required. Independent of the rural police each *peta* or sub-division was furnished with a body of *shibandi* amounting together to 3059 and receiving a monthly pay of £412 17s. (Rs. 4128½). They were armed with swords and shields and generally stationed at the head-quarters of the sub-division. A small body of police, one *náik* and twenty-nine men,



was organized for the protection of Kolhápúr city and another party of two *náiks* and twenty-five men was stationed at Panhála which had been notorious in former days as the head-quarters of depredators. In course of time the offices of *shaiikhdárs* and police *kárkuns* were abolished and the *shetsandí* horsemen also disappeared. In 1869 the police department was separately organized and *fauzdárs* or chief constables appointed for each sub-division, and the *mámlatdárs* were directed to allot half of the sepoys at their disposal to the *fauzdárs*. This newly constituted police was at first placed under the superintendence of the *nyáyádhish*. In 1870 the police department was organized on its present footing and placed under a district officer with the designation of Chief Police Officer. The police force was also with occasional small additions raised to its present strength.

The force is at present 486 strong and consists of the Chief Police Officer corresponding to the Police Superintendent in the British districts, a special police officer corresponding to a police inspector, seven *fauzdárs* or chief constables, six for the several sub-divisions and one for the city, thirteen *jamádárs*, twenty *havildárs*, forty-six *náiks*, and 398 constables. It is maintained at an annual cost of £5350 16s. (Rs. 53,508). On an area of 1961 square miles and a population of 624,827, these figures give one constable for every four square miles and 1285 people, and a cost of £2 14s. 6d. (Rs. 27½) to the square mile or 2d. (1½ as.) to each head of the population. Of the total police force, seven *fauzdárs*, ten *jamádárs*, and six *havildárs* are in charge of divisions and sub-divisions; a body of fifty that is one *jamádár*, five *havildárs*, five *náiks*, and thirty-nine peons remain at the head-quarters; three *náiks* and thirty-nine peons are employed in escorting prisoners; one *náik* and sixty-six peons are employed in guarding the district and the city jails; eighteen peons serve as orderlies to the *fauzdárs* or *jamádárs* in charge of stations; one *havildár*, thirty *náiks*, and 104 peons are stationed at the twenty-eight different police posts in the districts and twelve police stations in the city; one *havildár*, one *náik*, and forty-two peons are allotted to magistrates and other officers; sixteen peons are employed in serving processes; one *náik* and five peons are placed at the disposal of the excise department; one *náik* and three peons are employed at the lunatic asylum; and two *jamádárs*, seven *havildárs*, four *náiks*, and sixty-one peons are employed on miscellaneous police work.

Of these 306 are Maráthás, 100 Mahomedans, twenty-five Bráhmans, eight from each of the castes of Lingáyats Rajputs and Kolis, five Dhangars or Shepherds, four Mángs, three from each of the castes of Jains Barbers and Bhois, two Mhárs, and one from each of the castes of Prabhus, Gosávis, Vánis, Tailors, Potters, Butchers, Washermen, and Vadárs.

Fifty of the force are drilled and provided with firearms; the rest, except the *fauzdárs* and *jamádárs* who are armed with swords, are provided with batons. Fifty-four only out of the whole force can read and write, but there is a police school established to teach

## Chapter IX.

## Justice.

POLICE,  
1881.

## Chapter IX.

## Justice.

POLICE,  
1881.

the rest to read and write and also to give them some knowledge of their duties.

Besides this, of the police force kept in feudatory States the Ichalkaranji force is sixty-two strong maintained at a yearly cost of £472 4s. (Rs. 4722), the Vishalgad force is forty-six strong maintained at a yearly cost of £349 4s. (Rs. 3492), the Kāgal force is thirty-six strong maintained at a yearly cost of £287 16s. (Rs. 2878), and the Bāvda force is twenty-eight strong maintained at a yearly cost of £144 12s. (Rs. 1446). Kolhāpur has no mounted police, but their place is supplied by parties from the Red *Risāla* or mounted bodyguard of the Mahārāja.

OFFENCES,  
1877-1881.

The returns for the five years ending 1881-82 show a total of sixty-three murders and attempts to murder, twenty-five culpable homicides, 106 cases of grievous hurts, sixty-seven dacoities and highway robberies, and 14,166 other offences. During these five years the total number of offences gave a yearly average of 2885, or one offence for every 277 of the population. The number of murders varied from twenty-seven in 1877 to five in 1880 and averaged twelve; culpable homicides varied from eight in 1877 and 1880 to one in 1878 and 1881 and averaged five; cases of grievous hurts varied from twenty-seven in 1880 to sixteen in 1879 and averaged twenty-one; gang and other robberies varied from eighteen in 1878 to nine in 1879 and averaged thirteen; and other offences varied from 4610 in 1877 to 1999 in 1880 and averaged 2833. The details are :

*Kolhāpur Crime and Police, 1877-1881.*

YEAR.	Murders and Attempts to Murder.	Culpable Homicides.	Grievous Hurts.	Dacoities and Robberies.	Other Offences	Total.
1877 ...	27	8	21	15	4610	4681
1878 ...	11	1	21	18	3206	3257
1879 ...	11	7	16	9	2263	2306
1880 ...	5	8	27	11	1999	2050
1881 ...	9	1	21	14	2088	2138
Total ...	63	25	106	67	14,166	14,427

During the seven years ending 1883 the percentage of stolen property recovered varied from eighty-seven in 1879 to thirty-four in 1880. The details are :

*Stolen Property Recovered, 1877-1883.*

YEAR.	Property Stolen.	Property Recovered.	Percentage.	YEAR.	Property Stolen.	Property Recovered.	Percentage.
	£.	£.			£.	£.	
1877 ...	45,934	35,012	76	1881 ...	35,855	24,958	70
1878 ...	54,124	44,278	83	1882 ...	26,926	16,044	60
1879 ...	88,237	76,586	87	1883 ...	43,003	26,865	62
1880 ...	28,485	9702	34				

## JAILS.

Besides the central jail at Kolhāpur there are thirteen subordinate jails in which under-trial and short-term prisoners only are confined. The thirteen subordinate jails are at Karvir, Panhāla, Alta, Shirol,

## Chapter IX.

## Justice.

## JAILS.

Ráybág, Bhudargad, Gadinglaj, Katkol, Vishálgad, Bávda, Ichalkaranji, Ajra, and Kágál. The central jail at Kolhápúr was built in 1847-48 at a cost of £1200 (Rs. 12,000) and nearly the same amount was spent in 1873 in adding a storey to the northern part of the main building. It is situated near the Áditvár gate. It consists of the main building and out-houses of which two are used to confine prisoners, one for under-trial prisoners and one for females. The main building is square in form and is surrounded by a stone wall thirty feet in height and is protected by double doors to the north. The inner door is made of iron bars and the outer of wooden planks coated with sheets of iron. The northern portion of the building is double-storeyed only. There are fifteen cells closed with a railing of iron bars on three sides. On a bastion in the rampart to the south of the main building there are two solitary cells each measuring 8' x 8'. The space in their front is used as a room for the infantry guard. The building for the confinement of under-trial prisoners contains fourteen cells, ten out of which are provided with wooden bars and four with bars of iron and a wooden ceiling. One cell is allotted to a single prisoner. This building is entered by a door facing the west. Adjoining to this building is the prison for females. Part of it is closed with wooden bars and the remaining portion is kept open which serves as a cook-room for the jail. It is accessible by a door to the west.

There is a hospital attached to the jail which stands on a bastion on the rampart. It is 64' x 40'. It contains two rooms for the accommodation of sick prisoners. During the ten years ending 1881-82 the yearly average number of sick was 233·6 and of deaths 7·8. Inside the rampart wall to the east of the jail there is a quadrangle in which prisoners sentenced to death are executed.

A party of the Kolhápúr Infantry twenty-five strong under a *subhedar* furnishes a daily guard. Besides this a police party is used in guarding the prisoners when they are taken out. There are also sixteen officers belonging to the jail establishment such as *náiks* *havildárs* and *jamáddárs*.

At about 600 feet from the main building outside the rampart wall is the jail workhouse where cotton-weaving, carpet-making, carpentry, and cane-work are carried on. Long-term prisoners are made to work in the warehouse and others are employed by the town municipality and by the State public works department at a daily average wage of 3d. (2 as.). The women are employed in cooking and grinding corn. Except on Sunday, the prisoners daily work from six to eleven in the morning and again after a short rest from one to five in the evening. In 1883-84 the workhouse yielded a net profit of £67 14s. (Rs. 677). During the same year, of the total of 505 prisoners 400 were males and 105 females, and 478 were Hindus twenty-six Musalmáns and one Christian. There is a night-school in the jail for the education of prisoners who desire it. The school hours are from six to eight in the evening. The subjects taught are reading, writing, and simple arithmetic. During the year 1883-84 the net cost for each prisoner was £7 3s. 6d. (Rs. 71½). The State civil surgeon is the Superintendent of the central jail.

## CHAPTER X.

## FINANCE.

Chapter X.  
Finance.

THE earliest available balance sheet, that for 1846-47, shows a total revenue of £66,482 (Rs. 6,64,820) and a total expenditure of £51,734 (Rs. 5,17,340); the total revenue for 1882-83 amounted to £212,963 (Rs. 21,29,630) and the charges to £111,977 (Rs. 11,19,770). Leaving aside receipts and payments under the head of deposits and advances, the revenue under all other heads of the year came to £160,516 (Rs. 16,05,160), or, on a population of 800,189, an individual share of 4s. (Rs. 2). During the last thirty-seven years the following changes have taken place under the chief heads of receipts and charges.

## LAND REVENUE.

Land revenue receipts, which form 52 per cent of the entire revenue of the State, have risen from £46,558 (Rs. 4,65,580) to £111,771 (Rs. 11,17,710), and charges from £6452 (Rs. 64,520) to £9438 (Rs. 94,380). The increase in receipts is chiefly due to the large additional area brought under tillage, the confiscation of alienations, and the *dágevári* survey. The increase in charges is chiefly due to the employment of a better-paid staff.

## SÁYAR REVENUE.

Sáyar revenue has risen from £4289 (Rs. 42,890) to £9684 (Rs. 96,840). It is derived from farming the right of vending tobacco, *gánja*, and *bháng*.

## JUSTICE.

Judicial receipts, which consist chiefly of fines, have risen from £2045 (Rs. 20,450) to £2569 (Rs. 25,690). In 1882 the charges amounted to £2091 (Rs. 20,910).

## STAMPS.

Stamps are a new head since 1858-59. In 1882 the receipts amounted to £5352 (Rs. 53,520) and charges to £313 (Rs. 3130).

## REGISTRATION.

Registration is a new head. In 1882 the receipts amounted to £1026 (Rs. 10,260).

## EDUCATION.

Education is a new head. In 1882 the receipts amounted to £2083 (Rs. 20,830) and charges to £7012 (Rs. 70,120).

## INTEREST.

Interest receipts, owing to increased savings invested in Government securities, have risen from £96 (Rs. 960) to £5264 (Rs. 52,640).

## POLITICAL.

Political charges, owing to the formation of a separate agency for the Kolhápúr State, have risen from £749 (Rs. 7490) to £2811 (Rs. 28,110).

## REGENCY.

Regency is a new head opened in 1882. In 1882 the charges amounted to £12,214 (Rs. 1,22,140).

Police is a new head. In 1882 the charges amounted to £6804 (Rs. 68,040).

Jail charges have risen from £624 (Rs. 6240) to £1675 (Rs. 16,750).

Military charges, chiefly owing to the reduction of the old irregular cavalry and separation of the police force, have fallen from £18,264 (Rs. 1,82,640) to £16,979 (Rs. 1,69,790).

Medical charges constitute a new head. In 1882 the charges amounted to £2203 (Rs. 22,030).

Public Works charges have risen from £633 (Rs. 6330) to £15,557 (Rs. 1,55,570).

The following statement gives a detailed comparison of the 1846-47 and 1882-83 balance sheets:

*Kolhápúr Balance Sheets, 1846-47 and 1882-83.<sup>1</sup>*

RECEIPTS.			CHARGES.		
Head.	1846.	1882.	Head.	1846.	1882.
	£	£		£	£
Land Revenue ...	46,558	111,771	<i>Khatgi</i> ...	17,711	17,273
Sáyar Revenue ...	4289	9884	Political ...	749	2811
Judicial ...	2045	2569	Regency ...	...	12,214
Stamps ...	...	5352	Land Revenue ...	6452	9438
Registration ...	...	1026	Police and Magisterial ..	...	6804
Education ...	...	2083	Jails ...	624	1675
Tolls ...	...	1880	Judicial ...	...	2091
Interest ...	96	5264	Stamp ...	...	313
Miscellaneous ...	10,124	5731	Military ...	18,264	16,979
Local Cess ...	...	10,263	Education ...	...	7012
Loans, Advances, and	...	...	Medical ...	...	2203
Deposits ...	3370	52,447	Public Works ...	633	15,557
Municipal ...	...	4893	Miscellaneous ...	7301	17,607
Total ...	66,482	212,963	Total ...	51,734	111,977

Local Funds collected since 1870-71 to promote education and works of public use amounted in 1882-83 to £10,263 (Rs. 1,02,630). The revenue is derived from three sources, a special cess of one-sixteenth in addition to the ordinary land tax; the proceeds of certain subordinate funds including a toll fund, a cattle-pound fund, a ferry fund, and a travellers' rest-house fund; and some miscellaneous items of revenue.

In 1883-84, of four municipalities Kolhápúr had a city municipality; the other three were town municipalities at Narsoba's Vádi, Ichalkaranji, and Kágál. The Kolhápúr city municipality was administered by a body of Commissioners under the control of the Chief Revenue Officer. In 1883-84 the receipts for this municipality amounted to £5091 10s. (Rs. 50,915), of which £1069 16s. (Rs. 10,698) were collected from tolls, £648 4s. (Rs. 6482) from town duties, £1537 6s. (Rs. 15,373) from house and wheel taxes, £756 12s. (Rs. 7566) from market fees, and £1079 12s. (Rs. 10,796) from other sources. During the same year the charges amounted to £4371 14s. (Rs. 43,717), of which £469 6s. (Rs. 4693) were

Chapter X.  
Finance.

MILITARY.

MEDICAL.

PUBLIC WORKS.

LOCAL FUNDS.

MUNICIPALITIES.

<sup>1</sup> The charges given in 1882 are ordinary; besides this there was a large item under extraordinary charges.

## Chapter X.

## Finance.

## MUNICIPALITIES.

spent on the staff, £101 16s. (Rs. 1018) on lighting, £1021 16s. (Rs. 10,218) on conservancy, £1626 4s. (Rs. 16,262) on original public works, £607 10s. (Rs. 6075) on repairs, and £545 2s. (Rs. 5451) on miscellaneous purposes.

Of the town municipalities the municipality of Narsoba's Vádi where two large fairs are yearly held, showed in 1883-84 an income of £172 14s. (Rs. 1727) and an expenditure of £72 6s. (Rs. 723); the municipality of Ichalkaranji an income of £170 (Rs. 1700) and an expenditure of £166 (Rs. 1660); and the municipality of Kágál an income of £60 (Rs. 600) and an expenditure of £54 2s (Rs. 541). To several small towns, market places, and the Panhála sanitarium which have no municipalities, £207 18s. (Rs. 2079) were given during 1883-84 from State funds for conservancy and road repairs.



## CHAPTER XI.

## INSTRUCTION.

IN 1883-84 there were 190 schools or an average of one school for every six villages with 11,399 names or 6·27 per cent of 181,797 the whole population between six and fourteen years of age. Of these thirty were aided indigenous schools with 826 names. Under the Director of Public Instruction and the Educational Inspector Southern Division, the schooling of the State was supervised by a State deputy educational inspector. In 1883-84 education cost £7012 (Rs. 70,120) and school buildings £1616 (Rs. 16,160). The total fees received during the year amounted to £1673 (Rs. 16,730).

In 1848 four schools were for the first time opened, at Kolhápúr, Panhála, Alta, and Shirol. In 1854 the number of schools increased to ten with 466 names. Of these one was an English school at Kolhápúr. Besides these there were in 1854 122 indigenous schools attended by 1828 pupils. In 1866-67 the number of schools increased to twenty-five and of pupils to 1147. During the sixteen years ending 1883 the number of schools excluding the Rájárám college and high school has increased from twenty-five in 1868-69 to 189 in 1883-84, and the number of pupils from 1626 in 1868-69 to 10,986 in 1883-84. The details are :

*Kolhápúr Primary Schools, 1868-69 to 1883-84.*

YEAR.	Schools.	Pupils.	YEAR.	Schools.	Pupils.
1868-69 ...	25	1626	1876-77 ...	133	6570
1869-70 ...	35	2200	1877-78 ...	133	6207
1870-71 ...	59	3494	1878-79 ...	133	6218
1871-72 ...	101	4872	1879-80 ...	144	7223
1872-73 ...	129	5909	1880-81 ...	149	8093
1873-74 ...	139	6398	1881-82 ...	154	9191
1874-75 ...	138	6455	1882-83 ...	172	10,091
1875-76 ...	187	6281	1883-84 ...	189	10,986

Of the 190 schools in 1883-84 one was the Rájárám college and high school, one a training school, one a female training class, six second grade anglo-vernacular schools, 154 vernacular schools, nineteen night schools, and eight girls schools. The following table shows the number of the various classes of schools and the number of pupils attending them during the five years ending 1883-84 :

*Classes of Schools, 1879-1883.*

CLASS.	SCHOOLS.					PUPILS.				
	1879-80.	1880-81.	1881-82.	1882-83.	1883-84.	1879-80.	1880-81.	1881-82.	1882-83.	1883-84.
Rájárám College and High School.	1	1	1	1	1	284	313	323	343	413
Training School ...	1	1	1	1	1	24	25	13	12	12
Female Training Class.	...	...	...	1	1	...	...	...	10	12
Second Grade Anglo-Vernacular Schools.	5	6	6	6	6	716	895	1039	1056	1094
Vernacular Schools.	116	120	124	141	154	5623	6243	7088	7940	8622
Night Schools ...	17	17	18	18	19	599	650	721	732	746
Girls Schools ...	5	5	5	5	8	261	280	330	341	500
Total ...	145	150	155	173	190	7507	8406	9519	10,439	11,399

Chapter XI.  
Instruction.

SCHOOLS,  
1848-1883.

CLASSES OF  
SCHOOLS,  
1879-1883.

Chapter XI.  
Instruction.

RÁJÁRÁM  
COLLEGE AND  
HIGH SCHOOL.

In 1867 a high school was opened at Kolhápur. In 1871 it was named the Rájárám high school in memory of Rájárám (1866-1870). In 1880 a college class and a *sardárs'* or chiefs' class were attached. The college class is affiliated to the Bombay University and teaches up to the first B.A. standard. In 1883-84, of the thirty-eight students twenty-nine appeared for the Previous Examination, of whom twelve or forty-one per cent were successful; and nine appeared for the first B.A. examination, of whom five or fifty-five per cent were successful.<sup>1</sup> On the 31st of March 1883 there were 375 names on the roll of the high school, the average monthly number being 337 and the average daily attendance 306. The high school teaches up to the matriculation standard. During the sixteen years ending 1883, 181 students from the high school passed the matriculation examination.<sup>2</sup> In 1883-84 the *sardárs'* class was attended by eight *sardárs*. The monthly fees charged in the Rájárám college and high school vary from 10s. to 5s. (Rs. 5-2½) in the college class, from 3s. to 1s. (Rs. 1½-½) in the high school, and from £10 to £2 10s. (Rs. 100-25) in the *sardárs'* class. In 1883-84 the total cost of this institution to the State amounted to £3420 12s. (Rs. 34,206) or an average of £10 3s. (Rs. 101½) for each pupil. For the encouragement of education this institution has been endowed with three sets of scholarships, the Alfred, the Rájárám, and the *Peta* and *Sansthán* scholarships. In 1870, in honour of the visit to Bombay by his Royal Highness the Duke of Edinburgh, the Kolhápur Darbár founded the Alfred scholarships and for this purpose invested a sum of £4500 (Rs. 45,000) in Government securities. Of the seven scholarships one of £2 (Rs. 20) a month and tenable for four years is given to a matriculated student of the Rájárám high school, who joins the medical college in Bombay; two, each of £1 10s. (Rs. 15) a month and tenable for two years, are given to those who pass the Previous Examination from the Rájárám college and continue further study; and three, each of £1 (Rs. 10) a month and tenable for one year, are given to those matriculated students of the Rájárám high school who continue their study for the Previous Examination in the Rájárám college. In 1871, in memory of Rájárám Maháráj the Rájárám scholarships were founded by raising a public subscription of £2100 (Rs. 21,000) in Kolhápur and the Bombay Karnátak. The scholarships are sixteen in number and tenable for one year. They are valued at 10s. to 8s. (Rs. 5-4) a month and are given in the Rájárám high school to deserving students of the fourth to the

<sup>1</sup> From the college, up to 1883-84 thirty-two have passed the Previous Examination, two in 1880, four in 1881, fourteen in 1882, and twelve in 1883. In the first B.A. examination altogether nineteen have been successful, five in 1883 and fourteen in 1884.

<sup>2</sup> The details are: four each in 1868 and 1869, two in 1870, seven in 1871, eighteen in 1872, thirteen in 1873, twelve in 1874, twenty in 1875, six in 1876, nine in 1877, five in 1878, eighteen in 1879, ten in 1880, eighteen in 1881, seventeen in 1882, and eighteen in 1883. Of these thirty-four have graduated, one as M.A., seven as LL.B., two as L.M., twenty-four as B.A., and fifty-one have passed the following examinations: fourteen the first B.A., two the F.C.E., three the F.E.A., twenty-seven the P.E., three the Forest Class, and two the Agricultural Class of the College of Science, Poona.

seventh standards. To promote higher education among rural classes ten scholarships, named the *peta* and *sansthán* exhibitions, have been founded, six for the six *petás* or sub-divisions and four for the four *sanstháns* or feudatory states. They are given to deserving students from the country who join the Rájáráam high school. They are tenable for five years and worth 6s. (Rs. 3) a month. Besides this, out of the interest accruing from the poor boys fund started in 1869, books are supplied to poor boys studying in the high school. In 1882 this fund had a balance of about £130 (Rs. 1300) invested in Government promissory notes.

The training school was established in 1867 to provide trained teachers for the vernacular schools. During the sixteen years ending 1883-84 the total number of trained teachers sent out from this school was 159 or an average of ten for each year. During the year 1883 there were twelve students in the school. The course of study lasts for three years. The pupils are each given a subsistence allowance of 10s. (Rs. 5) a month.

The female training class was opened in 1882 to provide trained female teachers for the girls schools. In 1883-84 the class was under the supervision of Miss Little the lady superintendent. The standards taught are the fifth to the seventh. In 1883 there were twelve students. A teacher has lately been appointed to teach English to those who are being trained as mistresses.

Of the eight girls schools four are at Kolhápúr and the other four are one each at Bávdá a village near Kolhápúr, Panhála, Ichalkaranji, and Ajra. In 1883 these girls schools were attended by 500 girls. Besides these, there were in 1883 379 girls under instruction in the several boys schools.

The night schools are attended by labourers, artisans, and cultivators who cannot afford time to attend the ordinary day schools. The first night school was opened at Kolhápúr in 1871. In 1883-84, of the nineteen night schools three were at Kolhápúr and sixteen in other parts of the State. They were attended by 746 pupils or an average of thirty-nine for each school.

In 1883-84 there were thirty aided indigenous schools with 826 names on the roll. During the year 1883-84 the cost to the State on account of these aided schools was £105 2s. (Rs. 1051). Of the unaided private schools there were during the year 109 with an attendance of 2042. Of these one was a private English school at Kolhápúr with fifty-eight names; one a Sanskrit school at Kolhápúr with eighty-three names; one a Vedic school at Kokisra in Bávdá with thirteen names; eight vernacular schools with 162 names; nineteen Mission schools with 584 names; and seventy-nine indigenous vernacular schools with 1142 names. Of the nineteen Mission schools eight were opened by the Mission of the Society for the Propagation of the Gospel, one being a boys school attended by fourteen and seven girls schools attended by 222 girls; and the other eleven were opened by the American Mission, eight being boys schools attended by 308 and three girls schools attended by forty girls.

## Chapter XI. Instruction.

RAJÁRÁAM  
COLLEGE AND  
HIGH SCHOOL.

### TRAINING SCHOOL.

### FEMALE TRAINING CLASS.

### GIRLS SCHOOLS.

### NIGHT SCHOOLS.

### PRIVATE SCHOOLS.

**Chapter XI.****Instruction.****LIBRARIES.**

Of the fourteen libraries and reading rooms in 1883 two were at Kolhápur, and one each at Panhála, Hátka-langda, Shirol, Ráybág, Narsoba's Vádi, Gadinglaj, Gárgoti, Ichalkaranji, Ajra, Kágál, Gagan Báyda, and Malkápur. Of these the Kolhápur native general library is the largest. In 1883 it had 2969 books and 195 subscribers, an income of £220 4s. (Rs. 2202) including the balance and an expenditure of £143 12s. (Rs. 1436). It subscribed to forty-five newspapers. The yearly rates of subscription varied from 6s. to £12 (Rs. 3-120).

**NEWSPAPERS.**

At Kolhápur a weekly newspaper called the *Jnyán Ságar* or Ocean of Knowledge is published in Maráthi. It was started in 1870 and has about 150 subscribers.

## CHAPTER XII.

## HEALTH.

THE climate of the Kolhápúr plain, which varies from about 2000 feet above the sea in the west to about 1700 in the east, like the rest of the Western Deccan is temperate. Towards the Sahyádrí hills which are covered with wood and drenched during the rainy months, the air is always cooler than in the east, which during April May and June is liable to hot easterly winds. At the same time almost the whole territory is under the influence of the sea breeze, which sets in during the afternoon and lasts till about eight at night.

The prevailing diseases are fever and parasitic diseases of the intestines and skin. After the close of the monsoon fever prevails largely and is specially severe on the eastern slopes of the Sahyádris. As the natural drainage of the country is good and there are few morasses and extensive forest tracts, severe malarious fever is rare. About 1848 typhoid or malignant scarlet fever prevailed in Bávda and Vishálgad.<sup>1</sup> The colour of the native's skin made the detection of the disease difficult; and it was not till ulceration and sloughing of the throat supervened that many who were attacked applied for relief. Some of the cases proved fatal by suffocation, and in others from sloughing ulceration extending to the large vessels of the throat, fatal hæmorrhage ensued. This fever was confined to the hilly tract and originated in scanty and unwholesome food.

Both among males and females, old and young, strong and feeble, entozoal worms prevail throughout the year. Except in Kolhápúr city guineaworm is common throughout the State. Formerly guineaworm was very prevalent at Bávdá, about three-fourths of the hospital patients being affected by it. Of late, owing to the closure of a particular well the water of which was infected with germs, the disease has notably decreased. Tapeworm and ringworm are common and ascarides or threadworms are often found in children. Of skin diseases the chief are eczema, running scall, herpes, and scabies. They are not severe and, though liable to recur, are easily removed.

Of epidemics cholera and small-pox are the chief. Till late, Kolhápúr was well known as the hot-bed of cholera in the Bombay Karnátak. Cholera constantly broke at fairs or *jatrás*, where the conservancy and water supply are bad and food unwholesome. It generally prevailed about April-May, when a large fair sometimes attended by about 100,000 people is yearly held at Jotiba's hill.

## Chapter XII.

## Health.

## CLIMATE.

## DISEASES.

*Fever.*

### Worms.

## EPIDEMICS.

### *Cholera.*

## Chapter XII.

## Health.

## EPIDEMICS.

*Cholera.*

eight miles north-west of Kolhápur. Of late owing to improved sanitation and better water-supply cholera outbreaks are mild in nature. The following are the chief available details of cholera outbreaks during the thirty-five years ending 1883:

In 1849 cholera was mild and attacked children only. Many of the cases recovered. In 1850 cholera attacked adults only. In May 1854 cholera broke out in Kolhápur city. It was unusually fatal; for several days there were as many deaths as there were attacks. From the city the disease spread over the country. In 1855 cholera was brought from Pandharpur by pilgrims who died by dozens on the way. On the several roads guards were placed to prevent the pilgrims from entering Kolhápur city till they passed some days in quarantine. In 1859 cholera originated at Kágál and for five months raged severely throughout the State. Of the 4774 reported cases 2705 or fifty-seven per cent were fatal; for the city of Kolhápur the cases reported were 952 and deaths 404 or forty-two per cent. In 1860, except at Kolhápur, cholera broke out mildly in all parts of the State. It first appeared at Shirol in the east and ended at Bávdá in the west. In 1861 cholera first appeared at Shirol in July where 302 persons were attacked. It then travelled to Gadinglaj in the south, to Kolhápur in the north, and ended at Bávdá and Vishálgad in the west. Of 711, the total reported cases, 430 or sixty per cent were fatal. In 1862 cholera broke out twice in April and November. In the middle of April cholera broke out at the fair held on Jotiba's hill. From this hill it was brought by pilgrims all over the country, and raged severely till June. Of 3072 the total reported cases, 2088 or sixty-eight per cent were fatal; in Kolhápur city, of the 669 reported cases 440 or sixty-six per cent died. The November outbreak took place in four or five villages lying twelve miles north of Kolhápur. The disease appeared among workmen employed on road-making. It was probably brought by pilgrims from Pandharpur. Of the forty-five recorded cases twenty-three or fifty-one per cent died. In 1863 cholera broke out mildly throughout the State from May to September. Of 505 the total recorded cases, 316 or sixty-two per cent were fatal; in Kolhápur city twenty-six cases were reported of which ten or thirty-eight per cent died. In 1864 cholera raged severely from April to July. Of 7044 the total recorded cases, 4098 or fifty-seven per cent died. Of these in Kolhápur city the cases reported were 844 and deaths 441 or fifty-two per cent. In 1865 cholera broke throughout the State from May to August. Of 1281 the total recorded cases, 852 or sixty-six per cent died. Of these in Kolhápur city thirty-three cases occurred and twenty or sixty per cent died. The year 1866 was free from cholera. In 1867 only a few sporadic cases were reported. In 1868 cholera broke out in October. Of the 230 reported cases 101 or forty-four per cent died. It was brought by pilgrims from Pandharpur. This outbreak spread throughout the State and continued till August 1869. It first attacked a Pandharpur pilgrim at Vasi in the south of Kolhápur and then travelled to Shirol Ichalkaranji and Miraj in the east, to Gadinglaj in the south, to Kolhápur and Karvir in the north, and ended at Bávdá and Vishálgad in the west. In 1870, except at Kolhápur cholera



prevailed mildly in other parts of the State from September to November. It was brought by Pandharpur pilgrims. Of the 252 recorded attacks 153 or sixty-one per cent were fatal. In 1871 cholera appeared in November only at Malkápur and a few neighbouring villages. It appears to have been brought from Sátara. Of the twenty-two reported cases nine or forty-one per cent died. In 1872 cholera attacked 645 persons, of whom 297 or forty-six per cent died. The years 1873 and 1874 were free from cholera. In 1875 cholera broke out in Kolhápur city in July and August. The attack was specially severe among children. Of the 129 recorded cases fifty-eight or forty-five per cent died. In 1876 small-pox was followed by cholera, causing 283 attacks and 117 or forty-one per cent deaths. In 1877 cholera prevailed throughout the State for the greater part of the year. Of the 760 recorded cases 419 or fifty-five per cent died. In 1878 cholera appeared mildly in Kolhápur city, causing 146 attacks and sixty-four or forty-four per cent deaths. The years 1879 and 1880 were free from cholera. In 1881, except at Kolhápur cholera appeared mildly about August in other parts of the State. Of the 587 reported cases 231 or thirty-nine per cent died. In 1882 cholera raged severely from January to August. In Kolhápur city it appeared in February and disappeared at the end of May; in other parts it continued till August. It was most severe in May. Of 6281 the total cases recorded, 2696 or forty-three per cent died. Of these, for Kolhápur city the cases reported were 289 and deaths 159 or fifty-five per cent. This outbreak is attributed to scanty and unwholesome drinking water owing to want of rain during the years 1880 and 1881. In 1883 cholera was specially severe in Panhála. Of the 516 attacks reported 191 or thirty-seven per cent were fatal.

## Chapter XII.

## Health.

## EPIDEMICS.

*Cholera.**Small-pox.*

Before 1848 small-pox raged severely. Of late owing to State vaccination outbreaks of small-pox are rare and mild. Since 1872 small-pox has broken twice in 1876 and 1883. The 1876 outbreak raged throughout the State. It first appeared in January and was highest in March. Specially in Shirol, Alta, and Ichalkaranji it was fatal to children. In spite of additional vaccinators employed to check it, isolated cases of small-pox occurred till the end of the year. In 1883 small-pox prevailed in Alta, Gadinglaj, Bhudargad, Shirol, Ichalkaranji, and Kágál, where special vaccinators were employed to check its growth. Of 18,770 the total number of deaths in 1883, 1700 or nine per cent were returned as due to small-pox.

Epidemics of measles, chicken-pox, hooping cough, and mumps occur occasionally. The last epidemic of hooping cough was in the monsoon of 1871. Mumps were unusually prevalent from June to September in 1881.

In 1883-84, besides the civil hospital at Kolhápur there were four dispensaries at Gadinglaj, Malkápur, Kágál, and Ajra. The number of patients treated was 36,632, of whom 35,391 were out-door and 1241 in-door patients, and the cost was £2208 (Rs. 22,080). The following are the chief details:

HOSPITAL AND  
DISPENSARIES.

**Chapter XII.****Health.****HOSPITAL.***Kolhápúr.*

The Kolhápúr civil hospital was opened in 1847. A new building for the hospital called the new or Albert Edward Hospital has been built in 1883 at a cost of £28,000 (Rs. 2,80,000). The chief diseases treated were malarious fevers, respiratory affections, bowel complaints, affections of the ear and skin, and parasitic diseases. In 1883, 18,685 out-patients and 1175 in-patients were treated at a cost of £1696 (Rs. 16,960). During the year 136 major surgical operations were performed.

**DISPENSARIES.***Gadinglaj.*

The Gadinglaj dispensary was opened in August 1879. It is located in a substantial building of its own. The commonest diseases treated were malarious fevers, intestinal worms, rheumatic affections, and ophthalmia. In 1883, 7685 out-patients and thirty-seven in-patients were treated at a cost of £137 (Rs. 1370).

*Malkápur.*

The Malkápur dispensary was opened in September 1880. It is located in a temple. The chief diseases treated were fevers, respiratory affections, intestinal worms, and skin diseases. In 1883 5026 out-patients and fifteen in-patients were treated at a cost of £149 (Rs. 1490).

*Kágál.*

The Kágál dispensary which was opened on a small scale about 1876, was placed on a better footing in May 1882. It is located in a small building about half a mile from the town and has no accommodation for in-patients. In 1883, 1781 patients were treated at a cost of £57 (Rs. 570).

*Ajra.*

The Ajra dispensary was opened in November 1883. During the five months from November 1883 to March 1884, 2214 out-patients and fourteen in-patients were treated at a cost of £169 (Rs. 1690).

**LUNATIC ASYLUM.**

The lunatic asylum is attached to the Kolhápúr civil hospital. During the year 1883-84, of the thirty-seven lunatics treated thirty-five were males and two females; of these thirty-six were Hindus and one Musalmán. Twenty-two were cured or discharged, eight transferred, and seven remained at the close of the year.

Besides these there are jail and Kolhápúr infantry hospitals. During the year 1883, in the jail hospital 111 patients were admitted and three died; in the Kolhápúr infantry hospital 254 patients were treated, of whom 244 were cured or discharged, one died, and nine remained at the end of the year.

**VACCINATION.**

In 1883-84 under the supervision of the *darbár* surgeon the work of vaccination was carried on by eleven vaccinators under the charge of an assistant superintendent. The total number of operations was 28,949 besides 901 re-vaccinations. In 1883 vaccination cost £357 (Rs. 3570) which was paid from State funds. The cost of each operation was about 3*d.* (2 *as.*). Besides this vaccination is practised at the Kolhápúr civil hospital and three subordinate dispensaries.

**CATTLE DISEASE.**

Among cattle foot and mouth disease is the most formidable. During the hot and rainy seasons cattle and sheep are also attacked by a disease resembling cholera. The chief symptoms are shivering, hurried breathing, fever, loss of appetite, great thirst, swollen tongue, swelling beneath the jaw, salivation, purging, and the stools becoming bloody as the disease advances. The treatment consists externally to apply lime to the horns and cantary to the sides and

head either with hot iron or charred young bamboo; internally aromatics and astringents are given consisting of turmeric, chillies, carraways, ginger, black pepper, mango, *jāmbhul* bark, clarified butter, salt, mustard, *nāchni*, *masur*, and the juice of the wild onion. Care is taken to give no water. A fatal disease called *haran bahu* and resembling staggers sometimes attacks camels. The eyeballs of the animal attacked project and become red; it stares wildly, froths from the mouth, becomes violent, and sweats profusely. During the time when the east wind prevails, horses are often attacked by a disease called land wind or *kamri* that is paralysis of the loins. This disease is attributed to masturbation practised by entire horses.

During the seven years ending 1883 the total number of deaths was 130,579 or an average yearly mortality of 18,654, or according to the 1881 census of twenty-three in every thousand of the population. The yearly totals vary from a lowest of 13,787 in 1881 to 28,573 in 1877. Of the 18,770 deaths in 1883, 191 were returned as due to cholera, 1700 to small-pox, 10,032 to fevers, 3284 to bowel complaints, 187 to injuries, and 3376 to other causes. During the same seven years the total number of births was 128,959 and averaged 18,422. The yearly totals vary from a lowest of 7534 in 1878 to 26,965 in 1882. The details are:

*Kolhápúr Births and Deaths, 1877-1883.*<sup>1</sup>

YEAR.	Deaths.	Births.	YEAR.	Deaths.	Births.
1877 ...	28,573	10,818	1882 ...	18,442	26,965
1878 ...	20,674	7534	1883 ...	18,770	26,352
1879 ...	16,225	13,547	Total ...	130,579	128,959
1880 ...	14,108	18,596			
1881 ...	13,787	25,147			

<sup>1</sup> The death returns are believed to be fairly correct and the birth returns to be incomplete.

## Chapter XII. Health.

### CATTLE DISEASE.

### BIRTHS AND DEATHS.

## CHAPTER XIII.

## PLACES OF INTEREST.

## Chapter XIII.

## Places.

## AJRA.

Ajra, the chief town of the Ajra sub-division, lies forty-eight miles south-west of Ichalkaranji and twenty-four west of Sankeshvar. The town is prettily placed a little to the north-west of the meeting of the Chitri and Hiranyakeshi on a spur of the Sahyádris, about twenty miles east of the main crest. It is surrounded by jack and mango groves and the deep ravines of the Chitri and Hiranyakeshi flanked by high woody hills. The town stretches lengthwise south and north and covers an area of about  $2\frac{1}{2}$  square miles. It has two parts, Ajra proper, the old town fenced by an earthwork with an outer ditch, and Nabábpur of later growth to the north of the earthwork. Besides the river water the town has an abundant supply from wells. The climate is cool and pleasant during the hot season. In 1881 the population was returned at 3547 against 4210 in 1872, a decrease which is believed chiefly due to loss of life during the 1876 famine. Besides foot-paths to the villages round, Ajra is joined with Vengurla by the Amboli pass road and by a newly made cart track which runs past Gadinglaj with Nipáni and Sankeshvar on the Poona-Belgaum mail road. The chief traders are a few Nárvakar Vánis who sell ordinary every-day articles. The imports and exports are together estimated to be worth about £7500 (Rs. 75,000) a year. The chief export is rice, which used to be sent to Poona for the Peshwa's household and is still well known all over the Deccan. Besides rice, *hirda* or *Terminalia chebula* and coffee are exported. A weekly market is held every Friday and is largely attended by people from the neighbouring villages.

Ajra once belonged to the chief of Kápsi, through whom the Ichalkaranji chiefs take their name of Ghorpade. During the disorders of the latter part of the eighteenth century Ajra was a centre of border warfare. In 1746, through the influence of the third Peshwa Báláji Bájráv (1740-1761), Sháhu Rája of Sátára gave the town and sub-division of Ajra to Anubái Sáheb, the daughter-in-law of Náro Mahádev the founder of the present Ichalkaranji family. In 1792 the town and sub-division of Ajra were farmed to one of the ancestors of the present Phadnis or Phadnavis family of Ajra. Under the Phadnis Ajra was constantly at war with its neighbours Nesri, Bhudargad, and the Kolhápur State, and was guarded by a garrison 1000 strong kept at a yearly cost of about £3200 (Rs. 32,000). In 1800 one Chinto Rámchandra Phadnis led the small garrison of Ajra against Harpávada and Bellevádi and

lost his life in a fight at Bhudargad. But the bravery of the Phadnis family prevented Ajra from falling into the hands of the neighbouring chiefs. About 1820, after the fall of the Peshwás, the Ajra garrison was reduced, and at present (1884) only a few militia or *sanadis* are employed to do police work.

As the head-quarters of a sub-division Ajra has the usual revenue, police, and post offices. In the fair season, from January to April, it is also the seat of a subordinate civil judge or *munsif*. The town has a school with room for about 200 pupils, a dispensary, a reading room, a rest-house or *dharmashála*, and a few Hindu temples. The chief objects of interest are the temples of Rávalnáth and Rámling and the ruins of a hill fort. The temple of Rávalnáth has a rest-house attached and enjoys a yearly grant of £60 16s. (Rs. 608). In a deep ravine on the Hiranyakeshi, with a fine pool and waterfall, about a mile and a half north of the town, is the small stone temple of Rámling, with a life-size image of Nandi or Shiv's bull, and a Hindu Gosáin as its ministrant. Every year on *Maháshivráttra* Day in *Mágh* or January-February a fair is held attended by about 5000 people and with sales worth about £200 (Rs. 2000). A small hill at the north end of Nabábpur is crowned by the ruins of an old fort. According to tradition the older town spread over the top and slopes of the hill, but as in Muhammadan times it was constantly attacked by robbers, the people removed to Ajra which they strengthened with an earthwork and ditch. The town had formerly only two gates. Lately to give more air five fresh breaches have been made in the wall, and bamboo thickets which covered the ditch have been cleared.

## Chapter XIII.

## Places.

## AJRA.

Alta, from *alta* a red colour formerly made in the town, was the former head-quarters of the Alta sub-division. It lies in the Várna valley, about twelve miles north-east of Kolhápur and six miles south of the Várna. The town is surrounded on three sides by woody heights and has a good supply of well water. In 1881 the population was returned at 4012 against 4396 in 1872. The people are mostly Jains and live in brick and tile-built houses. Alta is said to be more than 800 years old. From 1765 to 1876 it was the head-quarters of the Alta sub-division, when as Alta was inconvenient for some newly-added villages, the *mámlatdár's* office was removed to the more central town of Hátka-langda. Weekly markets are held every Tuesday and Wednesday. During the disorders at the close of the eighteenth century Alta was twice burnt to the ground. It has a school with an average attendance of seventy-five boys. The school-house, which was built in 1872 at a cost of about £300 (Rs. 3000), has room for a hundred boys. The objects of interest are a Musalmán prayer-place called Ramzán Darga, and about a mile to the west of the town the temples of Sidoba a Lingáyat saint, of Dhuloba apparently a local Khandoba, of Alam Prabhu a Lingáyat saint, and of Rámling or Shiv. The Ramzán Darga is a square building, including the plinth, forty-four feet long by forty feet broad and including the dome thirty-three feet high. The prayer-place is visited by many Musalmáns and by a few Hindus. Every year on the 15th of *Savál* a fair or *urus* is held attended by about

## ALTA.

## Chapter XIII.

## Places.

## ALTA.

1000 people. The Darga enjoys rent-free land valued at a yearly assessment of £61 6s. (Rs. 613). Of Hindu temples the temple of Sidoba is a small tile-roofed stone and mortar building five feet long and five feet broad. It is visited chiefly by Kunbis. The temple of Dhuloba, which is built in Saracenic style, is twenty-five feet square and has a small central dome. It is said to have been built by a weaver of Kágál. Every year in *Chaitra* or March-April a fair is held attended by about 5000 people chiefly Maráthás. The temple of Alam Prabhu which is also built in Musalmán style, is twenty-seven feet long seventeen broad and ten high. It is chiefly visited by Lingáyats and Jains. According to a local legend Prabhu was a Lingáyat saint who came to Alta from Kalyán in the Nizám's territory. Adling, a disciple of Prabhu who came to seek his teacher, followed him as far as Alta. As he could find no further trace of him Adling thought Prabhu had buried himself alive at Alta. To show respect for his teacher Adling built the shrine and set up a lamp which is still kept burning and worshipped. There is a local story that the temple was visited by the Emperor Alamgir or Aurangzeb (1658-1707) and was presented by him with a *mácha* or footstool, and that in honour of this gift the shrine was named Alam Prabhu.<sup>1</sup> The original footstool has disappeared and a new one has been lately installed in front of the lamp. Some small domes in front of the temple are said to have been raised in honour of devotees of Shiv who performed the live-burial or *jivant-samádh*. The last live-burial was performed about seventy-five years ago (1808) by the grand uncle of the present *pujári* or ministrant. The cave temple of Rámling is on the side of a rocky hill. The chief cave was originally nearly twelve feet square, but three quarters of it have been turned into a cistern five feet deep. At the inner end of the temple are a rock-carved *ling* and a Ganpati from which water always trickles. Before they can reach the *ling*, worshippers have generally to pass through three or four feet of water. Outside of the cave-mouth a massive Hemádpanti structure thirteen feet square rests on stone pillars. By the side of the main cave is a row of seven small cells now dedicated to the seven Puránic sages or *sapta rishis*. Near the temple are several unfailling springs, of which the Nilganga or Blue Ganges and the Pápnáshi or Sin-destroyer are *tirths* or sacred pools. The position of the *ling* and the Ganpati seems to show that the caves are Buddhist or Jain and have been adopted for Bráhmanic worship.

## ARAG.

Arag, a village in Ichalkaranji, with in 1881 a population of 3596, forty-three miles east of Kolhápúr, has an interesting group of four temples. The chief temple, 27' x 16', which is dedicated to Lakshmi, consists of a series of arches built of stone and mortar. Every year from the dark 8th to the dark 11th of *Chaitra* or March-April a fair is held attended by about 500 people. Besides a mansion or *váda* belonging to the State, the village has a Jain monastery and a Musalmán tomb. The monastery, which is

<sup>1</sup> The name Alam is probably older than Aurangzeb and gave rise to the improbable story that Aurangzeb visited or made presents to the shrine.



Chapter XIII.  
Places.

38' x 16' x 9' high, is built of stone and cement and rests on eight-sided pillars. The domed tomb which is in honour of Shamonámir Pir is 17' x 12' x 14' high. The village has a school with an average attendance of forty-one boys.

**Bá'linge**, a village with in 1881 a population of 483, lies five miles south of Kolhápúr. Its chief interest is the temple of Kátyáyani prettily placed on a hill to the south of the village. The temple is an old stone building 40' x 20' x 12' high. The goddess Kátyáyani is held in great honour by the Hindus and is mentioned in the Karvir or Kolhápúr Purán as the great helper of Ambábái. The Kátyáyani stream which rises in this hill is the main feeder of the Kolhápúr water works. The holiness of the goddess and the beauty of the temple site make Bálinge a favourite picnic place for the people of Kolhápúr.

BÁLINGE.

**Bá'vda**, one of the fifteen forts built by Bhoja Rája of Panhála (1178-1209), lies thirty-six miles south-west of Kolhápúr on a peak of the Sahyádris more than 2500 feet above the sea. The fort rises sharply from the Konkan and is very difficult of approach. The hill and the country round were formerly thick with forest but are now somewhat bare. In 1660, along with Panhála Vishálgad and Rángna, Shiváji took Bávda from Ali Adil Sháh II. (1656-1672) of Bijápúr and gave it in *jágir* or estate to Nilo Sonadev. After again falling for a short time into the hands of Ali Adil Sháh the fort remained with Shiváji till his death in 1680. In 1689 when Sambháji was captured at Sangameshvar in Ratnágiri Bávda fell to the Moghals. During the reign of Rájárám (1689-1700) Rámchandra Nilkanth, the founder of the Bávda family, took Bávda from the Moghals and in reward was presented with it in grant. During the rivalry between Sátára and Kolhápúr (1708-1729), as he remained faithful to his party, Sambháji of Kolhápúr (1712-1760) allowed Bhagvantráv son of Rámchandra to continue to hold the Bávda estate. The Bávda estate then stretched in the Konkan as far as Málvan and Vijaydurg in Ratnágiri, and the Bávda chiefs, with a following of about 25,000 horse and foot, made many raids into the Konkan. In 1782 when the capital was moved from Panhála to Kolhápúr the privileges of the Gadkaris or fort garrisons were reduced and the Gadkaris of Bávda rebelled and successfully opposed a Kolhápúr army. In 1800 Bhagvantráv Pant Amátya repaired the fort and defeated and killed an officer of the Peshwa's who was sent to take it. In 1844, with the garrison of Sámángad the garrison of Bávda fort rebelled. After the reduction of Sámángad Bávda surrendered and the fortifications were partly destroyed.<sup>1</sup>

BÁVDA.

About a mile to the east of the fort lies the village of Bávda, with in 1881 a population of 1026 and 190 houses of which seventy-one were tiled and the rest thatched. An excessive rainfall averaging 220 inches during the twenty-one years ending 1881 makes the climate unhealthy. The water is abundant and excellent. Every Thursday a market is held at which the chief article sold is

<sup>1</sup> Details of the reduction of Sámángad are given below.

## Chapter XIII.

## Places.

## BÁVDA.

grain. Every year in *Chaitra* or March-April a fair is held in honour of Rám, at which the Bávda State spends about £600 (Rs. 6000). The fair is said to have been established on the advice of Shiváji's teacher Rámdás Svámi by Rámchandra Nilkanth Amátya the founder of the Bávda family. Besides Rám's fair, two Musalmán fairs or *urus*, attended by 500 or 600 people, are held in honour of Ghaibi Sáheb, one at the beginning of the rains and the other in *Kártik* or October-November. Besides the palace of the Pant Amátya, the village has the offices of the chief, his *kárbhári* or agent, the *munsif* or civil judge, and the chief constable, a post-office, and a school with an average attendance of forty-nine boys. Since 1848 a detachment of the Kolhápur Local Infantry has been stationed at Bávda.

## BÁVDA.

**Ba'vda**, a village with in 1881 a population of 3573, lies three miles north-east of Kolhápur. Within its limits are the office of the British Resident and the camp of the Kolhápur Local Infantry. In 1881 the camp had 1311 people. It has two boys schools, one for the village and the other for the troops, and a third a girls school with an average attendance of fifty-two girls. It has also a police post of one officer and three men. The village has rich sugarcane and vegetable gardens, which owing to the nearness of Kolhápur city yield large profits.

## BHÁDOLI.

**Bha'doli**, a village in the Alta sub-division, with in 1881 a population of 2798, lies twelve miles north of Kolhápur. The village takes its name from the temple of Bhadreshvar which is built of brick and mortar, is 122 feet square, and including the spire is twenty-three feet high. Besides the temple the village has a domed Musalmán tomb built of stone and mortar about 500 feet square and thirty-two feet high. It has a school with an average attendance of seventy-one boys.

## BHIMSÁGIRI.

**Bhimsa'giri**, a group of two or three temples, lies about a thousand yards west of Sámangad. The chief is Bhim's temple which has a stone-built *gabhar* or shrine with a quadrangular vestibule or *mandap*. It has room for about 300 people and is 100' x 84' x 14' high. In the shrine is a stone image of Máruti or the monkey-god. Close to the temple is an old underground excavation 75' x 40' x 15' deep, and about 200 yards east of the temple is a grove of mango and other trees. At this temple, from the dark 13th of *Mágh* or January-February to the bright 5th of *Phálgun* or February-March a yearly fair is held attended by about 10,000 people. The fair is said to have been started by Báburáv Gádnis a former commandant of the Sámangad fort. Before 1844 when the garrison of the Sámangad fort had considerable influence, the State spent about £110 (Rs. 1100) a year on the fair. Since then the grant has been reduced to £50 (Rs. 500). Near Bhim's temple stands the temple of Cháloba where in *Mágh* or January-February a yearly fair is held attended by about 3000 people who generally offer the deity 400 to 500 sheep.

## BHUDARGAD.

**Bhudargad**, one of the Kolhápur forts which in 1844 were dismantled under the advice of the Bombay Government, stands on a bluff

## Chapter XIII.

## Places.

## BHUDARGAD.

rock thirty-six miles south of Kolhápúr. It is 2600 feet from north to south and 2100 feet from east to west, and is enclosed by a broken stone and mortar wall with two gateways. Within it 170 people live in thirty-three houses, ten of them tiled and the rest thatched. At the foot of the hill are two hamlets in one of which every Monday a small market is held. Before the repairing of the fort (1667) the hill of Bhudargad had shrines sacred to Kedárling, Bhairav, and Jakhrubái, with a hamlet at the foot of the hill inhabited by the priests who performed the service of the deities and managed their festivals. In 1667 the fort was repaired and put in excellent order by Shiváji. Shortly after it was captured by the Moghals. About five years later the fort was retaken, and the standard colours of the Moghal general who was killed in the conflict were presented to the temple of Bhairav where they are still kept. About the close of the eighteenth century Parasuhrám Pant Bháu Patvardhan took the fort by bribing the garrison and held it for about ten years when it was retaken by the Kolhápúr State. Subsequently Parashurám Pant Bháu and Gopál Pant Ápte the chief of Ichalkaranji made several vain attempts to win it back. During this war, of the five hamlets which formerly clustered round the fort three were destroyed. In 1844 the garrisons of Bhudargad and Sámángad revolted and closed their gates. On the 13th of October 1844 Bhudargad was taken by a British force under General Delamotte, and dismantled.<sup>1</sup> Besides a mansion belonging to the State, a large granary with an excellent courtyard and a cistern built at a cost of about £500 (Rs. 5000), the chief object of interest is the temple of Bhairav which is about 3000 feet square and consists of a stone and cement shrine, a hall, and a northern veranda. In front of the hall stands a stone and mortar lamp-pillar. The temple has about twenty ministrants supported by a yearly cash allowance of about £56 (Rs. 560) and land valued at a yearly assessment of about £13 (Rs. 130). Every year from the dark first to the dark tenth of *Mágh* or January-February a fair is held attended by about 4000 people and with a sale of goods worth about £200 (Rs. 2000).

**Bid**, an old village in the Karvir or Kolhápúr sub-division, with in 1881 a population of 1932, lies on the Panchganga about nine miles south-west of Kolhápúr. Bid has a temple of Bideshvar, 51' × 26' × 45' high, and a Friday market, where small quantities of grain, coarse cloth, and vegetables are brought for sale. It has a school with an average attendance of forty-five boys. Though now a small village, Bid is said to have once been the capital of an old chiefship which included Kolhápúr and Panhála. Round the village are many ruins, among them an old stone temple with an image under which is a broken stone with the fragment of an inscription. The walls and columns, with numerous mouldings and much scroll work are in the style of about the thirteenth century. Small ancient gold coins are sometimes found near the old mud fort.

Bid.

<sup>1</sup> Details of the 1844 rebellion are given above under History, 241-242.

## Chapter XIII.

## Places.

## CHIKHALI.

**Chikhali**, a village in Kágál, with in 1881 a population of 2403, lies twenty-one miles north of Kolhápúr at the meeting of the Chitráganga and Vedganga. The village is apparently named from the *chikhal* or mud which the Chitráganga and Vedganga leave in large quantities during the rainy season floods. Twice a week on Mondays and Saturdays markets are held, to which grain and cloth are brought for sale. Chikhali has a school with an average attendance of eighty-nine boys and an old State mansion which is said to have been built in 1807.

## CHINCHLI.

**Chinchli**, an *indám* or alienated village belonging to the Desái of Chinchli in Shirol, lies on the Krishna about forty-two miles south-east of Kolhápúr. According to the 1881 census it had a population of 31,160 of whom 3110 were residents and 28,050 were visitors at the large fair of Mahákáli. It has a school with an average attendance of fifty boys. The place is chiefly known for the shrine of the goddess Mahákáli popularly called Máyáka. Four times a year pilgrims visit the shrine and on the full-moon of *Mágh* or January-February a large fair is held. The fair is attended by about 35,000 people some of whom come forty or fifty miles. Besides grain, cloth, and copper and brass vessels, large numbers of cattle are brought for sale. The sales average £6000 (Rs. 60,000). In 1883 the Political Agent took advantage of the large cattle fair to start a horse and cattle show. To support this show contributions were started by the Kolhápúr State and collected from the chiefs and gentry of Sátára and the Bombay Karnáta. On the 25th of February 1883, His Excellency Sir James Fergusson, the Governor of Bombay, held a *darbár* at Chinchli which was attended by about fifty of the Southern Marátha chiefs and gentry, and on the 26th opened the cattle show and distributed prizes.

## GADINGLAJ.

**Gadinglaj**, the head-quarters of the Gadinglaj sub-division, lies on the left bank of the Hiranyakeshi close to the Sankeshvar-Párpoli pass road forty-five miles south-east of Kolhápúr. About 280 years ago (1600), want of water is said to have forced the people to move the town to the river bank from an older site about 4600 feet to the north-west. Like other Kolhápúr towns Gadinglaj suffered greatly during the long wars at the close of the eighteenth century (1773-1810), especially at the hands of the Patvardhan Konherráv and the Nipánikar. The fort which was built about 1700 by an ancestor of the Kápsi family is now in ruins. The town is thriving. About thirty years ago (1853) it had 627 houses and 3000 people, in 1872 4670 people, and in 1881 1005 houses and 5002 people. The main road, which runs from the north gate to the river, has large tiled houses on both sides. On every Sunday a market is held when large quantities of rice and other grain are brought for sale. Till 1854 Sámángad was the head-quarters of the sub-division. In 1854 the new sub-division of Gadinglaj was formed and the *mámlatdár's* office moved from Sámángad to Gadinglaj, and in 1881 the *munsif's* court was moved to Gadinglaj from Kadegaon four miles north of the town. Of public buildings outside of the town are the *mámlatdár's* and *munsif's* offices built at a cost of £3498 (Rs. 34,980), a dispensary built at a cost of £853 (Rs. 8530), and a

standard rest-house built at a cost of £415 (Rs. 4150). It has also a library, a post office, and a vernacular school with an average attendance of 199 boys. The chief temple in honour of Káleshvar in the centre of the town is built of rubble and mortar 30' × 20' × 30' high. About three miles north of Gadinglaj is a temple of Bahiri, where every March a fair is held attended by about 2000 people.

**Gárgoti**, the head-quarters of the Bhudargad sub-division, with in 1881 a population of 1622, lies thirty miles south of Kolhápúr. On Sunday a weekly market is held to which grain and coarse cloth are brought for sale. Of public offices it has a mámlatdár's, a chief constable's, a sub-registrar's, and a post office, a rest-house, and a school with an average attendance of 123 boys.

**Ghunki**, a village in the Alta sub-division, with in 1881 a population of 2502, lies on the Várna, seventeen miles north of Kolhápúr. Near this village on the Poona-Belgaum mail road the Várna is bridged. The village has a branch school with an average attendance of twenty-seven boys. Formerly Ghunki was a frontier military station and had a detachment of 100 horse called the *jilbi pága* supported from the revenue of Ghunki and two other villages.

**Godchi**, a village belonging to the chief of Torgal, with in 1881 a population of 848, lies four miles north-east of Torgal and a hundred miles south-east of Kolhápúr. It has an old stone and cement temple of Virbhadrá, 54' × 22' × 32' high including the dome. The chief worshippers at this temple are Lingáyats. Every year on the fifteenth of *Márgshirsh* or November - December a large fair is held attended by about 10,000 people from a distance of twenty or thirty miles. The goods sold are estimated to be worth about £200 (Rs. 2000).

**Hátkalangda**, the head-quarters of the Alta sub-division, with in 1881 a population of 2415, lies on the Kolhápúr-Miraj road, fifteen miles north-east of Kolhápúr. According to a local legend Hátkalangda is named from a stone hand or *hát* which was set up in memory of a man who passed an ordeal by dipping his hands in boiling oil. The people, who are mostly Maráthás, live in 473 houses. The village roads are narrow and irregular, but well repaired from local funds at a yearly cost of £20 (Rs. 200). Every Wednesday a market is held at which the chief articles sold are raw sugar and turmeric. In a substantial building raised at a cost of £2704 (Rs. 27,040) are the offices of the mámlatdár, the chief constable, and the sub-registrar of the Hátkalangda sub-division. It has also a branch post office, a rest-house, and a school with an average attendance of seventy boys. The chief object of interest is a well preserved domed tomb or *darga* dedicated to Gorisáheb Pir. It is said to have been built about 500 years ago and is 33' × 26' × 33' high including the dome. The circumference of the dome is sixty-eight feet. Inside the dome is a Persian inscription written on a copper plate. The tomb enjoys rent-free land valued at a yearly assessment of £27 11s. (Rs. 275½). Of Hindu temples the temple of Narhari is 16' × 16' × 30' high and enjoys rent-free land valued at a yearly assessment of £3 10s. (Rs. 35); the temple of Vithoba has a good rest-house.

## Chapter XIII. Places.

GÁRGOTI.

GHUNKI.

GODCHI.

HÁTKALANGDA.

## Chapter XIII.

## Places.

## HERLA.

**Herla**, a large village in the Alta sub-division, with in 1881 a population of 3906, is on the Kolhápur-Miraj road eight miles north-east of Kolhápur. On every Saturday a market is held at which the chief article sold is grain. It has a police post of three men and a school with an average attendance of 111 boys. Formerly Herla was a military station with a detachment of horse called the *diván pága* or minister's troop. It has two old temples, one dedicated to Máruti and the other to Mahádev. The temple of Máruti, which is thirty feet long by twenty broad, is stone built and is about 200 years old. The temple of Mahádev seems older than the temple of Máruti and has a portico resting on stone pillars. It is thirty-four feet long and twenty-one broad. Herla has a Siláhára inscription on a stone in Old Kánarese characters dated *Shak* 1040 (A.D. 1118), making a grant to a Jain temple.<sup>1</sup>

## HUPRI.

**Hupri**, a village in the Alta sub-division, with in 1881 a population of 3335, lies ten miles south-east of Kolhápur. On every Saturday a weekly market is held at which the chief article sold is grain. It has a police post of three men and a school with an average attendance of eighty boys. It had a munsif's court which has since been moved to Shirol. Hupri had once a name for its fine piece goods, but of late the weaving of fine cloth has greatly declined. At present (1884) it has fifty looms but all of them are for coarse cloth. It has two old temples of Ambábái (17' x 15' x 27' high) and of Mahádev (15' x 13' x 18' high) both built of stone and mortar. Every April at Ambábái's temple a fair is held attended by about a thousand people.

## ICHALKARANJÍ.

**Ichalkaranji**, the head-quarters of the feudatory chief of the same name, lies in the Panchganga valley about eighteen miles east of Kolhápur and half a mile north of the river. The town is said to be formed of seven hamlets. The climate is healthy, but the water of the wells is brackish. Lately good drinking water has been brought in iron pipes from the Panchganga by the help of a steam pump raised on a tower built in the river. In 1881 it had 9107 people living in 1719 houses of which one thousand were two-storeyed. The streets are kept clean and in good repair. Most of the people are well-to-do and four or five are rich moneylenders. Every Wednesday and Thursday a market is held to which grain, cloth, and a considerable number of cattle are brought for sale. Besides an old mansion of the chief to the west of the town, surrounded by a thick mud wall enclosing a space about 6000 feet square, where are the offices of the State manager or *kárbhári* and the subordinate judge, there are three or four good rest-houses, a post office, a girls' school, and an anglo-vernacular school with an average attendance of 107 boys. Every year in October a large fair attended by 1000 to 2000 people is held in honour of Vyankatesh the guardian deity of the State. On the 24th and 25th of *Saffar* a Muhammadan fair or *urus*, attended by about 1000 people from ten to twenty miles round, is held in honour of Magdam Pir and Dari Pir.



**Jotiba's Hill**, also called Vádi-Ratnágiri, lies about nine miles north-west of Kolhápúr. The hill rises about 1000 feet from the plain in a truncated cone, and, though disconnected, forms part of the Panhála spur which stretches from the Sahyádrí crest to the Krishna. On the woody hill-top is a small village with 340 houses and 1564 people mostly *guravs* or priests of Jotiba. From very old times this hill has been considered specially sacred. In the middle of the village is a group of temples, the three best of which are dedicated to Jotiba under the names of Kedárling, Kedáreshvar, and Rámling. The temple of Kedárling stands between the two others. According to a local legend Ambábái of Kolhápúr being disturbed by demons went to Kedáreshvar in the Himálaya hills, practised severe penance, and prayed him to destroy the demons. In answer to her prayers Kedáreshvar came to Jotiba's hill, bringing with him and setting up the present Kedár *ling*. The original temple is said to have been built by one Návji Saya. In its place about 150 years ago (1730) His Highness Ránojiráv Sínde built the present temple. It is a plain building  $57' \times 37' \times 77'$  high including the spire. The second temple of Kedáreshvar which is  $49' \times 22' \times 89'$  high was built by Daulatráv Sínde about seventy-five years ago (1808). The third temple of Rámling,  $13' \times 13' \times 40'$  high including the dome, was built about a hundred years ago (1780) by one Málji Nilam Panhákar. In a small domed shrine in front of the temple of Kedáreshvar are two sacred bulls of black stone. Close to these temples is a shrine sacred to Chopdai which was built by Pritiráv Himmat Bahádúr about 125 years ago (1750). It is  $52' \times 46' \times 80'$  high including the dome. A few yards outside of the village stands a temple of Yamái built by Ránojiráv Sínde. It is  $47' \times 27' \times 49'$  high including the dome. In front of Yamái are two sacred cisterns, one of which ( $164' \times 143' \times 18'$  deep) is said to have been built by Jijábái Sáheb about 1743; the other called Jámadagnya *thirth* and built by Ránojiráv Sínde is  $54' \times 52' \times 13'$  deep. Besides these two *tirths* or sacred pools, five ponds and wells and two sacred streams flow down sides of the hill. One stream rising from the Kushávarta pool is called the Goda, the other which rises to the north of the hill and is known as Haimavati falls into the Várna. Most of the temples on Jotiba's hill are made of a fine blue basalt which is found on the hills. In many parts the style of architecture, which is strictly Hindu, is highly ornamented, several of the sculptured figures being covered with brass and silver plates. The chief object of worship is Jotiba, who, though called the son of the sage Pangand, is believed to have been Pangand himself who became man to help the rulers of the Deccan in their fights with demons. According to tradition Jotiba's destruction of one of the demons named Ratnásur gave the place the name of Ratnágiri in addition to those of Kedárling, Kedárnáth, and Náth. In honour of the victory over the demon, on the full-moon of *Chaitra* or March-April a yearly fair is held attended by 40,000 or 50,000 people some of whom occasionally come from a distance of 700 miles. The sale of grain, cloth, copper and brass vessels and sweetmeats is estimated to be worth about £4500 (Rs. 45,000). Besides this great fair, small fairs are held every Sunday and full-moon day and on the bright sixth of *Shrávan* or

## Chapter XIII.

## Places.

## JOTIBA'S HILL.

## Chapter XIII.

## Places.

## JOTIBA'S HILL.

August. On these days the image is carried round the temple in a litter with great pomp. The image in which Jotiba dwells is of a soft black stone, and the stone in which his wife Yamái lives is a rough unshaped block smeared with oil and redlead. On the great fair day in *Chaitra* or March-April a brass image of Jotiba amid the shouts of 40,000 to 50,000 people, is carried to Yamái for the yearly marriage. Part of the ceremony is to lay between Jotiba and Yamái a seal or *shikka* and a dagger or *katár*. To support the staff of ministrants the temples have a yearly revenue of more than £1200 (Rs. 12,000) of which His Highness Sindia pays £750 (Rs. 7500). Out of this revenue twenty-eight wayfarers are daily fed at the gateway, ten Bráhmans are busy in ceaseless prayer, and twenty-three servants and several horses and elephants are kept to attend the grand festival. Since 1873 a poll-tax of  $\frac{3}{4}$ d. to 1 $\frac{1}{2}$ d. ( $\frac{1}{2}$ -1 a.) has been levied from the pilgrims visiting the place on the chief fair days. The yearly collection amounts to about £360 (Rs. 3600) part of which is spent in mending the roads and keeping the place clean. There is a good rest-house and the water-supply has been lately improved. It is proposed to make a cart-road to join Jotiba's hill with the Kolhápur-Ámba pass road.

## KÁGAL.

**Ká'gal**, the head-quarters of the estate of the same name, which belongs to the Ghátge family, is twelve miles south of Kolhápur on the Poona-Belgaum mail road. It lies in the valley of the Dudhganga about a mile south of the river and is surrounded by rich garden land shaded by fine old mango trees. In 1881 the town had 6371 people living in 1046 houses. Its roads are good and well kept. Twice a week on Monday and Thursday, markets are held, and large quantities of grain and coarse cloth are sold. Between 1775 and 1825 Kágál was more than once sacked and burnt by the Rájás of Kolhápur. It has the offices of the chief of the State, the *kárbhári* or manager, the chief constable, the sub-registrar, and the *munsif*, and an anglo-vernacular school with an average attendance of 224 boys and twenty-two girls, an English and a native dispensary, a post office, and a library. The town has also a municipality, which without any local taxation is supported by a yearly fixed grant from the chief of £60 (Rs. 600). In 1882-83 the municipal expenditure amounted to £51 10s. (Rs. 515).

The oldest known mention of Kágál is in grants or *sanads* of the sixteenth century from the Bijápur government. No old buildings remain entire but there are ruins of mosques and temples. The old fort was destroyed by Yashvantráv Shinde of Kolhápur in 1780. In its place about 1813 the late Hinduráv Ghátge built a new fort 377 feet from east to west by 366 feet from north to south. It is enclosed by a ditch and a thick stone wall now much ruined. The eastern portion of the rampart was destroyed in 1858 by order of the British Government. Besides a large mansion built within the town by the late Hinduráv, after the model of the famous palace of Deeg, and several good houses belonging to the relations of the Ghátge family a large mansion or *váda* stands at a small distance of the town, built by the present chief at a cost of about £10,000

(Rs. 1 *lák*h). Of the public buildings lately raised by the chief at a cost of about £10,000 (Rs. 1 *lák*h) the most important are three large rest-houses, a fine school-house, three temples one sacred to Rám called Rámamandir where is the *kárbhári*'s office, a second dedicated to Máru<sup>t</sup>i, and a third to Rádhákrishna, and water-works from which pipes supply the town reservoirs with water. Every year in *Kártik* or October-November a fair or *urus* is held in honour of Saibi Pir, at which the chief spends about £200 (Rs. 2000). The fair is attended by about 10,000 people from Kolhápur and the neighbouring villages, and the sale of grain, cloth, fruit, and sweetmeats amounts to about £300 (Rs. 3000).

## Chapter XIII.

## Places.

## KÁGAL.

**Kále**, a village in the Panhála sub-division, with in 1881 a population of 1311, lies nine miles west of Kolhápur. The village is said to take its name from the goddess Káli whom according to a local legend, Dharma Rája, the eldest of the Pándavs, slew on the hill near the village. Marks on the hill still make the outline of Dharma Rája with his arrow fixed in Káli's body. The village has a police post of four men and a school with an average attendance of fifty boys. Every Monday a market is held at which the chief article sold is grain. The holiest temple which is dedicated to Dharma Rája, is twenty-five feet long and twelve broad.

## KÁLE.

**Kaneri**, a small village in the Karvir sub-division, lies six miles south of Kolhápur. The village is known for its Lingáyát monastery or *math* in a hamlet on a neighbouring hill. The monastery which is called Kadápácha Math, belongs to a Lingáyát Svámi or ascetic and is surrounded by a stone wall. In the middle of the monastery is a temple of Siddheshvar, 20' x 20' x 30' high. Round the temple of Siddheshvar are small shrines dedicated to Adkeshvar, Chakreshvar, and Rudrapád with the sacred bull in front. The monastery has a total yearly income of £150 (Rs. 1500). The head of the monastery has great influence and has between 5000 and 6000 Lingáyát disciples in Kolhápur, the Konkan, Bombay, the Karnáta<sup>k</sup>, Maisur, Belári, and Madras.

## KANERI.

**Kápsi**, the head-quarters of the Senápati's or general's estate of the same name, lies in the Gadinglaj sub-division about twenty-four miles south of Kolhápur. In 1881 it had 648 houses and 3414 people. On every Monday a market is held, to which grain, coarse cloth, and metal vessels are brought for sale. Kápsi has a police post and a school with an average attendance of 104 boys. The chief building is an old mosque 100 feet square and eight feet high, built of stone and mortar and plastered inside with stucco. Kápsi has a temple dedicated to Ái Sáheb, in memory of the pious Dvárká-bái Sáheb the wife of the well known Santájiráv Ghorpde.

## KÁPSI.

**Ká'sarde**, a village belonging to the Pratinidhi of Kolhápur, with in 1881 a population of 437, lies thirty-six miles north-west of Kolhápur. On a hill a mile and a half from the village stands a temple 26' x 13' x 8' high, sacred to Dhopes<sup>h</sup>var whose image is said to be *svyambhu* or self-made. According to a local legend, while a Váni of Karád named Purvata was returning from the sea coast with a pack bullock loaded with tin and iron, the animal strayed to the place where the self-made image of Dhopes<sup>h</sup>var was

## KÁSARDE.

## Chapter XIII.

## Places.

## KÁSARDE.

lying. The Váni followed his bullock and passed the night where the bullock had stopped. On rising next morning the Váni found that the tin and iron had turned into gold. In return for this gift of wealth the Váni built a temple to Dhopeshtar with part of the money, and that it might be afterwards used in completing the spire, he buried the rest in a corner to the north of the temple. Dhopeshtar issued an order forbidding any one digging up the treasure and it has never since been touched. The temple has a yearly income of £40 (Rs. 400) derived from the whole village of Kásarde and part of the village of Javali. It is sometimes visited as a health-resort by the Pratinidhi family.

## KATKOL.

**Katkol**, the seat of the chief of a detached group of eight Kolhápúr villages, lies about eight miles north-west of Rámdurg and eighty-five miles south-east of Kolhápúr. It is enclosed by a prickly-pear covered mud wall about fourteen feet thick and 7000 feet in circumference, with eleven towers nearly all of which have fallen. In 1881 the population was returned at 4292 against 4955 in 1872. On Friday a weekly market is held. Katkol has about 210 weavers of coarse cotton cloth and blankets. Under the mámlatdár of Gad-inglaj, Katkol has a joint officer who has the revenue and criminal powers of a *mahálkari* and can settle civil suits up to £5 (Rs. 50). It has a school with an average attendance of 119 pupils held in a school-house which cost £90 (Rs. 900), a private school attended by twenty-five boys, and a rest-house built at a cost of £110 (Rs. 1100). At an interval of five, seven, or ten years, in honour of Durgava, a large fair called *Rede Játra* or Buffalo Fair, is held attended by about 10,000 people from twenty-five to thirty miles round. At this fair buffaloes are offered to the deity. Of the Hindu temples the chief are the temple of the goddess Shri Kariyama  $24\frac{3}{4}' \times 21\frac{1}{4}' \times 13\frac{3}{4}'$  high, and the temple of Virbhadrá  $50' \times 14' \times 23'$  high including the spire. Katkol has also a Lingáyát monastery known as Choki Math  $66' \times 33' \times 20'$  high.

## KHIDRÁPUR.

**Khidra'pur**, an alienated village belonging to Sankeshvar Svámi, with in 1881 a population of 1036, lies on the Krishna about twelve miles south-east of Shirol. The chief interest of the village is the temple of Kopeshtar which lies in the centre of the village and is  $103\frac{1}{2}' \times 65' \times 52\frac{1}{2}'$  high to the top of the dome. The walls are made of black stone richly carved and the dome is covered with stucco. To the main building are attached two richly sculptured *mandaps* or vestibules. In the vestibule are two concentric squares the outer with twenty and the inner with twelve pillars all richly carved. In front of the temple is a round roofless structure called the *Svarga Mandap* or Heavenly Hall, on the plan of what would be a twenty-rayed star, only that the spaces for four of the rays are occupied by four entrances. On the outside on a low screen wall stand thirty-six short pillars, while inside is a circle of twelve columns. Further from the temple is a *naḡárlkhána* or drum-chamber. The outer walls of the shrine are broken at oblique angles as in the Nilang Hemádpanti temple. By the south door of the temple is a Devgiri Yádav inscription of Sinhadev in Devná-gari dated *Shak* 1135 (A.D. 1213) granting the village of Khandál-eshvar in Mirai for the worship of Kopeshtar. Besides this there

is a Jain temple, which is much smaller, the vestibule being twenty-one feet square inside with a small antechamber and shrine, the outer wall of the shrine being in the star-shaped Hemádpanti plan. The building is of black stone and the pillars of the hall are richly carved. Land valued at a yearly assessment of £37 10s. (Rs. 375) is granted rent-free to the priests of Kopeshvar. Every year in *Paush* or December-January a fair is held attended by about 2000 people.

**Khodsi** or **Khochi**, a village in the Alta sub-division, with in 1881 a population of 1739, lies on the Várna thirteen miles north-east of Kolhápúr. It has a school with an average attendance of fifty boys. The village is known for the temple of Bhairav Kshetrapál an incarnation of Shiva, with his wife Jogeshvari by his side. The body of the building is a square of fifteen feet, built of stone, with a portico seventy-five feet long and fifteen feet broad in front. The temple is said to have been built about 200 years ago (1680) by an *inám-dár* of Chávra in the Alta sub-division named Sultánráv Sínde. At the yearly fair held in *Chaitra* or March-April, among a number of poles or *shásan káthís* which parade the fair the place of honour is given to Sultánráv's pole. The fair is attended by about 10,000 people.

**Kini**, a village in the Alta sub-division, with in 1881 a population of 2660, lies thirteen miles north of Kolhápúr on the Poona-Belgaum mail road. It is held in *saranjám* or military grant by Sardár Himmat Bahádúr. Kini has a travellers' bungalow, a rest-house, and a school with an average attendance of sixty-one boys. It has two old temples, one of Mahádev twenty-one by fourteen feet and the other of Máruti forty feet by twenty-five.

**Kodoli**, a large thriving village in Panhála in the Várna valley, lies about fourteen miles north of Kolhápúr and a mile and a half from the river. In 1881 it had 4942 people living in a thousand houses, of which 100 were two-storeyed, 600 tiled, and 300 thatched. The people are mostly Kunbis who raise rice, sugarcane, turmeric, betel-leaves, and chillies, worth about £2000 (Rs. 20,000) a year. Kodoli has also 125 hand-loom which yield a yearly outturn of coarse cotton cloth worth about £2000 (Rs. 20,000). Every Thursday a market is held attended by about 1000 people to which grain and hand-woven cloth and yarn are brought for sale. Kodoli has a rest-house, a police post of five men, and a school attended by ninety boys and ten girls. It is well supplied with river and spring water. The chief temple, which is dedicated to Dattátreya, is 180 feet square. Every year on the dark 5th of *Mágh* or January-February a fair is held attended by about 1000 people from a distance of ten to fifteen miles.

**Kolha'pur**,<sup>1</sup> north latitude 16° 41' and east longitude 74° 17', is the capital of the Kolhápúr State and the head-quarters of the Political Agent for the Southern Marátha States. The city stands on rising ground about 1790 feet above the sea and about half a mile

## Chapter XIII.

## Places.

KHIDRÁPUR.

KHODSI OR  
KHUCHI.

KINI.

KODOLI.

KOLHÁPUR.

<sup>1</sup> For the origin of the name see above note 1 on page 1.

## Chapter XIII.

## Places.

## KOLHÁPUR.

from the right or south bank of the Panchganga. It is sixty-four miles east of the coast, seventy-six miles south of Sátára, and sixty-six miles north of Belgaum. According to the 1881 census Kolhápúr has a population of 38,599 living in 8023 houses. It is the largest city in the Bombay Karnátaḱ or Southern Maráṭha country. Including the suburbs it has a circumference of  $4\frac{1}{2}$  miles and an area of 358 acres. It is bounded on the north and east by the Jiti stream which runs dry during the hot season, on the south by the Varun pool and the Phirangái and Padmála lakes, and on the west by the Panchganga river and the Rankála lake.

## Aspect.

The land round the town is shallow *murum* or crumbly trap over true trap, open and bare except during the rains. On both banks it rises slowly from the river and on the south over waving ground to a range of low hills. The drainage of these hills is carried off by the Jiti stream which runs north along the eastern front of the town skirting the Ravivár ward at a distance of about 300 yards from the fort. From this it flows north below the Somvár ward and old Budhvár till it joins the Panchganga at Brahmaपुरi. On the south-west beyond the suburbs is the lake of Rankála with an area of about 500 acres. On the south-east somewhat above the town lies the Padmála lake. On the north-east, east, and south the land on the bank of the Jiti is tilled, and between the Rankála lake and the river on the west the fields are marshy. The Residency and military cantonment are on rising ground about  $2\frac{1}{2}$  miles north of the town. Near the centre of the town is Brahmaपुरi hill in which all the remains of the early settlement centre. Kolhápúr is entered by nine roads. On the north by a road from Poona over the Panchganga ford by Bávda village and the cantonment; on the east by three roads meeting in one, the Poona mail road from the north, the Miraj road from the east, and the Belgaum mail road from the south; on the south by a road from Bhudargad by the Kátyáyani hill; and on the west by three roads by the Phonda Bávda and Ámba passes. The buildings which show most on coming to the city are the *Nagárkhána* or Drum-chamber, the Palace, the High School, the Hospital, and Ambábái's temple.

## Climate.

Before the beginning of British superintendence in 1844, Kolhápúr was dirty and unhealthy. The city suffered from outbreaks of cholera, sometimes as in 1824 so severe that about 8000 people died in a fortnight. Since 1844, by widening cleaning and draining the streets, by removing dirt and nightsoil, by pulling down the ramparts and filling the ditch, and by increasing the water-supply, the health of the city has been greatly improved. Except from March to May when it is hot and at times oppressive, the climate is temperate, pleasant, and wholesome. From March to May hot winds prevail, but the sea breeze which begins in the afternoon and lasts till eight makes the evenings cool and pleasant. During the cold months from the river and lakes heavy fogs rise and hang over the city. The temperature averages  $76^{\circ}8'$  and the rainfall  $44^{\circ}8'$  inches. The well water is hard and brackish, but the water from the Kátyáyani hill is excellent. During the five years ending 1882 births averaged 21.6



in the thousand and deaths, which are more correctly recorded, 29·7. During the five years ending 1874-75 no case of cholera occurred. Since 1875 there have been several outbreaks of cholera but all except in 1881-82 have been mild. The prevailing diseases are malarious fever, bowel complaints, parasitic diseases, and affections of the eye and skin.

Kolhápúr is plentifully supplied with water from wells, the Panchganga river, the Kátyáyani conduit, and ten reservoirs and lakes. The well water is brackish and is chiefly used for washing. Except the Panchganga water which is used by the people of the Shukravár ward and the Rankála lake water which is used by the people of the Budhvár ward, the main supply of drinking water is from the Kátyáyani conduit. Before the Kátyáyani conduit was built, the city suffered much from want of drinking water. About the end of the eighteenth century (1792) a rich resident of Poona named Báburáv Keshav Thákur or Khatri, while on a pilgrimage to Kolhápúr, was asked by other pilgrims to bring water from Kátyáyani to supply Ambábái's temple. Báburáv asked the Rája's leave. According to the local legend, the Rája was at first unwilling to let a stranger supply the goddess with water but Ambábái warned him in a dream to grant Báburáv's request. In 1792 a masonry conduit was completed which brought water to two reservoirs in Ambábái's temple one for Bráhmans and the other for other castes. Afterwards, to supply Vithoba's temple with water two more reservoirs were built. These water works are said to have cost Báburáv about £30,000 (Rs. 3 *lákhs*). Báburáv also deposited £2000 (Rs. 20,000) with the well-known Kolhápúr moneylender Kodolkar the interest of which was to be spent in repairs. As it was a charitable work, the Kátyáyani water was not at first used by the ruling family and their dependents. In time the water began to be used by all, and in the palace and houses of the nobles several cisterns were built, into which water was brought from the main aqueduct. The Kátyáyani water is pure and wholesome. Of the ten reservoirs and lakes in the city the Rankála lake alone supplies drinking water. As the Kátyáyani water-supply was not enough for the whole city, in 1830 from the Rankála lake water was brought by a small conduit. As the level of the Rankála lake is low, the water does not go into the fort, but is distributed only in the suburbs. The Rankála lake lies to the south-west of the city and has an area of nearly three miles with a depth of thirty-five feet. The lake is named after the god Rank Bhairav, who is said to have been a great favourite with Maháalakshmi and to have a gold temple now hid under the water of the lake. The beginning of the Rankála lake is said to have been a quarry, from which according to the Jains, including the temple of Ambábái, stones were supplied to 360 *bastis* or Jain temples built by a Jain Rája Gandharáditya. Afterwards in the eighth or ninth century, an earthquake is said to have enlarged the quarry and filled it with water. The lake now receives water from two streams in the north and has also a waste weir outlet in the north. Lately in 1883 the Rankála water-supply has been much improved and increased by building a large reservoir near Kalamba village about three miles to the south which is capable of holding two years'

## Chapter XIII.

## Places.

## KOLHÁPUR.

## Water.

## Chapter XIII.

## Places.

## KOLHÁPUR.

## Water.

supply. A new cut-stone dam higher and stronger than the old dam has been built on the city side. New pipes have been laid and water is distributed by stand-cocks eighty or ninety feet apart. The use of Rankála water for bathing and washing has been forbidden and along the side of the dam troughs and baths are being built at an estimated cost of £2574 (Rs. 25,740). The improvements are not yet (1883) complete; up to October 1883 the cost was £24,196 (Rs. 2,41,960). None of the nine other lakes and reservoirs are much used for drinking. They are the Mhár reservoir in the north-east, the Koti and Rávneshvar pools in the east, the Padmála pool in the south-east, the Phirangái and Varun pools in the south, the Khambála and Kumbhár pools in the west, and the Kapil pool in the centre. The Mhár reservoir which during the hot season runs nearly dry, used to water the Kharala garden. The Koti and Rávneshvar pools are small and full of lotuses. The Padmála reservoir has its water carried into two reservoirs, one in front of the Mangalvár gate and the other in the Áditvár ward. Its water is partially used for drinking in the Mangalvár ward and is chiefly used in watering two State gardens the Sheribág in the south-east and the Káshibág in the east. Of the Phirangái and Varun pools in the south, the water of the Varun pool is impure and is used only in watering a small garden about the Bávdekar's mansion. It is full of a fine variety of water lily. The Khambála reservoir lies in the west within the limits of the old fort close to the Bábujamál shrine. Near this shrine the water is used for a large plantain garden. The Kumbhár pond, as its name suggests, is chiefly used by Kumbhárs or potters. The Kapil pool in the centre of the city receives so large a quantity of surface drainage that its water is undrinkable.

## History.

Kolhápúr, or as it seems to have been formerly called Karvir, is probably one of the oldest religious and trade centres in Western India. In Brahmapuri hill, near the centre of the present city, have been found Buddhist coins which are believed to belong to the first century before Christ; a small crystal casket which is believed to have enclosed Buddhist relics of about the same age and a shattered model of a brass relic-shrine or *śāghoba* whose shape also belongs to about the first century before Christ.<sup>1</sup> The discovery of a Shátakarni inscription probably of the first century after Christ at Banavási in North Kánara and the known extent of the power of that dynasty in the North Deccan, make it probable that, as suggested by Professor Bhándárkar, Ptolemy's (A.D. 150) Hippokura rejia Baleokuri refers to Kolhápúr the capital of king Viliváyakura, who from inscriptions is believed to have reigned about A.D. 150. From the fact that the old name of Kolhápúr is Karvir or the fragrant oleander *Nerium odorum*, Mr. Fleet has suggested that Kolhápúr may be the site of the great ancient trade centre of Tagar a name which like Karvir means the shrub *Tabernæmontana coronaria*. Against the identification of Tagar with Kolhápúr is to be set the fact that both in Ptolemy (A.D. 150) and in the Periplus of the Erythræan sea (A.D. 247) Tagar is placed to the east not to the south of Paithan, that as there were several ports in the Ratnágiri or Pirate coast,

which traded with Broach the trade between Kolhápúr and Gujarát would have passed by sea from some of the Konkan ports not by land road by Paithan; and that the details given in the *Periplus* of cloth being brought to Tagara from the parts along the sea-coast seems to point to communication with the Bay of Bengal and therefore to some place within the limits of the Nizám's country.<sup>1</sup> Next to Brahmapuri hill the oldest known object in Kolhápúr is the temple of Ambábái or Mahálakshmi, which is supposed to mark the centre of old Kolhápúr. In former times this great temple was surrounded by a circle of shrines several of which lie buried many feet under ground. At present (1883), besides the great temple of Ambábái, Kolhápúr has about 250 temples above and under ground. Every pool of standing water is sacred and in the city and country round are many broken images of Bráhmaṇ and Jain worship which are supposed to belong to temples destroyed by the Musalmáns in the thirteenth and fourteenth centuries. According to Major Graham<sup>2</sup> in the eighth or ninth century an earthquake overturned many temples and buildings in Kolhápúr. Among the traces of the earthquake are the two underground temples of Khandoba and Kártik Svámi, over which houses have since been built. In the old temple of Ambábái the wall is of unequal height in different places, and the ground has passed through so many changes that the original level cannot be discovered. In digging the foundations of the high school in 1870, and in making other excavations, at a depth of over fifteen feet shrines, stone slabs covered with strange figures, and old inscriptions have been found. In support of his statement that many of these changes are due to the action of an earthquake Major Graham refers<sup>3</sup> to several small mounds or upheavings near the city and to the discovery in 1849 of the bed of the Panchganga seventy feet above the level of its present bed. In the Karvir or Kolhápúr Mahátmya or account of the greatness of Kolhápúr, a modern (1730) Bráhmaṇical work,<sup>4</sup> Kolhápúr is mentioned as the Káshi or Benares of the south. According to local tradition, when the Jains were building the temple of Ambábái on Bráhmaṇpuri hill a fort was made by a Kshatri Rája Jaysing who held his court at Bid about nine miles west of Kolhápúr. In the twelfth century the Kolhápúr fort was the scene of a battle between the Kalabhurya or Kalachurya who had conquered the Kalyán Chálukyas and become the ruler of the Deccan and the Shiláháras of Kolhápúr, the feudatories of the Chálukyas. Bhoja Rája II. (1178-1209) of the Kolhápúr Shiláháras made Kolhápúr his capital, but the head-quarters of the State were soon after moved to Panhála about twelve miles to the north-west, and remained there till the country passed to the Bahmani kings.

## Chapter XIII.

## Places.

## KOLHÁPUR.

*History.*

<sup>1</sup> Bertius' Ptolemy 205; McCrindle's *Periplus*, 126. The discovery of the name Tagar in an inscription of the fifth century found near Hyderabad increases the probability of an eastern site for Tagar. Its name and position on the Godávári about 200 miles south-east of Hyderabad, suggest the town Tegur as a possible identification with Tagar. Of the present Tagar no information is at present available.

<sup>2</sup> Graham's Kolhápúr, 112.

<sup>3</sup> Graham's Kolhápúr, 317.

<sup>4</sup> Though it probably embodies old legends and traditions the Karvir Mahátmya or the Greatness of Kolhápúr was written as late as 1730.

## Chapter XIII.

## Places.

## KOLHÁPUR.

*History.*

Under the Bahmani kings (1347-1489) Kolhápúr seems to have been a place of no consequence. The only mention which has been traced in the Musalmán historians is Ferishta's notice of Kolhápúr as the place where Máhmud Gáwán (1469) encamped during the rainy season in his expedition against Vishálgad.<sup>1</sup> Under the Bijápúr kings, from 1489 till it came under Shiváji about 1659, owing to its nearness to the strong fort of Panhála, a Bijápúr officer was stationed at Kolhápúr. Under the Maráthás, especially after 1730 when it became independent of Sátára, Kolhápúr rose in importance. In 1782 the seat of government was moved from Panhála to Kolhápúr. Up to this time Kolhápúr's only protection against robbers and enemies was a mud wall. During the feuds between the Patvardhans and the Kolhápúr State (1773-1810) which filled the latter years of the eighteenth century, a stone wall thirty feet high and ten to twenty-six feet thick, was built more than  $1\frac{3}{4}$  miles in circumference. At equal distances the wall had forty-five bastions with battlements and loopholes and outside a deep and wide ditch with a rough glacis. In the wall were six gateways three of them double with stout wooden gates bristling with long iron spikes to keep off elephants. After the river reservoirs and the wards to which they led, the gates were named the Ganga, Rankála, Varuntirth, Aditvár, Mangalvár, and Shanvár. The entrance to each gate was across a drawbridge. The gates used to be shut at eleven in the evening and opened by four in the morning.<sup>2</sup> When the town was growing in the eighteenth century the people built houses without any order wherever sites could be had and the streets were narrow, often not broad enough for two carts to pass. As the city increased in size weekly markets came to be held outside of the walls. Beyond the walls ten suburbs or *peths* were founded. After the names of the founders, of the presiding god of the place, or of the days on which weekly markets were held, the new suburbs were called Ravivár, Somvár, Mangalvár, Budhvár, Sukravár, and Shanvár, and Otreshvar, Chandreshvar, Kesápur, and Lagmápur. In these suburbs the lanes are wide and are planted here and there with trees. Lately, to improve the air and health of the city the walls have been pulled down and the ditch filled.

<sup>1</sup> Briggs' Ferishta, II., 482-485.

<sup>2</sup> With four of the six gates some great event is connected. By the Ganga gate, which opened on the Panchganga river, no corpse except one of a member of the royal family was allowed to be carried. By the Aditvár gate, in 1857 the second band of mutineers led by Firangu Shinda entered the town, broke into the jail, and set the prisoners free. By the Mangalvár gate, in 1857 the mutineers of the 27th Kolhápúr Native Infantry tried in vain to enter the city. At the Shanvár gate, which is said to have been built by Ali Adil Sháh I. of Bijápúr (1557-1579), a hard battle was fought in 1800 between the Rája of Kolhápúr and the Patvardhans under Rámchandra, son of the well known Parashurám Bháu. In this gate, after a siege of two months a breach was made, scaling ladders were applied, and the city was on the point of being taken when an intrigue at the Poona court suddenly obliged the assailants to leave the city. In 1858, by breaking open the Shanvár gate, Sir LeGrand Jacob entered the city and arrested the mutineers under Firangu Shinda, who was shot by the treasury guard of the Kolhápúr infantry.

As the head-quarters of the State Kolhápúr has (1884) the offices of the *Diván* or minister, the Chief Judge, the Chief Revenue Officer, the assistants of the chief judge and the chief revenue officer, the divisional officers, the sub-divisional revenue and judicial officers, the executive engineer and the assistant engineer, the forest officer, and the deputy educational inspector. It has also a telegraph office in the camp, and two post offices one the disbursing office in the camp and the other a town sub-office in the city. Of educational institutions Kolhápúr has the Rájárám arts college attended by thirty-eight pupils. The college is affiliated to the Bombay University up to the first B. A., and has a *sardár* or chiefs' class attended by eight *sardárs* or chiefs. Besides the college, Kolhápúr has the Rájárám high school attended by 375 pupils, a normal school attended by twelve pupils, six vernacular schools for boys attended by 763 boys, a female training school attended by eight girls, four girls schools attended by 158 girls, and three night schools attended by 182 boys and men. It has also a native general library. In 1883 the Kolhápúr municipality had an income of £5091 10s. (Rs. 50,915) and an expenditure of £4371 14s. (Rs. 43,717).

## Chapter XIII.

## Places.

## KOLHÁPUR.

Of the buildings which have been lately raised by the State at a cost of about £250,000 (Rs. 25 *lákhs*), the chief are the high school a two-storeyed building with room for 300 pupils, which is built of stone and cement in the Indo-Saracenic style near the high school; an excellent girls school; the large hospital; the town hall with a good garden; the office buildings of the *mámlatdár* and *sadar-amin* and of the chief judge and the assistant judge; the native general library near the high school; four rest-houses; three markets or *mandayis*; five Maráthi school-houses; the *Risála* buildings, and the State stables. A large palace estimated to cost about £60,000 (Rs. 6 *lákhs*) is also under construction. Besides these buildings two bridges have been made one across the Panchganga and the other across the Jiti, and during the eight years ending 1883 the Kátyáyani and Rankála water works have been improved at a cost of about £70,000 (Rs. 7 *lákhs*).

## Objects.

Of about 250 temples in Kolhápúr city six are well known, the temples of Ambábái or Maháalakshmi, Vithoba, Temblái, Mahákáli, Phirangái or Pratyangiras, and Yallamma. Of these the temple of Ambábái, the largest and the most important, is in the middle of the town about a hundred yards north-west of the State palace. The temple is very old. The main portion of the building is of two storeys and is built of black stone brought from local quarries. The spire and domes of this temple are said to have been added by a Shankaráchárya of Sankeshvar; the Jains declare that the temple was a Jain temple dedicated to Padmávati and that the spire and domes are Bráhmanic additions. The architecture of the building supports the claims of the Jains to be its original possessors. The spire and domes do not harmonise with the carved work below which strongly resembles the style of the twelfth century in the Jain temples in the Bombay Karnátak. The image of the god Ganpati which ought to be carved on the lintel of every Bráhmanic

## Temples.

## Chapter XIII.

## Places.

## KOLHÁPUR.

## Temples.

temple is absent and the wall and domes are full of seated cross-legged figures, many of them naked. These details prove that this was originally a Jain temple. According to Major Graham, during some Musalmán persecutions in the fourteenth and fifteenth centuries the image of Ambábái was hid in a private dwelling and about 160 years ago (1722) was installed in the present temple by Sambháji Maháráj (1712 - 1760) who for this purpose sent Sidhoji Hinduráv Ghorpade from Panhála to Kolhápur.<sup>1</sup> The temple is in the form of a cross and is built with the mortarless close-fitting large blocks of stone known in the Deccan as the Hemádpanti style. It faces west on which side is the main entrance with the *nagárrkhána* or drum-chamber on the top. Besides the main entrance to the west three small gates open north, east, and south. The northern gate has a large bell, which is rung five times a day, at four in the morning, at noon, at one, at eight and nine o'clock in the evening. The body of the temple is built of local black trap without the help of any timber. Except a few doors it has no openings for air. Under the big dome on the east is installed the image of Ambábái; and on the north and south sides two smaller domes enclose images of Mahákáli and Mahásarasvati. Inside the big dome round the image of Ambábái is a closed dark passage with no opening of any sort and with lights burning day and night to enable the worshippers to go round the image. The cost of the building must have been immense; according to tradition it equalled the weight of the stones in gold. The upper works added by Shankarácharya are said to have cost about £10,000 (Rs. 1 *lakh*). The big hall in front was added during the administration of Dáji Pandit between 1838 and 1843. The main temple is surrounded by a stone wall in which are a number of other shrines including shrines of Dattátreya, Vithoba, Káshi-Vishveshvar, Rám, and Rádha-Krishna. The open space between the wall and the main building is paved with stone slabs. The temple has four inscriptions. One to the left of the entrance on the left side of the porch or outer *mandap* is written in Devnagri characters and is dated *Shak* 1140 (A.D. 1218); a second on a pillar on the left hand after entering the courtyard is in Devnagri characters and dated *Shak* 1158 (A.D. 1236); a third on a pillar of the small temple of the Navgrah to the left of the main building is written in Devnagri characters; and a fourth is behind the temple on the left hand when entering from the eastern gate. The temple of Ambábái is visited by large numbers of pilgrims many of whom come from long distances. Besides contributions from pilgrims which yearly amount to about £400 (Rs. 4000), the temple receives a yearly cash allowance of £500 (Rs. 5000). It is served by forty-two *pujáris* or ministrants. Every Friday night the image of Ambábái is paraded in a litter round the temple and a salute is fired.

<sup>1</sup> An extant *sanad* or deed by Sambháji assigning grants for the expenses of the temple, states that though under the Bijapur government (1489 - 1686) there existed many votaries well able to replace the image, Sambháji Rájá has alone the merit of re-establishing it in its ancient temple. Bom. Gov. Sel. New Series, VIII, 317.



Ambábái has three great days in the year. On the full-moon in *Chaitra* or March-April a brass image of the goddess Ambábái is carried in procession through the town in a triumphal car. On the bright 5th of *Ashvin* or September-October the image is carried in a litter in procession to the small temple of Temblái about three miles east of the city where the unmarried daughter of the headman of Bávda makes the deity the customary offering of a *kohala* or pumpkin. On the full-moon-day in *Ashvin* or September-October the dome and roof are covered with lamps.

The temple of Vithoba, which was probably built about the same time as Ambábái's temple, lies south-east near the Padmála or Mangalvár gate. A large space encloses five temples with a rest-house large enough for several hundred travellers. The chief temple, that of Vithoba to the right, is built of stone and is similar in style to the great temple of Ambábái. Another old temple to the left dedicated to Vishveshvar is similar in style to Vithoba's temple. The entrance is grand and has spacious rooms on the top. On the bright eleventh of *Ashád* or June-July and *Kártik* or October-November fairs are held in honour of the god Vithoba when flowers and leaves of the *bel* or *Ægle* marmelos and the *tulsi* or basil plant are offered.

According to the Karvir or Kolhápura Purán, Temblái the younger sister of Maháalakshmi, in consequence of a quarrel with Maháalakshmi left Kolhápura about 1800 years ago, and retired to a hill about three miles to the east of the city and remained there with her back turned on her elder sister. Ambábái is said to pay her sister one visit a year on the bright fifth of *Ashvin* or September-October. On this day a fair is held on the hill in honour of the goddess. An image of Ambábái is placed in a litter and carried in procession to the hill and a *kohala* or pumpkin is afterwards cut to pieces by an unmarried girl in memory of the destruction by the deity of a giant named Kolhásur. The procession is accompanied by the Rája with all his retinue. The fair is attended by 15,000 to 20,000 people and sweetmeats and other eatables as well as toys are offered for sale. Every third year and also during bad attacks of cholera and other epidemics a buffalo is offered to the goddess. The temple has a small allowance from the State and one *pújári* or ministrant is in attendance. Formerly every year in *Ashád* or June-July or in *Mágh* that is January-February it was customary in Kolhápura to offer a he-buffalo to the goddess Margái near Temblái. This practice has been stopped; but a sacrifice is still sometimes offered on special occasions, as was done during the sharp outbreak of cholera in 1881. For this offering Tuesday is the favourite day. A young he-buffalo set apart as a sacrifice is left at liberty for two or three years before he is expected to be wanted, to become fat and plump, because to be a fit offering the animal must be in good condition. On the morning of the appointed day the buffalo is anointed with oil and washed in hot water. Afterwards he is rubbed with redlead, sandalwood paste, redpowder or *gulál*, turmeric, and vermilion or *kunku*. About three in the afternoon its right thigh is quashed with a knife to make it bleed freely. The animal is then led round a certain part of the city to a certain distance his path being

## Chapter XIII.

## Places.

## KOLHÁPUR.

## Temples.

## Chapter XIII.

## Places.

## KOLHÁPUR.

## Temples.

marked by the drops of blood from the wound; palm juice, *náchni* gruel, baked grain, and pieces of lemon and cocoanut are thrown about by the village officers and others who escort the buffalo which, in the end, is slaughtered near the temple and offered to the deity.

The temple of Mahákáli, a favourite goddess of low class Hindus, lies in the new Budhvár ward. Every year in March April and July fairs are held in honour of Mahákáli. Goats are often offered. Formerly every two or three years a he-buffalo used to be offered, but this practice has been stopped.

The temple of Phirangai or Pratyangiras, a favourite goddess of the lower classes, lies between the Mangalvár and new Budhvár streets. In front of the temple is the holy Paulay pool. This goddess receives offerings of flour, salt, turmeric, and oil and she is supposed to have the power of curing children suffering from itch. Formerly buffaloes were offered, but lately goats have taken the place of buffaloes.

The temple of Yallamma a favourite goddess of the lower classes, lies in the east of the city. To this goddess unmarried women often make vows, the non-fulfilment of which is believed to be followed by disease or other bodily suffering. Some women who do not marry and become courtesans wear a necklace of white beads as a sign of their devotion to Yallamma. When married women become *jogtins* or ascetics, they must obtain a divorce before they adopt the precepts of Yallamma.

Besides these large temples, there are several under-ground shrines two to fifteen feet below the surrounding buildings. Pathways have been cut to their thresholds and the spires in many cases cleared and covered with fresh stucco. They are ten to twenty-five feet long and broad and fifteen to thirty feet high. The chief are the temples of Kártiksvámi and Khandobá. Besides these temples Kolhápúr has two large monasteries or *maths*, one belonging to the Sankeshvar Svámi and the other to a Jain Svámi. Outside of the city on the Panchganga in the north-west and close to the Brahmapuri hill are memorial temples in memory of deceased members of the Rája's family Sambháji, Shiváji III., and Ába and Báva Sáhebs. Shiváji III.'s temple which was built in 1815, is the largest and most elaborate, but it is an ill assorted combination of a large Musalmán hall and a lofty Hindu spire covered with stucco formed into mouldings and with a few ornaments. These tombs are *ling* shrines. Close by are a number of small shrines on the five *gháts* or flights of steps which lead to the river.

## KUMBHOJ.

**Kumbhoj**, a village in the Alta sub-division, with in 1881 a population of 4105, lies on the Várna eighteen miles north-east of Kolhápúr. The village is named after Kumbheshvar a form of Shiv who is the guardian of the village. Most of the people are Jains. Kumbhoj is known for its tobacco which is grown to an estimated yearly value of about £2500 (Rs. 25,000). On every Sunday a market is held. Kumbhoj has a school with an average attendance of 125 boys and a school-house built at a cost of £50 (Rs. 500). It has a

Jain temple of Bábabulli,  $40\frac{1}{2}' \times 34\frac{1}{2}' \times 37\frac{1}{2}'$  high including the spire; a Bráhmaṇ temple of Bānshankari, 200 feet square, and including the spire forty-nine feet high; and a domed Musalmán tomb dedicated to Hazrat Khátál Pir and built partly of stone and partly of burnt brick and mortar. During the 1876 famine an old reservoir to the south of the village was improved at a cost of £300 (Rs. 3000).

**Malkápur**, the head-quarters of the Pant Pratinidhi, the hereditary prime minister of the Kolhápúr State, lies twenty-eight miles north-west of Kolhápúr on the left bank of the Sháli river and close to the Kolhápúr-Ámba pass road. Malkápur was of little importance till in 1844 the Pratinidhi's head-quarters were moved to it from Vishálgad. In 1881 Malkápur had 2597 people living in 540 houses. On every Friday a large market is held attended by about 3000 people including traders from the coast. To mend the village roads and keep them clean £20 (Rs. 200) a year are granted from local funds. Besides the offices of the manager or *kárbhári*, the chief constable, and the *munsif*, Malkápur has a post office, a dispensary, and an anglo-vernacular school with an average attendance of 166 boys. It has two chief temples built of stone and mortar, one dedicated to Vishveshvar is  $58' \times 27' \times 23'$  high and the other dedicated to Bhimáshankar is  $55' \times 29' \times 18'$  high. A school-house has been lately built at a cost of £700 (Rs. 7000), and a good bridge thrown across the Sháli river.

MALKÁPUR.

**Panhála Fort** crowns one of the tops of the Panhála spur of the Sahyádris, about twelve miles north-west of Kolhápúr. The Panhála uplands are 2772 feet above the sea and about 700 feet above the Kolhápúr plain, and the hill top which the Panhála fort crowns rises about 275 feet above the uplands. The fort is about  $4\frac{1}{2}$  miles in circumference. For about half this distance it is protected by a scarp thirty to fifty feet high which in places is strengthened by a loopholed parapet wall. For the remaining half the fort is surrounded by a strong stone wall fifteen to thirty feet thick at the top and with bastions at convenient distances for carrying guns. The fort was entered through three magnificent double gateways which were reached from the tableland by long flights of stone steps. Of these three gateways two Vághdarvája and Chárdarvája have been destroyed and the third Tindarvája is still entire and is finely built with much light tracery on the door posts and architrave. About forty-six yards from the third gateway a breach about forty yards long marks the spot where the British troops forced an entrance when the fort was held by insurgents in 1844. North of the fort with a gorge about ninety yards wide is a natural basin, whose entrance is guarded by two large raised platforms. Two unfailing reservoirs and many pure springs afford an ample water supply, and a large area of rich soil and abundant brushwood secured the garrison from scarcity of grain or firewood.

PANHÁLA.

Panhála is the traditional residence of the sage Páráshar. The Karvir or Kolhápúr Purán a modern (1730) compilation mentions Panhála as Pannágálay or the home of Serpents. In old inscriptions the name appears as Pránlák and Padmanál. A copper

## Chapter XIII.

## Places.

## PANHÁLA.

plate found in Sâtára shows that in A.D. 1191-92 Panhála was the seat of the Silhára Bhoja Rája II. (1178-1209) who is first mentioned as living at Valvad, apparently either Valva about fifteen miles south or Valvda about  $4\frac{1}{2}$  miles north of Kolhápur; in 1187 as ruling at Kolhápur and about three years later (1191) as ruling in Panhála fort. Bhoja Rája is said to have built fifteen forts of which Bávda, Bhudargad, Panhála, Sâtára, and Vishálgad are the chief. About 1209-10 Bhoja Rája was defeated by Singhana (1209-1247) the most powerful of the Devgiri Yádavs. After Bhoja Rája's defeat Panhála seems to have fallen into the hands of petty Marátha robber chiefs. In 1376 inscriptions record the settlement of Nabhápur to the south-east of the fort. On the establishment of the Adil Sháhi dynasty of Bijápur in 1489, Panhála came under Bijápur and was fortified with great care. To the Bijápur government are ascribed the strong ramparts and gateways of the fort which according to tradition took a hundred years to build. Numerous inscriptions in the fort refer to the reign of Ibráhim Adil Sháh, probably Ibráhim I. (1534-1557). In 1659, immediately after the murder of the Bijápur general Afzul Khán, Shiváji took Panhála from Bijápur. In May 1660, to win back the fort from Shiváji, Ali Adil Sháh II. (1656-1672) of Bijápur sent Sidi Johár who laid siege to Panhála in which Shiváji had shut himself. After four months siege Shiváji escaped to Ránga about fifty-five miles south-west of Kolhápur, and shortly after Panhála and Pávangad were taken by Ali Adil Sháh in person. In 1673 Shiváji again took Panhála. In 1674 the Bijápur general Abdul Karim made an unsuccessful attempt on the fort, and till his death in 1680 Panhála remained in the hands of Shiváji, who for a time kept his son Sambháji under guard at Panhála. On Shiváji's death Sambháji won over to his side the commandant of Panhála and marching on Ráygad in the central Konkan overthrew Rájárám's faction and established himself as head of the Maráthás. About nine years later in 1689 when Sambháji was made prisoner by Aurangzeb's general Takribkhán at Sangameshvar in Ratnágiri, Panhála came under the Moghals. In 1692 Panhála was retaken by Parashurám Trimbak the ancestor of the Kolhápur Pant Pratinidhi family of Vishálgad. In 1701 the Emperor Aurangzeb laid siege to and took Panhála in person. In this year at Panhála, on the 28th of April, Aurangzeb received the English ambassador Sir William Norris who spent 200 gold mohars (£300) in fruitless negotiation with the Moghal emperor. Shortly after, in 1701, Panhála was taken from the Moghals by Rámchandra Pant Amátya, the ancestor of the present chief of Bávda. In 1705, Tárábái the widow of Rájárám (1689-1700) made Panhála her head-quarters. In Tárábái's war with Sháhu of Sâtára in 1708, Sháhu took Panhála and Tárábái fled to Málvan in Ratnágiri. Shortly after, in 1709, Tárábái again took Panhála, and since then Panhála has remained under Kolhápur. During the reign of Jijibái, who died in 1772, human sacrifices were regularly offered at Panhála. Parties of men scoured the country to procure human victims to be sacrificed within a few hundred feet of the queen's palace. The goddess to whom the human victims were offered was Mahákáli. It was believed that so long

as Bhaváni was pleased the fort could not be taken. Mahákáli's temple, where the human sacrifices were offered, lay in a dark thickly-wooded spot in the inner fort where the walls of two towers one of which is still known as Káli's Tower come close together. In addition to the regular sacrifices Major Graham mentions that he had seen a deed or *sanad*, apparently but this is not clear of the time of Jijibái, making over a plot of land to an oilman or Teli in reward for the grant of his daughter-in-law to be buried alive under one of the Panhála towers.<sup>1</sup> In 1782 the seat of the Kolhápúr government was moved from Panhála to Kolhápúr. In 1827, under Sháháji (1821-1837) Panhála and Pávangad were for a time made over to the British Government. In 1844, during the minority of Shiváji IV. (1837-1866), Panhála and Pávangad were taken by rebels who seized Colonel Ovens the Resident of Sátára, when on tour and imprisoned him in Panhála. A British force under General Delamotte was sent against the rebels and on the 1st of December 1844 breached the fort wall, took it by storm, and dismantled the fortifications. A garrison of 1845 militia and a hundred pieces of ordnance were left to guard the fort.

At present (1884) Panhála is the head-quarters of the Panhála sub-division and is the best health-resort in the Kolhápúr State. It has two parts, Panhála fort or Killa Panhála also called Huzur Bazár or the head-quarter market on the hill-top, and the suburbs of Ravivár, Mangalvár, Guruvár, and Ibhrámpur at the hill fort. According to the 1881 census the fort has 1203 people and the suburbs 926. The hill top is pleasantly broken and adorned with cliffs, pools, and shady springs. Except during the rains the climate is delightful, the days cool, and the nights fresh. The fort is famous for its freedom from cholera probably chiefly because of its plentiful supply of pure iron-charged water. The best spring is the Nágjhari or Cobra Spring. The chief reservoirs which hold water throughout the year are the Sádhuba pool with stone steps 221 feet long 148 broad and thirty-five deep, and Somála pool also with stone steps 220 feet long 190 broad and seventeen deep. Of the wells the chief is the Shringár or Andhár Váv which stands west of the fort close to the rampart.<sup>2</sup> Near the old Dharmakothi building, every Sunday a market is held attended by about 1000 people. In this market rice, millet, vegetables, spices, and cloth are sold to the value of about £50 (Rs. 500). In the suburbs at the foot of the hill top another small market is held every Wednesday. Panhála has the offices of the mámlatdár, the chief constable, and the sub-registrar, a vernacular school with a branch in the suburbs and a joint average attendance of 162 boys and three girls, a post office, a travellers' bungalow for European travellers, and three or four temples which are used as rest-houses by native travellers.

## Chapter XIII.

## Places.

## PANHÁLA.

<sup>1</sup> Major Graham's Kolhápúr, 497 and 502.

<sup>2</sup> In the Karvir Purán some of the ponds, springs, and wells are mentioned as *tirths* or holy pools and bear old mythological names. Thus the Sádhuba pool is called Paráshar's pool, the Somála ponds Soma pool, the Nágjhari Spring Nág pool, the *ting* well Vasanta pool, the Palang well Madan pond, the Kápur well Ashvaláyan pool, and the Mhár pond Stambha pool.



## Chapter XIII.

## Places.

## PANHÁLA.

The old roads have of late years been much widened and improved and are yearly repaired from State funds.

Of the ruins on the hill top one of the oldest is the citadel in the centre of the fort, surrounded by high ruined walls enclosing a tangled growth of jack, mango, guava, and other trees and bushes. Nothing remains of the old palace but stone foundations and plinths hid in shrubs and underwood. Of three enormous stone and cement granaries built with arched roofs and capable of holding provisions for a large army, the largest known as Ganga Kothi, a massive building with two entrances, is nearly choked with rubbish. On either side a staircase leads to a terrace where are small holes through which large quantities of grain used to be passed. The building is 10,200 feet square and thirty-five feet high. Of the two other granaries one is 152 feet long, forty broad, and eighteen high, and the other eighty-eight feet long, thirty-five broad, and thirty high. Besides these three large granaries the Dharma Kothi granary which stands close to the present mámlatdár's office is also a stone building fifty-five feet by forty-eight and thirty-five feet high with an entrance and a staircase leading to a terrace. On the east of the fort close to the rampart stands the Kalávantin's Sajja or courtesans' terrace-room. It is nearly a complete wreck except that traces of fine ornament remain in the ceiling. It is sixty feet by thirty-six and fifty-eight feet high. To the north of the fort stands a palace of His Highness the Mahárája of Kolhápur, a stone and mud structure two storeyed and tile-roofed with room for a hundred to two hundred men. To the east of the palace close to the rampart is a massive stone and mortar building called the Sajekothi. It is two-storeyed, thirty-six feet by thirty-one and forty-one feet high, with one entrance and a staircase leading to the upper storey. On the south of the fort close to the rampart stands a small stone building called the Tálimkhána or wrestling house with three domed rooms. The Redemahál to the south of the mámlatdár's office is 101 feet by fifty-three and thirty-six feet high. Close to the mámlatdár's office stands Sambháji Maháráj's temple, ninety feet by forty-six and including the spire fifty-five feet high. The temple is surrounded by an arch-roofed building which is used as a rest-house. Opposite Sambháji's temple is another dedicated to Jijibái Sáheb the wife of Sambháji Maháráj (1712-1760). Of Musalmán buildings the most important is the shrine of Sadhoba a Musalmán saint. It is surrounded by a stone and mud wall and is twenty-nine feet square and including the dome fifty feet high. Every year a fair or *urus* is held. This place is said to have been the seat of the sage Páráshar whose name the Kárvir Mahátmya associates with several objects of interest on Panhála hill. Among these objects to the south of the fort is a rock-cut cave of the sage Páráshar.

## PA'VANGAD FORT.

Pa'vangad Fort stands on the Panhála spur about half a mile east of the Panhála fort from which it is separated by a ravine. The chief defence of the fort is a scarped rock fifteen to twenty-five feet high. In most places the steepness of the rock has been increased by artificial scarping and it has been strengthened by a parapet wall of



black stone fourteen feet high. The two main entrances were pulled down in 1844 when the fort was dismantled. The fort though deserted has a good water supply.

## Chapter XIII.

## Places.

PÁNDAV DARÁH  
CAVES.

The **Pa'ndav Dara'h Caves**, apparently of Buddhist origin, are cut in a semicircular scarp about twenty-five feet high overlooking about a thousand feet of thickly wooded hill-sides above the plain, six miles west of Panhála and eighteen miles north-west of Kolhápur. The group of caves includes a large cistern running into the hill-side, eight dwelling cells, and two large caves a chapel and a school. In front of the caves are traces of a pillared veranda most of which has fallen into the ravine twenty feet below. Each of the two largest caves has a veranda, a hall divided into three sections or rooms with remains of pillars along the side walls, and an inner cell or shrine each with what is described as a carved elevation probably a *dúghoba* or relic-shrine in the centre. The veranda of the chapel is fifteen feet long by seven wide. The sections of the chapel hall are said to measure  $27' \times 12'$ ,  $28' \times 10'$ , and  $29' \times 3\frac{1}{2}'$ . The roof is flat and the height of the hall eight feet. In the back wall of the hall a door ( $6\frac{1}{2}' \times 2\frac{1}{2}'$ ) opens into an inner room or shrine ( $10' \times 7' \times 8'$ ) with a carved central elevation apparently a relic-shrine. The school hall which has a flat roof  $7\frac{1}{2}$  feet high is divided into three parts the outer  $32' \times 6\frac{1}{2}'$ , the central  $15' \times 9'$ , and the inner  $12' \times 9'$ . The cell of which the measurements are not given, has like the chapel shrine a carved central elevation apparently a relic-shrine.<sup>1</sup>

## PAVÁLA CAVES.

The **Caves of Pava'la**, which are of Buddhist origin, are cut in rock near Jotiba's hill six miles north-west of Kolhápur. As in the Pándav Daráh group there are two main caves, one which is supposed to have been the school and the other the chapel or *chaitya*. There is also a rock-cut water cistern. A narrow veranda formerly fronted by pillars is cut along the face of the hill. The entrance into the main chapel cave leads from a veranda ( $35' \times 4' \times 9'$  high) by a door ( $9' \times 5'$ ) with side windows each four feet by five. The larger cave is a hall nearly square ( $34\frac{1}{2}' \times 32'$ ) and nine feet high. The flat roof rests on three side rows of fourteen pillars each. Twenty-three cells open out from the sides of the hall, each about seven feet long, five broad, and seven high. Between the three side rows of pillars and the cells runs an open passage, forty-one feet long and four feet broad. The smaller cave ( $31' \times 16' \times 12\frac{1}{2}'$  high), which is supposed to have been a lecture room, is entered by a gate  $7\frac{1}{2}$  feet wide and 7 feet high, and has a rock-cut pulpit or raised seat for the teacher.

## RUKDI.

**Rukdi**, a large village in Alta with in 1881 a population of 3074, lies on the Kolhápur-Miraj road about nine miles east of Kolhápur and a mile from the Panchganga river. Most of the people are Jains and Musalmáns. Twice a week on Thursday and Friday markets are held where grain and piece-goods are offered for sale. Rukdi has a school with an average attendance of sixty-five boys held in a school-house which was built in 1870 at a cost of £233 8s. (Rs. 2334). Formerly Rukdi was the seat of a detachment

<sup>1</sup> Graham's Kolhápur, 315-316.

## Chapter XIII.

## Places.

## RUKDI.

of horse called the Bákrishna *pága* to guard the country round against freebooters. At present (1884) Rukdi has a small State stud for horse-breeding. The chief objects of interest are a tower, a temple of Mahádev, and a *darga* or Musalmán prayer-place. The tower, which is said to have been built by Sadáshivpant a mámlatdár of the Kolhápur State, is thirty-eight feet high and 175 feet in circumference. It was formerly used as a lock-up for prisoners and is now ruined. The temple of Mahádev is built of stone and is 15' x 15' x 11' high. The tomb, which is 22' x 22' x 18' high, is said to have been built in honour of Avaliya a Musalmán saint. According to the local story Avaliya rode on a tiger and used a snake as a whip, and was nicknamed Hajrat Ráje Bághsavár or the tiger-rider. Before he came to Rukdi, Rukma Devi the village deity after whom Rukdi is named, oppressed the people by demanding human sacrifices. In his travels Ráje Bághsavár who is said to have been a native of Arabia came to Rukdi. Surepán a brother ascetic asked him to punish Rukma Devi. Accordingly Ráje Bághsavár condemned Rukma Devi to perdition, turned her temple into a Musalmán tomb, buried her image in the foundations, and when he died was himself buried under the centre of the dome. The tomb has rent-free lands most of the proceeds of which are spent in a yearly fair or *urus*.

## RÁYBÁG.

**Rá'ybá'g**, the head-quarters of the Ráybág petty division, with in 1881 a population of 2408, lies twenty-four miles south-east of Shirol. In the eleventh century Ráybág is said to have been the head-quarter town of a Jain chiefship. According to a local story, the town was formerly so wealthy that on one market day the maid of a rich merchant bid £500 (Rs. 5000) for a gourd. By this offer she outbid the servant of Randulla Khán the local Bijápur governor. The servant in anger told her master that all the best things in the market went to the merchants. The governor, thinking that the town had grown overwealthy, ordered it to be plundered, a misfortune from which it has never recovered. At present (1883) it has 493 houses of which 428 are of the better class either terrace-roofed or tiled. The chief street runs north and south and is lined with good houses. Most of the people are Jains and Maráthás and the town is surrounded by a mud wall. It has a plentiful supply of well water. On every Monday a market is held, where grain and coarse cloth are offered for sale. Besides the office of a petty divisional officer under the mámlatdár of Shirol, Ráybág has a police post, a post office, and a school with an average attendance of forty-six boys. Ráybág has three temples of Someshvár Sidheshvár and Narsinha, a mosque of Langotbandha, and a domed tomb of Randulla Khán. The Someshvár temple is old and built of huge well-sculptured blocks of stone. It is fifty-one feet long, thirty broad, and twenty-four high. The Sidheshvar temple, which is built of black stone, is fifty-one feet long 43½ broad and 18 high. In 1875 it was repaired by the *inámdárs* or land proprietors of the Ráybág petty division. The Narsinha temple is an underground structure of black stone and mortar. The image of Narsinha is richly carved and is said to have been brought from the Krishna near Jalálpur. The Langotbandha mosque about 1175 feet to the north of the town is 17½ feet square

and 11½ feet high. Randulla Khán's domed tomb, built in honour of the Bijápur officer who is said to have sacked the town, is 29½ feet long 19½ broad and 22¾ high. It has been lately repaired by the State.

**Ra'ngna Fort** is on a flat-topped hill in the Sahyádris about thirty miles south-west of Bhudargad and fifty-five miles of Kolhápúr. The hill is steep on three sides with an easy ascent on the north. The top is girt by a wall of rough blocks of stone and mortar, leaving three pathways down the hill. Inside of the wall the level hill top is broken here and there by swelling ground. The fort, which is 4750 feet from east to west by 2240 feet from north to south, is deserted. It is watered by two small cisterns and three wells now overgrown by trees. On the hill sides which are covered with underwood and shrub, crops of *vari*, *náchni*, and *harik* are raised by wood-ash tillage. Since 1659, when along with Panhála it was taken by Shiváji and repaired, Ránga has remained in Marátha hands. In 1844 the fort was dismantled by order of the British Government.

**Sa'm'angad Fort**, on an isolated oval-topped hill three and a half miles south of Gadinglaj, has a greatest height of 2600 feet above the sea and a greatest breadth of 260 feet. The hill top is surrounded by an eight-feet high wall. It was well supplied with water from several rock-cut cisterns. The garrison formerly included 350 men, ten pieces of ordnance, 100 muskets, and 200 sabres. In 1676 Sámangad was thoroughly repaired by Shiváji. Though one of the smallest of Shiváji's forts, Sámangad was one of the strongest. It was besieged without success for twelve years by the Nizám's troops and by the Patvardhan and the Nipánikar. In 1844, injudicious changes introduced by the minister Dáji Pandit, by bringing their lands under the mámlatdár enraged the Sámangad garrison or Gadkaris who rebelled and shut the gates of the fort. On the 13th of October 1844 the fort was taken by British troops under General Delamotte and dismantled. Since 1844 the mámlatdár's head-quarters have been moved from Sámangad to Gadinglaj.<sup>1</sup>

**Shirol**, the head-quarters of the Shirol sub-division, lies thirty miles east of Kolhápúr and about four miles to the north of the meeting of the Panchganga and Krishna. A first class road joins Shirol with Kolhápúr. Shirol is sometimes called Ghumat Shirol or Shirol-with-the-dome, because it used to have a large domed tomb of a Bijápur officer named Nurkhán which Parashurám Bháu Patvardhan is said to have destroyed in 1779. Shirol is guarded by a ditch and a wall and is strengthened by an inner citadel. During the wars between Kolhápúr and the Patvardhans in the latter part of the eighteenth century Shirol changed hands several times. In 1780 it was finally taken by Shiváji III. (1760-1812) and has since remained under Kolhápúr. In 1831 the population was returned at 6944 against 8282 in 1872. The people, who are mostly Maráthás, Jains and Musalmáns, live in 1250 houses of which about a thousand are of the

### Chapter XIII. Places.

RÁNGNA FORT.

SÁMÁNGAD  
FORT.

SHIROL.

<sup>1</sup> Details of the 1844 disturbance are given above under History.

## Chapter XIII.

## Places.

## SHIROL.

better sort tiled or terrace roofed. The chief street runs north and south and is lined by good houses, some of them two-storeyed. To repair and clean the town roads a sum of £20 (Rs. 200) is yearly granted from local funds. As the water of almost all the wells is brackish, drinking water is brought about a mile from the river. On every Saturday a market is held where grain and cotton yarn worth about £20 (Rs. 200) are sold. Outside of the town, in a building lately completed at a cost of £4500 (Rs. 45,000), are the offices of the *mámlatdár*, the *munsif*, the chief constable, and the sub-registrar. Shirol has also a post office and an anglo-vernacular school with an average attendance of 148 boys held in a school-house which cost about £400 (Rs. 4000). The stud establishment at Shirol includes thirty broodmares. Shirol has a small palace where the *Kolhápúr Rája* often lives. It has two large temples, two mosques, and a tower. Of the two temples *Káleshvar's* is the oldest though of no great age as it is built of stone and mortar. It is thirty-five feet long, twenty-five broad, and twenty-eight high. The other temple, which is dedicated to *Dattátreya* an incarnation of the triad *Brahma Vishnu* and *Shiv*, is held specially sacred. The only object of worship in the temple is a slab of stone on which an open hand is carved. It is called the temple of *Bhojanpátra* or the dinner plate, and a stone vessel or *pátra* is still preserved in which, according to tradition, the god *Dattátreya* once took a meal or *bhojan* with a holy *Bráhma*n of Shirol. Of the two mosques which are said to have been built by *Nurkhán* of *Bijápúr*, one is thirty-two by twenty-two feet and the other thirty-five by twenty-seven feet. The ruined tower which stands in the centre of the town is said to have been built by the *Kolhápúr* State about 150 years ago (1733). It is thirty-five feet high and 150 feet round.

## SHIROLI.

**Shiroli**, a village in the *Alta* subdivision, with in 1881 a population of 3033, is on the *Poona-Belgaum* mail road about six miles north-west of *Kolhápúr*. In 1855 the village which was then almost entirely of thatched huts was destroyed by fire. Since the 1855 fire many tiled houses have been built, several of them two storeys high. *Shiroli* is a halting place on the journey from *Poona* to *Belgaum* and has two rest-houses. The water is drawn from a reservoir near the village about twenty-four acres in area. Besides a newly built *chávdí* or village office, *Shiroli* has a school with an average attendance of forty boys. Near *Shiroli* the *Panchganga* is crossed by an iron bridge close to which is a tomb in honour of *Bále Pir* where every April a fair or *urus* is held attended by about 10,000 people. In the centre of the village is a well-built temple of *Sarveshvar*.

## TORGAL.

**Torgal**, the head-quarters of the chief of *Torgal*, with in 1881 a population of 1516, is about a hundred miles south-west of *Kolhápúr*. It is enclosed by a bastioned mud wall which has given way in many places and is covered with prickly pear. Inside the wall is a citadel also surrounded by a mud wall. This citadel was built in 1700 and is the residence of the chief. *Torgal* is said to have been built about the year 1100 by a chief named *Bhutánkush*. In 1690 *Torgal*

was taken from the Bijápur government by Narsojiráv and given to him as a *sarajám* or military grant by Rájáráam (1689-1700) the head of the Maráthás. Torgal has the office of the chief, a post office, a police station, and a vernacular school with an average attendance of about fifty boys. It has 532 houses all flat-roofed and one-storeyed. On every Monday a market is held, where grain and cloth are offered for sale. Torgal has an old temple of Bhutnáth said to have been built about 1100 by Bhutánkush Ráj. If the story is true additions must have been made in later times as it is now of stone and mortar, sixty-three feet long forty-five broad and, including the spire, thirty-three feet high.

**Vadgaon**, a market-town in Alta, with in 1881 a population of 4890, is ten miles north of Kolhápúr. It is supplied with drinking water from a reservoir about 824 feet in circumference to the north of the town. The people are chiefly Maráthás, Shimpis, and weavers. Vadgaon has several main streets lined on both sides with tiled houses, some of them two-storeys high. During the feuds between the Kolhápúr State and the Patvardhans at the close of the eighteenth century Vadgaon was several times burnt. About 1761-62 it was plundered by Raghunáthráv uncle of the Peshwa. Formerly during the reign of Sambháji (1712-1760) Vadgaon was a favourite residence of the Kolhápúr family and had a strong detachment of horse. The troop of horse has been removed and Vadgaon is seldom visited by the Kolhápúr chief. It has (1883) a hundred looms for weaving coarse cloth, but of late years the craft has been falling. On every Monday a market is held, at which piece-goods, yarn, grain, raw-sugar, chillies, and turmeric are sold worth about £500 (Rs. 5000). Vadgaon has a police post of four men, a post-office, and a school with an average attendance of 125 boys held in a school-house built in 1870 at a cost of £460 (Rs. 4600). It has a large Bráhmánic temple of Lakshmi and a Jain temple. The temple of Lakshmi, which is about 4160 feet to the south-west of the town, is in Hemádpanti or pre-Musalmán style, twenty-four feet long twenty-one broad and thirty high. The Jain temple in the centre of the town is said to have been built in 1696 by one Adápa Bhugshet at a cost of £4000 (Rs. 40,000).

**Vá'di Narsinha**, commonly called Narsoba's Vádi, a *vádi* or suburb of Shirol, with in 1881 a population of 2381, a spot richly wooded with *bábhul* and tamarind, lies three miles south of Shirol at the meeting of the Krishna and Panchganga. It is named after Narsinha Sarasvati, who for twelve years is said to have lived at the sacred meeting of the rivers. Most of the people are Bráhmán *pújáris* or ministrants of the deity Narsinha. They live in about 300 houses of which 250 are flat-terraced or tiled and many are two-storeyed. Vádi Narsinha has a post office, a school with an average attendance of ninety-two boys, and a town municipality with in 1881 a yearly income of £190 (Rs. 1900) and an expenditure of £43 (Rs. 430). It is a holy place and is visited by large numbers of pilgrims. Vádi Narsinha has two large temples, one dedicated to Dattátreya and the other to Náráyan Svámi. The temple of Dattátreya to the south of the village on the river bank is twenty-four feet long twelve broad and twelve high. From the temple to the river

## Chapter XIII.

## Places.

TORGAL.

VADGAON.

VÁDI NARSINHA.



## Chapter XIII.

## Places.

## VĀDI NARSINHA.

bed runs a flight of steps 137 feet long and 127 broad. West of the temple of Dattātreyā lies the temple of Nārāyan Svāmi who is said to have been taught religion direct by Dattātreyā. It is fifty-one feet long twenty-two broad and fourteen high. At the meeting of the Krishna and Panchganga is another flight of steps of hewn stone and mortar, 143 feet long and sixty-seven feet wide.

Besides the two villages of Aurvād and Gaurvād in Belgaum granted rent-free to Narsinha Sarasvati, the temple is in the receipt of £134 (Rs. 1340) a year in cash. During a whole month from the dark fifth of *Māgh* or February-March a fair is held daily attended by about 5000 people from a distance of 200 miles. Piece-goods, copper and brass vessels, and other articles in daily use are offered for sale in temporary booths. The total sales in the month amounted to about £10,000 (Rs. 1 *lakh*). On the dark 12th of *Āshvīn* or September-October, the day on which Dattātreyā is said to have disappeared from the world, another small fair is held attended by about 10,000 people.

## VĀLVA.

**Vālva**, with in 1881 a population of 2579, is in Bhudargad on the right bank of the Dudhganga about fifteen miles south of Kolhāpur. It has a school with an average attendance of 100 boys. Vālva is known for its *churmure* or parched rice which is sent weekly in large quantities to the neighbouring villages. In 1786 Sakhārām Ghātge of Kāgal gave his brother Vishvāsrao Vālva and seven neighbouring villages as his share of the family estate. On the death of Vishvāsrao in 1824 the grant was continued to his fourth wife Ramābāi. On Ramābāi's death in 1861 the grant was attached, and in 1864, with the sanction of the British Government, it was resumed by the Kolhāpur State, the adopted son of Ramābāi being allowed the hereditary property of the district revenue superintendent or *deshmukh* together with the personal estate of Vishvāsrao. Of objects of interest Vālva has the mansion or *vāda* of the *dumāledār* or part-owner of the village, a square building of mud and sun-burnt bricks about 210 feet long and 110 broad. It has also an old mosque about eighteen feet long fourteen broad and fifteen high, with a tomb dedicated to a member of the Ghātge family. At this tomb, from the dark 8th to the dark 10th of *Māgh* in January-February a fair is held attended by about 2000 people.

VISHĀLGAD  
FORT.

**Vishālgad Fort** crowns the Gajāpur hill about forty-five miles north-west of Kolhāpur. It is 3200 feet long by 1040 feet broad. The walls, gateways, and towers are almost entirely ruined. According to the 1881 census it had 121 people living in fifteen houses. Besides the old mansion of the Kolhāpur Pratinidhi the chief building is a mosque with a tomb to Hajrat Malik Rahānpir, seventeen feet long by fifteen broad and eight high. This mosque is visited both by Hindus and Musalmāns. Every year on the 13th of the Musalmān month *Zilhaj* a fair or *urus* is held attended by 300 to 400 people. To meet the cost of this fair the mosque has a yearly cash allowance of £9 (Rs. 90). The fort is watered by the Bhopāl and Ardachandra or half-moon reservoirs and by a cistern. The Bhopāl reservoir which is said to have been built by Bhopāl Rāja, is 6400 feet square. The Ardachandra or half-moon reservoir is



seventeen feet long fifteen broad and eight deep, and is said to have been built by Rámchandra Pant Amátya who held the fort after its capture by Shiváji in 1659. The cistern, which also is said to have been built by Rámchandra, is 324 feet square and ten feet deep.

According to tradition, about the year 1000 Vishálgad was in possession of a Hindu king named Bhopál who built the reservoir which still bears his name. On the wall of the mosque which is dedicated to Malik Rahán Pir a Persian inscription runs:

'A Mara'tha king named Bhoj held the fort. I Malik Raha'n came and six times besieged it without success. In the seventh siege I took it. Be brave and thou shalt prosper.'

Another inscription on a tower known as the Daulat Buruj or tower of wealth, runs:

In this world 'perseverance overcomes difficulties.' 'The Daulat tower has been completed with elegance.' 'If you wish to learn its date, it lies in the letters Daulat Buruj.'

According to Major Graham the letters of Daulat Buruj give the apparently incorrect date of 645 that is A.D. 1247. The Musalmáns failed to maintain their hold of Vishálgad. About 1453, while attacking Vishálgad, Malik-ut-Tujár, a general of Alla-ud-din Khán Bahmani (1435-1457), was caught in an ambush and his whole army cut to pieces by a local Marátha chief named Shankarráv More. In 1469 Shankarráv was defeated by the Bahmani general Máhmud Gawán who took Vishálgad after a nine months' siege. After the fall of the Bahmani dynasty in 1489 Vishálgad came under Bijápur, and continued under Bijápur, till in 1659, it was taken by Shiváji and in 1660 given by him in grant to Parashurám Trimbak whose heirs still hold it. In 1661 a large Bijápur army under Phájlkhán besieged Vishálgad for several months and tried to take it by mining the western corner and bombarding it from the top of the Ghonasli hill. Traces of the wells which were dug for the Bijápur army remain at the neighbouring village of Gajápur and the rocky ground which was occupied by the troops is still known as Bád-sháhcha Mál or the royal terrace. In 1730 when Kolhápur was finally separated from Sátára, the grant of Vishálgad was continued to Janárdhan Pant by a fresh patent or *sanad* passed by Sambháji (1712-1760). Till 1844 Vishálgad continued to be the head-quarters of the Kolhápur Pratinidhi. In 1844 as the fort had been occupied by the rebels, it was dismantled and the Pratinidhi's head-quarters were moved to Malkápur.<sup>1</sup>

## Chapter XIII.

### Places.

VISHÁLGAD  
FORT.

<sup>1</sup> A translation of the Persian inscription at Panhála by Colonel J. W. Watson is given in the Appendix.

## SOUTHERN MARÁTHA STATES.

BESIDES Kolhápur, eight *jágirs* are under the superintendence of the Kolhápur Agency and comprise Sängli, Miraj Senior and Junior, Kurundvád Senior and Junior, Jamkhandi, Mudhol, and Rámdurg. The territories are divided into a large number of isolated patches. The prevailing language is Maráthi but in many parts Kánarese is spoken. Of these states Sängli, Miraj, Kurundvád, and Jamkhandi belong to the Patvardhan family and among these Sängli is the largest and most important.

### SÁNGLI.<sup>1</sup>

#### Description.

Sa'ngli consists of detached tracts extending from the British districts of Sátára and Sholápur in the north to the river Tungbhadra in the south of the Bombay Presidency. It has an area of 1083 square miles, and in 1881 had a population of 196,832 and in 1882-83 a gross revenue including alienations of £86,471 (Rs. 8,64,710).

#### SUB-DIVISIONS.

For administrative purposes the territory of Sängli is distributed over six detached sub-divisions with an average of 180 square miles, 40 villages, 32,805 people, and a revenue of £14,412 (Rs. 1,44,120). The following statement gives the details :

*Sängli Sub-Divisional Details, 1882.*

SUB-DIVISION.	AREA.	VILLAGES.	PEOPLE.		GROSS REVENUE, 1882.
			1881.	To the square mile.	
Mirajpránt ... ..	142	36	50,105	352	£ 24,890
Kuchi ... ..	185	30	24,351	132	7,859
Mangalvedha ... ..	277	32	21,898	98	11,081
Terdal ... ..	79	17	22,098	278	10,805
Sháhápúr ... ..	86	58	44,069	314	15,398
Shirhatti ... ..	314	69	34,311	109	16,429
Total ... ..	1083	242	196,832	1283	86,471

Of these sub-divisions, beginning from the north, Mirajpránt lies in the Krishna valley, mostly on the left bank and intermixed with villages belonging to the Miraj state and the sub-divisions of Karád, Válva, and Tásgaon in Sátára. The chief town in this sub-division is Sängli the capital of the State. Kuchi lies to the east of Mirajpránt of which it formed part till 1878, when it was separated for convenience of administration. The chief town is Kavtha

<sup>1</sup> The account of Sängli is compiled from materials supplied by the late Lieutenant-

Mahánkál about ten miles north-east of Sàngli. Mangalvedha lies south of Pandharpur in Sholápur, within the angle formed by the rivers Mán and Bhima. All the villages except four lie within a ring fence. The chief town is Mangalvedha about seventy-five miles north-east of Sàngli. Terdal lies west of the Mudhol and Jamkhandi states. Its villages are all in the Krishna valley and more or less mixed with villages belonging to Belgaum, Kolhápur, and Miraj. The chief town is Terdal about forty miles south-east of Sàngli. Sháhápur lies in the centre of the Belgaum district, mostly to the north and east of the cantonment of Belgaum. In this sub-division may be included the large isolated village of Dodvád which lies in Dhárwár. The chief town is Sháhápur about seventy miles south of Sàngli and two miles south of Belgaum. Shirhatti lies in the south-east corner of Dhárwár by which it is bounded on the north and west. Its southern boundary is the river Tungbhadra. The chief town is Shirhatti about 135 miles south-east of Sàngli.

**Description.**  
**SUB-DIVISIONS.**

The general aspect of the three northern sub-divisions of Mirajpránt, Kuchi, and Mangalvedha is treeless, flat, and monotonous. The geological formation is alike, black, gray, and a little red soil overlying the basaltic trap rock of the Deccan. A range of low hills, called the Dandoba, divides Mirajpránt from Kuchi. Capped with a somewhat hard iron-clay rock of a reddish hue, much resembling the laterite of the Konkan, and covered with grass and brushwood these hills present a more picturesque appearance than the usual run of hills in the Deccan. There are no other hills of any size but in Kuchi and the west of Mangalvedha are *máls* or undulating stony plains covered with spear grass, stunted acacias, and bushes of the *tarvad* *Cassia auriculata* and *nepti* *Capparis aphylla*. Among the southern sub-divisions Terdal is flat and monotonous in the north, but the country is more varied in appearance in the south where the fertile valleys of fine black and reddish sandy soil lie between low sandstone hills covered with cactus and thorny shrubs. In the east the villages are fairly well wooded. Sháhápur is rough, well wooded, and full of low rocky hills and valleys. The prevailing soil is red and the general aspect greener and more picturesque than that of the other sub-divisions. Shirhatti on the west is treeless and flat but has a fertile black soil. On the south and east the country is broken and hilly and covered with boulders of granite and gneiss thrown together in many places in the most fantastic confusion. On the east the hilly country ends in the auriferous Kapatgudd range whose deeply furrowed red sides are intersected by numerous bands of milkwhite and reddish quartz and strewn with other rocks of various colours.

**ASPECT.**

The general drainage is from west to east with a southerly tendency. No river rises in the State. The chief rivers that run through the State are the Krishna, Bhima, Mán, Verla, Agrani, Ghatprabha, Márkandi, and Tungbhadra. Of these the Krishna runs through Mirajpránt and Terdal. The alluvial deposits or *malis* on its banks are the richest lands in the State. The Bhima runs east and south-east and the Mán north in Mangalvedha.

**RIVERS.**

**Description.**  
**RIVERS.**

The Verla coming through Tásgaon joins the Krishna twelve miles north-west of Súngli. It is a rapid stream in the rains and subject to dangerous freshets. The Agrani, a rapid stream, runs south through Kuchi. The Ghatprabha runs north and the Márkandi south in Sháhápúr. The former is a brawling stream and flows over a rocky bed. The Tungbhadra runs south in Shirhatti. Of these rivers the Krishna, Bhima, and Tungbhadra are scarcely navigable in the monsoon, as the current is often too strong for boats to work against. Boats of about 1½ tons (50 *mans*) could work down the stream from the end of June to October. The main current of the Krishna which is often turned from one bank to the other, causes changes in the alluvial deposits on its banks. Tradition says that the Krishna once flowed from Súngli to Dhámni almost from north to south. Now the river takes a bend to the west at Súngli and joins the Várna at Haripur.

**WATER SUPPLY.**

The water-supply is ample and the water close to the surface in Mangalvedha, Kuchi, and Sháhápúr. It is fairly good in Mirajpránt and Terdal. But in Shirhatti, except near the hills, the water is deep below the surface and deficient. Shirhatti once had a number of large irrigating ponds, but many of them have now silted up and do not as a rule hold water enough for irrigation. Súngli has in all 140 ponds and 4490 wells and water-holes. Of these Mirajpránt and Terdal have fifteen ponds and 605 wells of which 126 are for drinking water only. Kuchi is well off for water, having ten ponds and 1028 wells. The ponds, especially the large ones at Bastavda and Agalgaon, and the bulk of the wells are used for irrigation. Besides these, there are two masonry dams, one near Balgavda and the other near Vajra Chavandha across the Agrani. To irrigate *málás* or gardens temporary earthen dams are yearly made across the streams which join the Agrani close to Kavtha Mahánkál. Mangalvedha has seventeen ponds and 484 wells. Of these the ponds at Khomnál and Talsangi and 384 wells are used for irrigation. Sháhápúr has fifty-five ponds and 1957 wells and water-holes of which sixty-one wells are used for irrigation. Shirhatti has forty-three ponds and 416 wells. Of these four large ponds at Shetikeri, Devihál, Kundarhalli, and Magdi and 232 wells are used for irrigation. Deaths by drowning in the ponds and wells are common, the average for the three years ending 1882 being twenty-five or 0·012 per cent of the total population.

**CLIMATE.**

The climate though hot is not unhealthy. The hottest subdivision is Mangalvedha. Next in the order of heat come Mirajpránt, Terdal, Kuchi, Shirhatti, and Sháhápúr. In the rainy season the climate is everywhere pleasant, except perhaps in Sháhápúr, where the rainfall is heavy and constant. In the cold season the air is dry and the nights cool.

**RAINFALL.**

The rainfall is heavy in Sháhápúr. In other parts it is moderate. Rain returns for the six sub-divisional stations are available for the three years ending 1882-83. During these years the highest fall is 70·18 inches at Sháhápúr in 1882-83 and the lowest is 13·88 inches at Súngli in 1881-82. The total average fall of the State is 33·17 inches in 1880-81 to 35·44 inches in 1882-83.

and averaged 25·74 inches. The following statement gives the details :

*Sángli Rainfall, 1880-81 to 1882-83.*

STATION.	1880-81.	1881-82.	1882-83.	Average.
	Inches.	Inches.	Inches.	Inches.
Sángli ... ..	17·60	13·88	32·13	21·20
Kavtha (Kuchi) ...	14·58	18·28	21·80	18·22
Mangalvedha ... ..	20·59	18·93	38·25	25·92
Terdal ... ..	19·33	15·70	16·78	16·95
Sháhápur ... ..	20·25	39·51	70·18	46·31
Shirhatti ... ..	19·06	23·44	34·49	25·66
Total average ...	20·17	21·63	35·44	25·74

During the two years 1881-82 and 1882-83 the maximum heat varied from 108° at Mangalvedha in 1882-83 to 85° at Sháhápur in 1881-82; the minimum varied from 69° at Kavtha in 1882-83 to 56° at Mangalvedha in 1882-83; and the mean varied from 90° at Terdal in 1882 to 73° in Sháhápur in 1882-83. The details are :

*Sángli Thermometer Readings, 1881-82 and 1882-83.*

STATION.	1881-82.			1882-83.		
	Maxi-mum.	Mini-mum.	Mean.	Maxi-mum.	Mini-mum.	Mean.
Sángli ... ..	105	58	84	104	61	84
Kavtha ... ..	97	61	88	99	69	78
Mangalvedha ... ..	107	66	83	108	56	82
Terdal ... ..	102	64	88	102	62	90
Sháhápur ... ..	85	64	74	93	66	73
Shirhatti ... ..	96	68	80	94	67	79

Gold and iron are procurable in Shirhatti. Tradition says that during the reign of Malikárjun (1451-1465) gold used to be smelted in Shirhatti. On the west of the Kapatgudd hills gold-washing used to be carried on in the bed of the rivulet that runs from Jetigiri to Bágevádi. Here gold is still found in pockets. Iron used to be smelted at Kuslápúr so late as 1879, but its smelting has also been discontinued for want of fuel.

Of building stone excellent basalt is obtained in the northern sub-divisions; a hard crystalline sandstone of light colour varying from gray to red in Terdal and Sháhápur, and granite and gneiss in Shirhatti, where they are quarried in slabs of large size by means of fire. Lime nodules or *kankar* are common everywhere. Salt from earth used to be manufactured till its production was stopped by Government in 1877. Saltpetre and carbonate of soda are procurable in paying quantities. In Shirhatti the soda is collected by washermen for bleaching clothes. Good clay for brick and tilemaking is obtained in Sháhápur.

Since 1881 the State forests have been strictly preserved and for this purpose one inspector with foresters has been appointed. In 1882-83 the total area under forest was 56,588 acres or nearly 88½ square miles. Of these Mirajpránt had forty-five acres, Kuchi seventy-four, Mangalvedha 587, Terdal 237, Sháhápur 19,312, and

## Description.

### RAINFALL.

### HEAT.

## Production.

### MINERALS.

*Gold and Iron.*

*Stone and Earth.*

### FORESTS.

**Production.**  
**FORESTS.**

Shirhatti 36,333. The most important and oldest forests are in Sháhápur, which has most of the trees and shrubs found in the uplands of the Sahyádris. In the other sub-divisions forests are in their infancy, and, except in the hilly parts of Shirhatti, are only fit for the growth of acacia and the *nim* *Azadirachta indica*. The forests have been divided into sixteen nearly equal parts, and in each part such timber as is fit to be cut is sold every sixteenth year. To dispose of other shrubs which reach their full growth in one to four years, the forests have been further divided into four parts. In each part the shrubs are cleared every fourth year and sold as fuel. Instead of selling by auction the right to graze freely, the grazing is now allowed in places where no damage to young trees is likely to be caused, and a fee per head of cattle is levied. Myrobalans and other forest produce, the right to collect which was formerly farmed, are now collected departmentally, and the results show an increase in the revenue. During the two years 1881-82 and 1882-83 the revenue amounted to £1181 (Rs. 11,810) and the cost to £443 (Rs. 4430), leaving a profit of £738 (Rs. 7380).

**DOMESTIC**  
**ANIMALS.**

The domestic animals are oxen, cows, buffaloes, horses, ponies, asses, sheep, goats, dogs, and a few camels.

*Oxen.*

The cattle of the State are generally good, except in Sháhápur where the breed is poor for want of good pasture. The bullocks are well known and have chiefly two breeds, the Maisur or *Hanam* and the *Gujaráthi* that is from Gujarát and Káthiáwár. Both breeds were introduced by the late chief Chintámanráv (1801-1851). The *hanam* breed is active, strong, and hardy. For draught it is the best. The *gujaráthi* breed, though handsome, docile, and powerful, is slow and heavy and more adapted for ploughing than road and other work where speed is needed. The indigenous bullocks are also strong and hardy, but the breed by long admixture with the *hanam* and *gujaráthi* has to a great extent lost its distinct characteristics. In Shirhatti where the Maisur strain prevails, the bullocks are specially good.

*Cows.*

The milch kine of Sángli and Mangalvedha have a name throughout the Bombay Karnátak. This is mainly due to a strain of the best Gujarát blood, as many cows and buffaloes from Gujarát and Káthiáwár were imported by the late chief Chintámanráv (1801-1851). The cows fetch £1 to £15 (Rs. 10 - 150).

*Buffaloes.*

She-buffaloes in Sángli and Mangalvedha are good and fetch £2 10s. to £10 (Rs. 25 - 100). He-buffaloes are not in much demand locally, either for draught or for agricultural purposes. The classes that generally use them are Vadárs, Beldárs, Ghosávis, Shikalgárs, and other wandering tribes. He-buffaloes locally fetch about 10s. (Rs. 5). Many young he-buffaloes are yearly exported to the Konkan where they are used for ploughing the muddy rice-fields and fetch £1 10s. (Rs. 15).

*Horses and*  
*Ponies.*

The locally bred horses are usually weedy and vicious. The ponies though smaller in size are of better quality and more hardy and useful. The best ponies are reared in Mangalvedha on the banks of the Bhima. A pony fetches £1 10s. to £12 (Rs. 15 - 120).



The ass is owned and used by Kumbhárs, Parits, Lonáris, Vadárs, Beldárs, and Kaikádis. The breed though small is hardy. The ass costs little to keep and is easily managed, a boy being enough to control some thirty animals or more. The practice prevails of slitting the nostrils, as it is believed to improve the animal's wind. A good ass fetches 2s. to £2 (Rs. 1-20).

Sheep are owned mainly by Dhangars in the northern and by Kurubarus in the southern or Kánarese sub-divisions. The sheep on the Tungbhadra in Shirhatti is taller and heavier than that of the northern sub-divisions and its wool is better. The prevailing colours are black, gray of different shades, and black and tan. Sheep are sheared twice a year, in January and July, and a fleece fetches about 7½d. (5 as.). Ewes breed once a year and produce a lambkin at a time, rarely two. The breeding season is usually June and the greatest number of lambs is consequently born in November. No artificial attempts at weening are made, the lambs being suckled till the following rutting season, that is for seven months. Males are castrated before a year old, fine weather being deemed necessary for the operation. The proportion of rams to ewes is one to twenty. A sheep fetches 4s. to £1 (Rs. 2-10).

The goat is kept by almost all classes either as a flesh-producing or milk-yielding animal. They have three varieties, the *kui*, *ghodsheli*, and *asvali*. The *kui* is a small animal with short hair, little erect ears, hornless or with small horns set back in the head and curving backwards, and generally of a white colour. The *ghodsheli* is a tall large animal, generally black. The horns are set forward in the head though they curve backwards. Animals of this breed but having very long horns are called *hanams*. There is also a hornless variety. The *asvala* is a middle-sized animal with long hair, particularly on the haunches, and drooping ears. The *ghodsheli* goats are esteemed the best milkers and the flesh of the *kui* is considered the best. The he-goat fetches about 6s. (Rs. 3) and the she-goat 6s. to 10s. (Rs. 3-5).

The common country dog is found all over the State. A few sporting Maráthás and Rámoshis have good country gray-hounds, particularly the tall hairy variety with longish sulky ears. The Dhangar or shepherd's dog is both useful and intelligent. Many of them have the cut of a Scotch colley though somewhat larger.

The few camels in the State belong to the chief.

The hides and horns of cows and buffaloes are the perquisites of the Mhárs in the northern sub-divisions and of the Holayás in the southern or Kánarese sub-divisions. The prices vary from 1s. (8 as.) for the hide of a calf to £1 (Rs. 10) for that of a buffalo. Goat skins fetch each 1s. 6d. to 2s. (Re. ¾-1) and sheep skins about half that sum. Buffalo horns are worth 6d. to 1s. (4-8 as.) a pair. Cow horns seem to have no market value.

In the northern sub-divisions antelopes, gazelles, hyænas, wolves, jackals, foxes, and three or four varieties of the wild cat are pretty common. In Shirhatti, in addition to these panthers are found.

## Production.

—  
DOMESTIC  
ANIMALS.  
Asses.

Sheep.

Goats.

Dogs.

Camels.

WILD ANIMALS.

**Production.**

In Sháhápur, except the bison and bear, all the wild animals of the Saháydri are generally found.

**GAME BIRDS.**

Most if not all of the birds found in the Deccan are met with in one or other sub-divisions. The same may be said of reptiles and fishes. No animal peculiar to the State is found.

**People.****CENSUS DETAILS.  
1872 and 1881.**

According to the 1881 census the population of the Sánгли State was 196,832 or 1283 to the square mile. Of these Hindus, excluding Jains, numbered 172,257 or 87·51 per cent, Jains 11,344 or 5·76 per cent, Musalmáns 13,082 or 6·64 per cent, and Christians 149. The percentage of males on the total population was 49·80 and of females 50·20. Compared with the 1872 returns the 1881 returns show a decrease from 223,663 to 196,832, that is a decrease of 26,831 or 11·99 per cent, which is chiefly due to mortality during the 1876-77 famine.

**RACES.**

The Hindu population mainly consists of two races, the Aryan in the north in Mangalvadha, Mirajpránt, and Kuchi, and the Dravidian in the south in Terdál, Sháhápur, and Shirhatti. Musalmáns mostly of Pathán, Arab, or Persian descent are pretty evenly scattered throughout the State. Foreigners are small in number, the principal being Gujarát and Marwár Vanis and Madrásis. The Peshwa's rule (1750-1817) added largely to the strength of the Konkanasth Bráhmans who were before in a small number. Of the 3680 Konkanasths returned in 1881, about 1500 are in the town of Sánгли.

**LANGUAGES.**

The principal languages spoken are Maráthi in the northern and Kánarese in the southern sub-divisions. Maráthi in its corrupt form is also spoken to some extent in Sháhápur and Terdál. Of the total population 97,114 or 49·33 per cent speak Maráthi and 83,911 or 42·63 per cent speak Kánarese. The other languages spoken are English, Hindustani, Gujaráti, Márvádi, Támil, and Telagu.

**CHARACTER.**

The people in the northern sub-divisions are fairer and better looking but those in the southern or Kánarese sub-divisions are superior in strength. The best wrestlers are found south of the Krishna.

**DRESS.**

Dress varies according to caste and creed. But as a rule the people of the northern sub-divisions may be distinguished by a tightly-wound turban from the Kánarese people in the south, who wear a loosely tied scarf or *rumál*. The men in the northern sub-divisions wear long drawers, loose from the thigh to below the knee, whence they suddenly begin to taper so as to fit tightly round the calf to which they are invariably drawn up. Another kind of drawers also commonly worn, extends to the knee only. On the head is worn a long tightly wound three-cornered turban of any colour and over the body either a coat or *angarkha*, a jacket or *bandi*, or a waistcloth or *dhotar*. In the south the drawers are not common except among the Berads and other low castes who generally dye them a dull brickdust-red with red ochre or *hurmuji*. The Kánarese generally wear a waistcloth or *dhotar* round the loins, another thrown over the body, or in the place of it a jacket or a short coat and on the head a white or coloured scarf or

*rumdi*. In addition to these, men generally wear a coarse blanket or *kámbli*. The dress of the women consists of two garments, the robe or *lugdi* about twenty-four feet long and three broad, and the bodice or *choli*. The robe is made of every colour, but is generally a dark blue, particularly in the Kánarese sub-divisions.

According to occupation the 1881 census returns divide the population into six classes :

- I.—In state service, learned professions, literature and arts 4900 or 2·4 per cent of the population.
- II.—In house service 7839 or 3·9 per cent.
- III.—In trade and commerce 5474 or 2·7 per cent.
- IV.—In agriculture 64,106 or 32·5 per cent.
- V.—In crafts and industries 15,741 or 7·9 per cent.
- VI.—In indefinite and unproductive occupations, including children, 98,772 or 50·9 per cent.

In the sixth class 3566 or 1·8 per cent of the population are returned as professional beggars and seventeen as *gathechors* or professional thieves. The *gathechors* literally mean bundle-lifters who neither deny their avocation of theft nor steal at night under pain of excommunication.

The following tabular statement gives the number of each religious class according to sex at different ages with the percentage of males on the total population :

*Sángli Population by Age, 1881.*

AGE IN YEARS.	HINDUS.		JAINS.		MUSALMA'NS.		CHRISTIANS.		TOTAL.	
	Males.	Females.	Males.	Females.	Males.	Females.	Males.	Females.	Males.	Females.
Up to 1 ...	2523	2560	157	193	201	180	1	1	2882	2943
" 1 to 4 ...	6588	6657	475	533	470	496	13	15	7546	7701
" 5 to 12 ...	20,714	19,571	1284	1164	1635	1560	17	15	23,650	22,300
" 13 to 20 ...	13,264	13,220	790	859	1018	963	6	5	15,078	15,052
" 21 to 30 ...	17,214	18,351	1005	1155	1401	1347	11	17	19,681	20,870
" 31 to 40 ...	12,741	11,692	855	808	962	845	13	8	14,571	13,353
" 41 to 50 ...	7140	7455	550	533	455	569	11	6	8156	8563
" 51 to 60 ...	3975	4645	296	385	318	352	2	4	4591	5386
Above 60 ...	1683	2255	112	200	134	171	3	1	1932	2627
Total ...	85,842	86,415	5524	5820	6594	6488	77	72	98,037	98,795
Percentage ...	43·60	43·90	2·80	2·95	3·35	3·29	0·03	0·03	49·50	50·20

Agriculture supports 64,106 persons or 32·5 per cent of the total population.

The bulk of husbandmen are Maráthás or Kunbis, Dhangars, and Mhárs in the northern sub-divisions and Lingáyats, Jains, Hanbars, Berads, and Holayás in the southern sub-divisions. Of these the Lingáyats and Jains are careful and provident. The Maráthás though hardworking are extravagant. The husbandmen living in the east of Shirhatti and in Sháhápúr and on the banks of the Krishna are well-to-do. Their condition elsewhere is not good. The rates of assessment are higher than those prevailing in neighbouring British villages, and the settlement period extends to only fifteen years.

The soil, though varying in quality, is on the whole fertile. In Mirajpránt the soil close to the banks of the Krishna, especially the

## People.

## OCCUPATION DETAILS.

## AGE.

## Agriculture. HUSBANDMEN.

## SOIL.

Agriculture.  
Soil.

*mali* or alluvial deposit, is excellent. The *mali* lands are particularly suited to maize, barley, beans, castor-oil, pumpkins, melons, brinjals, and tobacco. In Kuchi the soil is generally of the same kind as in the Mirajpránt. But the water is nearer the surface and more irrigated crops are grown, such as sugarcane, earthnuts, garden wheat, and sweet potatoes. The soil is also lighter and hence more *báji* is grown. In Mangalvedha the prevailing soil is black, but from the uncertainty of rainfall the average yield is not greater than in the other sub-divisions. A good crop is obtained only once in three years. Terdal, particularly near the Krishna, has much good soil, mostly black. Some of the sandy soil is also rich and specially suited to pulses which are largely grown. Plantains grow well under irrigation and yield a good profit. In Sháhápúr the prevailing soil is red, though the black and sandy soils are not uncommon. Other cereals and pulses are grown, but rice is the staple of the sub-division. The soil in places yields two crops a year, rice being followed by peas or lentils. A good deal of sugarcane is grown, particularly the *vare* variety which is light-coloured small and sweet, and, being raised on moist lowlands, needs little irrigation to mature it. The vegetables, fruits, and potatoes grown in Sháhápúr are superior. The coffee plant also succeeds well with a little care. In Shirhatti rich black soil prevails which is particularly suited to cotton, both indigenous and the acclimatised New Orleans. In favourable seasons rich crops of wheat are raised. *Jári*, gram, and safflower of superior quality are also grown. But as water is deep below the surface, wells for irrigation are scarce and little sugarcane and vegetables are grown.

HOLDINGS.

The average size of holdings varies from  $9\frac{1}{2}$  acres in Sháhápúr to  $40\frac{1}{2}$  acres in Kuchi. The largest holding is 336 acres in Mirajpránt.

STOCK.

According to the 1882-83 returns the farm stock included 10,657 ploughs, 53,627 bullocks, 28,578 cows, 19,342 she-buffaloes, 7810 he-buffaloes, and 93,366 sheep. The following statement gives the details :

*Sangli Farm Stock, 1882-83.*

SUB-DIVISION.	Ploughs.	Bullocks.	Cows.	She-buffaloes.	He-buffaloes.	Sheep.
Mirajpránt ...	630	8550	4333	4862	1094	14,583
Kuchi ...	1897	8180	4466	2463	1607	20,025
Mangalvedha ...	1091	3599	3618	1726	694	20,193
Terdal ...	605	6764	2061	1751	585	6709
Sháhápúr ...	2985	9440	7358	4789	2200	5141
Shirhatti ...	3443	17,114	6742	3751	1630	26,745
Total ...	10,651	53,627	28,578	19,342	7810	93,366

FIELD TOOLS.

The chief field tools are the *nángar* or plough, *kuri* or seed-drill, *kulav* or harrow, and *koipa* or bullock hoe. The plough is of two kinds the large or *thorla nángar* and the *nángar* or small hand plough. The seed-drill has usually three or four tubes, which are removed when the seed-drill is needed as a harrow. It is generally drawn by a pair of oxen and sometimes by two pairs in heavy soils. The harrow is usually drawn by one and sometimes by two pairs

of bullocks. It is used to break clods, loosen the surface where ploughing is not done, and to cover the seed. The bullock hoe is used for weeding.

The chief manures are town sweepings, ashes, and cow and sheep dung. Manure is as a rule used in irrigated lands in the dry part and generally in Sháhápúr where the rainfall is heavy. In tracts where the rainfall is not plentiful, manure is not much used, as in seasons of scanty rainfall it burns the crop. The most favourite mode of manuring seems to be the penning of flocks on the fields which need fertilising. For penning a hundred sheep the shepherd usually receives for every night six pounds (2 *shers*) of *javári* and a meal.

Of an area of 693,120 acres or 1083 square miles, 559,110 acres or 80·66 per cent are arable, 56,588 or 8·16 per cent forest, and 77,422 or 11·18 per cent unarable. Of the arable area 46,999 acres or 8·40 per cent were in 1882-83 fallow or under grass and 512,111 acres or 91·60 per cent under tillage. The details of the principal crops are : Of grains 181,408 acres were under Indian millet *javári* Sorghum vulgare, 47,437 under spiked millet *bájrí* Penicillaria spicata, 22,489 under wheat *gahu* Triticum æstivum, 8137 under rice *bhát* Oryza sativa, 6589 under Italian millet *rála* or *káng* Panicum italicum, 5027 under *náchni* Eleusine corocana, 1730 under *chenna sáva* Panicum miliaceum, 1021 under maize *makka* Zea mays, and 100 under barley *jav* Hordeum hexastichon ; of pulses 21,636 acres were under gram *harbhara* Cicer arietinum, 10,117 under *tur* Cajanus indicus, 5218 under *hulga* or *kulith* Dolichos uniflorus, 3122 under *matki* Phaseolus aconitifolius, 1707 under *mug* Phaseolus mungo, 422 under peas *vátána* Pisum sativum, 385 under *pávta* Dolichos lablab, 365 under *masur* Ervum lens, and 35 under *udid* Phaseolus radiatus ; of oil-seeds 10,308 acres were under safflower *kardai* Carthamus tinctorius, 3770 under earthenut *bhuimug* Arachis hypogea, 3475 under castor oil-seeds *erandi* Ricinis communis, 2270 under linseed *alsi* Linum usitatissimum, and 1367 under sesame *til* Sesamum indicum ; of fibres 60,743 acres were under cotton *kápus* Gossypium herbaceum ; of miscellaneous crops 2201 acres were under tobacco *tambákhu* Nicotiana tabaccum, 444 under sugarcane *us* Saccharum officinarum, and 111 under turmeric *halad* Curcuma longa.

Of these the early or *kharif* (M.) or *mungári* (K.) crops are sown between the first week of June and the beginning of August and, except cotton, harvested between October and December. The late or *rabi* (M.) or *hingári* (K.) crops are sown between September and November, according to the lateness or otherwise of the autumnal rains and mostly harvested by the end of March.<sup>1</sup> The principal

## Agriculture.

### MANURES.

### CROP DETAILS.

<sup>1</sup> The *kharif* crops include under grains *javári*, *bájrí*, rice, maize, *náchni*, *rála*, *sáva*, and *vári* ; under pulses *tur*, *matki*, *hulga*, *udid*, *chavli*, and *mug* ; under oil-seeds *korta* and *til* ; under fibres, cotton, *tág*, and *ambádi* ; and under garden crops chillies. The *rabi* crops include under grains *javári* and wheat ; under pulses gram, peas, and *masur* ; under oil-seeds safflower or *kardai* and castor oil plant ; and under narcotics tobacco. Of *javári* which is both a *kharif* and a *rabi* crop, the *kharif* varieties are called the *kahár* and the *rabi* varieties the *shálu*.

**Agriculture.****CROP DETAILS.**

irrigated crops are sugarcane, earthnut, *khapli* or spelt, *ratāle* or sweet potato, turmeric, and maize. Of these the sugarcane is planted in the cold season and ripens in about a year. The earthnut is sown about July and dug up in January. The *khapli* is sown in October and reaped in January or February. The sweet potato and turmeric are planted about July and take five or six months to ripen. The roots are not always dug out when ready, as they are not injured by being left longer under the ground. The maize is raised, when required, at all seasons. Besides these the *hundi* variety of *javari* is often in the east grown under well irrigation during the hot weather and reaped in the early part of the monsoon principally as a fodder crop.

**FAMINE,  
1876-77.**

Since 1801 from which year the State dates its existence, no famine seems to have occurred except in 1876-77. The scanty and badly distributed rainfall of 1876, eight inches at Sāngli compared with an average of twenty-two inches, led to failure of crops and distress amounting to famine over all the sub-divisions except Sháhápur.<sup>1</sup> The sub-divisions that suffered most were Mangalvedha and Terdal. In Mirajprānt and Kuchi the villages away from the Krishna and the Krishna canal and the whole of Shirhatti also suffered much. In all these sub-divisions the *khariif* crops withered everywhere except in places near the Krishna where the river had flooded the country or where artificial irrigation was available. In the absence of autumnal rains no *rabi* crops could be grown except in the *bāgāyat* or garden lands. In the beginning much difficulty was felt in raising funds for opening relief works. Owing to former bad administration the balance in the State treasury was small. Loans were raised from local bankers, but the funds were soon exhausted. Application was made to the British Government for an advance, but to continue the relief works, before the sanction of the Government of India could be obtained, small sums were from time to time advanced from the Kolhápúr treasury. The Government of India sanctioned a loan of £90,000 (Rs. 9 *lákhs*) to the Sāngli State to meet the famine. In the beginning of July 1877 the first part of the loan was paid and no further difficulty was felt as regards funds.

**RELIEF WORKS.**

The relief works consisted of making new roads and ponds, repairing old roads, clearing and repairing old wells and ponds, and pricklypear clearances. Owing to the want of a proper engineering staff the works were generally carried on on a small scale except in Mangalvedha and Mirajprānt where the State had the benefit of the advice of Captain Twemlow, R.E., executive engineer in charge of the Krishna bridge. The relief works cost £21,800 (Rs. 2,18,000) of which £11,662 (Rs. 1,16,620) were paid by the State and £10,138 (Rs. 1,01,380) from local funds.

**RELIEF HOUSES.**

In the beginning of the famine in November 1876 a charitable relief kitchen was started at Mangalvedha. In December 1876

<sup>1</sup> The rainfall in 1876 at Sāngli was as follows: In June 4·32 inches, in July 4·30, in August 0·41, and in September 0·5, that is a total of 8·53 inches.



another relief kitchen was opened at Sàngli. In May 1877 relief kitchens were started in other sub-divisions and kept till the end of December 1877. The relief house at Sàngli was started by private subscriptions and was aided by the State funds; in other places the relief houses were started by the State. The relief houses cost £2279 (Rs. 22,790) of which £1887 (Rs. 18,870) were paid by the State and £392 (Rs. 3920) were raised by private subscriptions.

The following statement shows the average daily numbers on relief works and at charitable relief houses with the amount of cost to the State : *Sàngli Famine, 1876-77.*

MONTH.	AVERAGE DAILY NUMBERS.		MONTH.	AVERAGE DAILY NUMBERS.	
	On Relief Works.	On Gratuitous Relief.		On Relief Works.	On Gratuitous Relief.
1876.			1877.		
November ... ..	5775	25	July ... ..	6188	1546
December ... ..	8641	53	August ... ..	5550	1357
			September ... ..	3245	1842
			October ... ..	1592	1098
			November ... ..	391	469
			December ... ..	.....	126
1877.			Total ...	70,095	10,356
January ... ..	8006	99	Average ...	5392	739
February ... ..	7169	108	Total Cost ...Rs.	2,18,000	18,870
March ... ..	5545	119			
April ... ..	6170	185			
May ... ..	6026	1508			
June ... ..	5847	1816			

Compared with 1872 the 1881 census returns show a decrease of 26,831 people, mostly due to the mortality during the 1876-77 famine.

The total cost of the famine was estimated at £24,397 (Rs. 2,43,970) of which £21,800 (Rs. 2,18,000) were spent on relief works, £1887 (Rs. 18,870) on charitable relief, and £710 (Rs. 7100) on special allowances to State servants. Adding to this £49,225 (Rs. 4,92,250) as loss by revenue the total amounted to £73,622 (Rs. 7,36,220). The loss by revenue included £17,232 (Rs. 1,72,320) as remissions on land revenue, £193 (Rs. 1930) as remissions to farmers and contractors, and £31,800 (Rs. 3,18,000) as the estimated loss in land revenue due to emigration.

The rainfall of 1877, though late and deficient at first, was in the end ample and the crops were generally good. In 1878 the season was favorable, but a plague of rats ate up almost every grain particularly in the eastern parts. Steps were taken to destroy the rats which were killed by thousands. But the destruction they caused led to much distress and in Mangalvedha there was what is known as the rat famine. In the next season in 1879 the plague disappeared. Since then the seasons have been generally favorable and the people have recovered from the famine.

Of the seventy-eight bankers in the State, twenty-four are in Sàngli, twenty-nine in Sháhápúr, fourteen in Rabkavi, four in Terdal, three in Shirhatti, and four in Mangalvedha. Their united capital is roughly estimated at £90,000 (Rs. 9 lákhs). Some of the bankers grant bills of exchange or *hundis* on Bombay, Poona, and

## Agriculture.

### RELIEF HOUSES.

Loss.

Cost.

Capital.

BANKERS.

**Capital.**

other large towns, mostly in the Bombay Karnátak. Besides these many petty traders carry on moneylending on a small scale.

**CURRENCY.**

At present (1885) the Imperial rupee is the only current coin. Formerly the current coin was the *Hukeri* rupee which was worth about 1s. 7½d. (13 *annas*). The *Hukeri* rupee is still occasionally used in making payments of some charitable allowances from the chief's *kháshgi* or private department; but owing to the scarcity of this coin payments are now generally made in the Imperial rupee at the exchange of the day. Of other old coins gold *mohars*, *putalyás*, *varáís*, and *hons* are sometimes sold in the market but they fetch only the value of the gold they contain.

**INVESTMENTS.**

All classes except bankers and traders generally invest most of their savings in gold and silver ornaments. The traders and bankers invest half their capital in business and the other half in ornaments which when needed are also used in their business. Some invest their capital in landed property.

**MONEYLENDING.**

Trade and moneylending go hand in hand. The bulk of the moneylenders in Sámglí are Bráhmans, Gujarát Márwár and Lingáyat Vánis, and a few Jains, Rajputs, Kunbis, and Musalmáns; in Sháhápúr they are Shenvis and other Bráhmans, Lingáyat Vánis, Jains, and a few Márwár Vánis; and in Rabkavi and Terdal they are mostly Lingáyat Vánis and Jains and a few Bráhmans, Márwár Vánis, and Kunbis. The moneylenders who have a capital of £500 (Rs. 5000) and upwards, keep a day book or *rojkharda*, the ledger or *khátávahi*, the cash book or *nagdivahi*, a book of articles advanced or *jángadvahi*, and a rough memorandum book or *háttipan*. Those who issue bills of exchange or *hundis*, also keep a bill register or *hundinordni*. The moneylenders whose capital is less than £500 (Rs. 5000), only keep the day book, the ledger, and the rough memorandum book.

**INTEREST.**

Compound interest is, as a rule, charged on sums either due on current accounts or advanced on movable pawned articles. On the first of *Kártik* (October-November) the new trade year day, interest is calculated on sums due for the previous year. This interest and the past year's balance form the principal for the next year. On money advanced on immovable property simple interest is generally charged. For traders the yearly rate of interest ranges from five to nine and for other classes from nine to twenty-four per cent and sometimes higher. On movable pawned articles, if of gold, the yearly rate is generally six and sometimes nine per cent; if of silver, the rate rises from nine to twelve per cent. The pawned articles should be worth one and a quarter times as much as the sums lent. Where immovable property is mortgaged the yearly rate varies from nine to eighteen per cent. Money invested in landed property usually yields a yearly rate of nine per cent and never higher than twelve per cent.

**LABOUR  
MORTGAGE.**

The practice of mortgaging labour prevails among labourers and the poorer cultivators. The persons who mortgage labour are generally those who wish to get married. Land proprietors usually advance money on labour mortgage. The period for pledged

service extends from three to seven years, the year being sometimes reckoned as one of thirteen months. To work off a loan of £10 (Rs. 100) a labourer has to work for seven years; during this period the labourer, in addition to the advance, yearly receives clothing worth 6s. (Rs. 3), that is £12 2s. (Rs. 121) in all, or less than 3s. (Rs. 1½) per month. The ordinary monthly wages of a menial servant are about 8s. (Rs. 4). When the labourer receives a meal from the master the length of the service is increased, but under either circumstance the mortgagee never gets less than a yearly interest of twenty-one per cent. In the case of a herdsman who understands the tending and milking of cows the terms of mortgage are easier. The herdsman also gets his food from the master. In such cases the mortgagee rarely gets more than nine per cent interest yearly.

Besides the pledged labourers there is a distinct class of hereditary bondsmen called Lekavlas. The Lekavlas, meaning sons of female slaves, are found in rich Bráhmaṇ and Marátha families. They are well treated and considered members of the family in which they are born. The Lekavlas form the property of their masters and at the partition of the family are divided like other property. The custom of keeping mistresses and treating their offspring as Lekavlas has been now less prevalent than before.<sup>1</sup>

Of skilled labourers the goldsmith yearly earns £10 to £50 (Rs. 100-500), and in the town of Sháhápur as much as £100 (Rs. 1000); the silversmith about £20 (Rs. 200); and the copper-smith £12 (Rs. 120). The carpenter in a town daily earns 7½d. to 1s. 3d. (5-7as.), the bricklayer 6d. to 1s. (4-8as.), the mason 6d. to 1s. 3d. (4-10as.), the blacksmith 10½d. to 1s. 3d. (7-10as.), the tailor 9d. (6as.), the barber 6d. to 7½d. (4-5as.), and the cotton-cleaner or Pinjári 6d. (4as.). The weaver in one day weaves an ordinary woman's robe or *sádi*, about twenty feet long and three wide, and on this earns about 6d. (4as.). The dyer daily earns 1s. 6d. to 2s. (Re. ¾-1) in the town of Sāngli where the dyeing of turbans and *rumáls* or scarves is largely carried on. Among unskilled labourers men earn 3d. to 6d. (2-4as.) a day, women 2½d. to 3d. (1½-2as.), boys 2½d. (1½as.), and girls 1½d. to 2½d. (¾-1½as.). The class that earns a livelihood by mere day labour is small. The poorer husbandmen when freed from field work are employed as day labourers. Unskilled labour is therefore dear, particularly at seed and harvest time when the daily wages rise to 6d. (4as.). Field labourers are generally paid in kind, from six to nine pounds (2-3 *shers*) of grain.

Gold and silver and saffron, musk, opium, and *attar* or rose and other essences are sold by the following table: Eight *gunjás* make one *mása*, twelve *másás* one *tola*, and twenty-four *tolás* one *sher*.

Capital.  
LABOUR  
MORTGAGE.

WAGES.

WEIGHTS AND  
MEASURES.

<sup>1</sup> The Lekavlas marry among themselves and with girls at least of equal status. For instance, the grandson by marriage of a Lekavla is considered purer than his grandfather and would never marry the daughter of a Lekavla; his wife must at least be the granddaughter of a Lekavla. Here, as elsewhere, the stigma attaching to illegitimate birth is washed out by time.

**Capital.**  
**WEIGHTS AND**  
**MEASURES.**

For the *tola* the Imperial rupee is now used which is less than the *pakka* or real *tola* by four *gunjás*. Inferior metals and groceries are sold by the following table: Two *pávs* one *achher*, two *achhers* one *sher*, five *shers* one *pásri*, two *pásris* one *dhada*, two *dhadás* one *adman*, two *admans* one *man*, twenty *mans* one *khandi*, and three *kacha mans* one *pakka* or Bengal *man* of eighty pounds. The *páv* weighs about  $6\frac{1}{4}$  Imperial rupees. Grain is sold by the following measure: Two *chiptas* one *mápta*, two *máptas* one *sher*, two *shers* one *adisri*, two *adisris* one *páyli*, sixteen *páylis* one *man*, twenty *mans* one *khandi*, thirty-two *mans* one *her* or *goni* that is a packbullock-load. The grain measures vary in different sub-divisions. The *chipte*, which is the unit of the grain measure, is generally equal to one pound; but in Shahápur and Dodvád it weighs half a pound, that is the measures here are half in weight of those current in other parts.

**Trade.**  
**ROADS.**

The State is fairly off for roads which are generally feeders to trunk lines in the British and other Native State territory leading to important trade centres. The State keeps  $130\frac{1}{2}$  miles of road in repair. Of these ninety-one miles are in good order,  $33\frac{1}{2}$  being in Mirajpránt, eight in Kuchi, twenty-two in Mangalvedha, five in Terdal, eight in Shahápur, and  $14\frac{1}{2}$  in Shirhatti. In Mirajpránt the chief roads are the Athni-Chiplun, Sàngli-Akli, Sàngli-Uplavi, and Bijápur-Pandharpur. The Athni-Chiplun is a high road running from Athni in Belgaum to Chiplun in Ratnágiri. Passing by Miraj and Sàngli it joins the Poona-Belgaum trunk road at Peth in the Válva sub-division of Sátára and branches westward at Karád for Chiplun by the Kumbhárla pass. Thirteen miles of this road run through the State and are kept in good repair. The Sàngli-Akli is a metalled road, two miles long running from Sàngli to the Akli bridge on the Krishna. At Akli it joins the road which runs westward from Kolhápur to Ratnágiri by the Amba pass. The Sàngli-Uplavi road runs eight miles north-east from Sàngli to Uplavi by Budgaon, Kavlápur, and Kumta. Of the Bijápur-Pandharpur road  $10\frac{1}{2}$  miles run through Mirajpránt and are kept in repair. Besides these a portion of the old Belgaum-Tásgaon road is kept in repair and a new road is being built from Sàngli to Nándre which is to be a station on the West Deccan Railway. In Kuchi a branch road, four miles long, joins Kavtha-Mahánkál with the Bijápur-Pandharpur road. Another road four miles long runs from Kuchi to Jáygavhán. In Mangalvedha the State keeps in repair six miles of the road from Sàngola to Mangalvedha in the west, six miles of the Mangalvedha-Sholápur road from Mangalvedha to Begampur on the Bhima in the east, and ten miles of the Mangalvedha-Pandharpur road from Maravde to Malevádi on the Mán in the north. The Sàngola-Mangalvedha road leads to Sàngli in the south-west. In Terdal a five-mile road runs from Terdal to Rabkavi. From Rabkavi this road runs on to Kaládgi through Mudhol. In Sholápur there are three roads the Poona-Dhárwár, the Belgaum-Vengurla, and the Belgaum-Panchgaon. Of these the first two are Imperial trunk lines. Of the Belgaum-Panchgaon road eight miles run through the State and are kept in repair.

In Shirhatti the Gadag-Pála road, which carries much traffic, runs for five miles and is kept in good repair. Besides this three roads run from Shirhatti, one to Chhabi four miles, another to Mágdi four miles, and a third to Mulgund  $1\frac{1}{2}$  miles. From Mulgund the road runs to Gadag which is at the junction of the east and south Deccan railways.

The State has fifty-five rest-houses. Besides these travellers find accommodation in the Máruti temples in the villages.

Sángli has six sub-offices and three village offices. The sub-offices are at SÁNGLI, Mangalvedha, Terdal, Rabkavi, Sháhápur, and Shirhatti. The village offices are at Mahánkál-Kavtha, Kavlápur, and Dodvád. They are in charge of schoolmasters who, in addition to their pay as schoolmasters, receive yearly allowances from the postal department.

Trade except in Sháhápur and SÁNGLI is in the hands of Lingáyat Vánis and Jains. At Sháhápur it is shared in by Shenvi Bráhmans many of whom are wealthy, and a few Maráthás, and at SÁNGLI by Bráhmans, Gujarát and Márwár Vánis, Maráthás, and Musalmáns. The trading season begins after the *Diváli* holidays in October-November and lasts till the *Akshad-tratiya* or 3rd of the first half of *Vaishákh* (April-May), on which day all cotton bargains are finally settled. The general practice is for petty traders or agents of large firms to go about from village to village to the growers and buy up the expected crop by either making an advance on it before it is harvested or after it has been garnered. The buyer then sends the grain to his master or the nearest favourable market, which is usually out of State limits. Many husbandmen, however, do not deal with these middlemen and take their produce in person to the nearest market for sale. The produce of Mirajpránt and Kuchi generally comes to SÁNGLI, Miraj, and Tásgaon for sale, of Mangalvedha to Pandharpur or Sholápur, of Terdal to Athni or Rabkavi, of Sháhápur to Sháhápur or Belgaum, and of Shirhatti to Hubli or Gadag. The growers in Shirhatti generally take cotton to Hubli or Gadag, but when it is likely to fetch higher prices at Sadáshivgad in Kánara, three or four of the husbandmen join together and take about a dozen cartloads to that port.

Weekly markets are held at nineteen places: two in Mirajpránt, at Kavlápur on Wednesday and at SÁNGLI on Saturday; two in Kuchi, at Kavtha-Mahánkál on Tuesday and at Manjarda on Wednesday; two in Mangalvedha, at Mangalvedha and Loni, both on Monday; two in Terdal, at Rabkavi on Monday and at Terdal on Thursday; six in Sháhápur, at Balekundri-Khurd on Monday, at Sulebhávi on Wednesday, at Dodvád on Thursday, at Sambre on Friday, and at Sháhápur and Máribál on Saturday; and five in Shirhatti, at Belhatti on Monday, at Itge on Tuesday, at Bidarhalli on Wednesday, at Banikop on Saturday, and at Shirhatti on Sunday. The chief articles sold at these markets are cattle, cloth, cotton, clarified butter, grain, groceries, metals, molasses, oil and oilseeds, salt, timber, and tobacco.

The chief exports are from Mirajpránt cotton, *kahár jvóri*, gram, oilseeds, molasses, tobacco, clarified butter, and brass and silver pots;

# Trade. ROADS.

## REST HOUSES.

## POST OFFICES.

## TRADERS.

## MARKETS.

## EXPORTS.

**Trade.**  
**EXPORTS.**

from Kuchi cotton, *khapli* wheat, *shálu jvári*, and tobacco; from Mangalvedha wheat, rice, *shálu jvári*, oilseeds, and gram and other pulses; from Sháhápúr rice, *sádís* or women's robes, *khans* or bodice-cloth, and *dhotars* or waistcloths; from Terdal wheat, *shálu jvári*, gram, *sádís* or women's robes, *khans* or bodicecloth, *dhotars* or waistcloths, and country yarn; and from Shirhatti cotton, wheat, *kahár jvári*, oilseeds, and pulses.

**FAIRS.**

Thirty-eight fairs are held, eight in Mirajpránt, seven in Kuchi, three in Terdal, ten in Sháhápúr, and ten in Shirhatti. The fairs last from one to three days. The attendance varies from about a hundred to 35,000 and the average sale from a few rupees to £5600 (Rs. 56,000). The following statement gives the details:

*Sángli Fairs, 1882-83.*

PLACE.	NAME.	MONTH.	AVERAGE SALE.	ATTENDANCE.
<i>Miraj Pránt.</i>			£.	
Kumath ...	Narsoba ...	April-May ...	...	500
Dudhondi ...	Gaurisáheb ...	January-February ...	10	400
Shirgaon ...	Khánsáheb Pir ...	December-January ...	13	500
Kavápur ...	Sidlingeshvar ...	March-April ...	...	500
Digráj (small) ...	Basaveshvar ...	January-February ...	10	800
Digráj (large) ...	Gaibi Pir ...	March-April ...	...	200
Bhadkamb ...	Pir Sáheb ...	October-November ...	...	20
Sávalvádi ...	Lakshmi ...	January-February ...	3	100
Agalgau ...	Yeláma ...	November-December ...	...	500
Ránjri ...	Mhasoba ...	March-April ...	...	300
Kokal ...	Yelama ...	November-December ...	...	300
Kharsing ...	Pir ...	April-May ...	...	200
Mánjard ...	Máruti ...	March-April ...	...	300
Tisangi ...	Sidhanáth ...	Ditto ...	...	1000
Bastavad ...	Pir ...	Ditto ...	...	200
<i>Terdal.</i>				
Terdal ...	Prabhusvámi ...	July-August ...	280	5000
Rabkavi ...	Shankarling ...	Ditto ...	60	5000
Hangandi ...	Digambar ...	Ditto ...	96	2000
<i>Sháhápúr.</i>				
Dodvád ...	Rajebux Pir ...	February-March ...	5	200
Mutga ...	Bhávakeshvari ...	June-July ...	10	1000
Másmamardi ...	Basaveshvar ...	March-April ...	10	1200
Sulebhávi ...	Kalameshvar ...	Ditto ...	30	2000
Kadoli ...	Lakshmi ...	September-October ...	3	100
Ditto ...	Ditto ...	May-June ...	30	2000
Sámra ...	Basaveshvar ...	March-April ...	...	100
Kákti ...	Sidheshvar ...	Ditto ...	50	4000
Honag ...	Badridev ...	January-February ...	30	2000
Márhál ...	Basaveshvar ...	March-April ...	10	500
<i>Shirhatti.</i>				
Shirhatti ...	Pakirsvámi ...	April-May ...	5600	35,000
Yerbudihál ...	Basavanna ...	March-April ...	70	5000
Yalvatti ...	Gundeshvar ...	April-May ...	60	2000
Adarkatti ...	Basavanna ...	March-April ...	20	1000
Kodilvád ...	Virbhadra ...	April-May ...	5	500
Varvi ...	Manappa ...	March-April ...	40	400
Sásarvád ...	Shankarling ...	February-March ...	100	2000
Májur ...	Durgava ...	April-May ...	30	500
Náráyanpur ...	Basavanna ...	Ditto ...	5	200
Rantur ...	Máruti ...	March-April ...	3	200

**Crafts.**

Of SÁNGLI crafts the most important are the dyeing of yarn and head-dresses and the weaving of cotton cloth and woollen blankets.

**DYEING.**

The dyeing of cotton and silk is largely carried on in the three Kánarese sub-divisions in the south, especially at Rabkavi and Sháhápúr. The favourite colour for *sádís* or robes among Kánarese women is blue; Marátha women wear robes of every colour. The



only fast colours produced on cotton goods are the red and different shades of indigo. Of these the indigo dyeing is simple; the dyeing in red is described below. Green, orange, yellow, and turkey-red yarn required for women's robes is obtained from Bombay. Formerly silk used to be dyed locally with vegetable and mineral dyes. Of late the cheaper aniline dyes which are imported from Europe and yield a variety of bright tints, have nearly supplanted the native fast colours.

Crafts.  
DYEING.

For dyeing red a *chaukadi* or set of twenty-four *chirtas* or hanks of country yarn is made into eight bundles each containing three hanks tied to one another. About three pounds (5 *shers*) of plantain bark ashes are mixed in a vat with a pitcherful of soft water. The mixture is stirred and allowed to stand for an hour, when the ashes settle down leaving clear water above. About three quarts of this water are then poured into a basin and with it are mixed about  $\frac{1}{2}$  pound (5 *tolás*) of goat's dung and  $\frac{1}{4}$  pound (1  $\frac{1}{4}$  *sher*) of sesame oil. The bundles are then steeped in this mixture one by one and piled upon each other without being wrung. The pile is closely covered for two days with sacking so as to shut out the air. On the third day a pitcher of water is again mixed with plantain bark ashes as stated above. About two or three quarts of this mixture are poured into a trough, in which the bundles are put two by two and trodden on to press out the oil. The bundles are then taken out of the trough and without being wrung are placed in the sun on a pavement to dry. The bundles at this time must not be placed upon one another but separately dried, or spontaneous combustion sets in. They are not allowed to remain long in the sun. The bundles while moist are taken to the veranda and spread there for a time. They are again placed in the sun for four hours to dry. Another pitcherful of water is then poured into the vat and the ashes therein stirred up. After a while when the ashes have settled down leaving clear water above, the same process as mentioned above is repeated five or six times. The yarn is then taken to a river or brook, washed, and dried on a pavement. It is now ready to receive the dye.

Dyeing Red.

To prepare the dye about twelve pounds ( $\frac{1}{2}$  *man*) of *suranji* roots are pounded. The powder is mixed with  $\frac{1}{2}$  pound ( $\frac{1}{4}$  *sher*) of sesame oil and again pounded. The same quantity of oil is again added and the pounding repeated a third time, the dye being reduced to a fine powder. About  $\frac{3}{4}$  pound (16 *tolás*) of this powder and  $\frac{1}{10}$  pound ( $\frac{1}{3}$  *tola*) of alum are then mixed with water enough to steep one bundle. Into this mixture one of the bundles is dipped, taken out, and placed in another vessel. In this way when all the bundles are dipped, they are left for the night. Next day they are taken to a river or brook and dried in the sun on a pavement. Then follows the fixing process. About three pounds (1 *pásri*) of fine carbonate of soda or *pápdí* and  $\frac{1}{4}$  pound of alum are pounded together to a fine powder, 1  $\frac{1}{2}$  pounds (2  $\frac{1}{2}$  *shers*) of oil being added to it while being pounded, and  $\frac{1}{2}$  pound (20 *tolás*) of this powder is mixed with water enough to cover one bundle. The bundles are then dipped one by one in the mixture as stated above and left for the night. Next day they are put into a large vessel and placed on the fire, and if necessary water is added so

**Crafts.****DYEING.***Dyeing Red.*

as to have the bundles an inch under the surface. The bundles while boiling are lifted by a stick, a string being previously tied round them for the purpose. A quart of water, if necessary, may also be poured into the vessel while the bundles are boiling. After they have been boiled for two hours, the bundles are taken out and next day washed in a river or brook and dried on a pavement in the sun. The colour thus produced is a fast dye and resembles that of the *khárva* cloth made at Nágpur in the Central Provinces. The dyed yarn is chiefly used in making women's robes or *sádís* and bodicecloths or *cholis*. For dyeing twenty-four hanks of cotton yarn valued at 12s. (Rs. 6) the cost amounts to about 9s. 6d. (Rs. 4 $\frac{3}{4}$ ).<sup>1</sup>

*Turban Dyeing.*

Turbans are well dyed at Sámglí. Ten different kinds of colours are given. To dye a turban about sixty feet long in *kusumbi* or bright rose red, two pounds of safflower are put into a cloth bag hung from a square wooden frame on four legs and a pitcherful of water is poured on them. After the water has run through the safflower is crushed by the hand and another pitcherful of water is poured into it, when water of a reddish tinge begins to ooze out. The safflower is then squeezed dry and mixed with  $\frac{1}{10}$  pound (4 *tolás*) of carbonate of soda. About half a pitcherful of water is poured giving a red colour. This red water is placed apart. Two quarts of water are again poured into the bag giving a reddish tinge. To this reddish water  $\frac{1}{40}$  pound (1 *tola*) of turmeric powder and  $\frac{1}{2}$  pound (20 *tolás*) of lemon juice are added. In this mixture the turban is first dipped and wrung. It is then dipped into the red water previously set apart, to which about 1 $\frac{1}{2}$  pounds (60 *tolás*) of acid are now added. The turban is then hung out to dry. If it be found on drying that the colour is not of the required shade the turban is dipped a second time into the red water. To dye *gulábi* or rose colour the process is the same as above, except that no turmeric powder is used and the quantity of safflower is reduced to one pound. To dye in *pyáji* or pale pink only half a pound of safflower is enough. To dye *motia* a still paler pink than *pyáji*, the red water obtained from half a pound of safflower is mixed with  $\frac{1}{2}$  pound (5 *tolás*) of acid and some water. The mixture is left undisturbed for about six hours, by which time the crumbled safflower is deposited at the bottom leaving reddish water above. The sediment at the bottom is now removed into another vessel and mixed with four quarts of water and  $\frac{1}{2}$  pound (20 *tolás*) of acid. The turban is then dipped into this mixture, wrung, and dried. To dye *keshri* or pale orange  $\frac{1}{10}$  pound (4 *tolás*) of soda and  $\frac{1}{10}$  pound (4 *tolás*) of turmeric powder are mixed with about two quarts of water. The turban is dipped into this mixture and wrung. It is then dipped into the red water obtained from a pound of safflower in the same way as for dyeing pink. To dye *nārangi* or orange the process is the same as for *keshri* except that four pounds of safflower are required.

<sup>1</sup> The details are, 4s. (Rs. 2) for twelve pounds ( $\frac{1}{2}$  *man*) of *suranji* roots, 1s. 7 $\frac{1}{2}$ d. (13 *as.*) for three pounds (1 *pásvi*) of carbonate of soda or *pápdí*, 2s. (Re. 1) for eight pounds of sesame oil, 1 $\frac{1}{2}$ d. (1 *anna*) for  $\frac{1}{2}$  pound (24 *tolás*) of alum, 3d. (2 *as.*) for plantain bark ashes, 3d. (2 *as.*) for fuel, 6d. (4 *as.*) as wages for pounding *suranji* and carbonate of soda, and 9d. (6 *as.*) as wages for dyeing, giving a total of 9s. 6d. (Rs. 4 $\frac{3}{4}$ ).

To dye *jámhala* or purple, the turban is first dyed with indigo. It is then dipped into the red water obtained from two pounds of safflower in the same way as for dyeing *kusumbi*. To dye green the turban is first dyed with indigo and then dipped into a mixture which is prepared by mixing  $\frac{1}{10}$  pound (4 *tolás*) of acid and  $\frac{1}{20}$  pound (2 *tolás*) of turmeric powder with water enough to wet the turban. To dye *abashái* or crimson  $\frac{1}{2}$  pound (20 *tolás*) of cochineal or *kirmaj-dána* and  $\frac{1}{4}$  pound (10 *tolás*) of dried pistachio flowers are pounded together and mixed with about two quarts of water. After boiling the mixture about  $\frac{1}{2}$  pound (5 *tolás*) of alum is thrown into it. A turban dyed pink as stated above, if dipped in this mixture and dried, becomes *abashái* or dark crimson. To dye *limboli* or yellow  $\frac{1}{10}$  pound (4 *tolás*) of turmeric powder and  $\frac{1}{20}$  pound (2 *tolás*) of soda are mixed with water and the turban is dipped into this mixture. The turban while moist is then dipped into another mixture prepared by mixing  $\frac{1}{2}$  pound (5 *tolás*) of alum with soft water. To dye *pistái* or bright green a turban dyed yellow as stated above is dipped into a mixture of  $\frac{1}{20}$  pound (2 *tolás*) of fine indigo powder and a pitcher and a half of water.

The weaving of cotton goods is carried on more largely in the Kánarese than in the Maráthi sub-divisions. The *súdis* or women's robes and *cholis* or bodicecloths woven at Rabkavi and Sháhapur have a name.<sup>1</sup>

Woollen blankets or *kambliis* are made all over the State. As the wool is not dyed, the blankets are either black, white, or gray of different shades or mixture of these colours in longitudinal bars. Occasionally the pattern is a black or white check of the kind known in Scotland as shepherd's plaid. The blankets are generally nine feet long and three feet wide and fetch 2s. 6d. to 5s. (Rs. 1 $\frac{1}{4}$  - 2 $\frac{1}{2}$ ). The best blanket fetches as much as £2 10s. (Rs. 25).

Of other crafts the brass work of Sàngli has a name in the Bombay Karnátak. To develop this industry the late chief Chintamanráv (1801-1851) introduced into Sàngli a colony of Karajgars or brass-workers. In Sàngli there are also some good stone masons who work to any design in the hard rock of the country basalt. They have lately been well employed in the Kolhápúr State.

Sàngli forms part of the states belonging to the Patvardhan family. The founder of this family was one Har or Hari Bhatt bin Bállam Bhatt, a native of the village of Kotavda in the Konkan. This man, after distinguishing himself by a long series of devotional austerities, was appointed *upádhyá* or family priest to Náro Mahádev, chief of Ichalkaranji in the Kolhápúr State. On the occasion of the marriage of this chief's son to the daughter of Báláji Vishvanáth the first Peshwa, in 1722, Har Bhatt was brought to the notice of the Peshwa, and his sons Govind and Rámchandra were ere long taken into the service of the latter. A third son Trimbak obtained service with the rája of Akalkot. After the death of Báláji Pant Peshwa Har Bhatt's family continued to enjoy the favour of

## Crafts.

## DYEING.

## Turban Dyeing.

## COTTON GOODS.

## BLANKETS.

## History.

<sup>1</sup> For details of weaving see Belgaum Statistical Account, pp. 336-347.

**History.**

his successors, and Govindrāv with his son Gopálrāv took an active part in the events of Báláji Bájirāv's reign. After a successful campaign against the Nawáb of Sávanur in which he distinguished himself, he received from the Nawáb a grant in *inám* of the fort of Dodvád, with the land assigned for its support, which form part of the present possessions of the Patvardhan family. It was in the reign of the Peshwa Mádhavrāv Ballál, however, that the fortunes of the Patvardhans reached their zenith. In 1761 the fort of Miraj with some *thánás* and customs duties were assigned to Govindrāv for the maintenance of troops.<sup>1</sup> In 1763-64 *saranjámi* lands of the annual rental of upwards of £250,000 (Rs. 25 *lákhs*) were assigned to him in association with his nephews Parashurám Rámchandra and Nilkanth Trimbak Patvardhan for the maintenance of 8000 horse. The *saranjám* was composed of a number of districts situated in different parts of the country between the 15th and 18th parallels of north latitude, some lying to the north of Pandharpur and others being so far south as to be watered by the Tungabhadra. The most compact portion of the *saranjám*, as well as the richest, was that in the neighbourhood of Miraj and adjoining the eastern frontier of Kolhápur. The headquarters of *saranjám*dárs were here, and the intention of the Peshwa evidently was to hold the Rája of Kolhápur in check by the establishment of such a powerful *saranjám* in his immediate vicinity. A considerable part of the Patvardhan's possessions being near the Maisur frontier the duty devolved on them of watching Haidar Ali also and bearing the first brunt of his attacks when he and his son chose to invade the Marátha territory.

Gratitude to their benefactor Madhávavrāv led the Patvardhans to aid that prince actively in his struggle for power with his ambitious uncle and guardian Raghunáthráv, generally known as Rághoba Dáda. Whenever the latter gained the upper hand he showed his resentment, as by the attack and capture of Miraj on one occasion, but his enmity was not so dangerous as the vindictive feeling which descended to his son Bájirāv, the last of the Peshwás, which nearly occasioned the ruin of the Patvardhan family, as will be seen further on. Besides taking a prominent part in the internal politics of the Marátha empire during Mádhavrāv's reign, the Patvardhans were actively employed in all the campaigns against Haidar Ali and

<sup>1</sup> The fort of Miraj was probably built by the Bahmani kings. The first mention of it in Ferishta occurs in the account of the revolt of Bahádur Giláni (A.D. 1493), which has been referred to in the historical sketch of Kolhápur.

The fort and district appear to have been at that time in the possession of a Hindu landholder Pota Naig (Briggs' Ferishta, III. 346). On the fall of the Bahmani dynasty Miraj passed into the hands of the kings of Bijápur. Ali Adil Sháh was kept there under surveillance during the latter years of the reign of Ibráhim Adil Sháh his father, and on the death of the latter made the place a *point d'appui* in the operations undertaken to secure the throne. The garrison took part afterwards in the revolt of Ismail against Ibráhim Adil Sháh II. (Ferishta, III. 180). When Shiváji commenced the operations which resulted in the establishment of the Marátha empire, Miraj formed part of the *jágir* of Rustam Khán, a Bijápur official, who is believed to have betrayed his trust. A Persian inscription on the mosque or *dargáh* at Miraj records that it was built in A.D. 1413 and renovated 280 years afterwards. A similar inscription records that one of the large gateway bastions was named after Sikandar Jallál Khán. This was the grandson of Allá-ud-din Báhmíni I. the son of his daughter who was married to Jallál Khán Bukhári. Sikandar revolted against his uncle Humáyun Sháh and was killed at Navalgund in A.D. 1458.

in the war with Jánoji Bhonsla of Berár. Before the death of Mádhavráv the grant of the *saranjám* was renewed to the family in 1774, the title deeds being made out in the names of Vámanráv the brother of Gopálráv, and his cousins Parashurám Rámchandra and Raghunáthráv Nilkanth. Though the family was not as yet divided, these chiefs resided severally at Miraj, Tásgaon, and Kurundvád, and may be said to represent separate branches. In addition to the *saranjám* Mádhavráv bestowed on the Patvardhans during his lifetime the districts of Chikodi and Manoli, but they never held these districts for any length of time continuously.

After the death of Mádhavráv Peshwa and the murder of his brother and successor Náráyanráv, the Patvardhans followed the standard of Raghunáthráv until it became known that the widow of the murdered Peshwa was in a condition that gave hopes of an heir to the *gádi*. The celebrated Nána Fadnavis then formed a council of regency, governing in the name of the widow, but the Patvardhans did not openly take part against Raghunáthráv till the birth of Mádhavráv Náráyan put him in the position of an usurper. They then openly espoused the cause of the infant Peshwa, but they soon had to leave Poona for their own territory to aid in repelling invasions made by the Nizám and Haidar Ali from different quarters.

Even before the death of their great patron Mádhavráv Ballál the Patvardhans had been engaged in constant hostilities with the Rája of Kolhápúr, as has been related in the historical sketch of that State, and these hostilities were now carried on with great vigour, as the Rája had entered into alliance with Raghunáthráv in conjunction with Haidar Ali of Maisur, who advanced with the declared intention of taking possession of the whole country south of the Krishna. The Patvardhans therefore took no part in the war with the English which broke out at this time, as they were fully occupied with their hostilities against Kolhápúr and with resisting the invasion from Maisur. In the latter operations they were not very successful as they incurred more than one severe defeat, and Pándurangráv, the grandfather of the present Chief of SÁNGLI, was wounded and taken as a prisoner to Seringapatam, where he died.

The leadership of the Patvardhans then devolved on Parashurám Bháu. After some rather unsuccessful operations against Haidar Ali, a temporary truce, it would appear, left Parashurám Bháu at liberty to return to his own capital and carry on the war with the Kolhápúr Rája, from whom he took Akivát, Shirol, and Bhudargad. A treaty was then concluded with the Rája, and the Patvardhan Chief was thus enabled to proceed to Poona, where he arrived in time to play a very distinguished part in the war with the English, which followed the repudiation of the convention of Vadgaon in 1779. The success of the operations against General Goddard, by which that officer was compelled to retreat from Khandála to Bombay with heavy loss, was attributable in a great measure to Parashurám Bháu's skill and exertions.

The Patvardhan Chief was next employed against Tipu of Maisur, who attempted to reduce the fort of Nargund. By specious promises the latter induced the Maráthás to retire, and as soon as

## History.

Patvardhans,  
1763-1885.

## History.

Patvardhans,  
1763-1885.

they were out of the way seized Nargund and Kittur. These acts brought on a war which lasted for about a year. Peace was then concluded, but very soon the conduct of the Maisur prince caused the formidable combination of the English, the Nizám, and the Maráthás, who in 1790 commenced operations against him. Parshurám Bháu was appointed to command the Maráthá forces on this occasion. In conjunction with a British detachment under Captain Little he besieged Dhárwár for seven months, after which the place capitulated. He then took the fort of Kushgal and after waiting to realise the revenue of the district joined the other Maráthá commander Hari Pant, and moved towards Seringapatam, which was being besieged by Lord Cornwallis. Before they arrived, however, the British were compelled by want of provisions to raise the siege temporarily. Parashurám Bháu was then detached from the main army, with Captain Little, to keep open the communications with the north. He preferred, however, to utilise his time and means by taking possession of the district of Bednor, and this occupation delayed him so long that, though repeatedly summoned by Lord Cornwallis, who had resumed the siege, he only arrived at Seringapatam just as the armistice which preceded the treaty with Tipu had been arranged.

On his return to Tásgaon Parashurám occupied himself with a war with Kolhápúr. In the course of this his son was defeated and taken prisoner. Though the latter was treated kindly and at once released, the Patvardhan, incensed at the repulse, renewed hostilities with such vigour that the town of Kolhápúr only was saved from capture by the submission of the Rája who agreed to pay £30,000 (Rs. 3 *lákhs*) and to give hostages for the payment of the amount. Not long after this war was declared against Nizám Ali, and Parashurám Bháu commanded the Maráthá army on the last occasion when all the chiefs of that nation assembled under the Peshwa's standard. In the battle of Kharda he had a narrow escape of his life, but was saved by the bravery of his son to win a decisive victory.

In 1795 the Peshwa Mádhavráv committed suicide. As the heir to the *gádi* was Bájráv, the son of the Raghunáthráv whom Nána Fadnavis and the Patvardhans had always opposed and whose schemes they had been the main instruments of defeating, they resolved to prevent his succession by getting the widow of the deceased prince to adopt a son. Bájráv, however, heard of this and secured the services of Daulatráv Sindia. The result of this step was that his opponents thought it advisable to come to terms with him and accept him as Peshwa. A series of plots and counterplots ensued. Parashurám Bháu and Nána Fadnavis conceived the idea of getting Bájráv's brother Chinnáji Appa adopted by Náráyanráv's widow and invested as Peshwa, and in pursuance of this plot had him seized and invested against his will. The two chief conspirators however had for some time past been suspicious of one another, and just at this juncture Nána fled to the Konkan under the apprehension that Parashurám Bháu was about to make him a prisoner. An open rupture then took place. Nána made overtures to Bájráv and incited the Rája of Kolhápúr to attack Parashurám Bháu's *jágir*,



while Parashurám gave up Nána's *jágir* to Sindia and appropriated his houses at Poona. The long series of intrigues finally ended in the apprehension of both by Sindia.

History.  
Patvardhans,  
1763-1885.

Parashurám Bháu, however, was not long kept in confinement, as a general was wanted to oppose the Rája of Sátára who had levied forces and was assuming independence. The Patvardhan offered his services, which were accepted. He soon defeated the Rája, but on the completion of this duty was much too wary to disband his troops. He then offered to head the contingent intended to co-operate with the English in the new war with Tipu that broke out in 1799. Owing however to the duplicity of Bájráv the promised aid was never given to the British, and part of the force intended to co-operate with them was turned against the Rája of Kolhápúr who had been actively employed for some time in recovering the places that had been taken from him by the Patvardhans, and in overrunning and pillaging Parashurám Bháu's *jágir*, in the course of which operations the latter's palace at Tásgaon was burnt to the ground. Incensed at these losses Parashurám Bháu without waiting for reinforcements, hurried on operations against the Rája who was aided by Chitursing brother of the Rája of Sátára. His eagerness and resentment were such that he kept the field during the rainy season. In September he encountered the Kolhápúr troops under the Rája at the village of Pattankudi, where he was defeated and mortally wounded. It was reported at the time that as the wounded chief lay on the ground Vishvásráv, brother of the notorious Sarjeráv Ghátge, took him up on his horse and carried him to the Rája, by whose orders he was cut to pieces. This story, however, has always been denied at Kolhápúr, and those who have had the best means of getting information have considered it to be untrue.

Rámchandraráv Appa Sáheb, eldest son of the deceased chief, fled after the battle to Poona to implore the aid of the Peshwa. This was readily granted, and a considerable force consisting of the Vinchurkar's and the Pratinidhi's troops and five of Sindia's regular battalions under European officers were despatched to Kolhápúr. The force met with a slight check at Shirol, but was reinforced and advanced to the capital. The Rája was there defeated and obliged to fly to Panhála, and the siege of the town was begun.<sup>1</sup> The siege was raised in consequence of an intrigue at Poona. On the death of Nána Fadnavis, which took place during the siege, the Peshwa arranged with Sindia that the latter should attack and possess himself of the late Parashurám Bháu's territory. The besieging force then broke up, Sindia's battalions marching on Tásgaon and Appa Sáheb flying to the Karnátaḱ leaving his *jágir* to be overrun and devastated.

Orders were then sent from Poona to the Peshwa's *Sar Subhedár* in the Karnátaḱ, Dhondo Pant Gokhle, to sequester the Patvardhan's territory in that province. As the *Sar Subhedár* was engaged in hostilities at the time with Dhundia Vágh, a freebooter who had

<sup>1</sup> For details of the siege see above Kolhápúr History, page 234

**History.***Patvardhans,  
1763-1885.*

escaped from Seringapatam, and was now plundering the country at the head of a considerable force, he kept the order secret, and thus got the Patvardhans to co-operate with him. When he was killed shortly afterwards in an engagement with Dhundia he was accompanied by Chintámanráv (the son of the Pándurangráv whose death at Seringapatam has been noted above), who was wounded on the occasion. After Gokhale's death Chintámanráv joined Colonel Wellesley (afterwards the Duke of Wellington), who had been sent to put down Dhundia, and the two sons of Parashurám Bháu shortly afterwards joined the British forces. The Patvardhans tried to get the English general to join them in an attack on Kolhápur, but he declined to do so, and managed to keep the peace between his allies. The result of the combined operations was that Dhundia, on the 10th September 1800, was defeated and killed at Konagal. At the suggestion of the British Resident at Poona the order for the sequestration of the Patvardhans' districts in the Karnátak was rescinded, and Colonel Wellesley handed over the districts released from the grasp of Dhundia to the sons of Pharashurám Bháu. The duplicity of Bájrát's conduct, however, at this time was such that the Patvardhans seriously entertained the notion of entering the service of the Maisur prince, but the project was not carried out. Just at this time Sindia was obliged to remove his troops from Tásgaon in consequence of the war with Holkar, and the Patvardhans were then enabled to return to their homes.

At the end of 1802 the Peshwa, driven out of Poona by Holkar, signed the treaty of Bassein and General Wellesley marched from Seringapatam to restore him to his capital. The Patvardhans immediately joined him and begged him to obtain for them the good offices of the British Resident. He did his best to reassure them, though the conduct of Bájrát, even at this juncture, was such as to make them naturally most suspicious, and they accompanied him to Poona. After the restoration of the Peshwa, General Wellesley brought the claims of the Patvardhans before him, and he promised to do justice. Appa Sáheb and Chintámanráv were induced to visit Bájrát and further promises were made, but nothing was settled when the British general left Poona to carry on the war against Sindia and the Rája of Berár. He had hoped that the Patvardhans and other Marátha chiefs would join him, but they met with no encouragement from the Peshwa to do so, and, indeed, seem to have been secretly dissuaded by him.

Their conduct on this occasion nearly led to the ruin of the family. At the close of the war, Bájrát, on the pretence of rewarding those who had done good service and punishing those who had failed to render due assistance, determined to make over the lands of the Patvardhans to Bápu Gokhale. As the latter felt himself unable to take over the *saranjám* without the assistance of the English, he applied to General Wellesley. Without deciding whether or not such aid would be given, which was for the Governor-General's consideration, the British commander pointed out in forcible language the impolicy, the injustice, and even the ingratitude of the course the Peshwa wished to pursue towards the

Patvardhans. In writing to the Governor-General he recapitulated all the arguments he had used, and suggested that the Peshwa's formal consent should be obtained to the British Government acting as arbitrator between him and the southern *jágirdárs*. This suggestion was approved, and Mr. E. Strachey was appointed to conduct the enquiries and negotiate the proposed settlement. Before leaving the Southern Marátha Country, General Wellesley took advantage of an interview he had with Hari Parashurám at Tásgaon, to point out what just grounds of complaint the Patvardhans had on their part given to the Peshwa, and to show how matters might be settled satisfactorily.

The proposed settlement, however, fell through for the time in consequence of the unwillingness of both the parties concerned to avail themselves of the means thus offered to them of putting matters on a satisfactory footing. Bájrív only wanted to ruin the Patvardhans and displayed his characteristic duplicity, while they, on the other hand, distrusted him and had an exaggerated notion of their own power. The British Government, therefore, withdrew its mediation and left the Peshwa and the *jágirdárs* to settle matters between them as they best could. The latter consequently assumed a semi-independent position, and only attended to the requisitions of the Poona government when it suited them to do so. Chintámanráv even harboured freebooters pursued by Bájrív's troops, and actually attacked the Peshwa's districts. The latter, in the meantime, consolidated his position by crushing a number of minor *jágirdárs* and watched his opportunity for dealing similarly with the Patvardhans.

A struggle was thus impending between these *jágirdárs* and their sovereign, which would have led to most serious consequences. Mr. Mountstuart Elphinstone, the Resident at Poona, perceived this, and saw that if the war commenced it would probably spread and affect British interests. He therefore proposed to the Governor-General in 1811 a scheme of mediation similar in most respects to that which General Wellesley had suggested. On this being approved he submitted to the Peshwa a draft of the terms which he thought should be offered, and having obtained his consent, he proceeded to Pandharpur at the head of a force strong enough to crush opposition, and summoned the Patvardhans. After some delay and attempts at evasion the latter accepted the terms. They thus bound themselves to give up all land and revenues which they had usurped and were holding without authorisation ; to serve the Peshwa according to the conditions on which they held their *saranjám* ; to carry on no hostilities unless duly authorised to do so, and to submit their disputes to the Peshwa. On the other hand, the Peshwa agreed to take no notice of past offences and to revive no old claims, while the British Government guaranteed to the *jágirdárs* their lawful possessions so long as they served the Peshwa with fidelity.

About this time several divisions of the *saranjám* took place among the members of the Patvardhan family which require notice. The first division was between Chintámanráv and his uncle

History.  
Patvardhans,  
1763-1885.

**History.**  
*Patvardhans,*  
*1763-1885.*

Gangádharráv. The latter, on the death of his brother Pándurangráv, had been left guardian to his nephew, and, with the proverbial policy of a paternal uncle under such circumstances, had appropriated a considerable portion of his ward's property. Chintámanráv in 1801 set to work to recover his possessions, and acted with such vigour that Gangádharráv had to shut himself up in the fort of Miraj, where he would have been besieged had not the other members of the family interposed and persuaded the uncle and nephew to agree to an amicable division. This arrangement was, in 1808, sanctioned by the Peshwa, who further exempted Gangádharráv from feudal allegiance to the senior branch of the family. It was arranged, too, that Gangádharráv should have the fort of Miraj, £10,000 (Rs. 1 *lakh*) being assigned to Chintámanráv for building a fort at Sángli, which he made his head-quarters. The example thus set was followed by other members of the family. The sons of Parashurám Bháu divided their father's estate into two portions, Jamkhandi being held by the elder and Tásgaon by the younger brother. The Kurundvád branch also divided, and the separate estates of Kurundvád and Shedbál or Kágvád were thus formed.

The settlement of Pandharpur secured its main object, the preservation of the peace of the country, by putting a stop to the disputes between the Peshwa and the Patvardhans, but the relations between the two parties continued to be anything but cordial. The leading members of the family, however, were with Bájráv when the treaty of Poona was signed in 1817, and though Chintámanráv had been very violent in his opposition to this engagement, the Resident secured the interests of the Patvardhans by a special article (number 10) in the treaty. This article was most distasteful to Bájráv, and it was not till he had exhausted every form of remonstrance that he agreed to it reluctantly.

Immediately after the attack on the Residency at Poona and the battle of Kirkee, in November 1817, Mr. Elphinstone sent circular letters to the *jágirdárs* setting forth the causes of the war with the Peshwa, and advising the several chiefs to withdraw their troops and stay quietly at home, in which event they would be guaranteed against any loss of territory or dignity. The Patvardhans who had joined the Peshwa's standard after the battle did not immediately respond to this invitation, but some of them sent *vakils* to the Resident. With a view to deprive them of any grounds for hostility against the British, Mr. Elphinstone instructed General (afterwards Sir Thomas) Munro 'to treat the country immediately under the Peshwa and the *jágir* of Gokhale as hostile, and that of all the other *jágirdárs* as friendly.' General Munro was also entrusted with the task of making a settlement with the *jágirdárs* based on that of Pandharpur, and was authorised to offer considerable additions to the possessions of those who should come in within a specified period. The Patvardhans did not by any means comply with the letter of the communication made to them by the British authorities, but they, at a very early period of the war, ceased to render any but a very nominal assistance to the Peshwa, and most of them left his camp before long on one pretext or another.

General Munro having been obliged by ill health to leave the Southern Marátha Country before the completion of the task assigned to him, Mr. Elphinstone himself negotiated with the several chiefs and fixed the terms granted to them. These terms were similar for the most part to those agreed on at Pandharpur in 1811, but some additional clauses were inserted to secure the due administration of justice in the *jágirdár's* territory and to prevent criminals from the neighbouring British districts being harboured there. The strength of the contingents to be supplied for service was considerably reduced and personal *taináts* or attendants were granted to several members of the family. The terms offered were gladly accepted by all except Chintámanráv of SÁNGLI, who declined to serve the British Government, and was allowed to cede territory of the annual rental of £13,500 (Rs. 1,35,000) in commutation of service. The chiefs with whom treaties were thus made were Chintámanráv of SÁNGLI, Ganpatráv of Miraj,<sup>1</sup> Ganpatráv of Tásgaon, Ganpatráv of Shedbál, Keshavráv of Kurundvád, and Gopálrav of Jamkhandi.

Very shortly after coming under the British Government the members of the Miraj branch of the Patvardhan family claimed a division. As their claim was in accordance with precedent it was admitted, and the Miraj portion of the *saranjám* was divided into four separate estates. About the same time the Jamkhandi portion of the *saranjám* was divided and the separate estates of Jamkhandi and Chinchni were formed. In 1854 a division took place in the Kurundvád estate as the brothers and nephew of the Chief insisted on a separation, which was allowed by Government.

As several holders of estates in this family had no heirs of their body the question of the right to adopt very soon came before the Government. The principle was then enunciated that in such cases adoption was not a right but a favour, the granting or refusing of which lay with the paramount power, and Government declared its intention of not granting this favour except under special circumstances, such as for instance in the case of a Chief who had distinguished himself by his good administration or in other ways. Under this rule the following estates lapsed to Government, the holders having died without leaving male issue : Chinchni in 1836 ; a share in the Miraj estate in 1842 ; another share in the same estate in 1845 ; Tásgaon in 1848 ; and Shedbál or Kágvád in 1857. Adoptions had been allowed in the two last cases, but, as the adopted persons after holding the estates died without male heirs of their body, further adoptions were not allowed. Besides these instances adoptions have been sanctioned in the SÁNGLI, Miraj, and Jamkhandi families. As the chiefs of the Patvardhan family have all, except the younger chiefs of Kurundvád, received *sanads* from Lord Canning permitting them to adopt, there will be no further lapses in default of male heirs of the body.

### History.

*Patvardhans,*  
1763-1855.

<sup>1</sup> The treaty was made in his name as he was the head of the Miraj branch of the family, but as he was a minor at the time his estate was managed and all negotiations were carried on by his uncle Mádhavráv.

**History.***Patvardhans,  
1763-1835.*

In 1848 the contingents furnished by the Patvardhan Chiefs were done away with, and this service was commuted to an annual money payment. The sums paid to the British Government on this account are £1255 16s. (Rs. 12,558) for Miraj Senior, £641 4s. (Rs. 6412) for Miraj Junior, £961 18s. (Rs. 9619) for Kurundvád, and £2084 (Rs. 20,840) for Jamkhandi.

As a rule, the Patvardhan family have shown much loyalty towards the British Government. During the insurrection in Kolhápúr in 1844 Chintámanráv of Sángli rendered most cordial and effective aid to the authorities. Afterwards when tried by the more severe test of the mutinies of 1857-58 the conduct of the Patvardhan Chiefs, with one exception, was such as to gain the thanks of Government.

The following changes have taken place in the *personnel* of the existing Patvardhan states since the subversion of the Peshwa's dynasty and their engagements with the British Government.

In Sángli Chitámanráv Appa Sáheb died on the 15th July 1851 and was succeeded by his son Dhundiráv Tátyya Sáheb, who was born in 1838. Before the birth of the latter another son of Appa Sáheb had died leaving a widow, who adopted a son. The old Chief was very anxious that this adoption should be recognised by the British Government, and finally his request was acceded to on the usual condition of *nazarána* being paid. When this sanction was accorded, however, Chintámanráv was expecting issue by his wife, and consequently did not care enough about the adoption to pay the *nazarána*. He made a will before his decease, fixing an allowance to his adoptive grandson Vináyakráv, the succession to the State devolving, as above stated, on his son. In 1873, during the regime of the present Chief Dhundiráv, the British Government, in consequence of abuses of administration, appointed an English officer as joint administrator, and this arrangement still continues.

After the division of the Miraj estate above narrated the headship of that branch of the family, the fort of Miraj, and the largest portion of the *saranjám* remained with Ganpatráv Tátyya, whose brother Moreshvarráv lived with him. The latter demanded a further division, which would have been effected but for the death of Ganpatráv in 1833, on which event Moreshvarráv withdrew his claim for a division, and was appointed guardian to the two young sons of his deceased brother, Gangádharráv and Náráyanráv, who were aged seven and five years respectively. He died in 1839, and the management of the minors' estate remained in the hands of two ministers, until Gangádharráv Bála Sáheb assumed the administration in 1849. In recognition of the latter's loyal conduct during the mutiny, he was allowed in 1859 to adopt, having no heirs of his body, and on his death in 1861 was succeeded by his adopted son Ganpatráv Tátyya Sáheb. The young Chief being a minor, arrangements were made for his education and for the management of his estate during his minority. He assumed the administration in 1871, and was shortly afterwards appointed a member of the Legislative Council of Bombay. Ganpatráv Tátyya Sáheb died in November 1874. His widow in June 1875 adopted with the sanction



of Government Gopálráv, the younger grandson of Vináyakráv Bháu Sáheb of Sàngli, who received on his adoption the name of Gangádharráv. He was at the time in his tenth year. During the minority of the Chief the State has been under the direct management of the Southern Marátha Agency.

The second share in the Miraj *saranjám* devolved, as above stated, on Mádhavráv, who died in 1859 and was succeeded by his son Lakshmanráv Anna Sáheb. Lakshmanráv died in February 1876 and was succeeded by his son Hariharráv. The latter died soon in May 1877, leaving an infant son Lakshmanráv. During the minority of the young Chief the State is being managed by joint *kárbháris* under Government supervision.

Keshavráv, the Chief of Kurundvád, died in 1827, leaving four sons named Raghunáthráv, Hariharráv, Venáyakráv, and Trimbakráv, all minors. The eldest was placed in charge of the estate in 1837, and before long a division was claimed by the younger brothers, which, after much correspondence, was finally sanctioned in 1854. The estate of Kurundvád was thus divided into two parts, the larger portion remaining with Raghunáthráv Dáda Sáheb, and the rest being assigned to Ganpatráv Bápu Sáheb (son of Hariharráv who had died), Vináyakráv Appa Sáheb, and Trimbakráv Ábba Sáheb. The last named Chief died in 1869 without male issue and it was decided that his share of the estate should devolve to his brother Vináyakráv and his nephew Ganpatráv, the elder brother being excluded from the succession. Raghunáthráv of the senior branch died in January 1876 and was succeeded by his son Chintámanráv.

Gopálráv, the Chief of Jamkhandi, died in 1840, having before his death adopted with the sanction of Government a boy then seven years of age, who received on adoption the name of Rámchandarráv Appa Sáheb and who, after receiving some education, was invested with the administration of his estate in 1853. Rámchandraráv Appa Sáheb still (1885) administers the affairs of his estate.

Since 1873 the State has been under joint administration. The court of the Chief and the Joint Administrator which is styled the *huzur* court, is in all matters the supreme court of appeal subject to the advice of the Political Agent and the orders of Government. The principal officers under the *huzur* court are: The *Kárbhári* who is the head of the revenue, police, public works, and *pága* departments and the criminal branch of the judicial department; the *náyab kárbhári* who assists the *Kárbhári* chiefly in supervising the work of the district officers and is also a magistrate of the first class; the *nyáyádhish* who is at the head of the civil branch of the judicial department, has the powers of an assistant judge and is the registrar of the district; three *munsifs*; six *mámlatdárs* each in charge of a sub-division; one *vahivátdár* for the detached town of Dodvád; seven *faujdárs*, one for Sàngli town and six for the six sub-divisions; one auditor who audits all accounts and is under the *Kárbhári*; and one *pattrak phadnis* who is in charge of the head-quarters treasury and is the head accountant of the State. In 1882-83 the total cost of administration amounted to £22,747 6s. (Rs. 2,27,473).

## History.

SÁNGLI.

Patvardhans,  
1763-1835.

## The Land.

STAFF,  
1884.

**The Land.**STAFF,  
1884.

Formerly each sub-division except Mirajpránt had an officer styled *subhedár* who was the chief revenue, magisterial, and judicial officer of the sub-division. In Mirajpránt there were instead of the *subhedár* officers styled *kamávísdárs* who were each in charge of about eight villages, and over the *kamávísdárs* was an officer styled *mokáshí*. At present (1884) for administrative and fiscal purposes the State is divided into six sub-divisions, each being in charge of a *mámlatdár*. The yearly salaries including allowances of the *mámlatdárs* vary from £90 to £120 (Rs. 900-1200). Of village officers the headman is called *pátíl* in the Marátha and *gauda* in the Kánarese sub-divisions. The headman is assisted by the accountant called *kulkarni* in the Marátha and *shyámbhog* in the Kánarese sub-divisions. As a rule each village has one headman and one accountant, but sometimes there are two headmen and as many as four accountants for each village. The headmen and accountants are now appointed for a period of five years. At the end of this term they are succeeded by other sharers in the *vatan* or hereditary office. The headmen are usually Maráthás, Lingáyats or Jains, and sometimes Dhangars. The accountants are all Deshasth Bráhmans. The headmen and accountants are assisted by Shetsandis and Mhárs who are paid in cash or rent-free land. The revenue of the State under the Patvardhans has always been collected in cash.

**TENURES.**

Sángli land tenures belong to five classes: *sheri*, *inám*, *mákte-kamávishi*, *khand-tota*, and *rayatwári*. The *sheri* lands are the crown lands which are periodically leased to the highest bidders. The *inám* or alienated lands are those granted for military or other service. Of the forty-two *inám* villages two are grants to temples, thirteen to district hereditary officers, ten to *saranjámzárs* or officers rendering military service, and seventeen are personal. The *mákte-kamávishi* or lands held by contract sum, comprise four villages which have been farmed in perpetuity by the Sháhápurkar family at a fixed rental for which they are personally responsible. The *khand-tota* lands are those on which the full assessment is not levied. The *rayatwári* lands are those now held under the revenue survey tenure.

**SURVEY.**

The survey settlement was introduced in 1865-66 in Shirhatti, in 1868-69 in Sháhápur and Mangalvedha, and in 1879-80 in Mirajpránt, Terdal, and Kuchi. It remains to be introduced in a few *inám* villages only. The revenue in the *kharif* villages is collected in December and February and in the *rabi* villages in February and April. *Takávi* or money advances are granted to holders at a yearly interest of  $6\frac{1}{4}$  per cent.

**Justice.**

In 1852 civil courts were established in Mirajpránt, Mangalvedha, Terdal, Sháhápur, Dodvád, and SÁNGLI. The SÁNGLI court had jurisdiction over the town of SÁNGLI and Vádi village only. In 1879, at the reorganization of the civil branch of the judicial department, the number of *munsifs'* courts was reduced to three. One of the three *munsifs* is stationed at SÁNGLI and has jurisdiction over Mirajpránt. Of the remaining two *munsifs* one has jurisdiction over Kuchi, Terdal, and Mangalvedha, and the other over Sháhápur,

Shirhatti, and Dodvád. They hold their court at the head-quarters of each of the sub-divisions for two months by turn. A clerk is permanently stationed at the sub-divisional head-quarters, who receives plaints and other emergent applications during the absence of the *munsifs* and executes decrees. The *munsifs* have original jurisdiction in suits up to £500 (Rs. 5000). Suits of more than £500 (Rs. 5000) are decided by the *nyáyádhish* who also hears appeals from the decrees of the *munsifs*. The *huzur* court is the final court of appeal. During the year 1882-83, 1380 original suits of the value of £12,774 (Rs. 1,27,740) were filed and 1500 including the arrears of the previous year were decided, and 1328 applications for executions of decrees were received and 1558 including the arrears of the previous year were disposed of. During the same year 137 appeals were filed by the civil appellate courts and 120 were decided.

Justice.

The registration department has been in existence since 1863. Registration was at first optional. Since 1875 the registration of all immovable property of the value of £5 (Rs. 50) and upwards has been made compulsory. The department is at present worked by a district registrar and six special sub-registrars. The *nyáyádhish* is the district registrar. The sub-registrars are stationed each for one sub-division. During the year 1882-83, 953 documents were registered. During the same year the gross receipts amounted to £393 (Rs. 3930) and the charges to £73 14s. (Rs. 737), thus leaving a credit balance of £219 6s. (Rs. 2193).

## REGISTRATION.

The administration of criminal justice is carried on by seventeen magistrates. Of these one the *Kárbhári* is the district magistrate and hears appeals; nine, the *náyab kárbhári*, six *mámlatdárs*, and two *munsifs* are magistrates of the first class, and seven, the six *aval kárkuns* or head clerks of the *mámlatdárs* and the *vahivátdár* of Dodvád are magistrates of the third class.

## MAGISTRACY.

In 1875 the regular police force was constituted. The force is at present (1883) 450 strong and consists of six *faujárs* or chief constables, eight *thánédárs*, twenty-two *jamádárs*, sixty-four *náiks*, and 350 constables. It is maintained at an annual cost of about £3222 10s. (Rs. 32,225). Of the police force 110 are armed with smoothbore muskets, and the rest have either batons or swords. In addition to the regular police, a body of forty-three *savárs* or horsemen is kept on the *shiledár* system at a yearly cost of £1740 10s. (Rs. 17,405). They are fairly well mounted and armed with swords and are available for police duties. Except the police and *savárs* no other military force is kept in the State. The State has three guns, one an iron siege gun and two brass field pieces. They are badly mounted and only used for firing salutes. During the year 1882-83 property of the value of £998 4s. (Rs. 9982) was stolen, of which property of the value of £284 8s. (Rs. 2844) or 28·4 per cent was recovered.

## POLICE.

Besides the central jail at Sánгли, there are seven lock-ups for under-trial and short-term prisoners. The central jail at Sánгли was built in 1867 and has room for about 300 prisoners. The seven lock-ups are at Kavtha, Mangalvedha, Terdal, Sháhápur, Shirhatti, Dodvád, and Mhaisál.

## JAILS.

## Finance.

It seems that during the last twenty years there has been a gradual decrease in the cultivable waste and a steady rise in the revenue. According to the balance sheet of the year 1883-84, the total revenue amounted to £77,773 (Rs. 7,77,730) and charges to £62,618 (Rs. 6,26,180). The following statement gives details of the 1883-84 balance sheet :

Sangli Balance Sheet, 1883-84.

RECEIPTS.		CHARGES.	
Head.	Amount.	Head.	Amount.
	£		£
Interest on invested Capital...	1233	Administrative ...	4638
Land Revenue ...	61,752	Allowances ...	3803
<i>Sāgar dāb</i> ...	1702	Amount paid to other States ...	2032
Octroi and Town Duties ...	803	Land Revenue ...	9307
<i>Abkāri</i> or Excise ...	2649	Civil ...	1039
Stamps ...	3117	Criminal ...	367
Registration ...	518	Police ...	3996
Law and Justice ...	1302	Stamps ...	255
Jails ...	122	Registration ...	129
<i>Pāga</i> ...	192	<i>Savārs</i> ...	1606
Education ...	1567	Jails ...	578
Public Works ...	110	<i>Khāsi</i> ...	9145
Forest ...	1002	<i>Pāga</i> ...	3201
Miscellaneous ...	1564	Lithographic Press ...	137
Recoveries of overpayments, &c. ...	140	Education ...	2669
		Public Works ...	6979
		Forest ...	1203
		Miscellaneous ...	1184
		Refunds ...	1767
		Medical ...	389
		<i>Dharmadāya Devasthān</i> ...	736
		<i>Ināmadārs and Hakdārs</i> ...	2323
		Minor Departments ...	4492
Total ...	77,773	Total ...	62,618

Formerly import export and transit duties were levied on all articles of merchandise. In 1837 the transit duties were abolished at the instance of Government. The import and export duties still remain, but they are light. Before the introduction of the survey settlement seventeen *bābs* or cesses were from time to time collected for the special use of the Chief as necessity arose.<sup>1</sup> Except a few which were also levied in Terdal, the cesses were all levied exclusively in Mirajprānt. Many of the cesses were in kind, but all were afterwards commuted into a cash payment under the name of *sarpatti*. The *sarpatti* was collected along with land rent and varied from  $1\frac{1}{2}$  to  $5\frac{5}{12}$  annas in the rupee. At the introduction of the survey rates the *sarpatti* was abolished. The husbandmen

<sup>1</sup> The seventeen cesses were : *Jakira* for the cost of war materials ; *ambrāi-patti* for expenses of the mango garden ; *kansābipendhya* green ears of *jvāri* on account of *hārda* or roasted grain for the Chief ; *ruithya* wood of the *ruī* *Calotropis gigantea* on account of charcoal for making gunpowder ; *palāthya* or cotton stalks on account of battens for roofs of State buildings ; *bhus-patti* or bran for State cattle ; *chitta-vāgh* for the keep of hunting leopards ; *patrāvālī* or leaves for making platters ; *darbār-kharch* on account of milk for Ganpatráv Sāheb, elder son of the late chief Chintāmanráv Appa Sāheb ; *kavāñi* for the expenses of drilled troops ; *daftardār-kārkun* for payment to the *daftardār* ; *palāñi-kārkun* for the clerk who made the crop inspection ; *trivāry-kārkun* probably for the triad of *kārbhāris* that formerly existed ; *potnis-kārkun* for payment to the treasurer ; *kamāvisdār-kārkun* for payment to a *kamāvisdār* ; *pāga-farmās* or fodder ropes and grain for State horses and elephants ; and *bhet* or present to the Chief from village officers on the occasion of their visit to him at Sangli in connection with the *tāluka jamābandi*.

have now to pay only the land rent and a one anna-cess in the rupee on account of local funds. In the *inám* villages where the survey and settlement have not yet been introduced, the *sarpatti* still remains. In addition to the *sarpatti* there are other cesses which, not being a charge on the land, were not abolished on the introduction of the survey settlement. They do not appear in every sub-division. The total revenue from these cesses amounts to about £2050 6s. (Rs. 20,503) a year.<sup>1</sup>

In 1882-83 there were 114 schools with 5066 names. Of these fifty were aided schools with 1492 names. Except the Sângli English school which was examined by the Educational Inspector Southern Division, the schooling of the State was supervised by a State deputy educational inspector. In 1882-83 the total cost of education exclusive of school buildings amounted to £2428 (Rs. 24,280). During the nineteen years ending 1882-83 the number of schools has increased from fourteen in 1864-65 to 114 in 1882-83 and the number of pupils from 620 in 1864-65 to 5066 in 1882-83. The following statement gives the number of the various classes of schools and the number of pupils attending them during the year 1882-83 :

*Sângli Schools, 1882-83.*

CLASS.	SCHOOLS.	PUPILS.
<i>State.</i>		
Anglo-Vernacular ... ..	3	200
Vernacular ... ..	46	2854
Night ... ..	6	207
Girls ... ..	5	249
Special Sanskrit ... ..	4	64
Total ...	64	3574
<i>Aided.</i>		
Indigenous ... ..	50	1492
Grand Total ...	114	5066

Of the sixty-four State schools, in three English was taught, in four Sanskrit, in twenty-five Maráthi, in thirty Kánarese and Maráthi,

<sup>1</sup> These cesses are fourteen in number : *mohotarfi* or *adánstra* a tax on shops and houses fetching about £1340 (Rs. 13,400) a year ; *jakát* or import and export duty in Terdal, Sháhápur, and Shirhatti, fetching about £640 (Rs. 6400) a year ; *avti-báb* for the right of being the measurers of corn for corn chandlers in Terdal and Sháhápur fetching about £20 (Rs. 200) a year ; *gánja-khoti* or right to sell *gánja* or smoking hemp, fetching about £16 (Rs. 160) a year ; *charsa* a cess of less than 2s. (Re. 1) on the average for each village, levied on Mhárs in Mirajprant, Kuchi, Sháhápur, and Shirhatti, in lieu of tanned skins formerly supplied by them and yielding about £11 10s. (Rs. 115) a year ; *pátdám* a cess on every second marriage of a woman in Terdal and Sháhápur, fetching about £6 (Rs. 60) a year ; *gavat-katámi* or a cess of about 2s. (Re. 1) for each village levied in Sháhápur in lieu of services done by the villagers in mowing grass in State *kurans* and yielding about £5 10s. (Rs. 55) a year ; *maghunda* a cess on looms in Sháhápur yielding about £4 (Rs. 40) a year ; *báshing-khoti* a cess in Sháhápur of about 6d. (4 as.) on each *báshing* or headdress worn at weddings by the bride and bridegroom, fetching about £210s. (Rs. 25) a year ; *deshmukh-rábtí* a cess on Mhárs in lieu of menial services personally rendered to *Deshmukhs* whose property has lapsed to the State ; and *charmijoda* a cess on Chámhbárs in lieu of shoes supplied, both levied in Mirajprant and yielding about £2 8s. (Rs. 24) a year ; *tambáku-daláli* a cess in Mirajprant on tobacco brokers fetching about £1 10s. (Rs. 15) a year ; *rábnuh* a cess of 10s. (Rs. 5) a year, levied in Mirajprant on Mhárs in lieu of menial services formerly done in person to the Chief ; and *khatik-khoti* a cess in Sháhápur for the right of selling meat, fetching 8s. (Rs. 4) a year.

Finance.

Instruction.

**Instruction.**

and in two Urdu and Persian. The Sāngli English school teaches up to the matriculation standard. Of the sixty-four schools twenty-six have their own buildings and the rest are located in village *chāvdis* or temples. For the encouragement of education the State has established four scholarships at a yearly cost of £22 16s. (Rs. 228). Of these two of the value of 16s. (Rs. 8) a month were in 1882-83 held by the students of the Sāngli English school, the third worth 12s. (Rs. 6) a month by a girl sent from the Sāngli girls school to the Kolhāpur Female Training School, and the fourth worth 10s. (Rs. 5) a month by a Sāngli student attending the workshop attached to the Science College at Poona.

**LIBRARIES.**

The four libraries in 1882-83 were at Sāngli, Kavtha, Terdal, and Shāhāpur. Of these the Sāngli library, which is the largest, was established in 1864. It was at first maintained solely by the State; but in 1879 its receipts were increased by monthly subscriptions. In 1882-83 it had 560 books, thirty-nine subscribers, an income of £64 (Rs. 640) and an expenditure of about £44 (Rs. 440). Of the income of £64 (Rs. 640) the State grant was £32 (Rs. 320).

**Health.****CLIMATE.**

The climate though hot is not unhealthy. In the rainy season the climate is everywhere pleasant, except perhaps in Shāhāpur, where the heavy constant rain is objectionable. In the cold season the air is dry and the nights often very cool.

**DISEASES.**

The chief diseases are fevers, guinea and round worms, skin diseases, diarrhoea, and chest and venereal affections. Epidemics of cholera, though not common of late, do sometimes occur. Small-pox is uncommon. Intermittent fever occurs in all the sub-divisions. In Shāhāpur it prevails throughout the year; in other sub-divisions it appears after the rains, continues in the cold season, and is rare in the hot season. Remittent fever is common in Shāhāpur and in other parts it is rare.

**DISPENSARIES.**

In 1882-83 the State had six dispensaries, one in each sub-division at Sāngli, Kavtha-Mahānkāl, Mangalvedha, Terdal, Shāhāpur, and Shirhatti. The first dispensary was opened at Sāngli in 1874. Except at Sāngli where an old building was available, the dispensaries are all located in new buildings. They have no accommodation for in-patients. In 1882-83 the total cost of the dispensaries amounted to £1304 (Rs. 13,040), of which the State contributed £364 (Rs. 3640), local funds £670 (Rs. 6700), and the Shāhāpur municipality £270 (Rs. 2700). The average number of patients treated at each of the dispensaries for the three years ending 1882-83 was 8211 at Sāngli, 2583 at Kavtha, 3489 at Mangalvedha, 2354 at Terdal, 5780 at Shāhāpur, and 3094 at Shirhatti.

**VACCINATION.**

In 1882-83, besides at the dispensaries, the work of vaccination was carried on by five vaccinators at a yearly cost of £118 10s. (Rs. 1185). During the three years ending 1882-83, 12,338 persons were vaccinated. Vaccination has now been made compulsory.

**BIRTHS AND DEATHS.**

During the three years ending 1882-83 the total number of deaths was 11,586 or an average yearly mortality of 3862 or according to the 1881 census of 19.62 in every thousand of the



population. The yearly totals vary from 3464 in 1880-81 to 4400 in 1881-82. During the same year the total number of births was 17,226 and averaged 5742. The details are :

*Sáṅgli Births and Deaths, 1880-81 to 1882-83.<sup>1</sup>*

YEAR.	Total Deaths.	Total Births.
1880-81 ...	3464	3980
1881-82 ...	4400	7159
1882-83 ...	3722	6087
Total ...	11,586	17,226
Average ...	3862	5742

**Digraj**, with 2896 people, lies on the right bank of the Krishna about five miles above Sáṅgli. It is the *saranjám* village of the Chaváns to whom it was granted in 1738 in military service by Sháhu of Sátára. By the Peshwás the Chaváns were transferred to serve under the Patvardhans of Miraj. The service has now been commuted into a money payment. The bulk of the people are Maráthás, to which caste the *saranjámddárs* and the *pátíls* also belong. The village is liable to be flooded during the rains. The soil is rich alluvial. Digraj has a Maráthi and a Hindustáni school, the *váda* or residence of the *saranjámclár*, five Hindu temples, two Jain *bastis* or temples, a *masjid* or mosque, and a *darga* or prayer-place.

**Dodváḁ**, with 3440 people, lies fourteen miles north of Dhárwár and forty south-east of Belgaum. During the times of the Chálukya kings of Kalyán, Dodváḁ was subject to the Mahámandaleshvar of Sugandhivarti the modern Saundatti. In an inscription on a stone-tablet near the Kalmath Bhávi well, the place is called Dodd-vád or big town. In 1639 the king of Bijápur granted half a *cháhur* of land in *ináṁ* to one Mulla Fallula son of Mulla Murulla, for keeping clean the Jamma *masjid* at Dodváḁ. In 1667 there is an order issued by the Bijápur government to the *diván* of Hisár or fort Dodváḁ,<sup>2</sup> authorizing him to spend annually a certain amount on account of the fort. This order clearly proves that the fort was built before 1667. Afterwards Dodváḁ formed part of the *jágir* of the Nawáb of Sávanur, and was included in the twenty-two sub-divisions taken by the Peshwa Bálláji Bájíráv in 1756. Of these it is said that some sub-divisions were returned to the Nawáb partly through the intercession of Gopalráv Govind Patvardhan. The Nawáb Abdul Hakim Khán, in acknowledgment of these services, gave Gopalráv the village of Dodváḁ in *ináṁ* in 1769, with the sanction of the Peshwa Mádhavrát Ballál. In 1792 Dodváḁ was taken by Tipu Sultán of Maisur and formed part of his dominion for one year. In 1793 the Peshwa's army took back the Dhárwár

## Health.

BIRTHS AND DEATHS.

## Places.

DIGRAJ.

DODVÁḁ

<sup>1</sup> The death returns are believed to be fairly correct and the birth returns to be incomplete.

<sup>2</sup> Dodváḁ has two stone tablets, probably of the times of the Chálukya kings, one of which is illegible and the other not yet deciphered.

**Places.****DODVÁD.**

district and restored Dodvád to the Patvardhans. At the division of the *saranjá*m in about 1801, Dodvád came to the share of Chintámanráv of Sánгли. The Chief of the Mirajmala State has also a share in Dodvád, which is yearly paid in cash at £457 14s. (Rs. 4577). In 1819 Dodvád was occupied by the British Government for about eight months to persuade the late chief Chintámanráv to acknowledge their suzerainty. The water-supply of Dodvád is chiefly drawn from two wells, the Kalmath Bhávi and the Dodd Bhávi. The Dodd Bhávi well, which is old, is excavated in rock and has four sides, each about 125 feet long. The water in the well is about twenty feet deep. Dodvád has an area of 10,208 acres and yields a yearly revenue of £1827 10s. (Rs. 18,275). It has a municipality with a yearly income of £80 (Rs. 800), a boys school with ninety names, and a girls school with about thirty names. Outside the fort and to its north-east is the office of the *vahivatdár*. To the south of this is an open plot of ground said to have been the site of a garden. The building of the *vahivatdár*'s office and the open plot are surrounded by a mud wall built on a lower level than that of the fort walls.

The fort at Dodvád faces east and is a quadrilateral with round semicircular and quadrilateral bastions. Its sides are ninety-seven feet long on the north, 727 on the east, eighty-five on the south, and 672 on the west. The fort is built on a rocky hillock or *mardi*. The walls, which are about twenty feet high, are built for half the height with stone and white earth and for the other half with bricks. They have holes for musketry beneath the parapet, which is four feet high. The fort has a ditch all round, twenty-five feet wide and twelve to nineteen deep. The rampart, the parapet, and the bastions are in good condition. The fort is said to have contained a large building and a *masjid*, but no traces of these now remain.

**KAVLÁPUR.**

**Kavla'pur**, with 3956 people, lies five miles north-east of Sánгли near a small stream which rising in the Dandoba hills runs into the Krishna. The village, which was formerly called Shingnápur and Kavandanyapur, is built on stony undulating ground choked in places with prickly pear. The well water is brackish and full of guineaworms. The stream that runs by the village has good water and flows for the greater part of the year. In this stream water can be had below the sand at all times of the year. The village has sixty wells for irrigation and four for drinking. It has two small ponds on the south. The bulk of the people are Maráthás. The Lingáyats and Jains number about 500 each. Formerly the people had a name of being troublesome, but they are now quiet. Kavlápur has an area of 7160 acres, of which 5768 or eighty per cent are cultivable, and yields a yearly revenue of £1680 (Rs. 16,800). It has twenty-two shops of grocers and grain-dealers and thirty looms of weavers. A weekly market is held on every Sunday. The village has a substantial schoolhouse having room for a hundred boys, and fourteen Hindu temples, one Jain *basti*, and a Musalmán *darga*. The most important temple is that of Shiddeshvar in the north, which has a rest-house or *dharmshála*.

**Mangalvedha**, the head-quarters of the Mangalvedha sub-division, lies between the angle formed by the junction of the Bhima and the Mán, about forty-two miles south-west of Sholápur, thirteen miles south of Pandharpur, and sixty-five miles north-east of Sàngli. It has according to the 1881 census 7805 people. Except in the west where it is stony, the soil near the town is a rich black loam yielding plentiful crops of *shálu jvári*, wheat, and gram. The aspect near the town is dreary and void of trees. The town is surrounded by a wall which was built in 1694 and is 6136 feet long and eight thick. It has three gates, the Sàngola on the south-west, the Borála on the east, and the Káshegaon or Pandharpur on the north. The wall has fourteen bastions, about twelve feet high and fourteen in diameter. The Krishna pond and ninety-three wells supply drinking water to the town. Two roads pass through the town, one from east to west joining the Sholápur-Sàngola road at Begampur and Andhalgaon and the other from north to south joining the Pandharpur-Bijápur road at Maravde on the Mán. In the Chauburji or the inner part in the fort are the offices of the *mámlatdár* and the *faujdar* and the *munsif's* court. Outside the Chauburji but within the fort near the gate are the dispensary and the travellers' bungalow. Outside the fort on the right of the gate is the building of the anglo-vernacular school and on the left the post office. To the east of the anglo-vernacular school is the Hindustáni schoolhouse. Mangalvedha has a municipality which had in 1882-83 an income of £124 14s. (Rs. 1247) and an expenditure of £129 8s. (Rs. 1294), the excess of charges over receipts being paid from the previous year's balance. Mangalvedha has twenty temples, of which eight are in the fort and twelve in the town. Besides these there is the Musalmán Jamma *masjid* in the fort opposite the dispensary.

Mangalvedha is said to be noticed as Mátulingpuri in the Bhim Mahátmya included in the Skand Purán, but this identification is doubtful. From innumerable monumental stone remains of the times of the Chálukya kings of Kalyán found scattered about the place, it is concluded that it must have been a town of great note during the ninth tenth and eleventh centuries. It is certain from the inscriptions that the town of Mangalvedha was subject to the dominions of the Kalyán kings and that a great officer of theirs lived at this place. It appears to have been subject also to the Bahmani kings of Bedar in the fourteenth century.<sup>1</sup> At the end of the Bahmani rule in 1489 Mangalvedha seems to have passed to the Bijápur kings and at the fall of the Bijápur kingdom in 1686 it became subject to the Moghals. The Emperor Aurangzeb during

**Places.****MANGALVEDHA.***Description.**History.*

<sup>1</sup> According to the local story a Bráhman named Dámájipant was employed at Mangalvedha as a revenue officer under the Bedar government. In 1460 a famine known as Dámájipant's famine wasted the Deccan. Dámájipant had charge of a large store of government corn at Mangalvedha. Hundreds of Bráhmans and others flocked to Mangalvedha and were fed by Dámájipant out of the government stores. Hearing of his breach of trust the Bedar king issued orders that Dámáji should be seized and brought before him. While Dámáji was on his way to Bedar the god Vithoba whom Dámáji worshipped took pity on his servant and appearing as a village Mhár at Bedar paid the price of the grain distributed by Dámáji. Colonel Etheridge's Famine Report (1868), 99-100.

## Places.

## MANGALVEDHA.

## History.

his stay (1698-1700) at Masnur village, eight miles east of Mangalvedha, used to pay a weekly visit to the *masjid* of Pir Gaibi Sáheb at Mangalvedha. It is said that while thus going from his camp at Mangalvedha through the waving fields of corn, Aurangzeb happened to enquire into the revenue of the *pargana* or sub-division and was told that only £10,000 (Rs. 1 *lakh*) were realized by his government. This amount he deemed to be very small and gave orders to double it for that year and to increase the same by £4000 (Rs. 40,000) more for the next year, that is the husbandmen of the *pargana* had to pay £20,000 (Rs. 2 *laks*) in 1699 and £24,000 (Rs. 2,40,000) in 1700. These exorbitant rates were continued for many years until in 1716, under the Sátára kings, Bahirji Ráje Pándhre in charge of the *pargana* found the country entirely depopulated and uncultivated. Pándhre induced the people to cultivate lands at £1 15s. (Rs. 17½) per *cháhur* of 120 *bighás* for the year 1717 and at £3 10s. (Rs. 35) for the following year, thus increasing every year by a multiple of £1 15s. (Rs. 17½) till it came to £10 10s. (Rs. 105) in 1722. The Pándhres were succeeded by the Shivdevs in the headship of the *pargana* and in 1750 by Meghashyámráv Krishna Patvardhan who acted as a *mámlatdár* of the Peshwa's government till in 1764 Mangalvedha became part of the *saranjám* granted to Govind Hari Patvardhan. In 1801, at the division of the *saranjám*, Mangalvedha came to the share of the Sángli branch.

## Fort.

The fort of Mangalvedha was probably built by the Bedar officials. These officials knocked down all the old Jain temples of which there were many at Mangalvedha and built the fort with the materials so obtained. For, in an inscription on a pillar in the temple of Vishvanáth dated the 3rd of the bright fortnight of *Bhádrapad* of *Shake* 1494 *Angirás Samvatsar* or A.D. 1572, it is stated that the *kulkarni* of Hippargi who was then a *majmudár* at Mangalvedha, had repaired an old pulled down temple in the fort near Jagbhávi with the permission of Mulla Yákub Khán and had placed in it the *ling* of Vishvanáth. The fort is 1245 feet long on the north, 1200 on the east, 1100 on the south, and 920 on the west. The wall is thirty-five feet high and thirteen wide. Except in the east where it was pulled down, the wall is in good condition. The fort has seven bastions called the Mardán, Karad, Chophála, Jagbhávi, Gachi, Kaikád, and Borále. Of these the Mardán, the largest bastion, is 47½ feet high and fifty in diameter. Of the remaining six smaller bastions five are round and one, the Chophála, is a rectangle. Their height is not uniform. The ditch round the fort is eighty-two feet wide and 6½ deep on the north side. The main gate on the east is 14' x 12'. Within the fort there is another small fort called the Chauburji which is a square having one of its sides 230 feet long, eighteen high, and eight wide. It has four bastions called the Ranmandal, Rahát, Bhut, and Badekhán. The bastions are twenty-five feet high and thirty in diameter. The Chauburji has two gates, one in the middle of the east wall 12' x 8' and the other in the middle of the west wall 17' x 4'. It is said to have been built by the Pándhres who were in charge of the *pargana* under the Sátára kings (1720 - 1750).

**Ma'njarda**, with 2587 people, lies in the Kuchi sub-division, about twenty-three miles north-east by north of Sāngli. It is built on a stony eminence on the left bank of a watercourse. It has an area of 3962 acres, yielding a yearly revenue of £470 (Rs. 4700). The bulk of the people are Maráthás to which caste the *pátíl* belongs. The village is well off for water, having 101 wells for irrigation. It has a good schoolhouse having room for seventy-five boys, five temples, and one mosque.

**Places.**  
**MÁNJARDA.**

**Ma'riha'l**, with 2560 people, lies on the road to Kaládgi about ten miles east of Belgaum. It is an *inám* village belonging to Shiti Páchhábi Sáheb. The village was originally granted in *inám* by the Bijápur government to one Mahmud Sakáb Pirjáde. The place is fairly well wooded, has a fertile soil, and yields a yearly revenue of £400 (Rs. 4000). The bulk of the people are Lingáyats and Maráthás. The water-supply is ample as there are 152 wells. Márihál has six temples and two mosques.

**MÁRIHÁL.**

**Mhaisa'l**, with 2877 people, lies about thirteen miles north-east of Sāngli and seven miles south of Miraj with which it is connected by a road. It lies about a mile from the left bank of the Krishna. Mhaisál is a *saranjám* village belonging to Kedárráv Shinde, to whose ancestor Khetroji Shinde it was granted in 1738 on military tenure by Sháhu of Sátára. The service has now been commuted into a money payment. The bulk of the people are Jains to which caste the *pátíl* belongs. The villagers are well off owing to the fertility of the soil. The drinking supply is mostly drawn from the river; it has also two ponds and thirty-six wells, of which twenty-seven are used for irrigation. Mhaisál has an area of 8868 acres and yields a yearly revenue of £2200 (Rs. 22,000). It has a Maráthi school, three rest-houses, eight temples including a Jain *basti*, and three Musalmán *dargás* and two *masjids*.

**MHAISÁL.**

**Na'ndra**, with 3918 people, lies on the left bank of the Verla about six miles north of Sāngli. As the soil is rich alluvial the village is wealthy. The bulk of the people are Jains who number 2922 or 74·57 per cent of the population. The village has an area of 7712 acres, of which 7292 or 94·55 per cent are cultivable and yields a yearly revenue of £2545 (Rs. 25,450). It has a substantial schoolhouse and a good *chávdi* or village office. It has twelve temples including a Jain *basti*, and a Musalmán *darga*.

**NÁNDRA.**

**Rabkavi**, a large trading town with 5028 people, lies in the Terdal sub-division on the south or right bank of the Krishna about 2½ miles from it. It is five miles west of Terdal, sixty north-east of Belgaum, and forty-six south-east of Sāngli. The town appears to have been called from the village goddess Rabbava. It is built on porous sandstone rock which when disintegrated gives a fertile soil. There are small hills on the north and west. As the town has few trees round it, the aspect is dreary and the climate during the summer oppressively hot.

**RABKAVI.**  
*Description.*

The town has an area of about a quarter of a mile. Its extreme length from north to south is 3330 feet and breadth from east to west 1980 feet. The town may be divided into three distinct parts,

Places.  
RABKAVI.  
Description.

the original old village, the old town, and the new town called the Chintáman Peth. The original village stands on a small hill in the south-west. It has a *gadhi* or small fort, the south wall of which is twenty-seven feet high and the northern wall is in ruins to the length of about ten feet from the top. Here the descendants of the original inhabitants of the village, chiefly Khattris, Lonáris, and Dhangars live and number about 250. The old town was founded by a *kaul* or lease granted to the traders in 1818 in the old Mhárváda which was removed for the purpose. The old town extends to the north of the village to the temple of Rabbava and had among the original settlers about twenty traders and fifty weavers. It has now 250 Bilejáds and as many Bangárs. The second *kaul* or lease was granted by the late Chief Chintámanráv in 1832 at the instance of one Parápa Umdi a rich banker of Rabbavi. The new town extends close to the old town from the temple of Rabbava which forms the boundary between the old and new town. It is called the Chintáman Peth in commemoration of the visit which the late Chief Chintámanráv paid to Rabbavi in 1846 on his way back to Sāngli from Belgaum, where he had gone to receive the present of a sword by the Honourable East India Company for his fidelity during the revolt at Kolhápúr in 1844. The second lease extended to twenty years and in two years the new town rose in importance and wealth through the exertion of the banker Umdi who induced the traders of Gokák, which was then under the Tásgaon branch of the Patvardhans, to settle at Rabbavi. About 600 looms sprang up in the new town to weave *sádis* or women's robes and about 300 Bangárs came in to give the red dye to the yarn.

Rabbavi has a protecting wall to the east, about 2640 feet long, which extends from the Asangi gate in the north-east to the Kumbhár gate in the south-west. The portion between the Asangi and Banhatti gates to the extent of 990 feet is in good condition, but that beyond the Banhatti gate is in many places in ruins. The wall is only two feet thick and on an average ten feet high and is said to have been built from a grant of £800 (Rs. 8000) made by the late Chief Chintámanráv from the *mohotarfa* proceeds of the town. The wall has four bastions, two outside the Banhatti gate, one on each side each seventeen feet high and thirteen in diameter at the top; and the other two outside the Asangi gate, one on each side each eighteen feet high and  $11\frac{1}{2}$  in diameter. The other parts of the town have no wall, but except at the Kumbhár-khind in the south where there is a passage, the houses on the boundary are so built that their rear walls have the appearance of one continuous wall. Rabbavi has four gates, the Asangi, Banhatti, Kumbhár, and Terdal. It has three main streets and fifteen smaller lanes. Of the three main streets one runs from the Terdal gate to the Kumbhár-khind and is 1430 feet long; the second runs from the Asangi gate by the town *chárdi* and joins the above street at the Kumbhár gate and is 1980 feet long; and the third is a cross street from the Banhatti gate in the east to the extreme boundary of the Bangár lane in the west.

Of the 5028 people according to the 1881 census 4591 are Hindus



and 437 Musalmáns. Among the Hindus 3504 are Lingáyats, 524 Marátha Kunbis, fifty-four Jains, twenty-six Bráhmans, and 479 other Hindus. Of about 700 houses in the town 250 belong to Bangárs or red yarn dyers, 250 to Bilejáds who formerly wove white cloth and now weave *sádis* only, 100 to Hatgars or weavers, 50 to Musalmáns including Momins and Niláris, and 50 to other miscellaneous craftsmen. The water supply of the town is drawn chiefly from three wells and the stream that runs east of the town. Of the three wells which were all sunk with the building of the new town about 1832, one is in the temple of Shankarling, another to the west side of the road passing by the west gate of the temple, and the third to the east of the building now occupied by the vernacular school number one. The water of the stream is not used for drinking in summer when it becomes scanty and muddy.

Rabkavi is a large trade centre and next to Sháhápur in the SÁNGLI State. The chief trade consists of dyeing silk and yarn and weaving *sádis* or women's robes. The dyers belong to two classes Bangárs and Niláris. The Bangárs give a red dye of various shades to the yarn and a yellow dye to raw silk; the Niláris give the blue. The Bangárs are Lingáyats and number about 400, and have several rich bankers amongst them. The Niláris are chiefly Lingáyats and Musalmáns and have no bankers among them. Rabkavi has a police *thánédár* under the Terdal *mámlatdár* and *faujdar* who makes nightly rounds and looks after the conservancy of the town. It has five good temples. Of these the temple of Shankarling, which is the principal temple, was built about sixty years ago by one Shidráam Sheti and lies in the centre of the town. It is 25½ feet long, twenty broad, and fifteen high from the plinth to the terrace. About 1832 a large quadrangular rest-house or *dharmshála* was built round the temple from a subscription of £6000 (Rs. 60,000) raised by the influence of the banker Umdí, who assisted in founding the new town. The whole temple including the rest-house forms a square, one side of which is 120 feet long. The other four temples were built about the time of building the new town. Of these the temples of Virbhadrá and Máruti are in the town and those of Parvateshvar and Malikárjun on a hill outside the town. The temples are beautiful and strongly built of chisel-dressed stone and lime.

Sa'ngli, the capital of the State, with 13,272 people, lies on the left bank of the Krishna about 2½ miles north-east of its confluence with the Várna. It is thirty miles east of Kolhápúr with which it is joined by a good road. The town, which occupies 10,458 acres, consists of three distinct parts, the old town, the new town, and the *khan* or quarry. The old town lies on a slight eminence immediately on the river bank on the south of a watercourse which separates it from the new town. The new town also lies on the river bank and was built in the beginning of the present century when the late Chief Chintámanráv established himself at SÁNGLI. The quarry lies east of the new town and is occupied by field labourers and the menial servants of the State. The streets in the old town are narrow and crooked, but they have nearly all been put into good order with kerb stones and properly constructed gutters.

## Places.

RABKAVI.

Description.

Trade.

Temples.

SÁNGLI.

Description.

**Places.**  
**SÁNGLI.**  
*Description.*

The watercourse between the old and the new town acts as a backwater of the river during the monsoon and becomes a bed of slimy mud. It is spanned by two single-arch bridges between the old and new town. The new town is well laid out with broad streets running at right angles to each other and is chiefly occupied by bankers, merchants, and the principal officers of the State. The houses are superior to those of the old town.

Sángli has according to the 1881 census 13,272 people, of whom 11,606 are Hindus and 1660 Musalmáns. Besides having many good roads, the town is well off for roadside trees, of which hundreds have lately been planted. The bulk of the people drink river water, but there is no lack of wells. To facilitate the fetching of water, the river has on both the banks five flights of steps or *gháts* erected by Apa Sáheb (1801-1851). Beginning down the river from the Chief's residence, the flights are, in order, the Máicha Ghát, the SÁNGLI Vádi, the Krishna, the Vishnu, and the Sudrácha Ghát. During eight or nine months of the year the quarry from which the fort ditch used to be supplied with water is full of water which is much used by the people living in the *khan* for washing clothes and watering cattle. Thirty-one wells in and about the town are used for irrigation. SÁNGLI has twelve gardens called the Motibág, Hirábág, Ambrái, Gármala, Vasantbág, and the gardens or *malás* of Ráv Sáheb, Tátya Sáheb, Bápu Sáheb, and Bái Sáheb, two of Máí Sáheb, and one of the god Ganpati. The town has a dispensary and a municipality and fourteen schools attended by 851 pupils.

*Fort.*

Of the places of interest the fort lies between the old town and the *khan*. It is an octagonal building with a round bastion at each external angle. It is surrounded by a broad moat about thirteen feet deep, which can be flooded for a part of the year from an old quarry on the east. The walls, which are about fifteen feet thick and seventeen high, are built of stone and mortar with a parapet, now destroyed, of burnt brick and lime. Formerly there was a low loopholed wall of stone and mud known as the Revni round the fort; but it has now nearly disappeared, the stones having been used for public buildings. The fort has only one entrance on the north if the breach made in 1857-58 be excepted. The first gateway is on the counter-scarp between the circular loopholed bastions about twenty-one feet high. There is no drawbridge or bridge as the ditch at this point was never excavated. On the edge of the scarp there is another and much stronger gate flanked on either side by two large circular bastions loopholed for musketry and opposite the gate is a large bastion commanding the entrance which here turns to the left. On either side of these flank bastions and running round the large bastion are bombproof chambers of burnt brick and mortar which used to serve as quarters for the garrison. These casemates are continued at intervals all round the fort. The fort was dismantled and disarmed after the mutiny in 1858. It never was a place of any strength being commanded from the high ground of the old town and is now practically indefensible. Inside is the *divánkhána*, a large building of stone and burnt brick purely in the Hindu style, which was formerly the Chief's residence, and

in which were located the treasury, the central jail, the State granaries, the State blacksmiths' and carpenters' workshops, and the *mámlatdárs'* and *munsifs'* offices. The fort has only two wells, of which one holds an ample supply of good water. No one now resides in the fort except the Chief's stepmother and her relations and such of the State servants as are on duty.

The Chief's residence is popularly called the *deul* or temple, as it is built within the quadrangular court of the five temples or *ganpati pancháyatan*, Ganpati, Sám̐b, Surya, Vishnu, and Amba. It lies in the new town and is a brightly painted two-storeyed building facing and close to the river. The quadrangular court of the *deul* is  $1\frac{1}{2}$  acres in extent and its wall is flanked by two bastions and is loopholed on the side facing the river. Of other buildings in the new town the cattle market is a large quadrangular open space just outside the entrance of the fort and to the north-west of it. On the west of this space is the anglo-vernacular school which was built in 1865. On the right hand side of the road entering the fort is a fine well completed in 1882. Between the two main streets which run east and west is the vegetable market with a row of small shops on either side. On the north-east of the town are the State gardens known as the Ámbrai, the Ganpati *mala*, the Ráv Sáheb's *mala*, and the Tátya Sáheb's *mala*. Near the *khan* or quarry and on its north are the offices belonging to the Joint Administrator and the State *Kárbhári*. SÁNGLI has thirty-four Hindu temples and two mosques. Six of the Hindu temples are used as resthouses or *dharmshálas*.

**Sha'ha'pur**, the head-quarters of the Sháhápur subdivision, lies about two miles south of Belgaum. It has 10,732 people living in 1732 houses. It is surrounded by a thick bamboo fence and entered by four gates formerly protected by loopholed bastions. These are now in a more or less ruined condition. Formerly there was a small fort or *gadhi* in the south, but this is quite in ruins now. The houses are much crowded and the streets are as a rule narrow though in fairly good order. The water-supply of the town is ample and of fairly good quality. Sháhápur is a prosperous trading town. The dyeing of yarn and the weaving of silk and cotton *sádis* or women's robes, and waistcloths are largely carried on. The town is well off for schools, there being, besides the State anglo-vernacular school, a school connected with the London Missionary Society and six indigenous schools. In the centre of the town is the Chief's *váda* or residence in which are now located the offices of the *mámlatdár* and the *munsif*; close to the *váda* the dispensary has a substantial building. Besides the Hindu temples, Sháhápur has a Protestant church and a Roman Catholic chapel.

**Shirhatti**, the head-quarters of the Shirhatti sub-division, lies twelve miles south of the Gadag station on the South Deccan Railway. It has 3292 people, of whom 2689 are Hindus and 603 Musalmáns. A small brook runs north and east of the town, which supplies good drinking water for about eight months in the year. Besides the brook there are eighty-five wells, but the water in

**Places.**

SÁNGLI.

**Buildings.**

SHÁ HÁPUR.

SHIRHATTI.  
*Description.*

**Places.****SHIRHATTI.***Description.*

sixty-five wells is brackish and is used only in watering cattle and washing clothes. Formerly Shirhatti had a large trade in blankets, *dangri* or coarse cotton cloth, and carpets, but the trade has now greatly fallen, only coarse cotton cloth and carpets being exported to a limited extent. It has the offices of the *māmlatdār* and the *faujdar*, the *munsif's* court, three schools, and a dispensary. Of the schools, one is anglo-vernacular, one vernacular, and one a girls school. The schools and the dispensary have nice buildings. There is a municipality which had in 1883-84 an income of £117 (Rs. 1170) and an expenditure of £178 (Rs. 1780), the excess charges being paid from the previous year's balance.

*History.*

Under the Bahmani kings (1347-1489) Shirhatti formed part of the Lakshmeshvar sub-division. Under the Bijāpur kings (1489-1686) Lakshmeshvar formed part of the *jāgir* of one Syad Mausun Bokhāri commonly called Ankushkhān. In 1607 (1016 *Fasli*) the fifth descendant of the first Ankushkhān is said to have given the *deshgat* of Lakshmeshvar including Shirhatti to one Khāngavnda, the ancestor of the present Desāi family of Shirhatti.<sup>1</sup> At the fall of the Bijāpur kingdom in 1686 the Shirhatti Desāis became subject to the Nawāb of Sāvanur. In 1756 eleven sub-divisions including that of Lakshmeshvar were given by the Nawāb to the third Peshwa Bālāji Bājirāv (1740-1761). From this year the Desāis ceased to exercise magisterial powers. They simply enjoyed the *inām* lands. In 1764 the Lakshmeshvar sub-division formed part of the *saranjām* granted to Govind Hari Patvardhan. In 1801 when the *saranjām* was divided the sub-division and the fort of Shirhatti came to the share of the Sāngli Chief Chintāmaurāv.

*Fort.*

Of the sixteen temples five are in the fort and eleven in the town. The three most important places of interest are the fort, Avlingva *math*, and Fakirsvāmi *math*. The fort, according to one account,

<sup>1</sup> The tradition about the grant of the *deshgat* is as follows: The ancestors of the Desāis of Shirhatti and Lakshmeshvar lived in Sagar and Kembhāvi in the Nizām's territory. They belonged to the Kud-Vakkal caste and were converted to Lingayatism by the Lingayat saint Fakirsvāmi the first. Avlingva, a lady of the Desāi family, accompanied by the *Fakirsvāmi*, left her native country with her two sons Bhimanna and Samanna and settled at Kadadi in Gadag. While going on a pilgrimage to Shrishail Malikārjun, Avlingva with her younger son Somanna and the *fakirsvāmi* is said to have lodged for the night in the house of the *jāgirdār* Ankushkhān at Lakshmeshvar. At night Ankushkhān began to play chess with his wife. When the game was at its height, the oil in the lamp proved short and the light threatened to disappear. Ankushkhān called for oil, but was told that there was none in the house. He is then said to have observed that whoever should manage to make the light of the lamp last to the end of the game, he would reward him even with his own *jāgir*. Avlingva, who had overheard this speech, then took her large pot of clarified butter and supplied the lamp with it. Ankushkhān continued the game and when it was over Avlingva requested Ankushkhān to fulfil his promise by surrendering the *jāgir* to her in reward. Ankushkhān then saw the folly of his thoughtless promise, but it was too late. He however attached the following conditions to the grant, that Avlingva's son Somanna should assume the name of Khāngavnda Desāi, use the same seal as was hitherto used by Ankushkhān, tie a *shelīmāni* bead round his neck, use a green flag and green dress, live in a house built after the Muhammadan fashion, give alms to the poor every Thursday in the *dargahs*, and use the Muhammadan language at his court. These conditions being agreed to, Ankushkhān made over the *jāgir* to Avlingva and retired to Majlāpur village about a mile east of Lakshmeshvar. The *fakirsvāmi* was also granted an *inām* on his agreeing to live after the Musalmān fashion and this appears to be the probable origin of the mixed term *fakirsvāmi*.

was built by Khángavnda Desái and according to another account by Ankushkán of Lakshmeshvar. It has fifteen bastions and is in good condition except in the north where the wall with three bastions was razed to the ground in 1858 by order of Government. The walls are nineteen feet high and fifteen thick. They are built of earth and unscoured rubble inside with dry pitching on the outside. The bastions are all round except the Virbhadrá bastion which is an octagon and built with well dressed stone. The gate which faces the east is  $10' \times 15'$  and has two bastions one on each side, measuring forty feet high and thirty in diameter. The fort is surrounded by a ditch which is about twelve feet deep and from eighty to a hundred feet wide at the top.

The Avlingva *math* or monastery, an excellent stone building, lies about half a mile east of the fort. The monastery was built about 260 years ago by Avlingva the founder of the Lakshmeshvar *deshgat*. It was originally intended for Avlingva's own tomb, but it is said that she was not buried here as she died not at Shirhatti but elsewhere. The monastery is a rectangle  $95\frac{1}{2}' \times 55\frac{3}{4}'$  and built of chisel-dressed stone and mortar. The whole superstructure is interspersed with ornamental decoration showing artistic skill. The building faces the north and may be divided into the front veranda and the main building.

The front veranda is  $55\frac{1}{4}' \times 16\frac{1}{4}'$  inclusive of the end walls two feet broad and is twenty-six feet high. It is the most decorated part of the whole building and begins from the level of the plinth which is five feet high all round. The plinth has four stone elephants in front of it. Above the two central of these elephants and on the surface of the plinth are the two main octagonal pillars in the veranda, broad at the base and tapering towards the top. The side of the octagon at the base is  $1\frac{3}{4}$  feet and the base one foot high. The shaft which is of a single stone is  $16'$  and the capital  $2' 8''$  and the entablature  $6' 4''$ . The front veranda has twenty carved images in four rows, each image  $15''$  high. They are variously occupied. Some are *chopdárs* or mace-bearers, some beat the drum, and some play the tamborine. There are nineteen carved images in the frieze on three sides of the veranda. The lower surface of the ceiling or roof is carved with lotus flowers and a pair of serpents coiling round each other as if mating. The veranda is open only to the length of thirty-one feet in the middle and the remaining  $24\frac{1}{4}$  feet are converted into two end rooms having their floor raised to the height of  $1' 10''$ . These rooms have each a balcony facing north. The entrance to the balcony is effected by a Gothic arched window  $4' 8'' \times 2' 8''$ . The end rooms have an upper floor each beginning at a height of  $19' 8''$  from the surface of the plinth. The upper floors have two balconies, one facing the north just above the lower balcony and the other exactly in the middle of the room facing towards the east in the eastern upper floor and towards the west in the western upper floor. The seats in the balconies have four pillars covered with an umbrella-like roof at the top. The entrance to these balconies is effected by Gothic arched windows of the same

Places.

SHIRHATTI.

Avlingva Math.

## Places.

SHIRHATTI.

*Avlingva Math.*

dimensions as those to the balconies on the lower floor. The upper floors also have Gothic arched windows opposite to those of the eastern and western balconies in the opposite inner walls. Their dimensions are about  $1\frac{1}{2}' \times 1\frac{1}{4}'$ . On the ground floor of these side rooms or rather open places there are two doors one in each to effect an exit into the eastern and western verandas. The dimensions of these doors are each  $4' 5'' \times 2' 8''$ .

The main building is  $70\frac{1}{4}' \times 37\frac{1}{2}'$  inclusive of the end walls, which are 11 feet high and  $3\frac{1}{4}'$  broad. It has an open veranda on three of its sides, each nine feet broad. Of these, two are covered with a stone slab roof on the east and west, and the third or the rear side is uncovered. The number of pillars in each side is eight, each  $10' 5''$  high and  $2'$  broad and  $2'$  long. The surface of the main building is  $1' 10''$  higher than that of the front veranda. It consists of the open front hall  $31' \times 20\frac{1}{2}'$  without the walls on three sides. It is eleven feet high and has four round and lathed pillars having a diameter of two feet and a height of eleven feet each. The first pair of these four pillars is put exactly opposite to the two octagonal pillars in the front veranda at a distance of  $13\frac{1}{4}'$  feet and the second pair is placed from the first at the distance of  $7\frac{3}{4}'$  feet. This hall is a plain work and without any carving except to the main door which gives entrance to the tomb-room and which is put in the middle of the northern wall five feet thick. Its dimensions are  $5' \times 2\frac{1}{4}'$ . The skill displayed in the carving on the sides and on the mantel of this door is excellent. The number of carved images is 148. In the centre of the mantel is the *ling* of Mahádev with the *nandi* or bull on the east and a devotee on the west. The other images are of human beings in various attitudes. This door has to its west the stairs leading to the upper storey. The entrance door to these stairs is placed nine feet distant from the main door and is  $2\frac{1}{4}'$  broad and  $4\frac{1}{2}'$  high. The steps of the stairs are each two feet broad and nine inches high. To the east of the main door at the distance of  $8\frac{1}{2}'$  feet is a niche  $4\frac{3}{8}' \times 2\frac{1}{2}'$ . The side walls have two Gothic arched niches in each of them. To this hall succeeds the tomb-room to its south. It is a square of thirty-one feet and is eleven feet high. To the south of the tomb-room are two smaller rooms. The eastern is  $18\frac{1}{4}' \times 9'$  and the western  $11' \times 9'$ . The partition wall between the tomb-room and the smaller inner rooms is two feet wide and eleven feet high and that between the smaller rooms is  $1\frac{3}{8}'$  feet broad and eleven feet high. The tomb-room has the place of the tomb in the centre of the room occupying a square of  $14\frac{1}{8}'$  feet enclosed within four pillars similar to those in the front hall. The tomb is carved with exceeding nicety as also is the ceiling above it. The tomb-room has two doors in its eastern and western walls. The dimensions of each of these doors are nicely carved, the centre of the mantel being allotted to Maháalakshmi who is represented as being constantly bathed by water from pots held in the trunks of two elephants one on each side of the goddess. Above this Maháalakshmi are ten carved lions in a row. The total number of carved images on the sides and mantels of each of these



doors, including those already mentioned, is fifty five. The outside of the walls of the main building is decorated with seventeen carved images of persons occupied variously. The terrace is covered with a layer of mortar about  $1\frac{1}{2}$  feet thick.

To the east of this large monastery and adjoining it there is another small monastery. It is built from the fifteenth foot from the south-east corner of the Avlingava *math* and extends towards the north to the length of forty-nine feet. It is built of first rate chiselled stone and mortar, but is a plain work. It consists of three parts, the open veranda  $19' \times 12'$ , the tomb-room  $19' \times 19'$  excluding the partition and the side walls which are two feet wide, and the inner room  $19' \times 12'$ . The inner room which is to the south of the tomb-room is entirely dark, but has three rectangular cellars. It has only one door in the centre of its north wall  $4\frac{1}{2}' \times 2\frac{3}{4}'$ . The tomb-room is a square having one of its sides  $6\frac{1}{2}$  feet long. It has four stone pillars each  $4' 8''$  in diameter and  $10' 5''$  in height. To the north-west corner of the tomb-room there is also a cellar which is reported to be an underground passage leading to a large cellar in the neighbouring *math* or monastery. The east and west walls of this room have two stone network windows, each of which is  $2' \times 1\frac{1}{2}'$  in the middle. The entrance door which is in the middle of the north front wall is  $4\frac{1}{2}' \times 2\frac{3}{4}'$ . Next to the tomb-room and to its north is the open veranda having an open Gothic arch in its west wall. The dimensions of this arch are  $5' \times 2\frac{1}{2}'$ . The veranda has two octagonal pillars above the north end of the plinth placed  $6\frac{1}{2}$  feet apart from the east and west walls. The distance between these pillars is four feet. The side of the octagon is three-fourths, the base one, the shafts five, the capital two, and the entablature five feet.

The Fakirsvámi *math* or monastery lies about a quarter of a mile north-west of the Avlingva *math*. It contains six tombs of the six Fakirsvámis. Five of the tombs are well built with stone and mortar. The *math* enjoys an *inám* of £100 (Rs. 1000) a year. The tomb of Fakirsvámi is highly venerated by the Lingáyats. On the fullmoon in *Vaishákh* (April-May) a fair is held in the compound of the *math* in honour of the Fakirsvámis. The fair is attended by about 30,000 people and articles are sold to the value of about £5000 (Rs.  $\frac{1}{2}$  *lák*h). Many miracles such as the granting of eyesight to the blind and of hearing to the deaf are attributed to the Fakirsvámis.

**Shrimantgad Fort**, formerly called Simántgad, lies near Devihal village ten miles south of Shirhatti and nine miles south-west of Lakshmeshvar. The fort, though geographically within Sāngli limits, belongs to Miraj Senior. It is said to have been built by the Sátára kings. The walls are thirty feet high and eight thick, the parapet at the top having loopholes for musketry. They are built of earth and unscoured rubble inside with dry pitching on the outside. The dry pitching is in good order and strong. The fort abounds in *bábhul* and other thorny shrubs which give shelter to poisonous reptiles. The fort has the shape of the segment of a circle. Of the thirty bastions the chord which faces the east has thirteen and

**Places.**

SHIRHATTI.

*Avlingva Math.*Fakirsvámi  
*Math.*SHRIMANTGAD.  
FORT.

**Places.****SHRIMANTGAD  
FORT.**

the arc seventeen. The largest bastion lies to the southern extremity of the chord; from the top of which the Tungbhadra, about ten miles distant in the south, is seen. Of the thirty bastions, six on the chord were razed to the ground in 1858 by order of Government. The remaining twenty-four bastions are in good condition. The fort has a temple of the goddess Vhallama which is a rectangular block 116' x 65'. Its height including the parapet is about fifteen feet. The temple was repaired in 1881 and is now tidy and clean. It has a yearly allowance of £12 10s. (Rs. 125), which is paid from the Lakshmeshvar treasury. The fort has five ponds with potable water. The largest pond is four-sided, having the opposite sides 210 and fifty feet long and the perpendiculars thirty-seven and forty-two feet. It has an area of 8295 feet and water eight to nine feet deep.

**TERDAL.***Description.*

**Terdal**, the head-quarters of the Terdal sub-division, lies sixty miles north-east of Belgaum, thirty-four north-west of Kaládgi, and forty-one south-east of Sánгли. It lies on the south or right bank of the Krishna which flows at a distance of  $4\frac{1}{2}$  miles from it. The town is built on a porous sandstone rock of a reddish colour and is surrounded by small hills of the same kind on all sides except the west. According to the 1881 census the population of the town including Kalhatti hamlet was returned at 6590 against 7716 in 1872. The decrease of 1126 in 1881 is not real and was due to the absence of a large number of people at the time of the census at the Chinchli cattle fair in Kolhápúr. Of the 6590 people 4663 are Hindus and 1927 Musalmáns. Among the Hindus 3191 or 68·43 per cent are Jains and Lingáyats.

Terdal is surrounded by the remains of an old fort wall, probably in part the remains of the fort mentioned in the inscription of the Nemináth temple;<sup>1</sup> but the loopholes for musketry show that the wall has been rebuilt or repaired in later times, as there was no gunpowder in 1122. The fort, though it may have been repaired by the Musalmáns, was not apparently built by them as they generally pulled down Hindu or Jain temples for the purpose, and no remains of stones from such are found in the ruins of the walls. But be this as it may, the fact remains that Terdal had a double-walled fort in king Gauk's time at its eastern side, the outer wall of which with all its bastions and gates is now nearly level with the ground, and the ditch between the outer and the inner wall filled up; the remnant of the inner wall with its bastions is in many places a mass of ruins, though at the east and west gates it is still well preserved. The east gate, otherwise called the pond-gate, which lies at a distance of 120 feet from the pond to the west of it, has two bastions and a portion of the fort inner wall joining them. The gate is in the middle of the two bastions and is twelve feet high and ten feet broad, with a Gothic arch of the height of eight feet above it from the spring of the arch. The height of each bastion is thirty feet and the diameter twenty-five feet; but the

<sup>1</sup> For the inscription see the footnote given in the account of the Nemináth temple below, page 376.

height of the wall is twenty-five feet. The distance between the east and the west gates of the fort is 920 feet. At 460 feet from each gate there is a detached tower standing on a rising spot of ground. Its height is fifty feet and diameter forty-two feet. On the upper part of this is a keep with a diameter of eighteen feet. This big bastion is close to the *sarkári vada* or *mámlatdár's* office and is in good condition. There was a large cannon on its top but it was removed to Súngli, and broken to pieces in 1857-58 by order of Government. There were two or three other cannons on the tops of other bastions then in existence but they were also taken to Súngli and similarly treated. The wall of the western gate as has been already said is in good condition. There are quarters for guards on both sides inside this gate, but they are now used for other purposes. Those on the north are used as a *chávdi* or village office by the *pátíl* and *kulkarni* and those on the south are converted into the sub-divisional lock-up. Outside the west gate of the fort, the town extends to the length of 1365 feet towards the west where it is bounded by a short wall running from north to south with a gate in the middle called the Shidhoba Gate. The length of the town from north to south is 2775 feet, beyond which extends the *majre* or hamlet of Kalhatti to an additional length of 660 feet towards the south. From the northernmost point of the town where the temple of *Sudgád Lakshmi* or Lakshmi of the Churchyard stands to a distance of 500 feet towards the south the town is very thinly populated, there being very few houses in that quarter. Terdal in king Gauk's time appears to have extended towards the north to the length of a mile or so to the field called *Vibhuti maddi*. In this field white earth and pieces of earthen pots are often discovered embedded in the soil. The frequent discovery of these things the people attribute to the former existence of human dwellings; but they must have existed several centuries ago, as there is no tradition of the town having extended so far to the north. The town is divided into seven sub-divisions: Old Peth, New Peth, Támbat Áli, Prabhusvámi Lane, Saráf-katta, the *killa* or fort, and Kalhatti. The houses in the town are built of stone and white earth with mud roofs. In very few of them, however, have lime and mortar been used. During the height of the summer these houses, which are generally badly ventilated, become insufferably hot, the temperature being increased by the heat given out by the surrounding bare sandstone rocks. At this season the people are much troubled by scorpions, which to escape the heat of the stones take refuge indoors. Scarcely a house escapes the scourge. The sting of the scorpions in the case of infants is not unfrequently fatal.

The supply of drinking water is solely drawn from the pond close to the east of the town. The pond was originally a stone quarry from which stones were taken for building the fort. It covers an area of thirteen acres and has a well thirty feet deep in the centre. It has a dry stone wall all around and five flights of steps on the north, west, and south. The pond is divided in two by a stone and mud dam in the middle of it. The water in the southern

Places.  
TERDAL.  
Description.

Water Supply.

**Places.****TERDAL.**

watering cattle and like purposes. Besides the pond the town has twenty-five wells, but the water of seventeen wells is brackish and used only for irrigation. The water in the remaining eight wells is drinkable and is used for drinking when the supply in the pond fails. A well, called the Nádgvandandbhávi, lies about one-third of a mile south of the pond and is known for the digestive property of its water. For this reason the water of the well is daily used for drinking by some of the people.

**Trade.**

Terdal is a large trading town. Formerly it had a large trade in copper and brass vessels but the trade now seems to have greatly fallen off. The number of coppersmiths' shops has now come down from fifty to ten. Brass lampstands and copper pots made of a single sheet of metal without joint or soldering are in great demand. The coppersmiths work on hire for the bankers who supply them with copper and brass sheets. They charge 2s. (Re. 1) for every ten pounds of weight of the work done and earn on an average £2 (Rs. 20) a month.

Terdal has 260 looms for weaving cotton cloth and thirty for weaving blankets. Of the 260 looms nearly three-quarters weave *sádis* or women's robes and the rest *dhotis* or waistcloths and the coarse *dangri* cloth. The *sádis* are generally twenty-one feet long and  $3\frac{1}{2}$  wide. They are not suited for Bráhma women as their manner of wearing requires a longer and broader *sádi*. The waistcloths or *dhotis* are generally fifteen feet long and  $3\frac{1}{2}$  wide. A piece of *dangri* cloth is eighteen feet long and three wide. The weavers yearly use yarn and silk of the value of about £13,000 (Rs. 1,30,000). Of these Europe gray and dyed yarns and silk of the value of £8000 (Rs. 80,000) are brought from Rabkavi and country gray yarn of the value of £5000 (Rs. 50,000) is bought locally at the weekly market which is held on every Thursday. The yearly outturn of cloth is estimated at about £20,000 (Rs. 2 lákhs).<sup>1</sup> Except part which is locally used, the produce is all sent out. The thirty looms employed in weaving blankets yearly produce about 2160 blankets at the rate of six blankets a month for each loom. The rate of six blankets a month is apparently small, but the weavers have themselves to spin the wool into yarn and then weave it into blankets. The blankets are eight feet long and three wide and cost 3s. each (Rs.  $1\frac{1}{2}$ ) on the average. Besides the blankets woven from wool-yarn spun by the weavers, many husbandmen spin wool-yarn at home and have it woven into blankets by the weavers, paying them as wages from 1s. 6d. to 2s. (Re.  $\frac{3}{4}$  - 1) a piece. The number of blankets thus woven amounts to about 1200 a year. The blankets are all used locally.

Of other articles Terdal yearly sends wheat, *javári*, *bájeri*, gram, cotton, and tobacco to the value of £6000 (Rs. 60,000) to Athni

<sup>1</sup> Of the 260 looms 195 weave 50,700 *sádis* a year at the rate of five *sádis* a week. Their value is estimated at £15,210 (Rs. 1,52,100) at the average value of 6s. (Rs. 3) a *sádi*. The remaining sixty-five looms each weave waistcloths and *dangri* cloth of the average value of about £6 (Rs. 60) a month, that is of the value of £4680 (Rs. 46,800) a year. Thus the yearly outturn both of *sádis* and waistcloths and *dangri* cloth amounts to the value of £19,890 (Rs. 1,98,900).

eighteen miles north and Rabkavi five miles east of Terdal. Both Athni and Rabkavi are connected with Terdal by made roads. A road three miles long, running from the west gate of the town, joins the Belgaum-Athni road at Pálbhávi village. Another road five miles long, running from the pond gate in the east, joins the town of Rabkavi. Of imports, rice is brought from Kolhápúr Belgaum and Chiplun, salt and molasses from Kolhápúr, spices and sugar from Athni, copper and brass from Poona Sátára and Hubli, and Europe cloth and Europe-made articles from Bombay. A weekly market is held on every Thursday.

Terdal has sixteen Hindu and ten Musalmán shrines. Of the sixteen Hindu shrines six are temples of Mahádev, two of Ganesh, one of Máruti, one of Lakshmi, one of Prabhusvámi, and three of Jain Tirthankars. Of these the temple of Prabhusvámi and that of the Jain Tirthankar Nemináth are most important.

The temple of Prabhusvámi lies in the south-west of the town. Prabhusvámi was a native of Kerur in Dhárwár. He came to Terdal as a Lingáyát ascetic with one Abákhán a Musalmán *fakir*, in the second quarter of the seventeenth century and lived for fourteen years on the spot on which the principal temple now stands. Both Prabhusvámi and Abákhán are said to have been persons of such great piety and holiness as to attract the homage of the Bijápúr kings and it was through their influence that one Krishna Gavnda of Terdal obtained the *deshgat* of the Terdal *pargana*. Krishna Gavnda, who was a Jain by birth, was induced to become a Lingáyát by Prabhusvámi. Krishna Gavnda compelled his wife Satyava to accept the same creed. The descendants of Krishna Gavnda who again became Jains from the time (1748) of Moghyapa Desái grandson of Krishna Gavnda, burn their dead; but Krishna Gavnda and his wife are buried side by side in the temple of Prabhusvámi. Prabhusvámi lived at Terdal for fourteen years and then left it for a place near Kurtakot where he died some years afterwards. The Lingáyáts of Terdal believe that Prabhusvámi did not die but became invisible and translated himself to heaven.

In this temple an earthen drinking pot of the *svámi's* is preserved under a brass cover and worshipped. The temple is strongly built of stone and lime. The central building which is the chief temple is forty-seven feet long, twenty-four broad, and seventeen high. This building faces the north and has a small room six feet square in the rear in which the worshipped pot and the other idols are placed. In front of this building, at a distance of forty-six feet, is built a *bhojanpátra* or place for keeping food to be offered to the god during the annual fair held on the last Monday of *Shrávan* (July-August). It is a room fourteen feet square and seventeen high. This room is filled with dressed food generally to about one-half of its height. After the ceremony of offering the food to the deity is over, it is distributed among the devotees. Close to the west of the *bhojanpátra* are the two tombs of Krishna Gavnda and his wife. To the west of the tombs is a large well having on its south the kitchen of the temple. On the north and east are five rest-houses or *dharmshálás* each having room for

Places.  
TERDAL.

Temples.

Prabhusvámi  
Temple.

**Places.****TERDAL.**

twenty-five travellers. The quadrangular wall that bounds the temple on four sides has a second story in the middle of its eastern portion which is used for the *nagārkhāna* or drumhouse. Underneath the drumhouse is the *mahādvār* or the entrance door of the temple. The side of the temple quadrangle is about 250 feet long and 175 feet wide.

**Neminath  
Temple.**

The Nemināth *basti* or temple lies in the fort and is dedicated to Tirthankar Nemināth whose symbol is a conch shell. It has on its north wall a stone bearing an inscription in old Kānares. The inscription has three different dates and may be divided into three parts. The first part bears the date of Monday the fifteenth of the bright fortnight of *Vaishākh* of *Shake* 1044 or 1045 (A.D. 1122) *Shubhakrit Samvatsar*. It records that king Parmādidev (who is said to have reigned between A.D. 1075 and 1126 and belonged to the Western Chālukyas), son of the king of kings Ahavmāldev, on his return from the conquest of Gujarāt and the subjugation of the king of the Chol country, founded Terdal, the first town of the twelfth division of the country called Kundi or Three-thousand. In this town the celebrated king Gauk, son of the king Virmalidev by his wife Bāchaldevi, built a temple and dedicated it to Nemināth by order of Kārtavirya of the Ratta family who was a Mahāmandal-eshvar of Tribhuvanmāldev, in *Shake* 1044 or 1045 *Shubhakrit Samvatsar* (A.D. 1122), with the assistance of the celebrated Sidhānti Māghnandi and granted an *inām* of seventy-two *mārs* of land. The second part of the inscription bears the date of Sunday the seventh of the dark fortnight of *Ashvin* of *Shake* 1104 or A.D. 1181 *Plavang Samvatsar* and records the grant of certain town duties to the temple of Nemināth by the Mānād of Terdal. The third part bears the date of Thursday the tenth of the bright fortnight of *Chaitra* of *Shake* 1109 or 1110 or A.D. 1187 *Plavang Samvatsar* and contains another grant of land of thirty-six *mārs* by Dandāyak-bhaidev. The stone on which the inscription is engraved is five feet long. Of this fifty-two inches are occupied by the eighty-four lines of the inscription containing the three grants and a long preface. The third fourth and fifth verses in the preface give a description of the town of Terdal as it then existed in a hyperbolic style.<sup>1</sup> The Nemināth temple has excellent ornamentation and mouldings. The building occupied by the idols may be divided into three parts, the front, the middle room, and the rear

<sup>1</sup> The description runs nearly as under: 'The sea which has the power of protecting the mountain, and which is the abode of the elephant and the alligator, encircles the land called Jambu-Dvīpa which has the golden mountain Meru as its centre. To the south of this mount Meru lies the country of Bharat containing the beautiful provinces of Kuntal and others. In this Kuntal province there prospers a land called Kundi or Three-thousand. In a central position of this Kundi land there flourishes the town of Terdal adorned with exceedingly fragrant rice fields, forests, wells great and small, lakes, hills, forts, rivers, moats, assemblages of learned men, temples of Mahādev, Ark, Shankar, and Jineshvar. It is impossible even for Aj or Brahma Dev to give a complete description of this twelvefold magnificence. Terdal with its moats, fort-walls, wells, lakes filled with lotus flowers, parrots and honeybees, holy abodes containing deities, Brāhmans, Vaishyas or traders, and other pious men, appears to adorn the world as the lotus-shaped eyes adorn the lotus-like faces of its beautiful women skilled in the science of love.'



room. The greatest length of the temple is seventy feet and its breadth forty feet. The temple has four beautifully carved whole stone pillars and twelve half pillars. The height of the temple including the plinth is sixteen feet to the floor of the second story.

There are three lifesize idols of Tirthankars in the temple, of which the two that are standing are in the middle room, each by the side of a whole pillar to the east and west. That which stands by the side of the east whole-pillar is of white marble and has a fivehooded cobra over its head. It is the idol of Párasnáth. That which stands by the side of the west whole pillar is of a black Gandaki stone and has a conch shell for its symbol on its pedestal. It is of the Tirthankar Nemináth. The third idol which is in a squatting position in the rear room is of black stone. It is also of Nemináth and has a conch shell engraved on its pedestal. There are two more black stone idols squatting in the two niches behind the standing Tirthankars; that behind Párasnáth is of Padmávatí and that behind Nemináth is of Devki. These are the images of two female devotees of the Tirthankars. There are more than thirty small idols of brass and white marble with a round plate of brass called the Siddhayantra in the temple. The temple which faces the north has a tall stone pillar called *mánstambh* in front of it at a distance of twenty feet. This *mánstambh* was built by Satyava wife of Moghyapa Desái the grandson of Krishna Gavnda Desái mentioned above, in *Shake* 1670 or A.D. 1748 to commemorate the return of the family to the ancestral Jain creed. The pillar is on a pyramidal pedestal of three steps and is  $16\frac{1}{2}$  feet high. The base is  $10' 9''$  square and the first step is three feet high. The second step is  $2' 9''$  high and the sides are  $7' 9''$  square. The third or last step is  $2' 4''$  high with the sides  $4' 9''$  square. The pillar may be divided into three parts. The first or the lowermost block of stone is one foot high with four sides each two feet long, the second is four feet high having four sides each of the same length as those of the lowermost block, and the third or the last part of the shaft is  $11\frac{1}{2}$  feet high with an octagonal shape, the octagon being inscribed in a square whose side is two feet long. Above the top of this octagonal shaft is a cup-shaped block of stone of the height of three feet. Over the mouth of this cup is a slab  $4\frac{1}{2}$  feet square supporting another square-shaped slab the sides of which are  $5\frac{1}{2}$  feet long. Upon this slab is erected a temple having a window on each of its four sides occupied by four images squatting in the attitude of prayer on a stone seat with a stone back two feet high. The images are one foot high and occupy a central position in each window. The windows are arched and have a cornice over them. Above this cornice is a stone with a *kalas* or dome of brass overtopping the whole structure. The whole length or rather height of this part of the structure from the top of the shaft to the top of the brass *kalas* is  $13\frac{1}{2}$  feet. On the second story over the rear room is a room having an idol of the Tirthankar Nemináth of white marble.

**Yelvatti Fort** lies about seven miles north-west of Shirhatti. The village has 1475 people. In 1846 Yelvatti fort with Hallápúr village was granted in *inám* by the Honourable East India Company to Chintámanráv of Sàngli for the services rendered in suppressing

## Places.

TERDAL.

Neminath  
Temple.YELVATTI  
FORT.

**Places.**  
**YELVATTI**  
**FORT.**

the rebellion at Kolhápur in 1844. The fort is a square 600 feet. It has twelve bastions twenty-five feet high inclusive of the parapet and forty feet in diameter. The wall is twenty feet high and ten thick. The fort was built about 250 years ago by the first Khán-gavnda Desái of Shirhatti. The northern wall of the fort is built of stone and mortar to the height of about four feet, the rest being of earth. The other three sides are built of stone and earth inside with strong dry pitching on the outside. It was owing to the weakness of the earthen wall on the north side that the fort was not pulled down with others in 1858. Yelvatti has a large well outside the village called the Malalva Bhávi which supplies drinking water to the whole village throughout the year. Another large well called the Sakrava Bhávi lies in the fort and holds much water ; but the washing of clothes has made the water unfit for drinking. Yelvatti has a Maráthi and Kánarese school. It has the temple of Gundeshvar which is visited by many people from a long distance. On the door of this temple is a stone tablet which says that on a *Kark-sankránti* day which fell on the twelfth of the bright half of *Ashadh* *Shake* 1073, *Prajápati Samvatsar*, A.D. 1151, the king Chálukya Vikram Chakravarti Tribhuvan Málá Vir Rangidev granted an *inám* of six *márs* of land to the god Gundeshvar and confirmed the grant by pouring water on the palms of the *pujári*. This Chálukya Vikram Chakravarti is said to have married a daughter named Málaldevi of Rayanna Shánbhog, a hereditary village officer of Yelvatti. The descendants of Ráyanna Shánbhog now live at Mulgund.

---

**MIRAJ SENIOR.**

**DESCRIPTION.**

**Miraj Senior**, with an area of 340 square miles and sixty-two villages, had in 1881 a population of 69,732 or 205 to the square mile and in 1882-83 a gross revenue of £37,173 (Rs. 3,71,730).

*Aspect.*

Miraj Senior consists of three detached sub-divisions, the *kasba* Miraj, Lakshmeshvar, and Modnimb. The *kasba* Miraj sub-division with thirty-five villages lies in the Krishna valley to the east of the Kolhápur State. Miraj, the capital of the State, lies close to the Krishna river, about six miles south-east of Sánгли. The sub-division is known for its rich black soil and mango and tamarind groves. The Lakshmeshvar sub-division, with fifteen villages, lies in the heart of Dhárwár adjoining the Sánгли sub-division of Shirhatti. It is dry, flat, and scantily wooded, but the soil is rich, even superior to that of Miraj. The Modnimb sub-division, with twelve villages, lies north of Pandharpur in Sholápur. Almost the whole sub-division is uneven and covered with long strata of rocks. The soil is inferior.

*Rivers.*

The Krishna enters the Miraj sub-division at Bamni village about six miles south-west of Miraj. It skirts the whole of the southern boundary of the sub-division and after a winding course of about sixty miles leaves the sub-division at Banojvád village. The Vávna runs by Kavtha-Phiram about sixteen miles west of Miraj and after running a short distance falls into the Krishna near Haripur belong-

ing to Miraj Junior. In the Modnimb sub-division the Bhima runs by the Sangni and Holi-budruk villages. No river runs through Lakshmeshvar.

The climate is healthy. The cold season from November to February is particularly pleasant and bracing. The rainfall at Miraj averages twenty-four inches.

The State has no forests. A small tract in the Modnimb sub-division has been lately set apart as a forest reserve under the supervision of the *mámlatdár*. Of domestic animals oxen in 1882-83 numbered 12,472, cows 6383, buffaloes 6509, horses 724, camels 13, asses 442, and sheep and goats 29,306. The best oxen are of the Maisur and the best cows of the Gujarát breed.

According to the 1881 census the State had 69,732 people against 82,201 in 1872, that is a decrease of 12,469 or 15·16 per cent, which is chiefly due to the mortality and emigration during the 1876-77 famine. Of the 69,732 people in 1881, 59,309 or 85·05 per cent were Hindus. The Bráhmans are chiefly Deshasths and Chitpávans. Karhádás, a subdivision of the Deshasths, are found to a small number at Miraj. The traders are Lingáyats, Gujarát, and Márwár Vánis. Of the other castes the chief are Maráthás, Dhangars, Raddis, Sális, Koshtis, and Sutárs. The chief degraded castes are Dhors, Chámbhárs, Mhárs, and Mángs.

The chief cultivating classes are the Lingáyats, Raddis, Maráthás, and to a small extent Bráhmans. Of these the Lingáyats and Marátha Kunbis are hardworking and skilful. Of the total area of 204,704 acres according to the revenue survey, 184,493 or 90·12 per cent are arable and 20,211 or 9·87 per cent unarable. Of the arable area 159,341 acres or 86·36 per cent were in 1882-83 under tillage and 25,152 or 13·63 per cent were fallow or under grass. The bulk of the State land is black soil, especially in Miraj and Lakshmeshvar. In Modnimb the soil is light red.

Almost the whole moneylending is in the hands of well-to-do Bráhmans, Vánis, and land proprietors. The rates of interest charged on petty loans secured by pledging ornaments or other movable property varies from six to twelve per cent. Advances on personal security are made at twelve to twenty-four per cent according to the credit of the borrower. Grain both for seed and food are borrowed by the poorer husbandmen to be repaid at harvest with the additional one-fourth or one-half of the quantity borrowed called *savái* or *didhi*. Provided the title is undisputed, valuable effects can be mortgaged at nine to twelve per cent and lands and houses at six to nine per cent of interest.

The State is well off for roads. All the chief towns and market places are joined by roads. The State has in all ninety-nine miles of *murumed* road of which fifty-one miles are in Miraj, fourteen in Lakshmeshvar, and thirty-four in Modnimb. The chief imports under grain are rice and wheat. Rice is largely brought from Ajra, Kolhápur, and Belgaum, and wheat from Bijápur and Chikodi. Teak for building is brought from Haliyál in Kánara. Of exports *javári*, *bájri*, and gram under grain are sent to Athni, Chikodi,

## DESCRIPTION.

## Climate.

## PRODUCTION.

## PEOPLE.

## AGRICULTURE.

CAPITAL.  
Moneylending.

## TRADE.

## TRADE.

Tásgaon, and Kolhápúr. Of other articles molasses, groundnut, tobacco, cotton, *sádis* or women's robes, and Momin turbans and blankets are sent to Tásgaon, Sàngli, Athni, Belgaum, Kolhápúr, and Chiplun. At Lakshmeshvar which exports much cotton, the indigenous cotton is cleaned by hand and the exotic by cotton gins. A factory for repairing the sawgins has lately been established at Lakshmeshvar. The manufactures consist chiefly of handwoven cotton cloth and silk goods. These articles are made with great success at Lakshmeshvar and to a limited extent at Miraj. At Lakshmeshvar and Shegli about 1500 families of Koshtis and Momins are employed in weaving. Europe yarn and silk and dyes are brought from Kumta and Hubli. The chief articles woven are *lugdis* or women's robes and *dhotars* or waistcloths. They are known for fineness and durability and find their way generally to Hubli, Dhárwár, Belgaum, and sometimes to Belári. Of minor articles the *satárs* or guitars made at Miraj, especially those made by Farid, are in great demand. The guitars fetch 10s. to £5 (Rs. 5-50) and find their way even to Bombay.

## HISTORY.

The history of the State is given above with that of Sàngli.

## THE LAND.

Land tenures are of three kinds, *sheri* or crown land, *inám* or alienated, and *rayatvári*. Except three alienated or *dumála* villages, all the villages of the State have been surveyed. The survey acre rates vary from 2s. 6d. to 5s. 4½d. (Rs. 1¼ - 2½) for rice land, from 4½d. to 8s. 10½d. (Rs. ⅓ - 4¼) for dry crop land, and from 7s. to 15s. (Rs. 3½ - 7½) for garden land. The land revenue is collected by three instalments in January March and May.

## JUSTICE.

The administration of criminal justice is carried on by eight magistrates. Of these one is a district magistrate and one a magistrate of the first class, three are magistrates of the second class, and three of the third class. For the administration of civil justice there are three courts, of which one is the *nyáyádhish* court at Miraj and two are of the *munsifs* at Lakshmeshvar and Modnimb. The *nyáyádhish* of Miraj, in addition to original jurisdiction as a first class sub-judge, exercises the powers of a small cause court in suits up to £5 (Rs. 50) and hears appeals against the decisions of the *munsifs* of Lakshmeshvar and Modnimb in suits below £5 (Rs. 50). The *mámlatdárs* of Lakshmeshvar and Modnimb are ex-officio *munsifs*. The *munsif* of Lakshmeshvar has power to try suits up to £100 (Rs. 1000) and that of Modnimb up to £50 (Rs. 500). In 1882-83 the police force numbered 328 men maintained at a cost of £1730 (Rs. 17,300).

## FINANCE.

In 1882-83 the State had a gross revenue of £37,173 (Rs. 3,71,730), of which the land and *sáyar* revenue amounted to £25,119 (Rs. 2,51,190), interest on Government securities to £2779 (Rs. 27,790), adjustment of alienated lands to £3196 (Rs. 31,960), local funds to £2425 (Rs. 24,250), and miscellaneous revenue to £2,455 (Rs. 24,550). There are municipalities at Miraj and Lakshmeshvar which spent in 1882-83 about £800 (Rs. 8000) on petty improvements and conservancy. The State pays a yearly contribution of £1255 16s. (Rs. 12,558) to the British Government.

In 1882-83 the schools numbered thirty-three with 2401 names and cost £1614 (Rs. 16,140). Of these schools one is anglo-vernacular, twenty-nine boys schools, and three girls schools. The anglo-vernacular school is at Miraj and was in 1882-83 attended by 169 pupils. Of the twenty-nine boys schools, fourteen are in Miraj, seven in Lakshmeshvar, and eight in Modnimb. Of the three girls schools, one is at Miraj and two at Lakshmeshvar.

The State has one dispensary at Miraj. The number of patients treated during 1882-83 was 9443 of whom forty-three were in-patients and the cost of the dispensary amounted to £340 12s. (Rs. 3406). During the same year 1752 persons were vaccinated in the three sub-divisions. In 1882-83 the number of births was returned at 1874 and of deaths at 1389.

The chief places are Miraj and Lakshmeshvar. MIRAJ, the capital of the State, with 20,616 people according to the 1881 census, lies about thirty miles east of Kolhápúr. In 1761, the fort of Miraj with some *thánás* was assigned by the Peshwa Mádhavráv Ballál to Govindráv Patvardhan for the maintenance of troops.<sup>1</sup> Miraj is a large trading town. Weekly markets are held on every Monday and Tuesday. The town has the offices of the *kárbhári*, the *nyáyádhish*, the *mámlatdár* and the *faujddár*, and a dispensary, a post office, a town-hall, a library, and eight schools. Of the eight schools one is anglo-vernacular, one Hindustáni, two Maráthi, one Kánárese, one a girls school, one a night school, and one for the Dhors or degraded castes. Miraj has no travellers' bungalow; but two State buildings are set apart for the use of European visitors. It has two old *dargás*, one of Mir Sáheb and the other of Samsuddin Mir, both built in 1491 (*Shake* 1413). The *dargás* had an endowment of five villages from the Bijápúr government, but one village of Dhamni and *inám* land worth £32 13s. (Rs. 326½) are now continued.

LAKSHMESHVAR, the head-quarters of the Lakshmeshvar sub-division, with about 10,800 people, lies about forty miles south-east of Dhárvár. The weaving of handwoven cloth is largely carried on in the town. Weekly markets are held on every Friday and Saturday. The town has the offices of the *mámlatdár* and the *munsif*, a travellers' bungalow, a sawgin factory, a post office, and eight schools. Of the eight schools, three are Kánárese, three Maráthi, and two girls schools. Lakshmeshvar has the temples of Someshvar and Lakshmilíng about 1000 years old, Jain *bastis*, and a Musalmán *masjid* about 400 years old. In honour of the god Someshvar, a yearly fair is held on the tenth of the bright half of *Vaishákh* (May-June). The fair is attended by about 5000 people. About fifty old inscriptions found at the place have been carefully preserved.

INSTRUCTION.

HEALTH.

PLACES.

*Miraj.**Lakshmeshvar.*

<sup>1</sup> The fort at Miraj was probably built by the Bahmani kings. A Persian inscription on the mosque or *darga* at Miraj records that it was built in 1413 and renovated 230 years afterwards. For details of the early history of the place see above footnote 1 on page 344.

## MIRAJ JUNIOR.

## DESCRIPTION.

**Miraj Junior**, with an estimated area of 208 square miles, had in 1881 a population of 30,541 or 146 to the square mile and in 1882-83 a gross revenue of £24,617 (Rs. 2,46,170). It has forty villages scattered in the British districts of Sātara, Sholápur, Poona, and Dhárwār. For administrative purposes the forty villages are divided into three sub-divisions, Kavtha, Gudgeri, and Kuroli. The greater part of the State is flat and has rich black soil. Some parts are hilly and treeless. The Krishna runs by Haripur, a sacred village at the junction of the Krishna and Várna. The climate is temperate and healthy. During the three years ending 1883 the rainfall averaged twenty-five inches.

## PRODUCTION.

Of minerals a black hard stone useful for building is found.

## PEOPLE.

According to the 1881 census, the State had 30,541 people against 35,601 in 1872, that is a decrease of 5060 or 14·21 per cent, which is chiefly due to the mortality and emigration during the 1876-77 famine. Of the forty villages, nineteen had less than 500 people, twelve between 500 to 1000, six between 1000 and 2000, one between 2000 and 3000, and two between 3000 and 5000.

## AGRICULTURE.

The bulk of the husbandmen are Lingáyats, Jains, and Maráthás. Of these Jains are thrifty and hardworking. The husbandmen of Gudgeri and Kavtha are fairly off, but those in Kuroli are in a poor condition. Of the whole area about five-sixths is cultivated.

## TRADE.

About thirteen miles of road, four in Kavtha and nine in Gudgeri are kept in repair. As the villages are scattered, the roads are feeders to the main lines in neighbouring British districts. During the seven years ending 1884, £2289 (Rs. 22,890) were spent on roads. Branch post offices have been opened at Budgaon, Haripur, and Gudgeri. The chief imports are salt, piece goods, and cotton and silk threads. The chief exports are cotton, wheat, and gram which are taken in carts to the ports of Chiplun and Kumta. Weekly markets are held at Gudgeri, Budgaon, and Kavtha, at which trade is carried on to a small extent. The only important industry is that of weaving *sádis* or women's robes and coarse or *dangri* cloth at Budgaon and Gudgeri.

## HISTORY.

The history of the State is given above with that of Sángli.

## THE LAND.

In 1884-85 survey rates were introduced into the Gudgeri *petha*; and the Kavtha and Kuroli *pethas* were surveyed and classified.

## JUSTICE.

The *mámlatdárs* in the three sub-divisions have the powers of a second class magistrate in criminal matters. The *munsif* at Budgaon has also the powers of a first class magistrate and has jurisdiction over the whole State. For the administration of civil justice there are three *munsifs'* courts in the three sub-divisions. The *munsif* at Budgaon has power to try suits up to £500 (Rs. 5000). In Gudgeri and Kuroli the *mámlatdárs* are ex-officio *munsifs*. The *munsif* of Gudgeri has power to try suits up to £200 (Rs. 2000) and that of Kuroli up to £50 (Rs. 500). The Joint *Kárbháris* have the powers of a Sessions Judge in criminal cases and



of a District Judge in civil suits. In 1882-83 the police force was 219 strong.

In 1882-83 the State had a gross revenue of £24,617 (Rs. 2,46,170) of which the land revenue amounted to £14,243 (Rs. 1,42,430) or 57·85 per cent. The State pays a yearly contribution of £641 5s. (Rs. 6412½) to the British Government.

FINANCE.

In 1882-83 the schools numbered eighteen with 916 names and cost £265 8s. (Rs. 2654). Of the eighteen schools two are girls schools at Budgaon and Gudgeri.

INSTRUCTION.

The State has one dispensary at Budgaon which was established in 1876-77. In 1882-83, 3651 patients were treated at the dispensary. The chief diseases are fever and bowel complaints. In 1882-83 cholera broke out in some villages of Kavtha. Of a hundred attacks thirty-two proved fatal. There is a vaccinator for the Kavtha sub-division by whom 951 children were vaccinated in 1882-83.

HEALTH.

Important places in the State are Budgaon, Gudgeri, Haripur, Kavtha, and Kilegaon. BUDGAON, the capital of the State, lies five miles north of Miraj. It has according to the 1881 census 2401 people, most of them being weavers. A weekly market is held at the place. Budgaon has a *mámlatdár's* office, a *munsif's* court, a boys school, a girls school, a library, a rest-house or *dharmshála*, and a dispensary. There is a State palace at Budgaon, but the Chief's family now lives in a garden near Miraj.

PLACES.

Budgaon.

GUDGERI, the head-quarters of the Gudgeri sub-division, lies three miles south-west of Lakshmeshvar in Dhárwár. It has according to the 1881 census 3128 people. A weekly market is held at the place. Gudgeri has a *mámlatdár's* office, a police post, a boys and a girls school, a post office, and a *dharmshála* or rest-house.

Gudgeri.

HARIPUR, with 2292 people, lies at the junction of the Krishna and Várna near Sángli. It is known for its sacredness. It has a boys and a girls school, and a branch post office.

Haripur.

KAVTHA, with 3675 people, lies twelve miles north of Miraj. It is an agricultural village and has a little trade in cotton and grain. It has a boys school and a temple of Mahádev about a thousand years old. The temple is visited by many people who pass months in the service of the *ling*, as it is believed that the diseases of the body and mind are cured by such devotional services.

Kavtha.

KILEGAON, with 626 people, lies north-east of Miraj. A fair is held every year in *Chaitra* (April-May), in honour of Basveshvar the god of the Lingáyats. It is attended by 5000 to 8000 people and articles are sold to the value of about £800 (Rs. 8000).

Kilegaon.

## KURUNDVA'D SENIOR.

## DESCRIPTION.

**Kurundva'd Senior**, with an area of 182 square miles and thirty-seven villages, had in 1881 a population of 35,187 or 193 to the square mile, and in 1882-83 a gross revenue of £11,766 (Rs. 1,17,660). Of the thirty-seven villages, thirty-four are in three clusters and three are detached. Of the three clusters, one called the *petha* Gad or Angol with twenty-five villages lies south of the cantonment of Belgaum; a second cluster called the *petha* Alás with seven villages lies east of the Kolhápúr State; and a third cluster called the *petha* Tikota with two villages lies about twelve miles east of Bijápúr. Of the three detached villages, Sohokar lies in the Athni sub-division of Belgaum, Jagulgaon in the Terdal subdivision of Sângli, and Vategaon in the Karád sub-division of Sátára. Except the Angol cluster which is hilly, most of the State is flat and treeless. Of the rivers the Krishna is joined by the Panchganga at Kurundvâd. The climate of Kurandvâd is generally hot, but the Angol cluster is considerably cooler. During the three years ending 1883 the rainfall averaged twenty-five inches at Kurundvâd and Tikota, thirty-two at Vategaon, and fifty-one at Angol.

## PEOPLE.

According to the 1881 census the population was returned at 35,187 against 39,420 in 1872, that is a decrease of 4233 or 10·73 per cent, which is chiefly due to the mortality and emigration during the 1876-77 famine. Of the thirty-seven villages, nine had less than 200 people, thirteen between 200 and 500, seven between 500 and 1000, three between 1000 and 2000, three between 2000 and 3000, and two between 5000 and 10,000.

## AGRICULTURE.

The chief cultivating classes are Maráthás and Musalmáns. The principal crops are *javári*, *bájri*, rice, wheat, gram, *tur*, *rála*, and sugarcane.

## CAPITAL.

The chief moneylenders are the Márwár and Gujarát Vánis. The rate of interest varies from six to twenty-four per cent according to the credit of the borrower. In the Kurundvâd cluster moneylending is carried on at three places Kurundvâd, Ganeshpur, and Alás. At Kurundvâd about £30,000 (Rs. 3 *lákhs*) have been invested in moneylending.

## TRADE.

In Kurundvâd, of imports, rice, cocoanuts, and betelnuts are brought from Belgaum, Sháhápúr, Nipáni, and Athni, and of cloth, the English cloth is brought from Bombay and the native hand-made from Sháhápúr and Yeola. Of exports, cotton is sold to Bombay merchants to the value of about £1000 (Rs. 10,000), and gram is sent to Belgaum and Sháhápúr. Before the 1876-77 famine coarse or *dangri* cloth, turbans, and waistcloths were woven to some extent, but the industry has now considerably fallen. In Tikota there are about twenty-five looms.

## HISTORY.

The history of the State is given above with that of Sângli.

## JUSTICE.

For the administration of criminal justice the State has six courts, one of the Chief with unlimited powers, one of the *Kárbhari* with powers of the second class magistrate, and four of the *mámlatdárs* at Kurandvâd, Angol, Tikota, and Vategaon, with

powers of the third class magistrate. The Chief has the powers of life and death, but appeals can be made to the Political Agent. For administering civil justice there are four courts, one of the *Kárbhári* with powers to try suits up to £500 (Rs. 5000), and three of the *mámlatdárs* of Kurundvád, Angol, and Tikota, who are ex-officio *munsifs* and have powers to try suits up to £20 (Rs. 200). Appeals from these courts lie to the Chief who has full jurisdiction in civil matters. The police force is fifty-four strong.

In 1882-83 the gross revenue amounted to £11,766 (Rs. 1,17,660), of which £9581 (Rs. 95,810) or 81·42 per cent were derived from land and £2185 (Rs. 21,850) or 18·57 per cent from other sources. The State pays an annual tribute of £961 18s. (Rs. 9619) to the British Government.

In 1882-83 the schools numbered five with 192 names and cost £103 (Rs. 1030). Of the five schools, one is an anglo-vernacular school at Kurundvád, three boys schools, and one a girls school. Besides these there are seven indigenous schools.

The State has one dispensary. In 1882-83 the number of patients treated was 1958 and the cost amounted to £196 (Rs. 1960). The chief diseases were worms, fever, and bowel complaints. During the year cholera broke out and caused 144 deaths.

KURUNDVÁD, the capital of the State, with 7880 people, lies near the junction of the Krishna and Panchganga, about twenty-five miles east of Kolhápúr. TIKOTA, with 7087 people, lies about twelve miles west of Bijápúr. Besides these, it has three large villages with a population between 2000 and 3000.

### KURUNDVÁD JUNIOR.

Kurundvád Junior with an estimated area of 114 square miles and forty-three villages, had in 1881 a population of 26,207 or 230 to the square mile and in 1882-83 a gross revenue of £11,300 (Rs. 1,13,000). It includes two clusters of villages, one in Belgaum and the other on the east of Sholápúr. The Yellur cluster with twenty-six villages lies for the most part to the south of Belgaum, and the Maindargi cluster with fifteen villages is bounded on the north, west, and south by the Akalkot State in Sholápúr. Besides the two clusters the State has two outlying villages, one Gallanhatti near Athni in Belgaum and the other Dovankatti near Konkanvádi in Kolhápúr. The climate is generally healthy. The rainfall measured thirty-eight inches at Yellur in 1884 and twelve inches at Maindargi.

According to the 1881 census the State had 25,811 people against 30,251 in 1872, that is a decrease of 4440 or 14·67 per cent which is chiefly due to the mortality and emigration during the 1876-77 famine.

Betel-leaves and oilseeds are sent from the Dudhni station on the Great Indian Peninsula Railway to Sholápúr, Poona, and Bombay. The chief industry is the weaving of coarse cloth and blankets at Maindargi, Dudhni, and Vadgaon.

JUSTICE.

FINANCE.

INSTRUCTION.

HEALTH.

PLACES.

DESCRIPTION.

PEOPLE.

TRADE.

## JUSTICE.

The Chief who resides at Kurundvād presides over the Sessions Court and decides appeals from the magistrate's decision. The police force is 143 strong. There are three lock-ups.

## INSTRUCTION.

The State has seven vernacular schools.

There are no places of importance.<sup>1</sup>

---

**JAMKHANDI.**

## DESCRIPTION.

**Jamkhandi**, with an estimated area of 492 square miles and eighty-eight villages, had in 1881 a population of 83,917 or 170 to the square mile and in 1882-83 a gross revenue of £41,243 (Rs. 4,12,430). Its villages lie chiefly between Belgaum and Bijápúr. For administrative purposes the State is divided into three sub-divisions, Jamkhandi, Bidri, and Kundgol. Of these the Jamkhandi sub-division, with thirty-nine villages, lies along the bank of the Krishna to the east of the Terdal subdivision of Sāngli; the Bidri sub-division with twenty-two villages, lies along the east bank of the Krishna adjoining the Jamkhandi sub-division; and the Kundgol sub-division, with twenty villages, lies south of Hubli in Dhárwár. Besides these there are seven outlying villages, of which Vathár and Shirandra are in Sátára, Mudir and Patkhat in the Mangalvedha sub-division of Sāngli, Yelgund in Belgaum, and Vithalpuri and Dhavalpuri in Ahmadnagar. The Krishna runs west to east for about thirty miles through the Jamkhandi and Bidri sub-divisions. About twenty-one villages lie on its banks. The slopes on both sides of the Krishna form what is called *gada* a rich soil. The climate is generally healthy. The rainfall averages twenty-eight inches at Jamkhandi, twenty-five at Bidri, and twenty-three at Kundgol.

## PRODUCTION.

The State has no forests. An attempt has lately been made to preserve the *nimb* *Azadirachta indica* and other trees in the low range of hills lying south of Jamkhandi. These hills cover an area of about thirty miles, spreading from Budgaon six miles west of Jamkhandi to Lingnur nine miles south-east of Jamkhandi.

## PEOPLE.

According to the 1881 census the State had 83,917 people against 102,346 in 1872, that is a decrease of 18,429 or eighteen per cent, which is chiefly due to the mortality and emigration during the 1876-77 famine. Of the eighty-one villages, six had less than 200 people, twenty-five between 200 and 500, twenty-three between 500 and 1000, nineteen between 1000 and 2000, three between 2000 and 3000, four between 3000 and 5000, and one between 10,000 and 15,000.

## AGRICULTURE.

The chief cultivating classes are Lingáyats, Jains, Maráthás, Musalmáns, Dhangars, and Berads. Of these the Lingáyats and Jains are hardworking and well off. In most parts *javári* and in a few parts rice is the staple crop. Of 236,684 acres, the total

---

<sup>1</sup> The history of the State is given above with that of Sāngli.

arable land, 226,891 or 95·86 per cent were under tillage and 9793 or 4·13 per cent were fallow or under grass.

The moneylenders are the well-to-do Bráhmans and the Lingáyat Marwár and Gujarát Vánis. The rates of interest charged are from twelve to twenty-four per cent on personal security, from five to six per cent on the security of gold and silver ornaments, and from nine to twelve per cent on the mortgage of land and houses.

The State is fairly off for roads. The roads that run through the State are the Athni-Mudhol for about fifteen miles from Maigur on the Krishna to Shidápur on the borders of Mudhol; the Jamkhandi-Bijápur for about six miles; the Jamkhandi-Savalgi and the Shervad-Pashupatihal in the Kundgol sub-division. These roads are all *murumed*. There is a considerable import of food grains, chiefly *javári* from several villages of Bijápur. Rice is brought from Belgaum and Dhárwár. There is little export of grain. The chief industry is the weaving of *sádis* or women's robes, *cholkhans* or bodicecloth, and coarse or *dangri* cloth. The weavers are Koshtis, Sális, and Momins. In the Jamkhandi subdivision there are about 1450 looms, of which 500 are at Jamkhandi, 800 at Banhatti, and 150 at Hunnur. The *sádis* and *cholkhans* being of the coarse kind are not used by the well-to-do classes, but there is a great demand for these articles among the lower classes. They are largely sent to Pandharpur, Sholápur, Bársi, and Sátára.

The history of the State is given above with that of Sángli.

The survey of the State has been completed and the survey settlement introduced in the Kundgol sub-division where the rates average 6s. (Rs. 3) per acre. In other sub-divisions the settlement has not yet been introduced.

For the administration of criminal justice the State has ten magisterial courts, one magistrate of the first class, six of the second class, and three of the third class. Besides these there are the Sessions Court presided over by the Chief and his *kárbhári*, and two appellate courts one of the Chief and the other of the *kárbhári*. For administering civil justice there are four *munsifs'* courts at Jamkhandi, Kundgol, Vathár, and Patkol. Against the decisions of these courts appeals are preferred to the *kárbhári*. The Chief is a first class treaty chief and exercises full jurisdiction in criminal and civil cases.

In 1882-83 the gross revenue amounted to £41,243 (Rs. 4,12,430) of which £34,868 (Rs. 3,48,680) or 84·54 per cent were derived from land, £4525 (Rs. 45,250) or 10·97 per cent from *sáyar* revenue, and £1850 (Rs. 18,500) or 4·48 per cent from local funds. The State pays a yearly contribution of £2084 (Rs. 20,840) to the British Government.

In 1882-83 the schools numbered twenty-four with 1229 pupils, and the cost amounted to £675 4s. (Rs. 6752). Of the twenty-four schools one is anglo-vernacular, one Hindustáni, four Maráthi and Kánarese, seventeen Maráthi, and one a girls school. The schools are inspected by a deputy educational inspector of the State.

CAPITAL.

TRADE.

HISTORY.

THE LAND.

JUSTICE.

FINANCE.

INSTRUCTION.

## HEALTH.

The State has one dispensary at Jamkhandi named the Prince of Wales Hospital. In 1882-83, 8660 out and 61 in-patients were treated at a total cost of £623 (Rs. 6230). There are two vaccinators and one inspector. In 1882-83 the number of primary vaccinations was 3298 and that of re-vaccinations sixteen, and the cost amounted to £101 14s. (Rs. 1017).

## PLACES.

*Jamkhandi.*

The State has besides Jamkhandi four large villages with more than 2500 people. JAMKHANDI, the capital of the State, with 10,409 people, lies about seventy miles south-east of Kolhápúr and thirty-five miles south-west of Bijápúr. The town has about 500 looms for weaving and the trade in *sádis* or women's robes, *khans* or bodice-cloth, and *mugtás* or silk waistcloths is largely carried on. Weekly markets are held in the town and at the Rámtirth hill near the town. An annual fair is held in honour of the god Uma Rámeshvar, which lasts for six days and is attended by 15,000 to 20,000 people. Jamkhandi has offices of the *kárbhári*, the *nyáyádhish*, the *mámlatdár*, and the *munsif*. It has also a municipality and a travellers' bungalow.

*Banhatti.*

Of the four large villages BANHATTI, with 3582 people, is a trading place and has about 800 looms for weaving. Weekly markets are held on every Tuesday and Monday. HUNNUR, with 2861 people, has about 150 looms for weaving. KUNDGOL, with 3672 people, lies south of Hubli in Dhárwár and has the offices of the *mámlatdár* and the *munsif*. A weekly market is held on every Wednesday. Cotton is largely grown in the sub-division and sent to Kumta, Kárwár, and Hubli. VATHÁR with about 3000 people, is the seat of the *thánédár* and the *munsif*.

*Hunnur.**Kundgol.**Vathár.*

## MUDHOL.

## DESCRIPTION.

Mudhol, with an area of 361 square miles and eighty-one villages, lies between 16° 26' 45" and 16° 6' 50" north latitude and 75° 31' 56" and 75° 4' 21" east longitude. It had in 1881 a population of 52,163 or 144 to the square mile and in 1882-83 a gross revenue of £24,536 (Rs. 2,45,360).

*Boundaries.*

Mudhol is bounded on the north by Jamkhandi, on the east by the Bágalkot sub-division of Bijápúr, on the south partly by the Bádámi sub-division of Bijápúr and partly by the Torgal sub-division of Kolhápúr, and on the west by the Gokák sub-division of Belgaum.

*Sub-Divisions.*

For administrative purposes the State is divided into five sub-divisions or *panch maháls*, called Mudhol, Dhavleshvar, Jamgi, Machaknur, and Lokápúr. Of the eighty-one villages sixty-nine are *khálsa* or State, and twelve *dumála* or alienated. Except one detached village in Sátara, the whole of the State, unlike the neighbouring Patvardhan states, is a compact country.

*Aspect.*

The general aspect is flat with slight undulations here and there. The greater portion of the surface is black soil, the remaining portion being the inferior *mál* land. The *máls* are mostly covered with spear grass and stunted acacias and *tarrads* or Cassia.



auriculata. The scenery is monotonous and the country presents a parched and barren aspect during a greater part of the year especially in the hot season.

In the east and west are small ranges of hills about 150 feet high. Their sides are not steep and can be ascended by men and beasts of burden though not by carriages. The hills are barren except those near Lokápur and Halgali, which are covered with low brush-wood used for fuel.

The Ghatprabha runs through the State dividing it into two nearly equal parts. It enters the district on the west at Márapur and leaves it on the east at Algundi without being joined by any tributaries. The banks are generally sloping and are cultivated. The bed of the river is sandy and muddy. The Ghatprabha is generally not fordable during the rainy months from July to October. About thirty-six villages lie on either bank of the river. About one-fourth of the soil belonging to these villages is submerged and enriched by the annual floods of the river.

Except during the rains when fever, cough, and diarrhoea are more common, the climate is generally healthy and invigorating. During the months of March April and May a hot suffocating east wind prevails. The regular rainy season begins in June and ends at the close of October. Occasional showers fall in April and May. The rainfall is barely enough for tillage and a slight failure occasions great distress. During the seventeen years ending 1883 the rainfall varied from 6·30 inches in the famine year of 1876 to 38·11 inches in 1877 and averaged 24·65 inches<sup>1</sup>.

Of minerals, building stone and lime are found in small quantities just enough for the requirements of the people. The stone is chiefly black basalt but a red stone is also found. Mudhol is not a wooded country; the chief trees of spontaneous growth are the *nimb* *Azadirachta indica*, the *bábhul*, and the tamarind. Lately about 12,000 roadside trees, chiefly the banyan, *nimb*, *pimpri*, tamarind, *umbar*, mango, and *bábhul* have been planted on the seven roads round about Mudhol. Of these trees the first five kinds have good growth.

According to the 1881 census the population was returned at 52,163 against 58,921 in 1872, that is a decrease of 6758 or 11·46 per cent, which is chiefly due to the mortality and emigration during the 1876 famine. Of the 52,163 people in 1881, 25,771 or 49·40 per cent were males and 26,392 or 50·60 per cent females; and 48·273 or 92·54 per cent Hindus and 3710 or 7·11 per cent are Musalmáns. The principal Hindu castes are: Bráhmans 1716, Vánis 1480, Lingáyats 9473, Jains 178, Maráthás 3091, Jangams 1538, Koshtis 1036, Raddis 6283, Telis 1171, Kolis 2675, Berads 2163, and Mángs 2389. The total number of houses is 11,497 of which 615 are of the better

## DESCRIPTION.

*Hills.**Rivers.**Climate.*

## PRODUCTION.

## PEOPLE.

<sup>1</sup> The details are: 24·76 inches in 1867, 16·55 in 1868, 24·13 in 1869, 23·37 in 1870, 12·29 in 1871, 24·14 in 1872, 19·37 in 1873, 30·89 in 1874, 26·83 in 1875, 6·30 in 1876, 38·11 in 1877, 32·99 in 1878, 31 in 1879, 24·38 in 1880, 19·50 in 1881, 34·02 in 1882, and 30·50 in 1883.

## PEOPLE.

class. It is not customary to build upperstoried houses with tiled roofs. The houses are *dhábi* or flatroofed and of one story. They are built of rubble stone and earth with *nimb* or *bábhul* beams and a flat roof of rafters of milkbush and *javári* stalks on which is laid earth about two feet thick. The houses of the better class are built of dressed stone and teak beams with a ceiling of planks of *bábhul*, mango, or *nimb*, or of bamboos.

## AGRICULTURE.

Of the total population 22,200 or 42·55 per cent support themselves by agriculture. The chief cultivating classes are Lingáyats, Jains, Maráthás, Raddis, Dhangars, and Musalmáns.

## Crops.

The crops are: of cereals *javári* Indian millet, *bájri* spiked millet, wheat, and *rála* *Panicum italicum*; of pulses gram *tur* *Cajanus indicus*, *matki* *Dolichos biflorus*, and *pávta* *Dolichos lablab*; of fibres cotton and *ambádi* Bombay hemp; of oilseeds *kardai* or safflower; and of miscellaneous crops sugarcane, betel-leaves, chillies, and plantains.

The staple crop of the State is *javári* which is of two kinds, *kár* a red and *shálu* a white variety. The *kár javári* is sown about the middle of June at the beginning of the south-west monsoon. *Tur*, *mug*, *matki*, and *ambádi* are sown in the same field with *kár javári* at certain intervals. *Shálu javári* is sown early in September at the beginning of the north-east monsoon, and cotton and *kardai* are sown about the month of October. *Kár javári* is reaped in November, and *mug* and other subordinate crops which are sown with it are reaped about the end of January and in February. Cotton is gathered from the beginning of March to the end of April, generally in three pickings. Wheat, gram, and *kardai* are reaped in February and March. Sugarcane is planted at the beginning of March and cut in January and February. Black soil is suited for cotton, gram, and wheat, and the same with a mixture of clay and sand is suited for *javári*. Manure is not used except for gardens and *masári* or red soil. About a hundred cartloads are required per acre for sugarcane and plantains, and thirty for *javári* and chillies.

## CAPITAL.

The chief moneylenders are Gujarát, Márwár, and Lingáyat Vánis, and a few Bráhmans. The yearly rates of interest vary from twelve to 37½ per cent on personal credit and from six to twelve per cent on the security of movable and immovable property.

## TRADE.

## Roads.

The State is well off for roads. Since 1865 eighty-two miles of road have been made with eighteen bridges, seventeen culverts, and about thirty-five drains. About 12,000 trees have been planted on roadsides. There are seven chief lines 66½ miles long, which run from Mudhol to Mahálingpur, Jamkhandi, Gulgali, Kaládgi, Lokápur, Rámdurg, and Yádvád. Of these the Mudhol-Mahálingpur road runs twelve miles north-west and is metalled, drained, and bridged except on the Soregaon stream. It has 4750 roadside trees and five bridges, nine culverts, and twenty-five drains built at a cost of £5027 (Rs. 50,270). The Mudhol-Jamkhandi road runs six miles north. It has 1750 roadside trees and seven bridges and seven drains built at a cost of £1715 (Rs. 17,150). Two streams on the roads are yet to be bridged. The Mudhol-Gulgali road

runs  $8\frac{1}{2}$  miles north-east. It has 1100 roadside trees and one bridge and four drains near Mudhol, built at a cost of £170 (Rs. 1700). The Mudhol-Kaládgi road runs twelve miles south-east and is *murumed* and drained and bridged except at a few places. It has 1875 roadside trees and two bridges, eight culverts, and twenty-nine drains built at a cost of £3761 (Rs. 37,610). The Mudhol-Lokápur road runs fourteen miles nearly south and is *murumed*. It has 1150 roadside trees and has one bridge and one drain near Lokápur built at a cost of £169 (Rs. 1690). The Mudhol-Rámdurg road runs eight miles south and was built during the 1876 famine. It has no bridges or drains. The Mudhol-Yádvád road runs six miles south-west. It has 975 roadside trees and six drains built at a cost of £173 10s. (Rs. 1735). Besides these there are two small branch roads to Shirol and Dhavleshvar which have two bridges built at a cost of £163 12s. (Rs. 1636). The total cost of bridges culverts and drains amounts to £11,178 (Rs. 1,11,780).

Besides the old temples and rest-houses in most villages, nineteen new rest-houses or *dharmshálas* have been built since 1862 at a cost of £2313 (Rs. 23,130); of these three at Mahálingpur, Mudhol, and Lokápur are large, decent, and built of roughly dressed stone. Besides these there are two State bungalows at Mudhol and Mahálingpur, which are used by Natives of rank and Europeans.

The State has two sub-post offices at Mudhol and Mahálingpur. They are subordinate to the Kaládgi post office and in charge of deputy postmasters.

The traders who number about 290, are mostly Lingáyat and Márwár Vánis, Bráhmans, Telis, and Koshtis. The chief imports are gold, silver, tobacco, silk, indigo, cocoanuts, betelnuts, dates, copper and brass vessels, hardware, and iron bars. They come chiefly from Bombay, Vengurla, Poona, Belgaum, Sholápur, Nipáni, Kolhápur, and Belári. Of exports, *javári*, gram, wheat, and *tur* are sent to Nipáni, Athni, Sankeshvar, and Vengurla. As many good roads have been opened during the last twenty years, the trade is now carried chiefly in carts instead of by pack bullocks.

The chief industry is that of weaving *sádís* or women's robes, waistcloths, and coarse *dangri* cloth. The craft supports about 1066 persons of whom 915 are Koshtis. Coloured yarn and silk are bought from Lokápur traders who bring these articles from Bombay. Of the 1066 weavers about 360 work independently, and the rest work on hire for traders, who supply the yarn and silk. The weavers who work on hire daily earn 3d. (2 as.), besides a commission of  $\frac{3}{4}$ d. to  $1\frac{1}{4}$ d. ( $\frac{3}{4}$ - $1\frac{1}{4}$  as.) on each piece of cloth woven.

The survey settlement was introduced in 1868. The maximum acre rates are 2s. to 2s. 9d. (Rs. 1- $1\frac{3}{8}$ ) for dry crop land, 12s. (Rs. 6) for rice land, and 7s. (Rs.  $3\frac{1}{2}$ ) for garden land. In the sixty-nine State villages the survey raised the assessment on the cultivated land from £7763 6s. (Rs. 77,633), the average collection of previous eleven years, to £8201 2s. (Rs. 82,011) that is an increase of £437 16s. (Rs. 4378) or 5.33 per cent.

For the administration of civil justice there is a *nyáyádhis* court with powers of a first class sub-judge. Against the decisions of the

TRADE.  
Roads.

Rest Houses.

Post Offices.

Traders.

Crafts.

THE LAND.

JUSTICE.

## JUSTICE.

*nyáyádhish* appeals lie to the Chief. For administering criminal justice there are two courts, one of the Chief with full powers and the other of the *Kárbhari* with the powers of a district magistrate. The regular police force which was organized in 1873, is eighty-nine strong. Besides these thirty-nine *shiledár savárs* or horsemen assist the regular police force.

## INSTRUCTION.

In 1883 the schools numbered twenty-one with 1038 names on the roll and an average attendance of 766. The cost amounted to £677 (Rs. 6770), the whole of which was paid from local funds. Of the twenty-one schools one is an anglo-vernacular school at Mudhol, four are Kánarese, fourteen Kánarese and Maráthi, one a girls school, and one a night school. For these schools, sixteen school-houses have been built at a cost of £5942 (Rs. 59,420) and five rest-houses and temples repaired at a cost of £350 (Rs. 3500) to serve as schools. Mudhol has one library with ninety-three subscribers and a yearly subscription of £24 (Rs. 240).

## HEALTH.

The chief diseases are fevers, intestinal worms, skin diseases, ophthalmia, respiratory affections, and ulcers. Cholera and small-pox sometimes break out. In 1878 cholera prevailed from January to May and caused 290 deaths. In 1882 cholera again broke in May and continued till the end of June. Fifty-seven persons were attacked, of whom thirty-three or fifty-seven per cent died. Mudhol has one dispensary which was opened in 1872. During the year 1882-83 seventeen in and 7207 out-patients were treated. During the five years ending July 1882, the total number of deaths was returned as 6398, giving a yearly average of 1279 or 2·5 per cent of the total population. During the same period the total number of births was returned as 4512, giving a yearly average of 902 or 1·8 per cent of the total population.<sup>1</sup>

## PLACES.

*Mudhol.*

The chief places are Mudhol and Mahálingpur. MUDHOL, the capital of the State, with 7148 people, lies on the left bank of the Ghatprabha, about twelve miles south of Jamkhadi and eighteen north-west of Kaládgi. It had a wall all around, of which a part still exists. Outside the wall is a market or *peth* with shops of the Lingáyat, Gujarát, and Márwár Vánis. Here a market is held on every Friday, which opens at noon and closes at sunset. Besides from the river, the water-supply for drinking is drawn from wells and two ponds which lie north-west of the town. The water from the ponds is brought by an aqueduct into two reservoirs built in front of the Rám temple. The reservoirs are about 1850 feet from the ponds. Besides these, there are two more ponds, the Mahárráv and the Siddheshvar which are used for bathing, washing clothes, and watering cattle. Mudhol has had a municipality for the last fifteen years, which has made good roads throughout the town with side gutters and built public latrines. It has the offices of the *kárbhari* and the *nyáyádhish*, a dispensary, a jail, a post office, a library, five rest-houses or *dharmaśhálás*, and five schools. Of the five schools one is anglo-vernacular, two Maráthi,

<sup>1</sup> The death returns are believed to be fairly correct and the birth returns to be incomplete.

one a girls school, and one a night school. The *váda* or old residence of the Chief is in the centre of the town and like all other houses is flatroofed.

PLACES.

MAHÁLINGPUR, a trading town, with 6651 people, lies twelve miles north-west of Mudhol at the foot of a small hill. The town is named after the temple of Mahálingeshvar which stands on the top of the hill. About one-third of the people are Lingáyats Vánis or traders. Mahálingpur is the largest trading town in the State, and has a name for its *khans* or bodicecloths, which find a market even in Poona, Sholápur, and Bombay. There are about 700 looms for weaving cloth. A market is held on every Tuesday. Mahálingpur has a municipality, a police post, a post office, two rest-houses, a Maráthi school and a State *váda*, and a bungalow. A yearly fair is held in honour of the god Mahálingeshvar, on the bright tenth of *Bhádrapad* in September-October. The fair lasts six days and is attended by about 10,000 people. The charges of the fair are met from a State allowance of £42 4s. (Rs. 422), which is spent by the *panch* or leading Lingáyats of the town under the supervision of a State official.

Mahálingpur.

The Chief of Mudhol belongs to the Bhonsla-Ghorpada family, which, like most Marátha families of distinction, claims to be of Rajput or Kshattriya origin. The original name was Bhonsla, and tradition has it that the Mudholkar is descended from a common ancestor with the great Shiváji. This name however has been almost entirely superseded by the second designation, which is said to have been acquired by one of the family who managed to scale a fort, previously deemed impregnable, by fastening a cord round the body of a *ghorpad* or iguana. There are two branches of the great Ghorpada family, the Sáthkás and the Naukás, to the former of which the Mudhol Chief belongs, while the other division is represented by the *Senápati* of Kápsi in Kolhápur, and others, among whom was the Muráráv of Gutti, who played such a prominent part in the Madras Presidency in the last century.

HISTORY

All that is authentically known of the history of the Mudhol family is that it held a high position at the Court of Bijápur, from which it received the *jágir* it still holds. One of the kings of the Adil Sháhi dynasty is said further to have conferred the title of Rája or, more correctly perhaps, Ráje, which is still retained by the Mudhol chiefs, together with the privilege of using the *morchals*, and the dignity of exemption from the *mujra* or obeisance of a subject.

The Mudhol *jágir* is first mentioned in connection with the early history of Shiváji. When the latter commenced the work of laying the foundations of the Marátha empire and revolted against the Bijápur monarchy, Mahmud Adil Sháh, the then king, resolved in 1649 to checkmate the Marátha adventurer by making a hostage of his father Sháhji. Accordingly orders were sent to Báji Ghorpada of Mudhol, who was then serving in the Karnatak with Sháhji, directing him to apprehend the latter. The Mudholkar thereupon invited his colleague to an entertainment, at which he treacherously seized his guest and sent him as a prisoner to Bijápur. On

## HISTORY.

his arrival there, Sháhji was ordered to put a stop to his son's rebellion and when he declared his inability to do so, urging that Shiváji was in rebellion against his own father as well as against the Bijápur State, the king, to use the words of Grant Duff, 'enraged at his supposed contumacy, ordered him to be confined in a stone dungeon, the door of which was built up, except a small opening, and he was told that if within a certain period his son did not submit the aperture should be for ever closed.'

This threat however was not carried into execution, owing to the powerful influence brought to bear by Shiváji, and Sháhji was after a time released from his dungeon. He was however kept a prisoner at large for four years, at the expiration of which period he was allowed to go to his *jágir* in the Karnátak. Before this permission was granted he was bound down by a solemn engagement not to molest the Mudholkar, with whom he was ordered to exchange hereditary rights and *ináms* as a token of friendship. The exchange however was never made, and Sháhji, immediately on being liberated, wrote to Shiváji, charging him by his filial relation to him to 'punish Báji Ghorpada of Mudhol.' This injunction was not forgotten, but events did not admit of its being acted upon till some ten years afterwards, in 1661, when Shiváji, watching his opportunity, swooped down from Vishálgad, though surrounded by hostile forces, and marched rapidly to Mudhol, where he killed Báji Ghorpada, after which he burnt the town and returned in triumph.

Báji was succeeded by his son Máloji, who on the fall of Bijápur in 1686 was confirmed in his possessions by Aurangzeb. But little is known of the history of the family for the next three generations till we come to Máloji's great-grandson who bore the same name. This chief, who is said to have lived so long as to have been contemporary with all the Peshwás from Báláji Vishvanáth to Bájiráv, played an active part in all that went on during his eventful life. He agreed to serve the Peshwa with a fixed quota of horse for his hereditary estate, and held considerable *saranjáms* besides during his lifetime. He served against the Maisur princes, against the British in the campaign which resulted in the convention of Vadgaon, against the Nizám in the battle of Kharda, and against Holkar, and his long and active life came to an end in 1805. He was succeeded by his son Náráyanráv, who died in 1816, leaving three sons Govindráv, Lakshmanráv, and Venkatráv. These three brothers were at Mudhol at the time of their father's death, and the eldest, Govindráv, immediately claimed the succession. He was opposed however by Venkatráv's mother, and the question was referred to Poona, whither the parties proceeded. The Peshwa passed no formal decision in the matter, but Venkatráv's mother seems to have succeeded by bribery and intrigue in getting her son tacitly recognized as his father's successor. Govindráv was provided for by a command under Bápu Gokhle, and he and his second brother followed the fortunes of the Peshwa in the war with the British, which broke out in 1817. The elder of the two brothers was said to have been killed at the battle of Ashta, and Lakshmanráv, on the subversion of the Peshwa's dynasty, went to Baroda, where he took service with the Gaikwár. In this way Venkatráv was left in possession



of Mudhol, and Mr. Elphinstone accordingly concluded an engagement with him as the *jāgirdār*.<sup>1</sup>

HISTORY.

Some six or seven years after this, Mr. Elphinstone, who was then Governor of Bombay, was surprised to receive a communication purporting to be from Govindrāv, who was supposed to have been killed at the battle of Ashta. The writer asserted that he was the veritable Govindrāv, that he had been wounded in the battle but had concealed himself, and, after recovering from his wounds, had spent some years in visiting the sacred places in Hindustān. On an investigation being made into this claim there seemed at first grounds for believing that extraordinary as it was there was foundation for it, for Venkatrāv did not deny that this person might be his brother; Govindrāv's wife was so assured of the identity of the claimant with her husband that she went and lived with him, and many who had known Govindrāv in his youth were convinced that this was really the man. More careful enquiries however which were made during the following three years resulted in the conviction that the claimant was an impostor.<sup>2</sup> It was ascertained afterwards that he was a Gosāvi, whose remarkable resemblance to the deceased Govindrāv had been remarked at Baroda by the latter's sister.

Venkatrāv died in 1856, leaving a son Balvantrāv, then thirteen years of age, during whose minority the estate was managed by a *kārbhārī* appointed by Government and receiving his instructions direct from the Political Agent. Many improvements were effected during this period and the debts were all paid off, so that when in 1861 the young Chief was allowed to assume the administration he found his estate in good order, free from debt, and with a considerable balance in hand in the treasury. His tenure of power was but shortlived as he died in 1862, leaving two children, a girl who had been married a short time previously to a nephew of the Kolhāpur Rāja, who afterwards became by adoption Chief of Kāgal, and an infant son, aged one year, named Vyankatrāv. The widow claimed the administration of the estate during her son's minority, but Government ordered that the *kārbhārī* and the *munsif* should manage the estate, consulting the young Chief's mother on all reasonable occasions and being guided as far as feasible by her wishes, but being held directly responsible to the political authorities. The usual beneficial results have followed this arrangement. The estate has been surveyed and assessed, considerable sums have been spent on public works, and much has been done to further the spread of education. Notwithstanding the expense of these measures a considerable surplus has accrued, which has been invested in Government securities. The young Chief on attaining majority in 1882, was put in charge of the State.

<sup>1</sup> The Rāja was bound by this engagement to furnish a quota of twenty horse. In 1848 however this service was commuted to an annual cash payment of Rs. 2671½.

<sup>2</sup> The proceedings and arguments used in the case, bear a curious similarity to the famous Tichborne case. For instance, one chief ground for deciding that the Marātha claimant was an impostor was that he was utterly unacquainted with Kānarese, which Govindrāv used to speak fluently.

## RÁMDURG.

## DESCRIPTION.

Rámdurg, with an area of 140 square miles and forty-six villages had in 1881 a population of 29,570 or 221 to the square mile and in 1882-83 a gross revenue of £17,576 (Rs. 1,75,760). The State, unlike the neighbouring Patvardhan states, is a compact country and lies between Dhárwár and Bijápur. It is bounded on the north and west by the Torgal cluster of Kolhápúr, on the east by the Bádámi sub-division of Bijápur, and on the south by the lapsed state of Nargund which now forms part of the Navalgund sub-division of Dhárwár. The aspect of the State is generally flat and treeless with slight undulations. The Malprabhha runs west to east through the State for about twenty-five miles and has sixteen villages bordering on it. Besides this, five streams run through the State. Of these the Hukeri coming from Madkavi in Bádámi joins the Malprabhha at Sangal; the Tupanihal coming from Parasgad runs by Hebbál; the Bennihal coming from Navalgund joins the Malprabhha at Menasgi; the Gadagnihal coming from Navalgund joins the Tapnihal at Hebbál; and the Tolnihal coming from Navalgund joins the Bennihal at Osoṭi. The climate is generally hot and healthy. The rainfall at Rámdurg averages about twenty-two inches.

## PEOPLE.

According to the 1881 census the population was returned at 29,570 against 38,031 in 1872, that is a loss of 8461 or 22·24 per cent which is chiefly due to the mortality and emigration during the 1876 famine. Of the 29,570 people in 1881, 14,576 or 49·29 per cent are males and 14,994 or 50·70 per cent females; 27,663 or 93·55 per cent Hindus, 1903 or 6·43 per cent Musalmáns, and four Christians. The population is almost entirely Kánarese. The total number of houses was returned at 7350, of which 6640 were occupied and 910 unoccupied, giving fifty-two houses for each square mile and 4·59 persons for each house. There is one town Rámdurg with 6810 people. Of the villages six had less than 200 people, eleven between 200 and 500, fourteen between 500 and 1000, five between 1000 and 2000, and one between 3000 and 5000.

## AGRICULTURE.

The chief cultivating classes are Lingáyats, Maráthás, and Musalmáns. The bulk of the soil is black. The chief crops are *javári*, *báji*, rice, wheat, gram, and *tur*.

## TRADE.

Three roads pass through the State, the Rámdurg-Nargund for nine miles, the Belgaum-Kaládgi by Panchgaon for 1½ miles, and the Rámdurg-Belgaum for 1½ miles. Weekly markets are held on Sundays and Mondays at Rámdurg, on Fridays at Sarebán, and on Tuesdays at Mavhal. The chief imports are groceries, cloth, gold, silver, silk, and timber, chiefly from Bombay, Belgaum, Kumta, Rájápur, and Hubli. The chief exports are grain, cotton, and cloth. Of these grain is sent to Belgaum, Dhárwár, and Hubli and cotton to Kumta. Handwoven cloth, which was in 1883 woven of the estimated value of £18,000 (Rs. 1,80,000) goes to Rájápur, Chiplun, Bágalkot, Hubli, and Sháhápur.

## THE LAND.

The survey of the State has been completed. Before the survey settlement was introduced, the lands were resumed at the will of the

Chief. Under the survey settlement land is not resumed except on failure to pay the rent. The revenue is collected by two instalments. The *kharif* or early instalment falls due in January and March and the *rabi* or late in February and April.

THE LAND.

Since 1878 the State has been under joint administration during the minority of the Chief. The Joint Administrators of whom one is appointed by Government and the other by the grandmother of the Chief, have the powers of a Sessions Judge and the State *kárbhári* of a district magistrate. Civil suits are brought before a *munsif* who has powers to try suits up to £500 (Rs. 5000). Appeals against the *munsif's* decisions lie to the joint administrators who also decide original suits of more than £500 (Rs. 5000). The police force was fifty-nine strong, besides a few *savárs* or horsemen.

JUSTICE.

In 1883 the schools numbered nine with 591 names on the roll and the daily average attendance of 493.

INSTRUCTION.

The State has one dispensary at Rámdurg. In 1882-83 the number of patients treated was 4299. During the year 999 children were vaccinated.

HEALTH.

The only town of any size is Rámdurg with 6810 people.

PLACES.

The forts of Rámdurg and Nargund which are said to have been built by Shiváji, were, at the time of the latter's death, in charge of a Bráhmaṇ named Appáji Suru. They were taken by Aurangzeb's troops in 1692, but were recovered some fifteen years afterwards by the dexterity of a servant of Appáji, a Chitpávan Bráhmaṇ named Rámráv Dádáji Bháve, whose posterity was destined to supersede that of his master. Appáji at first resumed charge himself, but as he grew older he left everything in the hands of Rámráv, who, at his request, was formally invested with the charge of the two forts in question, and further received from the Rája Sambháji, grandson of Shiváji, the title of Pant Sachiv.

HISTORY.

In 1728 Appáji died, leaving an adopted son named Balvantráv. Rámráv acted as guardian to the latter, but administered the *saranjáṃ* in his own name. He was assisted in this task by his nephew Dádáji whom he had summoned from the Konkan and who displayed great vigour and ability. Among the *ináms* and grants bestowed upon Dádáji for services rendered was the *taraf* of Konnur which he received from the Nawáb of Sávanur, who retained however a third part of the revenue to which the Peshwás afterwards succeeded. By an order of Rája Sambháji, dated 1734, the whole *sarkári-amal* between the rivers Ghatprabha and Tungabhadra was assigned to Dádáji.

Some twelve years after the death of Appáji, Rámráv, accompanied by his son Yogiráv, went on a pilgrimage to Benares, during which he died. On Yogiráv's return he procured the assassination of his cousin Dádáji, who had been left in charge of the State and would not give it up. This led to a feud between him and Bháskaráv the murdered man's son, and Balvantráv, Appáji's heir, took advantage of the opportunity to recover his adoptive father's estates which, in 1758, were formally assigned to him, Yogiráv and Bháskarráv receiving personal *saranjáṃs*. The latter, however, made interest

## HISTORY.

with the Peshwa Mádhavrát Ballál, who made the estates over to them as a *sarvasthán saranjám*. Balvantrát received an allowance of £1200 (Rs. 12,000), in lieu of which his descendants, some thirty years after, managed to get possession of the town of Hebli, which is still held by the family.

Of the two holders of the *saranjám* Bháskarrát, and after him his adopted son Venkatráv, held the management, the other shareholder only receiving an allowance. In 1778 the estate came under Haidar Ali of Maisur, who exacted service on the same conditions as the Peshwa, but his son Tipu some years afterwards wished to impose further burdens. Venkatráv resisted, and in consequence Nargund was besieged by the Maisur troops. The place held out gallantly, and an army of observation being sent from Poona, Tipu agreed to relinquish his late demands if the fort were surrendered. No sooner however were the Marátha forces out of the way than he violated the articles of capitulation, and took Venkatráv and his family as prisoners to Maisur, where the unfortunate Chief's daughter was placed in the Sultán's seraglio. Rámrát, the representative of the other branch of the family, managed to make his escape on this occasion.

The operations of the allied armies under Lord Cornwallis against Seringapatam restored Venkatráv to liberty, and in 1791 a new *sanad* was granted by the Peshwa, bestowing the estate on him and Rámrát. Through the influence of Parashurám Bháu Patvardhan the latter received Rámdurg on this occasion as his appanage, but by far the largest portion of the estate was assigned to the other branch of the family. This arrangement lasted for some nineteen years, but in 1810 Náráyanrát, the son of Rámrát, having interest with the Peshwa, claimed to share equally with Venkatráv. This claim was admitted by Bájrát, who happening to be in the neighbourhood, himself put Náráyanrát in possession of his share and fixed the amount of the contingent to be furnished by each moiety of the estate which was thus regularly divided.

When the war between the Peshwa and the English broke out the Rámdurg Chief had some troops with the former, but he soon joined General Munro, and consequently received most liberal terms. The British Government gave up its claims to the contingent which Náráyanrát had been bound to furnish to the Peshwa, and only called on him to pay annually £346 17s. 6d. (Rs. 3468½) in commutation of the rights in the Konnur *jágir*, which the Peshwa had held. The other articles of the engagement were similar to the terms granted to the other chiefs in the Bombay Karnatak.

In 1827 Náráyanrát died leaving no male issue. The only collateral descendants of the founder of the family being the Nargund Chief and two sons, who were considered ineligible for adoption in consequence of being married, it was determined at first to resume the Rámdurg estate. The widow of the deceased protested against this decision as did the Nargundkar, who claimed the reversion of the State to himself. At last, in 1829, it was ruled that Rádhábái the widow should be allowed to adopt, and should be recommended

to adopt Hariharráv, the youngest son of the Nargund Chief, a boy then fourteen years of age. This arrangement was most unpalatable to the lady, but at last she conformed to the wishes of Government, and after making careful provisions and stipulations for her own dignity and authority, adopted the lad, who received on the occasion the name of Rámráv.

Rádhábái seems to have been a lady of remarkable force of character and considerable administrative ability. She managed her estate well; but she loved power too much to willingly delegate any portion of it to any one, especially to her adoptive son, with whom her relations were never cordial. Her treatment of him was such that he left Rámdurg in disgust some seven or eight years after his adoption, and went to Nargund, where he remained till, through the intervention of Government, a proper allowance was secured to him. The quarrels between him and Rádhábái, however, continued till the death of the latter in 1857 put him in possession of the estate.

Rámráv assumed power at a most critical period, and his loyalty was severely tested. His half-brother Bháskarráv, the Chief of Nargund, discontented at being refused permission to adopt, prepared to revolt against the British Government, and endeavoured to persuade the Rámdurgkar to join him. Rámráv not only refused, but informed Mr. Manson, the Political Agent in the Southern Marátha Country, of the correspondence, when the latter went to Rámdurg on his way to Nargund, in the hope of being able to dissuade the chief of that place from his fatal purpose. At Rámráv's earnest request Mr. Manson gave up his intention of seeking an interview with Bháskarráv at Nargund, but he unfortunately proceeded in that direction with a small escort, and the Nargundkar, mistaking his intentions, attacked his camp on the night of the 29th May 1858, and murdered the unfortunate gentleman, taking back his head to Nargund as a trophy. Bháskarráv then openly raised the standard of revolt, but his fort was speedily taken and himself captured, after which he was hung at Belgaum and his estate confiscated.

In the following year the Rámdurg Chief having no issue, prayed to be allowed to adopt, which request was granted by Government. He did not, however, avail himself of the permission till 1866, when he adopted a lad of about fifteen years of age, the son of a collateral descendant of the Bháve family, residing in Kolhápúr, who on adoption received the name of Yogiráv. The Chief received a *sanad* of adoption in 1862.

Rámráv died in 1872 and was succeeded by his adopted son Yogiráv. Yogiráv Bápu Sáheb was married in 1867 to the daughter of the Chief of Sángli. He died in 1878, leaving a minor son Venkatráv. During the minority of the Chief the State is managed by joint *kárbháris*<sup>1</sup>.

<sup>1</sup> The historical section of the Patvardhan States and Mudhol and Rámdurg is contributed by the late Colonel E. W. West.



Appendix A.  
THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

## APPENDIX A.

*Kolhapur City Thermometer Readings and Rainfall, 1851-1881.*

Months.	1851.					1852.					1853.					1854.					1855.				
	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	
January	59	88	62	79	...	55	82	62	77	...	60	81	67	76	...	64	82	67	77	...	60	76	65	74	0.10
February	61	91	68	84	...	64	84	66	79	...	65	87	72	82	1.00	63	87	68	78	...	67	77	69	76	...
March	69	95	75	90	...	67	90	70	86	...	73	95	77	88	0.06	72	90	74	85	0.78	70	88	73	79	2.84
April	73	96	76	93	1.04	68	93	74	89	1.04	73	92	77	89	2.90	75	94	77	89	0.06	71	87	77	84	1.13
May	72	96	74	88	1.11	68	91	75	86	2.80	76	95	78	90	2.65	76	94	78	88	1.95	76	91	78	89	8.89
June	72	89	74	79	7.53	73	90	75	81	9.52	73	90	75	80	7.46	74	86	75	80	9.30	74	80	77	82	9.44
July	73	89	74	77	14.35	72	82	74	77	15.23	71	76	72	74	41.09	71	79	72	76	15.53	72	78	74	76	2.66
August	72	89	73	76	3.92	71	79	72	75	10.80	72	80	73	76	3.63	73	78	73	76	5.84	73	79	74	78	2.85
September	71	80	72	79	4.83	71	80	73	77	12.35	72	91	73	78	4.30	72	79	74	78	4.03	72	81	75	78	9.50
October	70	82	73	78	4.00	73	83	75	80	2.63	72	84	74	80	0.77	71	81	73	77	11.13	74	81	75	81	0.11
November	69	82	73	80	0.45	68	84	71	81	...	68	85	73	80	...	71	79	71	77	0.94	67	79	70	77	...
December	55	81	61	77	0.20	61	82	67	74	0.68	60	78	65	75	...	67	78	70	76	...	70	79	64	75	1.04
Average	74	79	71	82	39.69	67	84	71	80	55.55	69	86	73	80	63.91	70	83	72	79	43.76	70	82	72	79	38.56



Appendix A.  
THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

MONTHS.	1866.					1867.					1868.					1869.					1870.				
	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.
January ..	67	81	69	77	...	65	76	69	74	0.43	62	85	66	75	...	68	76	68	75	...	60	82	68	76	...
February ..	67	85	71	80	...	68	85	73	80	...	70	88	72	84	...	70	86	71	81	...	67	89	77	82	...
March ..	74	91	77	85	1.25	73	89	76	85	0.40	70	92	76	89	0.49	69	92	74	87	1.21	70	90	75	85	0.40
April ..	76	96	80	89	0.55	74	90	77	86	1.80	80	92	80	89	2.17	77	95	71	83	4.35	71	93	75	85	1.22
May ..	75	91	78	85	8.67	77	88	78	85	6.25	75	89	78	86	3.95	73	94	82	89	3.39	76	94	79	91	0.33
June ..	73	83	76	78	11.29	76	85	76	80	8.06	74	89	76	83	4.53	74	89	76	87	2.38	74	87	76	86	4.82
July ..	74	81	75	76	16.30	74	79	74	76	5.63	74	80	74	76	14.37	75	86	76	82	16.27	71	84	74	80	9.65
August ..	73	78	73	77	5.23	72	76	72	75	11.35	73	78	74	76	4.62	73	82	73	77	3.39	71	81	72	76	4.92
September ..	73	79	74	77	6.40	73	76	73	75	1.16	73	81	74	77	4.19	74	83	76	81	5.61	72	81	74	78	3.98
October ..	72	80	74	76	3.28	70	80	75	78	6.73	71	82	76	80	6.69	72	83	74	80	0.40	72	83	75	80	9.01
November ..	68	81	72	79	0.27	62	84	68	78	4.12	67	79	70	76	1.17	69	83	69	79	0.67	60	86	79	79	...
December ..	64	76	67	77	0.11	62	84	64	79	...	62	78	66	74	...	64	79	66	75	...	61	91	70	85	...
Average ..	71	83	73	79	59.35	70	82	72	79	45.93	70	85	73	79	42.48	71	86	72	81	37.77	68	86	74	82	34.33

Appendix A.  
THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

*Kolhapur City Thermometer Readings and Rainfall, 1851-1881—continued.*

Months.	1861.					1862.					1863.					1864.					1865.				
	Thermometer.				Rain.	Thermometer.					Thermometer.					Thermometer.					Thermometer.				
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Rain.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Rain.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Rain.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Rain.
January ..	80	89	64	85	0.11	60	91	63	87	..	60	90	62	74	..	50	88	59	82	..	62	88	65	86	0.19
February ..	64	99	66	91	..	64	95	66	92	..	60	97	65	88	0.12	61	89	63	86	..	62	90	68	86	0.02
March ..	65	99	70	93	..	63	96	70	96	..	68	98	71	94	0.43	63	95	70	93	..	60	98	72	93	..
April ..	75	102	73	98	2.51	73	100	75	95	1.14	73	105	75	97	0.74	72	99	75	94	0.65	72	103	76	90	5.92
May ..	72	101	74	96	1.25	73	99	74	90	1.63	69	102	74	96	..	71	95	74	91	1.50	75	96	76	89	6.75
June ..	70	86	72	82	4.23	72	95	74	83	10.90	72	91	73	81	11.88	72	91	74	80	12.93	73	85	75	84	2.17
July ..	70	80	71	75	14.96	73	84	74	80	7.27	71	79	72	76	8.90	71	82	72	76	13.41	73	82	73	78	7.10
August ..	70	80	71	75	13.06	70	80	73	77	8.36	70	78	71	76	5.36	71	82	71	77	4.04	71	81	72	76	11.56
September ..	69	83	70	79	2.36	73	89	75	83	7.73	70	85	71	78	1.71	70	85	71	80	3.85	69	86	71	79	0.94
October ..	63	90	69	81	6.76	69	90	72	87	7.72	63	90	71	83	5.18	69	90	71	87	0.17	69	91	71	84	4.31
November ..	57	93	65	89	..	62	89	63	81	0.27	62	83	66	86	..	64	88	70	85	0.98	62	91	72	86	0.55
December ..	57	87	61	85	..	57	86	61	83	..	61	85	64	81	0.65	63	88	66	85	..	62	86	67	85	0.10
Average ..	66	90	68	85	45.79	63	90	63	86	45.07	63	90	69	84	34.07	66	89	63	84	37.76	63	89	71	83	39.61

MONTHS.	1866.					1867.					1868.					1869.					1870.				
	Thermometer.				Rain.	Thermometer.					Thermometer.					Thermometer.					Thermometer.				
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	In.
January	58	89	64	85	...	60	89	64	85	...	59	87	63	85	...	60	91	63	88	...	52	89	64	83	...
February	59	94	65	86	...	62	93	63	89	...	58	98	65	90	...	60	95	62	89	...	58	98	64	87	...
March	69	100	73	94	...	67	95	71	90	...	58	98	69	93	...	65	99	70	93	...	65	99	70	93	0.12
April	69	101	70	92	...	70	97	74	98	2.65	70	104	75	96	0.75	71	108	75	98	0.86	68	99	72	96	1.35
May	71	99	75	95	...	74	97	76	92	1.75	74	100	72	94	3.72	74	101	76	94	2.24	70	99	72	94	1.23
June	72	98	74	85	6.91	73	86	75	80	9.39	72	95	75	82	10.21	73	91	75	85	3.77	70	95	72	85	1.27
July	70	82	72	78	10.86	70	87	73	79	5.45	70	85	73	80	7.88	72	89	73	79	6.82	70	82	70	77	13.40
August	70	81	71	77	5.95	70	79	72	77	7.19	70	99	72	82	7.63	72	89	73	80	5.47	70	84	70	79	5.23
September	70	85	71	80	0.93	68	82	71	78	1.91	70	84	71	80	3.46	71	83	72	79	5.03	69	82	68	80	7.22
October	64	89	72	86	3.91	70	89	72	83	10.35	68	92	72	87	2.55	69	89	72	83	2.22	65	85	73	82	9.65
November	59	89	66	85	...	53	83	64	84	0.76	61	91	65	83	...	56	89	67	82	2.28	60	87	68	88	0.55
December	58	85	64	82	...	59	87	63	84	...	60	83	63	85	...	56	89	65	83	1.90	56	85	57	82	...
Average	64	91	69	85	32.56	66	89	70	84	39.95	65	93	69	86	36.25	66	93	70	86	30.29	64	90	68	85	44.02

Appendix A.  
THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

Appendix A.  
THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

*Kolhapur City Thermometer Readings and Rainfall, 1851-1881—continued.*

Months.	1871.					1872.					1873.					1874.					1875.				
	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				Rain.	Thermometer.				
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.		Minimum.	Maximum.	Mean Minimum.	Mean Maximum.						
January	58	87	63	83	0.59	57	77	64	74	In. ...	61	89	56	85	In. ...	51	87	53	81	In. ...	53	85	59	81	In. ...
February	60	95	65	89	...	60	98	65	81	...	66	91	71	86	0.34	59	86	64	88	0.14	58	94	65	87	...
March	60	99	63	95	0.04	68	100	54	95	...	60	101	64	92	...	64	93	70	95	...	69	98	71	97	0.06
April	70	100	74	98	1.17	72	100	75	95	1.48	70	99	73	98	2.97	64	106	69	100	2.71	70	99	74	95	0.73
May	73	96	74	87	2.32	72	99	74	96	2.35	71	100	75	96	3.69	70	103	74	96	2.93	70	95	72	83	1.40
June	71	85	73	79	8.34	71	99	74	87	8.52	71	86	73	82	2.03	71	84	73	81	12.03	71	91	73	83	9.95
July	70	76	70	74	11.01	70	73	71	74	12.93	70	85	71	75	12.03	69	73	70	76	16.99	70	80	70	77	26.97
August	69	79	70	76	6.32	70	80	70	77	3.94	69	85	70	77	4.37	69	77	70	75	6.44	70	79	70	77	7.60
September	69	81	70	78	2.45	69	82	71	79	4.51	69	88	70	76	2.13	71	80	72	77	6.72	69	80	70	77	7.34
October	67	82	72	73	8.41	63	87	63	83	3.64	64	88	70	81	3.72	64	88	71	82	3.20	65	89	70	84	0.83
November	66	81	72	73	0.85	57	89	63	86	0.56	57	91	63	88	0.26	60	85	64	81	0.15	61	83	67	83	0.04
December	60	79	63	70	...	53	86	61	81	1.56	57	88	62	85	...	54	87	61	82	0.18	52	86	60	85	0.42
Average	66	86	69	82	33.50	62	97	67	84	39.54	64	90	63	85	31.54	63	80	68	84	56.42	64	88	68	83	55.34



## Kolhápúr City Thermometer Readings and Rainfall, 1851-1881—continued.

Months.	1876.				1877.				1878.				1879.				1880.				1881.			
	Thermometer.			Rain.	Thermometer.			Rain.	Thermometer.			Rain.	Thermometer.			Rain.	Thermometer.			Rain.	Thermometer.			Rain.
	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.	Minimum.	Maximum.	Mean Minimum.	Mean Maximum.
January	50	89	62	86	58	88	64	87	56	89	60	86	54	86	60	81	52	85	55	84	53	87	58	83
February	60	88	64	87	64	90	67	87	63	85	63	82	56	86	59	85	53	92	59	80	55	89	61	85
March	65	96	72	93	70	96	73	93	64	99	73	87	66	97	83	95	68	97	71	93	65	96	68	88
April	70	99	75	96	70	99	71	92	73	99	74	95	71	102	74	97	73	99	76	91	72	99	76	91
May	70	97	75	95	69	102	74	96	73	97	75	95	69	90	77	86	75	99	71	89	78	101	79	93
June	71	94	73	89	70	99	73	84	73	97	74	88	72	85	73	82	69	80	74	83	73	90	75	80
July	71	86	72	84	71	85	73	82	71	87	73	81	72	85	70	84	71	81	72	85	70	83	72	80
August	71	80	72	78	71	85	72	80	71	85	70	80	71	83	71	77	72	86	73	82	72	82	72	77
September	71	85	72	78	71	83	72	76	71	85	73	81	72	79	73	78	73	86	73	84	70	81	73	80
October	65	90	72	87	72	80	72	79	73	84	73	78	70	82	70	82	72	86	74	84	65	87	72	84
November	60	89	64	83	60	89	65	84	64	89	68	82	64	86	62	82	63	85	70	82	54	89	64	81
December	60	89	63	87	64	89	65	89	55	89	57	88	51	85	51	81	56	87	60	82	52	86	53	82
Average	65	90	69	87	67	90	70	85	67	90	69	85	64	87	69	83	66	88	69	84	64	89	69	83

## Appendix A.

THERMOMETER  
READINGS AND  
RAINFALL,  
1851-1881.

## APPENDIX B.

## TREES.

Appendix B.  
TREES.

THE following is an alphabetically arranged list of principal trees found in the Kolhápur State :

*Ain* Terminalia tomentosa is perhaps the commonest, most easily grown, and hardiest tree in the western forests. It grows to a considerable size and is much used in building and for field tools. Its deeply crooked bark is astringent and yields a black dye. *Amba* Mangifera indica, the mango, though it occurs on all the western ranges, is not a very common forest tree, but especially in the west is found near every village. The wood is used by carpenters and the fruit is much eaten. Fine grafted Ratnágiri mangoes have lately been introduced but it is not yet known how they will thrive. *Arjun* Terminalia arjuna is commonest in the west along the banks of rivers and hill streams. It grows to a great size and in many respects is considered as good as the black *ain*. The wood is used both for building and for field tools. *Asan* Pterocarpus marsupium grows in most of the Sahyádri and other western hill reserves. It is a large wide-spreading tree and yields strong useful timber. It stands water and is much used for the frames of wells. Its bark is a strong astringent and its leaves are eaten by cattle and are said to cure worms. *Ávla* Phyllanthus emblica grows on the wooded plateaus or belts of the western hills. Its hard lasting wood is used for boxes, for veneering, and for well rings as it does not decay under water. Its astringent bark is used in diarrhoea and its fruit is occasionally pickled or preserved in sugar.

*Bábhul* Acacia arabica is the most useful and the commonest tree in east Kolhápur. It grows rapidly and freely in black soil especially in clay deposits along river banks. Its wood, though seldom straight, is hard and is much used for building, for field tools, and for fuel. Its bark is used in tanning and yields a yellow dye. Its sap is a useful gum and during the hot season its pods are a valuable food for sheep and goats. *Bakul* Mimosa elengi is a handsome garden tree with very sweet smelling flowers and is seldom found in the forests. The wood is used in building, the fruit is eaten, and from the flowers a scent is distilled. *Bandára* Lagerstræmia lanceolata is very handsome when full grown. It blossoms during the hot season. Its wood is light coloured straight and elastic and is used much for building. *Báhva* Cassia fistula is common over almost all the western reserves but is seldom more than a shrub. Early in the hot weather it is covered with long pale yellow tassels like large taburnum flowers. Its wood is used in building and for field tools. Its bark and roots yield a strong purgative. *Beheda* Terminalia bellerica is very scarce but where found is used for all purposes, having the same qualities as the black *ain* tree. Its fruit is used as a cure for cough. *Bhendi* Thespesia populnea most occurs in gardens and on roadsides ; it is rarely found in forests. It is a useful roadside tree, as it grows readily from cuttings. The hollow trunk is of little use but its straight shoots yield



rafters, which are much valued in house building. *Bibba* Semecarpus anacardium grows in many reserves both in the west and in the east. It is a middle-sized tree and has such bitter sap that it is seldom cut until it is dry. Its wood serves for minor uses and its pulpy fruit is a great favourite among all classes of natives. The nut is used for blistering and as a cure for worms. *Bor* Zizyphus jujuba is a garden tree, and when well matured yields close and even-grained wood. Its bark is much used and its fruit is very popular.

*Chandan* Santalum album, the sandalwood tree, is found in a few of the Karvir and Bhudargad reserves as well as in Ajra and Bávda. *Chinch* Tamarindus indicus, the tamarind, grows to a large size in gardens and grass lands. It yields heavy firm timber, much used in building and making sugarcane crushers and oil mills. The acid pulp of the pods is used both as food and medicine and its half-roasted seed is a cure for dysentery. *Chiva* Bambusa arundinacea, the bamboo, grows almost everywhere especially on the banks of streams and rivers, in damp grounds, and in other cool places. The canes are used in roofing and for many purposes and are split for matting and basket-making. Its leaves are given to horses suffering from cold.

*Dháman* Helicteres isora is common in the western forests though rare in the east. In suitable soil it grows to a moderate size. Its wood serves for cot frames, wheels, axe-handles, knives, pickaxes, grinding mills, and carpenter's tools. The leaves are eaten by cattle and the fruit by men.

*Hedu* Nauclea cordifolia is irregularly distributed over several of the Sahyádrí spurs. It grows to a great size and its timber, though of no great strength, is easily worked and lasts well if not exposed to the weather.

*Hirḁa* Terminalia chebula is common in almost all the forests of the Bhudargad, Panhála, and Gadinglaj sub-divisions and in the subordinate states of Bávda, Vishálgad, and Ajra. Its good yellowish brown timber is used for field tools and its fruit is highly valued for making ink and as a dye. The fruit, the myrobalan of commerce, is one of the chief forest exports. In 1881-82 the crop amounted to 1330 *khandis* and yielded the State a revenue of £4500 (Rs. 45,000).

*Jámbhul* Eugenia jambolana grows freely where there is a good supply of water. Its timber is fine, hard, and closegrained. As it does not rot in water, it is much used for lining wells and watercourses. There are some fine *jámbhul* groves along the banks of the river Ambardi near the village of Mán in the Malkápur State, and on the flat ground near the foot of the western slope of the fort of Panhála. Its leaves and bark are astringent and its purple berries are a favourite food.

*Káju* Anacardium occidentale grows in the southern forests of Ajra and in the west on the Bánda hills. It is a small tree with a very ornamental leaf. Its wood is not deemed of value, but its fruit is eaten with relish and its bitter juice is used as a flux for soldering metals. *Kalamb* Nauclea parvifolia is common in the west and grows to a considerable size. Its closegrained wood is used for planks and beams for the flooring and frames of houses. It is held in veneration by the Hindus as Krishna's favourite tree. *Kalvin* grows to a considerable size and is found in most of the forest reserves. Its straight closegrained wood does not suffer from the attacks of insects and is used for building and other purposes. *Kawath* Feronia elephantum, the woodapple, is common in gardens. Its wood is white, hard, and finegrained and is used both for building and for ornamental carving. The pulp of the fruit with sugar and water is an excel-

## Appendix B. TREES.

Appendix B.  
TREES.

lent cooling drink. *Khair* *Acacia catechu* occurs in few places and is stunted and weak. Its very strong wood is considered more lasting even than teak. *Kinjál* *Terminalia paniculata* common all over the western reserves grows to a large size and yields good timber. *Koshimb* *Schlichera trijuga* grows in several of the western reserves. Its heavy hard wood is applied to many building and field purposes, as well as for rollers in sugarcane mills, for pestles, and for cartwheel spokes. *Kuchla* *Strychnos nux-vomica*, the vomit nut, is a middle-sized tree and yields hard and durable wood, which is used for several purposes. The very bitter root is used in intermittent fevers and venomous bites. The seeds have intoxicating properties. *Kumbha* *Careya arborea* grows in many of the Sahyádrí forests. Its timber is not very heavy but takes a good polish and is well veined. It is used for building and other ordinary purposes. Its bark yields a coarse but useful cordage.

*Nánábondára* *Lagerstræmia parvifolia* is plentiful in the western forest ranges. It grows to a considerable size and yields closegrained, straight, elastic wood, which is used in building and for many ordinary purposes. *Nándruk* *Ficus retusa* is not common in the western forests. It is much liked for roadsides as it is easily grown from cuttings. It is pleasant to look at and gives a thick shade. Its wood serves for several minor purposes. *Nimb* *Azadirachta indica* is rare in the western forests. It grows freely in black soils, gardens, and enclosures and along the edges of fields. It yields a fine highly valued wood and its bitter bark leaves and roots are much used as medicine.

*Palas* *Butea frondosa* thrives in the forests as well as near villages. The wood is not valued but its leaves are much used by Hindus as food platters. Its gay scarlet blossoms brighten the forest in the early hot weather. Its seeds are a cure for worms. *Phanas* *Artocarpus integrifolia*, the jack tree, though rare as a wild tree, is scattered over all the western hills and is common in the village groves in the west. The fruit is much valued and the timber is very useful to carpenters. *Pimpal* *Ficus religiosa* is common in all parts of Kolhápúr. It is much venerated by Hindus and is often planted near temples, houses, and other buildings. Its wood is light and of no use except as fuel.

*Ránphanas* *Artocarpus hirsuta* is found in the south-west of Kolhápúr and in the Chándel reserves of Vishálgad. The tree grows to a large size and yields good timber, which is mostly used in housebuilding.

*Ságván* *Tectona grandis*, the teak, is found on the Sahyádrí slopes but except in a few places in Panhála, Bhudargad, and Bávda it seldom grows to any size. Its timber is used only for rafters. *Shindi* *Phoenix sylvestris*, the wild date palm, grows along the banks of streams, rivers, and water-courses. Its unfermented or partly fermented juice is drunk by the lower class Hindus. Its leaves are plaited into mats and baskets. *Shisav* *Dalbergia sisu*, the blackwood tree, occasionally occurs on the higher slopes of the Sahyádrí hills. *Shivan* *Gmelina arborea* occasionally occurs in the Bhudargad and other forests. When full grown it yields excellent timber. *Sonchápá* *Michelia champaca* is grown in gardens and enclosures. Its handsome mottled timber is used in building, but it is chiefly valued for its fragrant yellow flowers.

*Umbar* *Ficus glomerata*, both a forest and a garden tree, yields straight grained timber which weathers well and is much used for the doors of native houses. Its fruit is eaten by the poor and its roots yield a medicinal extract.

*Vat* or *Vad* *Ficus indica*, the banyan, is one of the best roadside trees, cuttings, if watered and in good soil, growing to a magnificent size. Its

wood serves as fuel. *Vehela*, found in several forest reserves, grows to a considerable size and yields light timber.

The following trees are also cultivated in irrigated lands: *Ananas* *Ananas sativus*, pineapple; *dálím* *Punica granatum*, pomegranate; *kel* *Musa sapientum*, plantain; *limbu* *Citrus acida*, lime; *mahálung* *Citrus medica*, citron; *náral mád* *Cocos nucifera*, the cocoa palm; *pápanas* *Citrus decumana*, pomelo or shaddock; *peru* *Psidium pomiferum*, guava; *rámphal* *Anona reticulata*, bullock's heart; and *sitáphal* *Anona squamosa*, custard apple.

The following list gives the names of the chief healing plants found in Kolhápúr :

*Adulsa* *Justicia adhenatoda* is found everywhere. The leaves are a useful emetic. *Agasta* *Æschynomene grandiflora* is found everywhere. Its bark is a bitter tonic. *Agháda* *Achyranthes aspera* is found everywhere. An infusion of the root is a mild astringent in bowel complaints. *Ajavla* *Ocimum pilosum* is found in almost all forests. The bark is useful in dressing wounds. *Akáshvel* *Ipomæa quamoclit* is found in the forest. It is used to dress ulcers and as a cure for sore-eyes. *Akkalkádhá* *Anthemis pyrethrum* is found in the gardens. It is a strong stimulant. *Ale* *Zinziber officinalis*, ginger, is grown in gardens. It is used in dropsy. *Amba* *Mangifera indica* is found everywhere. Its kernel is an astringent in piles. *Arjun* *Terminalia arjuna* is found on the Sahyádrí range. The bark is used as a tonic and externally as a vulnerary. *Ásan* *Pterocarpus marsupium* is found on the Sahyádrí hills. The bark is highly astringent. *Ashók* *Saraca indica* is found in the plain east. The bark is used in diseases of the womb. *Ávala* *Phyllanthus emblica* is found everywhere in the district. The fruit is used in fevers diarrhoea and bilious complaints. *Bábhul* *Acacia arabica* grows in the plain country. The bark is used as a tonic and astringent. *Badám* *Prunus amygdalus*, the almond, is planted in gardens and is used as a tonic. *Badishep* *Anethum fœniculum* is sown in fields. The fruit and root are given to children suffering from dysentery. *Báhva* *Cassia fistula* is found on the Sahyádrí range and is an agreeable laxative. *Bakul* *Mimusops elengi* is found everywhere in the district and possesses tonic and astringent properties. *Bala* *Pavonia odorata*, of four varieties, is found in gardens. The root is astringent and tonic. *Bálantshep* *Anethum sowa* is grown in fields and is used in rheumatism. *Bávchi* *Psoralea corylifolia* is found in wastelands. The seeds are used as a cure for skin diseases. *Beheda* *Terminalia bellerica* is found on the Sahyádrí range. The pericarp is used in powder in expectorant electuaries. *Bel* *Ægle marmelos* is found everywhere. The fruit is used in diarrhoea and dysentery. *Bhárangi* *Clarodendron serratum* is found on the borders of fields. The root is a cure for fever. *Bhokar* *Cordia myxa* is found everywhere. The bark is a mild astringent. *Bhopla* *Cucurbita hispida*, the gourd, is sown near homesteads. The unhusked seeds are eaten with sugar in cases of tapeworm. *Bhuikohla* *Convolvulus paniculatus* is found in the Konkan. The root is used in gonorrhoea. *Bibvu* *Semecarpus anacardium* is found on the Sahyádrí range. The root is used as a vesicant and a counter irritant. It is used in dyspepsia and piles. *Bokháda* *Ficus scabriuscula* is found everywhere in the district. The bark is used for curing white leprosy. *Bor* *Zizyphus jujuba* is found in forests. The root is a cure for nausea. *Brahmi* *Hydrocotylea asiatica* is found in watercourses. The plant has diuretic properties. *Chákhvat* *Chenopodium viride* grows wild. The leaves are used as a cure for worms and bile. *Chandan* *Santalum album*, sandal, is rarely found in gardens. The wood is useful in biliousness vomiting and

## Appendix B.

## TREES.



Appendix B.  
TREES.

fever. *Chápha* *Michelia champaca* is found everywhere. The bark is used as an aromatic bitter. It has many varieties. *Chár* *Buchanania latifolia* is found in the Konkan. The fruit is used in bilious cases. *Chibud* is planted in water lands. The seeds produce cough and cold. *Chikanmul* *Sida cordifolia* grows everywhere. The root possesses mucilaginous properties. *Chinch* *Tamarindus indicus* is found in fields. The pulp has excellent antiscorbutic properties. *Chitrak* *Plumbago zeylanica* is found in the Konkan. The root is a cure for dyspepsia. *Chuka* *Rumex vesicarius* is grown in watered lands. It is cooling and astringent. *Dagadphul* *Parmelia caperata* grows in rainy weather on stones. It is chiefly used as a perfume. *Dálím* *Punica granatum* is grown in gardens. The flowers and the bark of the root are astringent. *Darbh* *Poa cynosuroides*, *mol* *Saccharum munja*, and *devnal* *Arundo libialis*, are found on the banks of rivers. A decoction from the roots of these three plants is used as a diuretic. *Davna* *Artemisia abrotanum* is grown in gardens and used as a cure for headache. *Devdángri* *Vangueria spinosa* (?) causes sickness. *Devkápús* *Gossypium religiosum*, the holy cotton, is grown in gardens. The unripe capsule soaked in opium is a cure for dysentery. *Dháman* *Helicteres isora* is found on the Sahyádrí hills. It is used as a tonic in bilious affections. *Dhamása* *Hedysarum alhagi* is found in the plain east. It is used as a bitter and astringent. *Dhane* *Coriandrum sativum* is grown in fields. The seed is a carminative. *Dhávda* *Anogeissus latifolia* is found in the Sahyádrí crests. The bark is used in colds, bile, and consumption. *Dháyti* *Grislea tomentosa* is found in the western hills. The flowers are a stimulant. *Dhotra* *Argemone mexicana* is found everywhere. The seed is an emetic. *Dodka* *Cucumis acutangulus* is used as an aperient. *Dorli* *Solanum indicum* is found in fields over almost all of the Kolhápúr State. The root is used in fevers, worms, and colic. *Dráksh* *Vitis vinifera*, the grape, is grown in gardens. The dried fruit is used as a laxative. *Dudhvel* *Hemidesmus indicus*, country sarsaparilla, has in its root an excellent substitute for sarsaparilla which is much used in rheumatism and boils. *Dupári* *Pentapetes phœnicea* is planted in gardens. The leaves are a stimulant. *Durva* *Cynodon dactylon* is found everywhere. It is acidulous and used to check nausea. *Erand* *Ricinus communis*, the castor plant, is found all over the State. All parts of the plant are used as purgatives. *Gela* *Randia dumetorum* is found in the Konkan. The fruit acts as an emetic. *Ghol* *Portulaca oleracea* grows wild. Its juice is used in gonorrhœa. *Ghosále* *Luffa pentandra* is grown near homesteads. The leaves and fruit are useful in fever. *Gokarna* *Aletris hyacinthoides* is grown in gardens. The root is used as a laxative for children and the seeds as a purgative. *Gulvel* *Cordifolius cocculus* is found in the forests. Its starch or *satva* is considered a useful stomachic. *Gunja* *Abrus precatorius* is found everywhere. It is used in gonorrhœa. *Halad* *Curcuma longa*, turmeric, of three varieties, is grown in gardens; it is a cordial and stomachic. *Haliv* *Lepedum sativum* is used for purifying the blood. *Hinganbet* *Balanites ægyptiaca* is found in the plain parts of the State; the fruit has emetic and purgative properties. *Hirda* *Terminalia chebula* is found on the Sahyádrí range; the fruit possesses purgative properties. *Isband* *Donosonia inerimis* is used in charms against witchcraft. *Jái* *Jasminum auriculatum*, *málati* *Jasminum grandiflorum*, and *kund* *Jasminum pubescens* are planted in gardens. *Jámbhul* *Syzigium jambolanum* is found everywhere. A decoction of the bark is used in chronic dysentery. *Jásvand* *Hibiscus indicus* is grown in gardens; the leaves are used in mild cases of gonorrhœa. *Jatámávshi* *Valeriana jatamansi* is found near streams. The root is a stimulant. *Jeshimadh* *Glycirriza glabra*

is a useful demulcent root. *Jhámbar* *Citrus acida* is grown in gardens. The juice makes a cooling drink and is useful in cases of indigestion. *Kadupadval* *Trichosanthes anguina* is found in the forests. The plant and fruit are used as a cathartic. *Kákadshingi* *Rhus kakrashingi*: the galls have astringent and tonic properties. *Kákjangha* *Leea hirta* is found in the Konkan. It is used for cough and fever. *Kalamb* *Nauclea parvifolia* is found below the Sahyádris. The bark is used in bilious complaints. *Kalingad* *Cucurbita citrullus*, the watermelon, is grown in watered land. The seeds are cooling and diuretic. *Kánda* *Allium cepa*, onion, is grown in watered land. The juice is used for earache and the seeds are demulcent. *Kánchan* *Bauhinia variegata*, of two varieties, is found everywhere. The bark is used in skin diseases. *Kágoni* *Solanum nigrum* grows wild in fields. The berry is considered a tonic and useful in heart disease. *Kanher* *Nerium odorum* is planted in gardens. The root is used as a cure for colic. *Kavandal* *Trichosanthes palmata* is found in the open east. The fruit is used as a fumigatory in purulent discharges from the nose. *Karanj* *Pongamia glabra*. The decoction of the leaves is used in cases of rheumatic pains. *Karda* *Carthamus tinctorius* is grown in fields. The seeds are laxative. *Kárli* *Momordica charantica* is grown in fields. The seed is a cure for worms. *Karmrang* *Averrhoa carambola* is found in most forests. The fruit is cooling in fever. *Karvand* *Carissa carandus* is common in the forests. The berries are useful in minor bilious complaints. *Kásh* *Saccharum spontaneum* is found on the banks of rivers. The root is useful in cases of biliousness. *Kavaskuili* *Dolichos pruriens* is found in the forest. The seeds are nourishing. *Kavath* *Feronia elephantum*, the woodapple, is found in the plain country. The unripe fruit is astringent and used with other medicines in dysentery. *Kavli* *Anodendron paniculatum* is found in the hilly parts of the State. *Kel* *Musa sapientum*, the plantain, is found everywhere. The juice is highly astringent and is used to stop bleeding. *Ketki* *Pandanus odoratissimus* is grown on stream banks and in marshy grounds. The flour is used for cough. *Khad-yánág* *Gloreosa superba* is found in the Konkan. The root is a tonic and alterative. *Khair* *Acacia catechu* is found on the Sahyádrí range. It is of two varieties and its bark has astringent properties. *Kiráit* *Gentiana cherayta* is found in the hilly west. It is a bitter tonic. *Kohla* *Cucurbita melopepo*, the pumpkin gourd, is grown in watered lands. It is considered a tonic. *Kolshinda* *Asteracantha longifolia* is found in water-courses. The seed called *tálimkhána* is valued as a tonic. *Koránti*, of four varieties, is found in gardens. The leaves are used for itch, to counteract poison, and as a cure for coughs. *Korte* *Vernonia anthelmentic* is grown in fields. It is used as a cure for itches. *Kuchla* *Strychnos nuxvomica*, the vomit nut, is found in the Konkan. It is used in cases where strychnine is useful. *Kuda* *Echites antidysenterica* is found in the Konkan and the hilly parts of Kolhápúr. The bark and seeds are a tonic and febrifuge. *Kutki* *Helleborus niger* is found above the Sahyádris. The juice is used in dysentery. *Kuvarphod* *Aloe perfoliata* is found everywhere. The succulent pulp of the leaf is used as a poultice for boils. *Lájálu* *Mimosa sensitiva* is found in fields. A decoction from the roots is used in cases of gravel. *Lasun* *Allium sativum* is grown in gardens. It is used as a cure for colic. *Limbu* *Citrus limonum* is grown in gardens. The juice is cooling in fever, the rind is a stimulant. *Mahálung* *Citrus medica* is grown in gardens. The fruit is used as an aromatic bitter. *Máka* *Eclipta prostrata* is found in water channels. It is applied externally as a cure for scorpion bites. *Manjishta* *Rubia munjith* is found in the open east. The root has alterative properties. *Marva* *Artemisia indica* is planted in gardens and is used as an aromatic tonic. *Máth*

## Appendix B.

## TREES.

## Appendix B.

## TREES.

*Amaranthus tristes* is grown in garden lands. The leaves are a condiment. *Methi* *Trigonella fœnugræcum* is grown in fields. The seed is a tonic. *Mirvel* *Piper nigrum* is found in the Konkan. The fruit is a carminative and stomachic. *Moha* *Bassia latifolia* is found on the Sahyâdri. The bark is used as a medicine and the flowers make a spirit. *Morshenda* *Cæsalpinia pulcherrima* is found in the Konkan and is used in dysentery. *Mûla* *Raphanus sativus* is grown in gardens. The leaves and roots are used as a cure for buboes. *Mundi* *Sphœranthus indicus* is found everywhere. It is used as a cure for swollen glands. *Muradsheng* *Helicteres isora* is used as a fomentation in rheumatism. *Nâgarmotha* *Cyperus pertenus* is common in the fields. The root is used as a tonic. *Nâral* *Cocos nucifera*, the cocoa palm, is found in the Konkan. The water of the unripe nut is used in urinary disorders. *Nigdi* *Vitex trifolia* is found everywhere. The leaves have discutient properties. *Nimb* *Azadirachta indica* is found everywhere in the State. It is of three varieties and its fruit is useful in leprosy. *Nirdung* *Cactus indicus*, of many varieties, is found everywhere. The juice is a strong purgative. *Ova* *Ptychotis ajowan* is sown in gardens. The seed is stimulating. *Pâdal-mul* *Heterophragma chelonivides* is found on the Sahyâdri hills. The root is used as a cooling drink in fever. *Palas* *Butea frondosa* is found everywhere. The flowers boiled in water are used for warm fomentation to the hypogastric region in retention of urine. *Pân* *Piper betel*, the betel vine, is grown in watered lands. The leaves are useful as an aromatic and astringent. *Pâthri* *Elaphantophus scaber* is found in the western uplands. It is used in cooking and as a medicine in fever. *Phanas* *Artocarpus integrifolia*, the jack tree, is found near homesteads and gardens. The bark is used as an antidote for bile. *Peru* *Pesidium guava*, the guava, is grown in gardens and is supposed to cure biliousness. *Pimpal* *Ficus religiosa* is found everywhere in the State. It is of two varieties. The infusion of the bark is given in scabs. *Pimppli* *Piper longus* is found in the Konkan. The fruit and the stem have aromatic properties. *Pimpri* *Hibiscus populneoides* is found everywhere in the State. The bark is used for coughs, cold, and bile. *Pithvan* *Hedysarum lagopodioides* is found in the Konkan. It is a tonic and a cure for colds. *Pittapâpda* *Fumaria parviflora*, of four varieties, is found in the western uplands. It is a tonic and alterative. *Raktarodha* *Suretunia febrifuga* is found on the Sahyâdri hills. The bark is used as a tonic. *Rânmg* and *Rânudid* are found in the forest. The root leaves and fruit of both are used in gonorrhœa. *Ringni* *Solanum jacquini* is found in fields. It is an expectorant and the root is a diuretic. *Ritha* *Sapindus emarginatus* is found in the forest and used as an emetic. *Rosegavat* *Andropogon calamus* occurs occasionally in gardens. The root and oil are used for rheumatic pains. *Rui* *Calotropis gigantea*, of four varieties, is found everywhere. The juice is used in syphilis. *Sâg* *Tectona grandis* is found on the Sahyâdri hill. The seeds are used as a diuretic and the wood is useful to subdue inflammation caused by the marking-nut. *Sâlvân* *Desmodium gangeticum* is found in the Konkan. It is used in fever cases. *Saphedmusali* *Curculigo alba*, and *Dukarkand* grow during the rains in the Sahyâdri hills. The bulbous roots of both plants are used as a tonic. *Sarâte* *Reullia longifolia* is found in the forest. The fruit leaves and root are used in gonorrhœa. *Sâtvin* *Alstonia scholaris* is found in the forests. The bark is a powerful tonic in bowel complaints. *Sâvar* *Bombax malabaricum* is found everywhere: the bark is a cure for syphilis and the juice is called *mochras*. *Shatâvari* *Asparagus racemosus* is found everywhere but chiefly in the Konkan. *Shami* *Mimosa suma* is found everywhere; the fruit and flowers are used in cough. *Sherga*



## Appendix B.

## TREES.

Moringa pterygosperma is found everywhere. A decoction of the root bark is given in cases of stone. *Shikekái* Acacia concinna is found in the forests. The fruit is used as a purgative. *Shiras* Albizzia lebbek is found in the forests on the Sahyádrí range. The flowers are applied to boils and swellings and the leaves are useful in ophthalmia. *Shisav* Dalbergia sisu is found on the Sahyádrí hills. It is used in aborting. *Shivan* Gmelina arborea is found on the Sahyádrí hills. Its decoction is used in bilious fevers. *Supári* Areca catechu, the betel palm, is found in the Konkan. The nut possesses astringent properties. *Suran* Amorphophallus campanulatus, elephant's foot, is found on the Sahyádrí hills. The tuber is a cure for hæmorrhoids. *Tákla* Cassia tora is found in the plain east. The seeds and leaves cure itchy eruption. *Tálimkhána* Asteracantha longifolius, the seed is a tonic and diuretic used in gonorrhœa. *Tamúlpatra* Laurus cassia is found on the Sahyádrí hills. The leaves are used as a spice. *Tándulja* Amaranthus oleraceus is grown on uplands. It is used as an antidote against poison. *Tarvad* Cassia auriculata is found in the western uplands. The bark is used as an astringent and tonic. *Tetu-mul* Calosanthus indica is found on the Sahyádrí hills. It is a bitter tonic and stomachic. *Tivas* Dalbergia ougeinensis is found on the borders of the Sahyádris. The bark is used as a medicine for leprosy and gonorrhœa. *Tondli* Bryonia grandis is planted near homesteads. The leaves and roots are used as a cure for buboes. *Tulas* Ocimum sanctum is found everywhere. The juice of the leaves mixed with limejuice is a cure for ringworm. *Tumba* Leucus cephalotis is found in the western uplands. It is a mild stimulant. *Tut* Morus indica, the mulberry, is grown in gardens; the berries are a cure for biliousness. *Umbar* Ficus glomerata is found everywhere in the State. The bark has astringent properties and used for gargles. *Undin* Calophyllum inophyllum is found in nine of the villages west of the Sahyádris. The bark is used in colds and leprosy. *Unháli* Tephrosia purpurea is found in the plain east. The plant is taken internally as a bloodpurifier. *Uparsál* Ichnocarpus frutescens is found in the forests. The roots are useful in skin diseases. *Us* Saccharum officinarum, the sugarcane, is grown in watered lands. The root is demulcent. *Válcheriche bhát* Cassalpinia digyna is found on the Sahyádris. The root is a strong astringent. *Válu* Andropogon muricatum is found near streams. The root is an aromatic tonic. *Váluk* Cucumis sativus is grown in gardens. The seed is used as a cooling diuretic. *Vángi* Solanum melongena, brinjal, grows in gardens. The fruit is a good tonic. *Vánghkartoli* Momordica dioica grows on uplands. The root is used in hæmorrhoids. *Vardhára* Rearea santatoides grows in wells. The stem is used as a bitter tonic and in diabetes. *Vasu* Boerhaavia diffusa is found in the plain east. It has slight laxative properties. *Vat* or *Vad* Ficus indica, the banyan, is found everywhere. The bark is used as a medicine in cases of cough and bile. *Vávdíng* Embelia rives is found in the Konkan. The berries are a cure for worms. *Vekhand* Acorus calamus, of two varieties, grown in gardens. It is used in bowel complaints. *Velpádal* Hetrophragma chelonioides is found in the Konkan. The infusion from the root is a cooling drink in fever. *Velu* Bambusa arundinacea, the bamboo, is found everywhere. The silicious concretion found in the joints of the female bamboo, called *vansh-lochan*, is useful in cases of cough, consumption, and fever. *Vet* Calamus rudentium. The rattan brayed in cold water is applied to mice bites. *Vishnukránt* is found on the uplands. It is used for worms and to cure wounds.

## APPENDIX C.

## MARÁTHA SURNAMES.

## Appendix C.

MARÁTHA  
SURNAMES.

THE following is an alphabetical list of Marátha surnames<sup>1</sup>:

Adkáre, Ádsul, Ágláve Áhereráv, Alpáte, Antrále, Anvále, Árchale, Ásve, Avalkar, Avtáde; Bábar, Bád, Badad, Bádal, Bágál, Bákar, Bándé, Barage, Barangule, Báte, Bávchikar, Bávdhankar, Bávle, Bedge, Belánde, Bhádirge, Bhagat, Bhákad, Bháme, Bhápkar, Bhátmáre, Bhiláre, Bhingári, Bhiungde, Bhuikar, Bhogay, Bhoite, Bhoj, Bhonsle, Bhor, Bhujbal, Bhujvar, Bicháre, Bichukle, Binikar, Birámne, Bitle, Bode, Bogar, Bokde, Boráde, Bote, Burse; Cháلكhe, Chapte, Chaudhare, Chávat, Chavhán, Chende, Chhatre, Chikhle, Chitruk; Dábháde, Dádhmode, Dáingde, Dalvi, Damde, Dandvate, Daphle, Dasále, Dengde, Devkar, Dhage, Dháigunde, Dhamdhere, Dhanavde, Dhapupse, Dhátav, Dhángde, Dhemre, Dhenkne, Dhere, Dhopre, Dhulap, Dhumál, Dinde, Divthankar, Dodphade, Dongre, Dubal, Dumbre; Gáikvád, Gájre, Garad, Garje, Gavas, Gavli, Gavsekar, Gele, Ghadshi, Gháil, Ghárgé, Ghátge, Ghodke, Gholap, Ghongáne, Ghonge, Ghorpade, Ghugre, Ghule, Ghure, Ghutugde, Gidde, Gije, Gojáre, Gore, Gujál, Gujar, Gunjál; Hagvane, Hajáre, Hándé, Himne, Hinge, Hitápe, Hotále; Ichu, Igrálkar, Indulkar, Ingle, Ingvale, Ipáre; Jádhav, Jagdale, Jagtáp, Jamdáde, Jamedár, Jartáre, Jatápate, Jhámbré, Jinjurte, Jitvadekar, Joshi, Jugdár, Juvekar; Kabáde, Kachre, Kadam, Kákde, Kále, Kámble, Kámekar, Kamte, Kándar, Kándvi, Kank, Kánsare, Kanse, Karle, Karpe, Karvalkar, Káshid, Káte, Káthkar, Káthvate, Kavde, Kembde, Kesarkar, Kesre, Khábkar, Kháde, Khair, Khákre, Khale, Khálvate, Khandágle, Khándekar, Khánvilkar, Kharáde, Khardekar, Khare, Khedar, Khirságar, Khodke, Khokde, Khole, Khopkar, Khule, Kirat, Kirdatta, Kirtekar, Kodag, Kodge, Kokáte, Kolse; Kolte, Kore; Lád, Lagháte, Lágvankar, Lahre, Lakde, Lánde, Lándge, Látvade, Lávand, Laváte, Lombte, Londhe, Lugde, Lungse; Magar, Mahádik, Mahángure, Málusre, Mándavkar, Mándgule, Mandlik, Mándvekar, Máne, Manve, Marde, Márekari, Margale, Maske, Methe, Misál, Mohite, Mole, Morbále, More, Mudade, Mulik, Mundeкар; Nádkе, Nágtalak, Náik, Nalávde, Nalge, Nálhe, Nan-navre, Nátle, Navár, Nigvekar, Nikam, Nimbálkar, Niprul, Nitavde, Nogdand; Páchundkar, Padalkar, Padiyár, Padvale, Págham, Pálav, Pálkar, Pámbré, Pándhre, Pandit, Panhále, Parab, Pátáde, Pátankar, Patháde, Paule, Pavár, Páygan, Pendhári, Phadtare, Phákde, Pharáte, Phasalkar, Phávde, Pimpre, Pingle, Pisál, Pol, Pote, Povle, Punugad; Radtonde, Rájgire, Rájmane, Rakte, Randive, Ráne, Ran-navre, Ransing, Rasál, Ráut, Ravalde, Ravde, Ráyjop, Redekar, Rendálkar, Rote; Sáble, Salgar, Sálím, Sálonkhe, Sálvi, Sangle, Sanmukh, Sánthe, Sárang, Sátal, Satále, Sátpute, Sávant, Saváshe, Seráde, Shankar, Shatphale, Shede, Shelár, Shelke, Shevále, Shinde, Shipalkar, Shirasvade, Shirke, Shitole, Siste, Sole, Somáse, Sonmule, Sonugde, Supal, Supekar, Survasi, Surya; Tadsare, Takekar, Tákvadekar, Támbde, Tanpure, Táte, Tátugde, Távre, Telvekar, Thamke, Thánekar, Thombre, Thopar, Thorát, Thorbole, Thorvat, Tikáde, Tikhe, Tingre, Tipye, Tivte, Todkar, Toraskar, Tore; Uduge, Ukshikar, Undre, Upalkar, Upár; Vádinge, Vádkar, Vágh, Vághmáre, Vagre, Váimde, Válekar, Vónáre, Vánkde, Várange, Velvankar, Vicháre, Vir; Yádav, Yekre, Yevle.

The common Marátha *devaks* or marriage guardians are *dangadi* and *samudramaryáda*, creepers; *vat* Ficus indica the banyan tree; Pankanis fruit; lotus, sun, and *mandár* flowers; *kumbhárkukda* and peacock feathers; *pánchpállvi* or five kinds of leaves, and the edge of a sword.

<sup>1</sup> From materials supplied by Ráv Sáheb Rámchandra Rájáram, State Kárbhári, Miraj Junior.

## APPENDIX D.

## SPIRIT POSSESSION.

IN Kolhápúr a patient is believed to be possessed by an evil spirit if his eyes are bloodshot or bleared as if with drink, if he suffers from shooting pains, if he keeps crying or weeping, if he talks too much, does not speak for days or answers questions by abuse, if he refuses food for days or eats too much and yet feels hungry, if he lets his hair fall loose and sways his body to and fro, if he faints, suffers from cramps, or spits blood.

The people of Kolhápúr divide spirits into two classes, *Gharche Bhut* that is family or house spirit, and *Báherche Bhut* that is outside spirit. The influence of a house or family spirit is confined to the house or family to which it belongs. It is generally the ghost of a member of the family who died with some unfulfilled desire. In appearance and character the ghost resembles the dead person. The leading outside spirits are: *Vetál* the ghost king; *Alvanti* a Hindu woman who died in childbed; *Asra* the water fiend; *Brahma-purush* or *Brahma Samandh* the Bráhmañ ghost; *Chandkái* the child convulser; *Chudel* the pregnant Musalmán woman; *Elmakaltái* the mother of seven sons; *Phirangi* the unquiet European; *Gira* the ghost of a drowned Mhár; *Jakhin* a married Hindu woman who died with some wish unfulfilled; *Khavis* the Musalmán priest; *Kalkái* the mother destruction; *Mhasoba* and *Mhaishásur* the Buffalo spirit; *Mahávir* the great warrior; *Munja* a threadgirt Bráhmañ boy; *Sura* a Musalmán ghost; and *Jhoting* an uneasy low class Hindu. These spirits are believed to live on air, to dwell on trees, near ponds and wells, and at the meetings of rivers and roads. They are much given to wandering at night. When a traveller passes within its reach the spirit takes the form of a man, and suddenly changing to some ferocious animal terrifies its victim so that he is unable to offer any resistance to its attack.<sup>1</sup> *Vetál* is the king of ghosts and spirits. His features and his body are like those of a man except that his hands and feet are turned back. His eyes are a tawny green, his hair stands on end, and he holds a cane in his right and a conch shell in his left hand. *Vetál* lives on air. When he goes his rounds he is dressed in green and either sits in a litter or rides a horse. Some of his spirits walk before and others walk after him, holding lighted torches and shouting.<sup>2</sup> *Alvanti* is the ghost of a Hindu woman who died in childbed. The *Asrás* are seven in number and look like Bráhmañ women. Each wears a dress of a different colour. They generally haunt rivers and ponds, and the person whom they attack runs towards water. They correspond to the Musalmán *parís*. *Brahma Samandh* is the ghost of a married Bráhmañ. He is dressed in a loincloth, a shouldercloth, and a cap. He lives in empty houses, in places where the dead are burned, and on river

## Appendix D.

SPIRIT  
POSSESSION.

<sup>1</sup> Major Graham's Statistical Report of Kolhápúr, 1854, 172.

<sup>2</sup> *Vetál* and his troop seem to correspond with the German Hellequin who in France is called the air-fighting spirit, in Spain the old army, and in England Arthur's Hunt. Compare Grimm's Teutonic Mythology, III, 941-942.



## Appendix D.

SPIRIT  
POSSESSION.

guardian. He does not learn his art but wins the favour of his guardian spirit or god by devotion and the spirit or the god enters the *devrishi's* body whenever he asks him. The *mantri* or charmer generally learns the art of exorcism from a *guru* or teacher. Both *devrishis* and *mantris* are Hindus. Musalmán exorcists are called *vastáds* or teachers. The *vastád* generally learns his charms from a teacher. Both Hindu and Musalmán exorcists are bound to keep certain rules. If, while a Hindu exorcist is eating the lamp in the room gets extinguished, or if he happens to overhear the talk of a woman in her monthly sickness, if any one sweeps in the room or mentions the name of any spirit the exorcist should at once stop eating and fast during the rest of the day. An exorcist must avoid certain vegetables and fruits and must never eat stale or twice-cooked food. A Musalmán exorcist must avoid eating *udid* *Phaseolus radiatus* pulse of which spirits stand in awe and he must not eat flesh or other food cooked by a woman during her monthly sickness.

The Hindu and the Musalmán exorcists take different measures to drive out evil spirits. Both systems are held equally effective. As a rule the Hindu method is used in scaring a Hindu spirit and the Musalmán method in scaring a Musalmán spirit. Most Kolhápúr Hindu exorcists are Guravs or temple ministrants. The exorcists are both men and women, but women are preferred to men especially when an *asra* or water spirit or an *alvantin* or pregnant woman's spirit has to be scared.<sup>1</sup>

Women exorcists are generally possessed by some familiar spirit who tells them the name of the spirit that has attacked the patient and the means by which the spirit can be scared. The first step usually taken is to leave cooked food near the well or river bank where the spirit lives. When the effects of the seizures are not serious the exorcist generally gives a *táit* or small copper or silver box to the patient to guard him against spirit attacks. In the *táit* is a piece of paper inscribed with mystic letters. In some cases a five-coloured silken thread, black, red, yellow, white, and green, is tied either to the patient's arm or neck. The thread has seven knots in which is tied a piece of paper or the bark of the Indian birch or *bhury* tree inscribed with mystic Maráthi or Urdu words. The treatment for scaring family and outside spirits is the same. The following cases illustrate the measures generally adopted for scaring Kolhápúr spirits: (I.) One evening Sita the wife of Rám, a head constable in the Kolhápúr city police, a woman of about thirty-five and six months with child was passing the Paulay pond near the Phirangái temple on the south of Kolhápúr town. As she was passing the pond Sita slipped, fell,

<sup>1</sup> So in Europe in the Middle Ages (A.D. 1100-1600) exorcism and witchcraft were practised more by women than by men (compare Staleybrand's Translation of Grimm's Teutonic Mythology, III. 1039). In explanation of the worldwide preference for witches over wizards Grimm writes: 'To woman, not to man, was assigned the culling and concocting of powerful remedies as well as the cooking of food. Her little soft hand could best prepare the salve, weave the lint, and dress the wound. The restless lives of men were filled with war, hunting, husbandry, and handicraft. To women experience and leisure lent every qualification for secret sorcery. Woman's imagination is warmer and more susceptible than man's and at all times an inner sacred power of divination was revered in woman. Women were priestesses and prophetesses, and the power of sleep-walking still shows itself strongest in women. Fancy, tradition, knowledge of drugs, poverty, and idleness turned women into witches. It seems doubtful whether among early tribes the woman has softer hands or more leisure than the man. The basis of the early belief in women as priestesses, diviners, spirit-scarers, and, after death, as guardian ghosts and goddesses seems to be that women are more liable than men to hysteria and the other nervous seizures whose symptoms are typical symptoms of spirit possession.'

and spilt a basket of cowdung cakes which she was carrying on her head. She got up in haste, gathered the cakes into the basket, and went home. On reaching home she told her husband and the other people of the house of her fall and said she felt much frightened by it. For three or four days she seemed none the worse. On the fifth day when she was in the house some one came to the door and called Sita Sita. She went out, but saw no one. After a few minutes her name was again and again called. This frightened her greatly. She told her neighbours and they advised her not to leave the house. For several days Sita's name continued to be called, and she sometimes thought she saw a figure near the air-hole in the house wall. Tired of listening to her complaints her husband one day stayed at home. To his astonishment he heard the words Sita Sita repeated several times. One day he saw a figure near the air-hole. He was convinced that some evil spirit was haunting his house. Rám made several attempts to get rid of the spirit. He scattered charmed ashes in the house and sprinkled the walls and floor with cow's urine; still the spirit continued to haunt the house and call Sita Sita. This went on for the three remaining months of Sita's pregnancy, during which she grew lean and pale. In due course she was safely delivered of a child. Nothing unusual happened for about fifteen days, when she was suddenly seized with a fit. While lying on her cot she began to say *Hu Hu*, and would answer nothing. Her hands and feet were cramped and she would not suckle her child nor take any care of it. The people thought she was ill and gave her medicine, but the medicine had no effect. They then judged that her sickness must be the work of an evil spirit. They called an exorcist by name Krishna, by caste a Gurav or temple ministrant. The exorcist came, ordered fire to be brought, and setting it before Sita dropped some incense on it, held Sita's head over it, and began repeating incantations. After a few minutes Sita, or rather the spirit in Sita, began to speak in Hindustáni. She said: 'I will not go, I will keep the woman for myself.' The Gurav took two small pieces of paper, drew on them a rough sketch of Vetál with his cane and his conch shell, repeated charms, and near Sita's face burnt the pieces of paper on which Vetál was drawn. On this Sita said 'Don't do that, don't use your charms, I am leaving the woman. I am a Pardeshi sepoy. I was a soldier in the twenty-seventh Regiment and was killed when the regiment mutinied. I saw the woman passing the Paulay pond and I wished to take possession of her. I made her fall and I often came to this house and called her by her name. I am now leaving her. Give me a dinner of rice, wheat bread, clarified butter, and plantains, and lay them at the place where Sita fell.' When she, or the spirit in her, had done speaking, Sita rose from her cot, went out of the house, laid her head on the ground, and the spirit left her. The Gurav ordered four lemons, charmed them, and tied one of them in a corner of the woman's robe and told her husband to see that the lemon was kept tied to her robe till she was well. The other three lemons were buried each in front of one of the house-doors. When this was done Sita went back into the house and fell exhausted on the cot. After a day or two she began to improve and in about a week was well. Her husband prepared the rice, wheat, butter, and plantains which the spirit had asked for and laid them near the spot where Sita had fallen, and the soldier never again troubled her. (II.) About eight years ago a tailor named Govind, about thirty-five years old, was bringing his wife from her father's house to Kolhápúr. Tired by the journey they sat on a river bank to rest. While resting Govind saw something round his wife's neck. He asked her what it was and she said that it was a *táit* or charm given to her by a wise man as a guard against spirits. Govind laughed, took off

## Appendix D.

SPIRIT  
POSSESSION.

## Appendix D.

SPIRIT  
POSSESSION.

the charm, beat it with his shoe, split it in pieces, and threw the pieces into the river. When they reached Kolhápúr, Govind began to talk nonsense, ran into the street, and showed signs of madness. Several medicines were given him but with no effect. After several days had passed a Musalmán exorcist named Shaikh Muhammad was called. Govind was brought and made to sit before the exorcist. Shaikh Muhammad took a piece of paper, drew a rectangular figure on it, divided the rectangle into several small spaces by drawing lines across it and, except one space which he marked with a dot, filled them all with numbers. Govind was shown the paper and was told to look at the space which was marked with the dot. No sooner did Govind look at the dot than the spirit in him said: 'I was asked to guard this woman and was placed in a *táit* or charmed box tied round her neck. This man took me out, beat me with his shoe, and threw me into water. I will never leave the man who has thus insulted me.' The exorcist then took five pieces of paper, wrote mystic letters on them, set them on five pieces of cloth, and made them into rolls. These rolls he lighted in front of Govind and when the smoke entered his nose Govind cried 'I am willing to leave this man.' The spirit was asked what he would like to have. He said, 'Lay some brandy, green tobacco, and the liver of a goat near the river in which the *táit* was thrown, and I will never again trouble this man.' They did as he wished and Govind was cured.

When the exorcist fails to effect a cure, the patient is generally sent to Narsoba's Vádi, three miles south of Shirol, which is sacred to the god Dattátreya. There he daily bathes in the sacred Krishna, pours water over the god, reads or listens to sacred books, and walks many times round the temple. At the time of the *dhupáriti* or incense-burning and lamp-waving, the patient is seized with convulsions and begins to sway to and fro. The spirit then generally agrees to leave him. The patient is taken to the river, bathes in the holy water, and the spirit leaves. In some cases the spirits are very hard to get rid of. The patient remains at Narsoba's Vádi for months, spending the time in the service of the god. When the god Dattátreya is pleased with the patient's devotion he appears to him in a dream and tells him to perform certain ceremonies or to go home and take medicine, as his illness is a bodily disease and is not caused by spirit possession. If the patient is a Musalmán he goes either to the village of Shirváda where is a tomb of the saint Chánd Sáheb or to Karadgaon where is a tomb of the saint Bangalish. At either of these places the patient gives much of his time to the service of the saint. He bathes early, kneels before the saint, walks round his tomb, and goes home. When he has continued doing this for a number of days the spirit suddenly shows itself. The patient stands near a post as if tied to it, cries aloud 'Don't beat me, don't burn me, I am going.' The patient is at once taken to a river, bathes in it, and the spirit leaves him. The patient feeds Musalmán ascetics, presents the saint's tomb with clothes, and goes home. Though the learned among them profess to disbelieve in spirit attacks most Jains and Lingáyats are little less subject to spirit seizures than the corresponding classes of Bráhmanic Hindus. Among all three sects the belief in spirit seizures among men of the higher classes is said to be growing weaker, but among high class women it is still strong. Among Maráthás, Kunbis, and other middle and lower classes the belief in spirit seizures is universal. Among Musalmáns as among Hindus some of the best informed and the strictest in faith profess a disbelief in spirit possession. But the opinions of the mass of Muhammadans is much the same as the opinion of the mass of Hindus except a few learned Jains and Lingáyats. Whenever any illness baffles the skill of the physician its origin is ascribed to spirit possession. The only class of Kolhápúr



Hindus who profess not to believe in spirits is a sect of Vithoba's devotees called *Málkaris* or wreath-wearers. Even these wreath-wearers in all cases of unaccountable sickness secretly resort to spirit-scarers.

The diseases which in Kolhápur are generally believed to be spirit seizures are fever, pain in the hands and feet, pain in the stomach, loss of appetite, hiccough, and any sudden or unusual illness. The belief in spirit attacks has of late years been declining. The people say that some of the most dreaded spirits have disappeared, the *Brahmapurush* and the *Munja* that is the Bráhmaṇ ghosts, because they will not visit a place where cow-killing is allowed and the *Khavis* or Musalmán ghost because he will not visit a place where pig-eating is practised. Only the low class spirits are left and their power is not what it was.

**Appendix D.****SPIRIT  
POSSESSION.**

## APPENDIX E.

TRANSLATION<sup>1</sup> OF THE TWENTY-FOUR PERSIAN  
INSCRIPTIONS OF PANHÁLA.

## Appendix E.

*No. 1. In the enclosure of the Shrine of Pir Sád-ud-dín (Sádoba),  
evidently brought from one of the gates.*

A.H. 806.

Oh friend listen to the voice of the assembly. The able man Sikandar converted the hill into a road and named the Sikandar bastion with this date. It informs one of 806 with a golden call.

*No. 2. In the Andhár Báv at Panhála.*

A.H. 909.

In Panhála at the commencement of his rule, may God increase his prosperity, good fortune, and rank. This will remain as a glorious memorial of him. Now A.H. 909 Abú Yúsúf is the official entrusted with the construction of this work. The cause of this building being the best of its day is this, that this lofty building was completed in the reign of the king of the age, Adil Sháh. A bastion, a reservoir, and this building were constructed (as it were) on the heads of the black-eyed damsels of Paradise. A life-giving spring flows from its reservoir, and they<sup>2</sup> placed it on the shelf (as it were) of a palace, by the order of a man of high and excelling rank. With victory, with happiness, and excellence, this was brought into sight.

*No. 3. Epitaph on a Tombstone in Sád-ud-dín's Enclosure.*

A.H. 915.

The death of Ab-dul-Razzák. May the mercy of God rest on him. A.H. 915.

*No. 4. Inscription from the Somála Pond.*

*Central portion of the Inscription.*

A.H. 917.

If you wish (to ascertain) the date of (the building of) this pond and the name of its builder, ask me in an excellent manner. Its date is 'The gate of a pond of Panhála (Bab Houze Panhála).' Malik Iskandar is the constructor thereof.

NOTE.—The date 917 is found in the words 'Bab Houze Panhála' according to the system of numeral computation.

*On the border of the Stone.*

In the time of the just Sultán, Sultán Mahmud Sháh Bahmani. May God, whose name be exalted, preserve his country and rule. In the days of the rule of Adil Khán Gházi, may the days of his good fortune be prolonged, the construction of this pond was carried out at the suggestion of Malik Haidar Iskandar Bahádari. May his prosperity be eternal.

*No. 5. In Sádoba's Dargáh Enclosure.*

Epitaph,  
A.H. 919.

The death of Shekh Ibráhim. On him be the mercy of God. A.H. 919.

<sup>1</sup> By Colonel J. W. Watson, Acting Political Agent, Kolhápúr and Southern Marátha Country.

<sup>2</sup> 'They' refers to the damsels of Paradise. They are represented as it were bearing the reservoir on their heads as native women carry their water vessels and placing it on the shelf of the 'lofty' place' instead of on the shelf for water, in the usual native house.

*No. 6. Outside the Tin Darwázah.*

In the reign of Ali Sháh of exalted rank. A ruler of the world of the dignity of Jamshid, and resembling him in justice and honor.

Abu Aka Saud built this bastion, who was at that time the governor of this place. As to the year of its date a clever man said, the bastion is so lofty that the air of the mountain summit hath become a pathway for the horsemen.

A.H. 934 is found in the words 'Bagúft ála buruj Jui Kohpá aswâr.'

*No. 7. On the Tin Darwázah.*

In the name of God, the compassionate, the merciful. This sentence is the key of the gate of the treasury of the ruler (God). The rebuilding anew of the fortress of the seat of government Panhála, took place in the days of the rule of my Emperor the Protector of the world, in the kingdom of Panhála, Ibráhim Adil Sháh. May God preserve his kingdom. In the date of the year A.H. 954. In the administration of Malik Daud Aka who was deputy governor during the absence of the Emperor. Inscribed by Salar son of 'Ahmad the minister.'

*On the border of the above.*

Such a building there is not anywhere on the face of the earth. The water which is in this well is not inferior to the pure water<sup>1</sup> of Paradise. Whoever drinketh of it, saith this :

May the mercy of God rest on the builder of this structure, for nothing can be better than it.

The carver hath inscribed on stone these words :

The world will not keep faith. Be thou happy. You should not plant the tree of grief in your heart and always read thou the book of pleasant meaning. You must eat and carry on affairs.

It is clear how few days we can stay in this world. The builder and digger of this water supply was Daud Aka.

*No. 8. Inscription at the Nág Jhari.*

The mountain and the heavenly vault have met together and opened thence a hundred fountains. Many have come and gone, but this fountain and hill have remained in their place. In the time of Ibráhim Adil Sháh, A.H. 955, Daud Aka built this.

*No. 9. Over the Spring in Sádoba's Pond.*

In the name of God, the great artificer and dispenser of justice, who bringeth forth sweet water from the rock. In the reign of the king of kings with (all) glory. The victorious Ibráhim the chosen king. As to the construction which you see of this excellent reservoir, it was built by Malik Khidr chief Khawás. It was in the date A.H. 964 that this spring became a memorial of Khidr. Oh God preserve this for ever, for the sake of the Prophet and Ali : upon them be peace.

*No. 10. At the Chár Darwázah.*

In the name of God, than whom in every place there neither hath been nor will be any other than that God. In the reign of the king of kings, king Ali, this bastion was built by the power and grace of God. It was built by Shams-ud-din chief of the cavalry, who was at that time deputy governor. He built this one bastion to the fort by expending treasure. In the year A.H. 985.

## Appendix E.

A.H. 934.

A.H. 954.

A.H. 955.

A.H. 964.

A.H. 985.

<sup>1</sup> This is a quotation from the Kurán. The actual words in the inscription are only 'the pure water,' but the passage in the Kurán is descriptive of that water of Paradise.



## Appendix E.

No. 11. *On a stone near Ambábái's Temple originally from the Tiger Gate.*

A.H. 987.

The Lion of God, the victorious one, Ali son of Abi Tálib Ahmad Ali, who hath the title of Shams-ul-mulk, is in heart and soul the slave of that Ali.

*On a separate stone.*

The date of the building of this bastion was A.H. 987.

No. 12. *In the Shrine of Sádoba, brought evidently from one of the gates.*Shahur San,  
994.

In the reign of the victorious Ibráhim Adil Sháh. His servant was Maksud Aka, and he built a gate of the Panhála fortress, in the date of the year Shahur San 994. The inscriber of this was Maláz Ghufrán.

No. 13. *Inscription at the Sajjah Kothi.*Shahur San,  
1008.

In the reign of Ibráhim Adil Sháh of handsome face, a heart-delighting palace was built on the summit of the terrace of the fortress. In breadth one *nauras* by two *nauras* in height. Maksud Aka built this charming dwelling. In Shahur San 1008 in the month of Rajab this excellent mansion was constructed. Oh Lord! King of Heaven! may this pure palace last for ever.

No. 14. *In the Mosque at Ibráhim Purah.*Shahur San,  
1021.

It is the saying of God, may He be exalted, 'And in truth mosques are the property of God.' Do not pray to any other but God (within them). In the time of Ibráhim Adil Sháh, the warrior in the line of battle, occurred the building of the mosque and its reservoir of water. It was built by Maksud Aka, and completed in Shahur San 1021 in the month of Rajab. The inscriber of this was Maláz.

No. 15. *In the enclosure of Sádoba's Dargáh (evidently from one of the gates.)*

A.H. 1088.

This gate recalls to remembrance the year A.H. 1088. From it (flows) a stream which forms a pond. At that place is a wonderful shrine. This was a place of resort of Khidr Muhammad son of Farid-ud-din Khán Sálár.

No. 16. *Near the Kázi's house.*

Call upon Ali the object of the (divine) wonders. Thou wilt find him an aid to thee in trouble; and every grief and sorrow will be dissipated owing to thy grace. Oh Ali! oh Ali! oh Ali!

No. 17. *Near the Barah Imám.*

*Three lines remain of a quatrain.*

I have not seen that its like hath been in the world. In the reign of king of kings of pure religion; a chosen sovereign like Ali Bádshah.

No. 18. *Near the Choki of the Chár Darwázah.*

Oh thou opener of gates! (i.e. God).

No. 19. *In the enclosure of Sádoba's Dargáh.*Epitaph evidently  
on a beloved child.

The coolness of my eyes, the fruit of my heart. He called into existence until he had need of him and thus He made affairs grievous to me.

No. 20. *In the enclosure of Sádoba's Dargáh.*

Epitaph.

Everything (earthly) perisheth, God alone remaineth for ever.

No. 21. *In the enclosure of Sádoba's Dargáh.*Epitaph evidently  
over a son born  
after several years  
of childless married  
life.

A bulbul drank the blood of a heart,  
And thereby gained a rose.  
He spent a hundred years of misery  
In grief over his memory.

*No. 22. In the enclosure of Sádoba's Dargáh.*

Whoever places his foot near my dust may the black-eyed damsels of Paradise be a reward to him for his journey. Oh beloved one when thou fatiguest thy foot by visiting me, sit for a short time by the dust of this poor one.

*No. 23. In the enclosure of Sádoba's Dargáh.*

Recite for me the Fatihah with willing breath,  
For no utterance can be better than that.  
The waftings of the blessings of the breath of Jesus  
Have made my tomb redolent with the odour of roses and sweet basil.

NOTE.—The Fatihah is that portion of the Kurán recited by Muhammadans over the dead. It is the first chapter.

*No. 24. On the Chár Darwázáh.*

Oh God bless Muhammad and the family of Muhammad and give them peace, and bless all the prophets and messengers of God. Praise be to God, Lord of both worlds.

**Appendix E.****Epitaph.****Epitaph,**





# INDEX.

## A.

**Abdul Karim** : Bijápur general (1674), 314.  
**Abdul Waháb** : Arab reformer (1700-1800), 150.  
**Ábu** : pond, 12.  
**Age details** : 37-38.  
**Agriculture** : husbandmen, seasons, crops, arable land, holdings, stock, field tools, field operations, manure, irrigation, rotation, fallows, crop details, famines, 153-191.  
**Agya** : see Kolambi.  
**Aitan** : Lingáyat initiation ceremony, 129.  
**Ajra** : forest block, 22, 23 ; town details ; position, people, imports, exports, weekly market, history, temples and fair, 290-291.  
**Ajurica** : old name of Ajra, Somdev composed the *Shahdárnav chandrika* at, 223.  
**Akka Nágamma** : Basav's (1100-1168) sister and Vijjal's wife, 119.  
**Alam Prabhu** : temple at Alta, 292.  
**Ali Adilsháh II** : king of Bijápur (1656-1672), gives Bávda in *jágir* to Nilo Sondev, 293.  
**Allá-ud-din II** : tenth Bahmani king (1435-1457), 224.  
**Alta** : survey details, 256 ; town details, market, school, temples, mosque, 291-292.  
**Amba** : pass, 5.  
**Ambábái** : temple of, description, inscriptions, pilgrims, temple holidays, 309-311.  
**Ambardi** : stream, 9.  
**Ambira** : stream, 9.  
**Ambis** : watermen, 104.  
**Amboli** : pass, 5, 6.  
**Anaskura** : pass, 5.  
**Anderson** : Colonel G. S. A., Political Agent (1867), 254.  
**Ándhrabhritiyas** : early Deccan kings (B.C. 90-A.D.300), 218.  
**Appáji Suru** : founder of the Rámdurg State, 397.  
**Arable land** : 156.  
**Arag** : village, temples, monastery, fair, 292-293.  
**Arálaya** : progenitor of Chámhbárs, 109.  
**Asandoli** : forest block, 22, 23.  
**Asheg** : holiness of, 125 note.

**Aspect** : outlying belts, hill-top Konkan, plain, 2-4.

**Atárs** : perfumers, 86, 148.  
**Atigre** : pond, 12.  
**Aurangzeb** : Delhi emperor (1658-1707), 147, 148, 226-227, 361-362.  
**Avlingva** : Lingáyat monastery at Shirhatti, 369-371.  
**Avliya** : Musalmán saint, 318.  
**Ayyansing I.** : see Gandaráditya.  
**Ayyansing II.** : see Vijayáditya.

## B.

**Báburáv Keshav Thákur** : builds the Káttyáyani conduit (1792), 305.  
**Bahádur Giláni** : Bahmani officer (1486), being instigated by Yusuf Adilkhán of Bijápur seizes Goa, Kolhápur, and other places ; sends expedition against Bombay, seizes vessels from Gujarát ; his conduct excites the anger of Mahmud Begada (1459-1511) king of Gujarát, who sends (1493) an embassy calling on the Bahmani king to punish his rebellious vassal ; failing this Begada threatens the king with an attack ; thereupon Máhmud Sháh II. marches against Bahádur Giláni who makes offers of submission, but again commences hostilities ; takes refuge in Panhála and is killed in an action with the royal troops, 225.  
**Bahirgad** : fort, 4.  
**Baidarus** : see Berads.  
**Bairágis** : beggars, 115.  
**Báji Ghorpade** : Mudhol chief (1649), 393-394.  
**Báláji Bájiráv** : third Peshwa (1740-1761), 290.  
**Baldev** : Basav's (1100-1168) father-in-law, 119.  
**Bálinge** : village, temple of Káttyáyani, 293.  
**Ballál** : Siláhára king, inscription of, 221.  
**Balutedárs** : 41, 42.  
**Balvantráv** : Mudhol chief (1856-1862), 395.  
**Banhatti** : trading village, markets, 388.  
**Bápu Gokhale** : Peshwa's general (1817), 348, 394.  
**Barutgars** : Musalmán firework makers, 148-149.  
**Basav** : founder of the Lingáyat faith (1100-1168) 97 ; his early life, 119 ; his religious doctrines, 120.

**Bánda** : hill fort, 4, 5 ; history, 293 ; hill pass, 5 ; village, British Resident's office ; Native Infantry camp, schools, market, fairs, 294.

**Bedars** : see Berads.

**Beggars** : 115-118.

**Beldárs** : pickaxe men, 93.

**Berads** : 104-105.

**Bhádara** : forest block, 22, 23.

**Bhádoli** : village, temple, tomb, 294.

**Bhagvánlál** : Dr., 81.

**Bhairavgad** : hill fort, 5.

**Bhandáris** : distillers, 105.

**Bhándárkar** : Professor R. G., 81, 306.

**Bhangis** : nightsoil men, 109.

**Bháts** : bards, 100.

**Bherla** : wild sago palm, 24.

**Bhim Bahádur** : Kolhápur Sardár (1804-1805), 189.

**Bhimságiri** : group of temples, 294.

**Bhogávati** : stream, 9, 10.

**Bhois** : fishers, 105.

**Bhoj I** : Siláhara king (1098), 221.

**Bhoj II** : Siláhara king (1178-1209), Rája of Panhála, his inscriptions, extension of his territories, building of hill forts, his subjugation of hill tribes, 223 ; makes Kolhápur his capital, 307, 314.

**Bhudargad** : hill fort, 7 ; position, temples, history, 294-295.

**Bhudargad-Nipáni** : hill range, 7, 9.

**Bid** : village, temple, inscription, 10, 295.

**Bijjal** : see Vijjal.

**Bills** : 192-193.

**Birds** : 34.

**Births and Deaths** : 289 ; ceremonies, 46-48, 60, 72, 80, 91, 114, 128, 131, 132, 144-146.

**Blights** : 187, 188.

**Bohorás** : Musalmán traders, 150.

**Borrowers** : 194, 195.

**Boundaries** : 1.

**Bráhmans** : 43-64.

**Brahmapuri hill** : temples in honor of the deceased members of the royal family at, 312.

**Bricks** : 21.

**Bridges** : 8, 10, 202.

**Buddhists** : 152.

**Budgaon** : town details, palace, 383.

**Budkis** : holes in river beds, 12, 161, 177.

**Building stone** : 19.

**Bulb vegetables** : 180, 181.

**Buruds** : basket makers, 93-94.

## C.

**Capital** : 192.

**Carriers** : 206.

**Carts** : 159.

**Cattle** : feed of, 27 ; keeping, 28, 30 ; diseases, 288, 289.

**Census details** : 35-40.

**Cereals** : 164-168.

**Chálukyas** : see Western Chálukyas.

**Chámbhárs** : leather-workmen, 109-110.

**Chandgad** : hill fort, 7.

**Chandramil** : old town, 219.

**Changes** : in the system of dispensing justice, (1848), (1862), (1867), (1873), (1874), (1882), 268, 270.

**Chhatris** : husbandmen, 88.

**Chikhli** : village, market, school, 296.

**Chikotra** : feeder of the Vedganga, 11.

**Chima Sáheb** : brother of Shiváji IV. (1837-1866), 243.

**Chinchli** : cattle fair at, 25, 27 ; village, temple, 296.

**Chintámanráv** : Chief of Sáugli (1800), helps Colonel Wellesley against Dhundiya Vágh, 348 ; helps in suppressing the rebellion of 1844 ; his death (1851), 350, 352.

**Chinto Rámchandra Phadnis** : leads (1800) the small garrison of Ajra against Harpávda and Bellevádi and storms Ibráhipur, 290.

**Chitpávans** : Bráhmans, 43.

**Chitri** : tributary of Hiranyakeshi, 11.

**Christians** : 151-152.

**Cholera** : 285-286.

**Chudbudke Joshis** : hourglass drum astrologers, 115-116.

**Climate** : 15-16, 285.

**Coloured earth** : 21.

**Communities** : 40-42.

**Copper** : 207-208.

**Courts** : civil, 270-272 ; criminal, 273.

**Craftsmen** : 93-100.

**Crops** : 156-157 ; rotation of, 163-164 ; details, 164-187.

**Currency** : 192.

## D.

**Dáji Pandit** : State Kárbhári, Kolhápur (1838-1843), 242 ; revenue and judicial system under, 247-248, 310, 319.

**Dámáji Pant** : revenue officer at Mangalvedha under Bedar kings (1347-1489) ; tradition of, 361 note 1.

**Dambal** : a great Buddhist temple at, 120 note.

**Dángs** : 21.

**Dantidurg** : see Dantivarma II.

**Dantivarma II** : Ráshtrakuta king (753), 219.

**Dari Pir** : fair in honor of, 298.

**Dásris** : musicians, 100.

**Daulatráv Síndia** : (1795-1827), 234, 235, 299.

**Dayris** : *Daur* drum players, 101.  
**Delamotte** : General, English commander (1844), 295, 315, 319.  
**Depressed Classes** : 109-115.  
**Description** : 1-17.  
**Deshasths** : Bráhmans, 43-60.  
**Devaks** : family guardians, 66, 95, 130 ; worship of, 75-76, 414.  
**Deváangs** : class of Koshtis, 95.  
**Devda** : hill path, 5.  
**Devgiri Yádavs** : early Deccan kings (1180-1300), 218.  
**Devrukhás** : Bráhmans, 60-61.  
**Dhangars** : cow-men, 24, 27-28, 103.  
**Dharmaráj** : temple dedicated to, 301.  
**Dhayads** : iron smelters, 18.  
**Dheguji Meghuji** : Cloud of Clouds, name of the Teacher of Mhárs, 114.  
**Dhondo Pant Gokhale** : Peshwa's Sarsubhedár in the Karnátak (1795), 347-348.  
**Dhors** : tanners, 110-111.  
**Dhundiya Vágh** : freebooter, defeated and killed (1800), 348.  
**Dhundiráj Tátya Sáheb** : Chief of Sângli, 352.  
**Digraj** : village, temples, mosque, 359.  
**Diksha** : purification ceremony among the Lingáyats, 129.  
**Diseases** : 285.  
**Dispensaries** : 288.  
**Dodvád** : town details, history, wells, fort, 359-360.  
**Dombáris** : tumblers, 31, 116.  
**Dombingaon** : see of Dheguji Meghuji, 114 note.  
**Domestic animals** : 25-31.  
**Dravids** : Bráhmans, 61.  
**Dress** : 44-45, 61, 67-69, 88, 89, 116, 125.  
**Dudhganga** : river, 8, 10-11.  
**Dukalvals** : begging bards, a class of Mángs, 111.  
**Dvarkábái Sáheb** : temple dedicated to, 301.  
**Dyes** : 172-173.

## E.

**Earth** : 208-210.  
**Elphinstone** : Mr. Mountstuart, British Resident at Poona (1811-1818), 349.  
**Epidemics** : 285-287.  
**Exports** : 207.

## F.

**Fairs** : 205-206.  
**Fallows** : 164.  
**Family gods** : 44, 62, 63, 91, 97, 99, 100, 101, 105, 106, 111, 127.  
**Famines** : (1876-77), 188-191.  
**Fasts** : Kunbi, 92.

**Fergusson** : Sir James, Governor of Bombay, (1883), 296.  
**Ferishta** : Muhammadan historian (1550-1611), 308.  
**Ferries** : 8-11, 201.  
**Firoz Sháh** : Bahmani king (1397-1422), establishment of the Musalmán power in Kolhápúr before the reign of, 224 note 1.  
**Fibre Plants** : 171-172.  
**Field Tools** : 157-159.  
**Fighting Classes** : 65-86.  
**Fish** : 34.  
**Fleet** : Mr. J., 81, 306.  
**Forests** : 21-25.  
**Forest Tribes** : 24.  
**Fruit** : trees, 184-187 ; vegetables, 181-182.

## G.

**Gádayli** : feeder of the Kására, 9.  
**Gadinglaj** : survey details, 263 ; sub-divisional headquarters, position, people, fort, temples, fair, 296-297.  
**Gái Kasábs** : Musalmán beef butchers, 150.  
**Gandaráditya** : Siláhára king (1109-1136), his inscriptions, 221.  
**Gandharvagad** : hill, 8.  
**Gang robberies** : 274.  
**Garbhádhán** : conception ceremony, 58-59.  
**Gargoti** : town, market, school, 297.  
**Gárudis** : snake charmers, 111, 116.  
**Gavandis** : masons, 94.  
**Gavlis** : cow-keepers, 103.  
**Geology** : 13-15.  
**Ghadshis** : musicians, 101.  
**Ghatprabha** : river, 8, 9, 11.  
**Ghisádis** : tinkers, 106.  
**Ghotge** : hill pass, 6.  
**Ghunki** : village, old military station, 297.  
**Ghumat Shirol** : see Shirol.  
**Glass** : 210.  
**Godchi** : village, temple, fair, 297.  
**Golaks** : Bráhmans, 61.  
**Gold and Silver** : 207.  
**Gomati** : sacred stream, tributary of the Panch-ganga, 10.  
**Gondhal dance** : 116-117.  
**Gopál Pant Ápte** : Chief of Ichalkaranji, 295.  
**Gopáls** : Mhárs beggars, 117.  
**Gori Sáheb Pir** : tomb of, 297.  
**Gosávis** : religious beggars, 117-118.  
**Gotras** : family stocks, 44.  
**Graham** : Major, 250, 307, 310, 315, 415, 416, 417.  
**Gudgeri** : town, 383.  
**Gugul** : gum ceremony among the Lingáyats, 129-130 and note.



**Gujarát** : Bráhmans, 61-62 ; Vánis, 86.  
**Guravs** : Lingáyat priests, 101.

## H.

**Haidar Ali** : Maisur king (1763-1782), 150, 345.  
**Hajáms** : see Nhávis.  
**Hajrat Ráje Bágh Savár** : see Avliya.  
**Halad Kunku** : turmeric vermilion ceremony, 57-58.  
**Halsi** : see Palásika.  
**Hanbars** : cattle-keepers, 94.  
**Haran Shikáris** : stag hunters, 31.  
**Hartálika worship** : 56-57.  
**Hanmant** : hill pass, 6.  
**Harbhat bin Bálambhat** : founder of the Patvardhan States (1714), 343.  
**Hariáli** : grass for cattle, 27.  
**Haripur** : sacred village, 383.  
**Hátkalangda** : tributary of the Panchganga, 10 ; head-quarters of the Alta sub-division, local legend, fair, tomb of Gori Sáheb Pir, temples, inscriptions, 297.  
**Hatkars** : class of Koshtis, 95.  
**Healing Plants** : 409-413.  
**Heat** : 17.  
**Herla** : village, old military station, temples, inscription, 298.  
**Hills** : 4-8.  
**Himmat Bahádur** : Kolhápúr Sardár, 189, 299, 303.  
**Hinduráv Ghátge** : (1813), builds a new fort at Kágál, 300.  
**Hippokura** : old name of Kolhápúr, 218.  
**Hiranyakeshi** : river, 8, 9, 11.  
**Holdings** : 156.  
**Holidays** : 71, 88, 92, 108, 138.  
**Honey** : production of, 24-25.  
**Hospital** : Kolhápúr civil, 287, 288.  
**Houses** : 39.  
**Human sacrifices** : 230-231, 314.  
**Hunnur** : village, 388.  
**Hupri** : village, market, temples, fair, 298.  
**Husbandmen** : 88-93, 153-155.

## I.

**Ibráhim Adil Sháh I** : Bijápúr king (1534-1557), 314.  
**Ichalkaranji** : survey details, 254, 255 ; town details, temple, mosque, fairs, 298.  
**Imports** : 206, 207.  
**Infirmities** : 37.  
**Inscriptions** : Panhála, 422-425.  
**Instruction** : 281-284.  
**Insurance** : 192.

**Interest** : rates of, 194.

**Iron** : ore, 18 ; process of smelting, 18-19, 208.

**Irrigation** : 161, 162.

## J.

**Jacob** : Sir LeGrand, Political Agent (1858), 308.  
**Jails** : 276, 277.  
**Jains** : strength and distribution ; Púrasnáth and Mahávir saints, doctrines, daily life, religion, customs, 133-146.  
**Jámbhli** : feeder of the Kásári, 9.  
**Jamkhandi** : State, description, production, people, agriculture, capital, trade, justice, finance, health, instruction, health, places, 386-388 ; town details, trade centre, temple, fair, 388.  
**Jayanti** : sacred stream, tributary of the Panchganga, 10.  
**Jayasinh III** : Western Chálukya king (1024), 219.  
**Jews** : 152.  
**Jijibái** : widow of Sambháji II. (1712-1760), and regent (1760-1772) of Shiváji III. (1760-1812), 230-231.  
**Jingars** : saddle makers, 94.  
**Jiti** : see Jayanti.  
**Jotiba's hill** : 20 ; position, temples, holy pools, fairs, 299, 300.  
**Justice** : civil, criminal, 266-268.  
**Jvári** : cultivation of, 166-167.

## K.

**Kabnur** : see Hátkalangda.  
**Kadamb**s : early Deccan kings (500-550), 218.  
**Kadvi** : feeder of the Várna, 9.  
**Kágál** : survey details, 255-256 ; town details, fort, history, temple, fair, 300-301.  
**Kágzis** : Musalmán paper makers, 149.  
**Káhárs** : class of Bhois, 105.  
**Kaikádis** : basket makers, 107-108.  
**Kájirda** : hill pass, 5.  
**Kaláls** : liquor-sellers, 106.  
**Kále** : village, local legend, temple, 301.  
**Kállamma** : Jain deity, 95.  
**Kalyán** : seat of Vijjal (1156-1167), Jain king of the Kalachuri family, 119.  
**Kánsa** : feeder of the Várna, 9.  
**Kanauj** : Bráhmans, 62.  
**Kándra** : stream, 9.  
**Kaneri** : village, Lingáyat monastery, temple, 301.  
**Kanheri** : seat of Sidhgiri in Sátára, 94.  
**Kánta** : variety of honey bee, 24, 25.  
**Kánvs** : sect of Mádhyaandins, 62.  
**Kápshi** : valley, 11 ; town, temple, mosque, 301.  
**Káranjkars** : see Jingars.  
**Karhádas** : Bráhmans, 62.

**Karvir** : ancient name of Kolhápúr, 1, 306 ; survey details, 257-260.  
**Kásarde** : village, temple, legend, 302.  
**Kásári** : stream, 9, 10.  
**Kásárs** : bellmetal smiths, 95.  
**Katkol** : hill, 4 ; temples, monastery, fair, 302.  
**Kavandanyapur** : old name of Kavlápúr, 360.  
**Kavlápúr** : village, temples, 360.  
**Kavtha** : village, temples, 383.  
**Káyasth Prabhus** : writers, 64.  
**Khadki** : local breed of bullocks, 25.  
**Khánápúr-Mudhol** : hill range, 7.  
**Khátiks** : butchers, 106.  
**Khatris** : weavers, 95.  
**Khelna** : hill fort, 4.  
**Khidrápúr** : village, temples, inscriptions, fair, 302-303.  
**Khodsi** : village, temple, fair, 303.  
**Kilegaon** : village, fair, 383.  
**Kini** : village, temples, 303.  
**Kodoli** : village, weaving industry, temples, fair, 303.  
**Kolambi** : variety of honey bee, 24.  
**Kolhápúr** : origin of the name of, 1 ; old historic place, 218, 306 ; see of Dheguji Meghuji, 114 ; town details, area, and boundaries, aspect, climate, water-supply, 303-305 ; history, 306-308 ; municipality, schools, 309 ; temples, Ambábái's, 310, Vithoba's, Temblái's, 311 ; Mahákáli's, Phirangái's, Ellamma's, underground shrines, monasteries, 311-312.  
**Kolhápúr Rájás** : genealogy of, 246.  
**Kolhápúr Siláháras (1055-1125)** : 218-223 ; family tree of, 220.  
**Kolhátis** : see Dombáris.  
**Kolis** : ferrymen, 106-107.  
**Kolsunda** : wild dog, 32.  
**Komtis** : traders, 86, 87.  
**Korvis** : basket-makers, 31, 108.  
**Koshtis** : weavers, 95.  
**Krishna** : river, 8, 9, 11.  
**Kudaldámvád** : old name of Kurandvád, grant at, 223.  
**Kumbhárs** : Marátha and Rajput potters, 95-96.  
**Kumbhi** : stream, 9, 10.  
**Kumbhoj** : village, market, temples, tomb, 312, 313.  
**Kumri** : woodash tillage, 21.  
**Kunbis** : husbandmen, 88-92.  
**Kundgol** : town, market, 388.  
**Kundi** : hill pass, 5.  
**Kurundvád Junior** : State, description, trade, justice, 385-386.  
**Kurundvád Senior** : State, description, people, capital, trade, justice, finance, instruction, health, town details, 384-385.

## L.

**Labbays** : Musalmáns, 150.  
**Labourers** : 103-107.  
**Láds** : class of Koshtis, 95.  
**Lád Kaháls** : see Kaláls.  
**Lakshmeshvar** : town, school, temples, inscriptions, 381.  
**Lakshmisén** : Jain Pontiff, 95.  
**Lamáns** : caravan men, 108.  
**Land** : the ; staff (1844-1884), 247-249 ; village officers, village servants, 249 ; tenures, 249-251 ; cesses, 251 ; revenue history (1708-1884), 251, 254 ; survey (1869-70) 254, (1870) 255, 256, (1870-71) 256, (1870-1872), 256, 257, (1871-72) 257, (1872-1883) 257-260, (1875-1882) 260-263, (1880-81) 263 ; survey results (1868-1882) 255, (1870-1882) 256, (1854-1882) 257, (1871-1882) 257, (1850-1882) 258, (1854-1882) 259, (1856-1882) 260, (1874-1882) 261, (1855-1882) 262, (1856-1882) 262-263 ; season reports, 263-265.  
**Land Mortgage** : 195.  
**Leaf vegetables** : 183-184.  
**Leather** : Lingáyats dislike to, 124 note, 211.  
**Libraries** : 284.  
**Lime** : 20-21.  
**Ling** : spirit-scaring power of, and origin of wearing of, 118 ; note 2.  
**Lingáyats** : strength and distribution ; Basav's life, his doctrines, sects, daily life, customs, 118-133.  
**Lingáyat Math** : description of a, 122-123.  
**Lingvants** : see Lingáyats.  
**Local communities** : Musalmán, 151.  
**Local Funds** : 279.  
**Locusts** : 188.  
**Lohárs** : blacksmiths, 96.  
**Lokvant** : origin of the name of, 123 note.  
**Lonáris** : lime-burners, 31, 107.  
**Lunatic Asylum** : 288.

## M.

**Mádhavráv** : fourth Peshwa (1761-1772), 344, 345.  
**Mádhva Bráhmans** : see Vaishnavs.  
**Mahálingpur** : trading town, temple, fair, 393.  
**Mádhyaandins** : Bráhmans, 62-63.  
**Magdam Pir** : fair in honour of, 298.  
**Magistracy** : 272-273.  
**Mahádev** : hill, 8.  
**Mahálakshmi** : worship of, 57.  
**Mahávir** : last Jain saint, 133, 134.  
**Maháwats** : Musalmán elephant drivers, 149.  
**Mahimatgad** : hill fort, 4.  
**Máhmud Gáwán** : Bahmani minister (1469), besieges the fort of Vishálgad and, encamps at Kolhápúr, captures Vishálgad, takes Goa and

- other places and appoints one of his officers Khush Kaddam as his deputy to take charge of the newly conquered country, 224, 308.
- Mainghole** : forest block, 22, 23.
- Malik-ut-Tujár** : Bahmani general (1453), persuaded by a Rája of the Shirke family to attack Shankarrái of Khelna and is defeated and massacred, 224, 323.
- Mális** : gardeners, 93.
- Malkápur** : town, temples, 313.
- Máloji** : Mudhol Chief, 394.
- Malprabha** : river, 11.
- Malprabha-Gandharvgaḍ** : hill spur, 7.
- Manbet** : forest block, 22, 23.
- Mangalvedha** : town details, history, fort, inscriptions, 361-362.
- Mangar** : feeder of the Kásári, 9.
- Mangalágauri** : worship of, 56.
- Mángs** : depressed classes, 111-112.
- Mangsoli** : cattle fair at, 26.
- Mánjarda** : village, 363.
- Manohar** : hill, 5.
- Masantosh** : hill, 5.
- Manüre** : 160-161.
- Manyárs** : Musalmán glass-bangle sellers, 149.
- Maráthás** : 65-85; history of the origin of the name of, 81-85; ornaments, 70; surnames, 65-66, 414.
- Marátha Vánis** : traders, 87.
- Marihál** : village, temples, mosque, 363.
- Mársinh** : Siláhára king (1058), 220.
- Marriage** : details, 38; ceremonies, 50-55, 73-79, 89-91, 114, 129-131, 141-144.
- Márwár Vánis** : traders, 87.
- Masons** : 20.
- Medárket** : progenitor of the Buruds, 94.
- Mehmans** : Musalmáns, 150.
- Mehtar** : Kumbhár headman, 96.
- Memans** : see Mehmans.
- Meshris** : class of Márwár Vánis, 87-88.
- Mhaisál** : village, 363.
- Mhárs** : depressed classes, 112-115.
- Mhasái Páthár** : forest block, 22, 23.
- Mhasrang** : forest block, 22, 23.
- Minerals** : 18-19.
- Miraj Junior** : State, description, people, agriculture, trade, justice, places, 382-383.
- Miraj Senior** : State, description, production, people, agriculture, famines, capital, trade, history, land details, justice, instruction, health, places, 378-381; town details, copper-plates at, 219, 381; fort, 344 note 1.
- Mixed sowings** : 162-163.
- Moghals** : Musalmáns, 147.
- Momins** : see Mehmans.
- Moneylending** : 194.
- Mot** : leather bag, 12.
- Movements** : 42.
- Mudhol** : State, description, production, people, agriculture, trade, history, land, justice, instruction, health, places, 388-395; town details, wells, ponds, temple, 392-393.
- Muhammad Sháh II** : Bahmani king (1463-1482); sends his minister Mahamud Gawán against Shankarrái, 224.
- Mukris** : Musalmán traders, 150.
- Municipalities** : 279-280.
- Munro** : General (1818), 350, 351.
- Musalmáns** : 147-151.
- Musicians** : 100-101.
- N.**
- Nádás** : ropemakers, class of Mángs, 111.
- Nakshatras** : lunar asterisms, 155 note.
- Námdev** : devotee of Vithoba of Pandharpur, 98.
- Nálbands** : Musalmán farriers, 149.
- Nána Phadnavis** : Poona minister (1773-1800), 345, 346.
- Nándni** : see of the Jain head priest, 136.
- Nándra** : village, 363.
- Naráyanráv** : Mudhol Chief (1805-1816), 394.
- Narcotics** : 173, 174.
- Nardava** : pass, 6.
- Naro Mahádev** : founder of the Ichalkaranji State, 238 note.
- Narsoba's Vádi** : cattle fair at, 25.
- Newspapers** : 284.
- Nhávis** : barbers, 101-102.
- Niláris** : indigo dyers. See Rangáris.
- Norris** : Sir William, English ambassador (1701), 314.
- O.**
- Offences** : 276.
- Oil Pressing** : 212-214.
- Oilseeds** : 169-171.
- Otáris** : casters, 96-97.
- Outlying belts** : aspect of, 2.
- Outram** : Colonel (1844), 242.
- Ovans** : Colonel, Sátára Resident (1844), 315.
- Ozanne** : Mr. E. C., 191 note.
- P.**
- Padmále** : pond, 12.
- Padmanál** : old name of Panhála, 313.
- Padmanáladurga** : capital of Bhoj II. (*Shah* 1112), 222.
- Paithan** : 306.
- Palásika** : capital of the early Kadambs (500-550), 218.
- Pán** : betel vine, 173-174.
- Páncháls** : 97.



**Pancháyat** : caste council, 96, 266-267.  
**Panchganga** : river, 8, 9-10, 305, 307.  
**Pándav Daráh** : Buddhist caves, 317.  
**Pandharpur** : treaty at (1811), 349.  
**Pándurangráv** : grandfather of the present Chief of Sāngli, wounded and taken prisoner to Seringapatam, 345.  
**Panhála** : hill fort, 6; health resort, 16, 293; survey, 260-263; fort details, history, human sacrifices, town details, reservoirs, market, temples, tomb, fair, Paráshar's cave, 313-316.  
**Pannagálay** : another name of Panhála, 313.  
**Paper** : 214-216.  
**Parashurám Bháu Patvardhan (1774-1799)** : Sāngli Chief, destroys (1779) domed tomb of Nurkhán at Shirol, 319; engages himself in war against Kolhápúr and Haidar; assists the Peshwa's troops against the English; is appointed commander of the Marátha forces sent to assist the English against Tipu Sultán of Maisur; is engaged in war with Kolhápúr; commands the Marátha army in the battle of Kharda; contrives with Nána Phadnavis to place Chinnáji Appa on the Peshwa's *gádi* after the death of Mádhavrát II; is confined but afterwards released; is sent to oppose the Sátára Rája; Kolhápúr king ravages Parashurám's *jágir* and burns Tásgaon; directs his forces against the Kolhápúr Rája; is mortally wounded at Pattankudi village, 344-347.  
**Parashurám Trimbak** : (1692) takes possession of Panhála fort, 314.  
**Parasnáth** : Jain deity, 95, 133.  
**Párpoli** : pass, 5, 6.  
**Parits** : washermen, 102.  
**Pársis** : 152.  
**Passes** : hill, 5, 201.  
**Pátáne Prabhus** : writers, 64.  
**Patháns** : Musalmáns, 147-148.  
**Páthantánás** : cobblers, a class of Mángs, 111.  
**Pátharvats** : stone cutters, 97.  
**Pavála** : Buddhist caves, 317.  
**Pávangad** : hill fort, 6, 315, 316, 317.  
**Peddlers** : 206.  
**Perfumes** : 216-217.  
**Phonda** : pass, 5, 206.  
**Phonda Savgaon** : hill range, 7.  
**Pilgrimages** : 128.  
**Plough** : a, 156.  
**Pod vegetables** : 183.  
**Police** : 274-276.  
**Ponds** : 12-13.  
**Post offices** : 203-204.  
**Potphugi** : stream, 9.  
**Pova** : variety of honey bee, 24, 25.  
**Prabhánvalli** : hill path, 5.  
**Prabhus** : writers, 64-65.

B 569-55

**Prachitgad** : hill fort, 4, 5.  
**Pránlák** : old name of Panhála, 313.  
**Prasiddhagad** : hill fort, 5.  
**Prayág** : meeting of the Bhogávati and the Kásári, 16.  
**Prices** : 196-197.  
**Ptolemy** : Egyptian geographer (A.D. 150), 218, 306, 307.  
**Pulses** : 168-169.

## R.

**Rabkavi** : town details, fort, trade centre, temples, 363, 365.  
**Raddis** : husbandmen, 93.  
**Rághvendrácharya** : Vaishnav Pontiff, 63.  
**Railways** : 200.  
**Rainfall** : 16-17, 400-405.  
**Rájárám** : Sátára king (1689-1700), 226.  
**Rájárám II** : seventh Rája of Kolhápúr (1666-1870), his minority and education; his visit to Europe; his death, 244, 248.  
**Rajputs** : fighting class, 85-86.  
**Rámánuj** : Vaishnav Pontiff, 134.  
**Rámchandra Appa Sáheb** : Parashurám Bháu's son, 347.  
**Rámchandra Pant** : founder of the Bávda Amátya family (1689-1729); defends Vishálgad and Rángna against the Moghal forces, 226, 293.  
**Rámdás Svámi** : Shiváji's (1627-1680) spiritual teacher, 294.  
**Rámdurg** : State, description, people, trade, history, land, justice, instruction, health, 396-399.  
**Rámoshis** : 107.  
**Randulla Khán** : Bijápúr governor of Ráybág, 318.  
**Rangáris** : dyers, 97.  
**Rángna** : hill fort, 5, 293; description, history, 319; pass, 6.  
**Rangrezs** : Musalmán dyers, 149.  
**Rankále** : pond, 12, 161; legend of, 305-306, 309.  
**Ránojiráv Sínde** : 299.  
**Ráshrakutas** : early Hindu king (760-973), 218.  
**Ráuls** : 97.  
**Ráybág** : hill, 4; pond, 12; survey details, 257; town, temples, tomb, 318-319.  
**Reaping** : 162.  
**Reeves** : Mr., Commissioner (1844), 242.  
**Registration** : 272.  
**Reserved trees** : 25.  
**Rest-houses** : 202-203.  
**Rice** : varieties of, 165 and note I; cultivation of, 165.  
**Rivers** : 8-11.  
**Roads** : 198-200.  
**Roadside trees** : 25.  
**Rukdi** : village, town, temple, *darga*, 317-318.

## S.

**Sális** : weavers, 95.

**Sálvan** : hill, 8.

**Sámángad** : hill range, 7; fort, 7; copper-plate grant found at, 219; fort, description, history, 319.

**Sambháji** : Shiváji's son (1680-1689), 314.

**Sambháji II.** : second Kolhápur Rája (1712-1760), Tárábái is (1712) confined and the administration conducted by Rámchandra Pant Amátya; Chin Kuli Khán the first Nizám with a view to weaken the Marátha power supports Sambháji against Sháhu of Sátára; Sambháji is defeated by the Pratinidhi and driven to Panhála and Tárábái and Bhavánibái taken prisoners to Sátára; treaty with Sháhu (1730), 227-229.

**Sametshikhar** : death-place of Párasnáth, 133.

**Sangameshvar** : Lingáyat place of pilgrimage in Bijápur, 119, 120.

**Sangars** : wool weavers, 97-98.

**Sangli** : copper-plate grant at, 219; State, description, production, people, agriculture, famines, capital, trade, fairs, history, land details, justice, instruction, health, places, 324-377; town details, fort, Chief's residence, 365-367.

**Sarasvati** : underground stream, 9.

**Sárbáns** : Musalmán camel drivers, 149.

**Sarjeráv Ghátge** : Kágál Chief (1800), 234 and note.

**Sátin** : variety of honey bee, 24.

**Saváshás** : Bráhmans, 63.

**Sávgaon** : battle at (1808), 235.

**Saving Classes** : 194.

**Schools** : 281-283.

**Season Reports** : 263-265.

**Sedbál** : village, inscription at, 219.

**Servants** : 101-102.

**Service Mortgage** : 195.

**Settlement** : forest, 22.

**Sháháji** : Shiváji's father (1594-1664), 81; Rája of Kolhápur (1821-1837), 238-240.

**Sháhápur** : town, schools, temples, churches, 367.

**Sháhu** : Rája of Sátára (1708-1749), 229, 290, 314.

**Shaikhs** : Musalmáns, 148.

**Sháli** : stream, 9.

**Shambhu** : fourth Rája of Kolhápur (1812-1821), 237.

**Shamonámir** : tomb of, 293.

**Shankaráchárya** : Smárt Pontiff, 60, 134.

**Shenvis** : Bráhmans, 63.

**Shepherds** : 102-103.

**Shetsandis** : village watchmen, 274.

**Shilvants** : origin of the name of, 23 and note; 123 note.

**Shimpis** : tailors, 98.

**Shingnápur** : old name of Kavlápur, 360.

**Shirhatti** : town details, history, fort, monasteries, fair, 367-371.

**Shirol** : survey details, 256-257; town, temples, mosque, 319-320.

**Shirolí** : village, temple, fair, 320.

**Shiváji** : founder of the Marátha empire (1627-1680); obtains possession (1659) of Panhála and Pávangad from Rustum Jhamán by bribery; reduces Rángna and Vishálgad; defeats Rustum Jhamán near Panhála; marches with a large army into the Konkan; being attacked by the Bijápur army under Sidi Johár (1661) shuts himself up in Panhála; marches against Mudhol, the *jágir* of Báji Ghorpade; retakes Panhála (1673), 225-226, 293, 295, 319.

**Shiváji II.** : first Kolhápur Rája (1700-1712); Tárábái's administration of government; Aurangzeb marches against Panhála and Vishálgad and receives Sir William Norris, English ambassador in Panhála; Aurangzeb moves to Ahmadnagar and Pant Amátya retakes Panhála which becomes the capital of Kolhápur; release of Sháhu and his successful struggle with Tárábái for sovereignty; Shiváji dies in 1712, 226-227.

**Shiváji III.** : third Kolhápur Rája (1760-1812); Jijibái, widow of Sambhaji II. adopts the son of Sháháji Bhonsle of Khánvat under the name of Shiváji and manages the State; establishment of the family of Patvardhans by the Peshwa; English expedition against the maritime possessions of Kolhápur terminated by the capture of Málvan and a treaty (1766); human sacrifices to Amábái by Jijibái; her death (1772); Yashvant-ráv's management of the State affairs; revolt of the Chiefs of Bávda, Kágál, and Vishálgad (1777); Mahádji Sindia is sent by the Peshwa against Kolhápur authorities who agree to pay fifteen *lákhs* of rupees; Parashurám Bháu captures Rángna; Ratnákarant's administration; successful expedition headed by the Rája against the Desái of Sávantvádi; second treaty with the British Government (1792); war with Parshurám Bháu Patvardhan; war with Sar Desái of Sávantvádi and Chief of Nipáni; third treaty with the British Government; his death, 230-237.

**Shiváji IV.** : sixth Rája of Kolhápur (1837-1866), 240-243.

**Shiváji V.** : eighth Rája of Kolhápur (1870-1883), 244-245.

**Shivgad** : hill, fort, 5; "pass, 5-6.

**Shivtás** : see Páthantánás.

**Shopkeepers** : village, 206.

**Shrávaks** : see Jains.

**Shrimantgad** : fort, details, temple, ponds, 371-372.

**Sidi Johár** : Bijápur general (1661), 225, 314.

**Siddhagiri** : religious teacher of the Buruds, 94.  
**Siláháras** : early Kolhápúr kings (1050-1120), 219-223.  
**Singhan** : Devgiri Yádav king (1209-1248), 314.  
**Sinhdev** : Devgiri Yádav king (1213), 302.  
**Sinhgad** : death of Rájaram at, 226.  
**Singnápúr** : holy place in Sátára, 110.  
**Small-pox** : 287.  
**Snakes** : 33-34.  
**Soil** : 155.  
**Sonárs** : goldsmiths, 98-99.  
**Sowing** : 160.  
**Spices** : 174-180.  
**Spirit-possession** : Jain belief in, 139-140, 415-421.  
**Stone** : 208.  
**Storing** : of grain, 162.  
**Strachey** : Mr. E., appointed to negotiate settlement between Bajiráv Peshwa and the Patvardhans, 349.  
**Sub-Divisions** : 1.  
**Sugar** : 179-180.  
**Sugarcane** : area, varieties, cultivation, season, mill, sugarmaking, 175-180.  
**Surnames** : 43-44, 63, 64, 65, 66, 87, 103, 105, 106.  
**Sutárs** : carpenters, 99.  
**Syeds** : Musalmáns, 148.

## T.

**Takarribkhán** : Moghal general, captured Sambháji (1689), 226.  
**Tálkhat** : hill pass, 6.  
**Támbats** : coppersmiths, 99.  
**Támbolis** : betel-leaf sellers, 88.  
**Tarábái** : widow of Rájaram (1689-1700) puts her son Shiváji on the Kolhápúr throne and assumes administration; confines her husband's second widow Rájasbái with her son Sambháji; takes her abode in Panhála; disowns Sháhu's claims to the Marátha territories; collects forces to meet Sháhu but being defeated flees into the Konkan; retakes Panhála; is confined for a time after her son's death (1712); again taken prisoner, 226-227, 228.  
**Taylor** : the Reverend J., English missionary, (1870), 151, 152.  
**Telangs** : Bráhmans, 63, 64.  
**Telegraph** : 204.  
**Telis** : oilmen, 99.  
**Temblái** : younger sister of Mahálakshmi of Kolhápúr; temple, Mahálakshmi's yearly visit, he-buffalo offering, 311-312.  
**Tenures** : 249-250.  
**Terdal** : town, wall, gates, temples, inscriptions, 372-377.

**Thackeray** : Mr., Political Agent (1824), killed in the Kittur disturbance, 238.  
**Thermometer Readings** : city, 400-405.  
**Threadgirding** : ceremony of, 48-50, 140-141.  
**Threshing** : 162.  
**Tiles** : making of, 21.  
**Tipu** : Sultán of Maisur (1782-1799), 150.  
**Tirguls** : Bráhmans, 64.  
**Tivra** : hill pass, 5.  
**Tolls** : 200.  
**Torgal** : town, citadel, temple, 320-321.  
**Townsend** : Mr., Political Agent, Kolhápúr (1844), 247.  
**Trade Centres** : 204-205.  
**Traders** : 86-88.  
**Trees** : 22-23; reserved, 25; roadside, 25, 406-409.  
**Triveni** : see Prayág.  
**Tulsi** : stream, 9, 10.  
**Tungjái** : hill, 8.

## U.

**Ulvi** : Lingáyat place of pilgrimage, 119, 120.  
**Unsettled Tribes** : 107-109.  
**Upárs** : grindstone makers, 99-100.  
**Uttar Bhudargad** : hill spur, 23.

## V.

**Vaccination** : 238.  
**Vadárs** : quarrymen, 31, 108-109.  
**Vadgaon** : town details, history, temples, 321.  
**Vádi Machál** : hill fort, 4.  
**Vádi Narsinh** : town, temples, fair, 321, 322.  
**Vádi Ratnágiri** : see Jotiba's hill.  
**Vágjái** : hill, 8.)  
**Vairágis** : see Bairágis.  
**Vaishnavs** : Bráhmans, 60.  
**Vaishya Vánis** : see Marátha Vánis.  
**Vájantris** : Máng musicians, 111.  
**Vájsaneya** : section of Mádhyandins, 62.  
**Váki** : forest block, 22, 23.  
**Valhárs** : beggars, 118.  
**Válmik** : reputed author of the Rámáyan, 106.  
**Válva** : *dumála* village, history, mosque, fair, 322.  
**Várna** : river, 8, 9; forest block, 22, 23.  
**Vásudev** : beggars, 118.  
**Vat Puja** : fig tree worship, 56.  
**Vathar** : town, 338.  
**Vedganga** : river, 8, 9, 10, 11.  
**Vegetables** : bulb, fruit, pod, leaf, 180-184.  
**Vijayáditya** : Siláhára king (1142-1154), inscriptions, 222.  
**Vijjal** : Jain king of Kalyán (1156-1167), 119.  
**Villages** : 39-40; police, 273.



**Vishálgad** : hill fort, 4, 6, 293 ; mosque, fair, tradition of the building, water-supply, inscriptions, history, 322-323.

**Vishálgad Panhála** : hill range, 6-7.

**Vyankantráv** : becomes Chief of Mudhol (1817), 394.

### W.

**Wages** : 195.

**Wahábis** : Musalmán sect, 150-151.

**Wallace** : Colonel (1844), takes Rángna and Vishálgad, 242.

**Watching** : of crops, 162.

**Weaving** : 211-212.

**Weeding** : of crops, 162.

**Weights and Measures** : 195-196.

**Wellesley** : General (1800), 235.

**Wells** : 11-12.

**West** : Colonel E. W., tutor of Rájárám II. (1868-1870) accompanies him to Europe, 244.

**Western Chalukyas** : Hindu kings (550-760), 218.

**Western Chálukyas** : Hindu kings (973-1180), 218.

**Wheat** : grain, 166.

**Wild animals** : 31, 33.

**Wilson** : Dr. John, 81.

**Wood ash tillage** : 163.

**Writers** : 64-65.

### Y.

**Yashvantráv Sinde** : Kolhápúr minister (1772-1782), 231, 232, 300.

**Yelvatti** : fort, description, wells, temples, history, inscriptions, 377-378.

